



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE EXECUTIVE ENGINEER (SEW)

(CLIFTON / SADDAR DISTRICT SOUTH)

DEFUNT K.D.A OFFICE OPP: BILAWAL HOUSE
NEAR BILAWAL CHOWRANGI CLIFTON KARACHI.

Cell: 0334-3324756

SUBJECT:- **REPLACEMENT & LAYING OF OLD UNSERVICEABLE / DAMAGED 8" DIA, 12" DIA, 15" DIA AT BLOLCK-2, BATH ISLAND & CIVIL LINE FATIMA JINNAH ROAD CLIFTON SADDAR DISTRICT SOUTH.**

Estimated Cost On Item Rate Basis. Issued to M/S. _____
Time Limit 30 Days
Tender Cost Rs.500/= Pay Order No. _____ Dated: _____
Penalty Rs.500/=

ISSUING AUTHORITY

Sr.	Description	Quantity	Rate	Per	Amount
01.	Scarifying the existing road surface.	3360 Sft		% Sft	
02.	Dismantling and removing road metalling.	6720 Cft		% Cft	
03.	Excavation for Pipe line in trenches, and pits in all kinds of Soils or murum i/c. trimming and dressing sides to true alignment and shape leveling of bads of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by the Engineer Incharge. Providing fence guard's ligts, flags and temporary crossing for non-vehicular traffic where over required lifts upto 5 ft (1.52m) and lead upto one chain (30.5m). Lift 0' - 5'	7850 Cft.		% 0Cft	
04.	Add for additional lift of every three ft or part three of in item No.1 to 15 (A&B) for excavation for Pipe lines & storage tanks trenches and pits. 5' to 8' 8' to 11'	2415 Cft 2070 Cft		% 0Cft % 0Cft	
05.	Full Hire Charges of Pumping set per day inclusive of the wages of driver and assistant, fuel and electric energy plate from required for placing the pump etc, at lower depth with suction and delivery pipe for pumping out water pound at various depth from trenches including the cost of erection and dismantling after completion of job of 10HP form 10 Feet Depth.	35 Days.		P/Day	
06.	Providing laying RCC Pipes with (Rubber Ring Joint and fitting i/c. cutting, fitting and jointing with rubber ring i/c. testing with water to specified pressure. 08" Dia 12" Dia 15" Dia	350 Rft 560 Rft 230 Rft		P/Rft P/Rft P/Rft	
07.	Providing M/H 4 feet internal diameter without RCC manhole cover with CI frame (15Kg) and feet clear depth cast in situ 1:2: 9" thick wall 1:4:8 cement concrete in 6ft dia and 6 inch thick in foundation, 1:2:4 CC in benching ½" thick cement plaster 1:3 cement mortar on inside wall and surface of channel and benching to top including making required numbers of main and branches channels ¾" dia bars M.S foot rest at 12" C/C including cost of excavation in all kinds of soil, back filling and disposal of excavated stuff etc complete, as per design and instruction of the Engineer Incharge including C.I frame 15 Kg.	17 Nos.		Each	

SUBJECT:- REPLACEMENT & LAYING OF OLD UNSERVICEABLE / DAMAGED 8" DIA, 12" DIA, 15" DIA AT BLOLCK-2, BATH ISLAND & CIVIL LINE FATIMA JINNAH ROAD CLIFTON SADDAR DISTRICT SOUTH.

Sr.	Description	Quantity	Rate	Per	Amount
08.	Add or deduct for extra / less depth then 5 ft of 4 ft dia manhole i/c. footrest.	(-) 07 Inches		P/Inch	
09.	Making connection with existing Manholes i/c. her cost of cutting holes in walls making them goodd in cement concrete 1:2:4 and making the required channel etc complete.	12 Nos.		Each	
10.	Refilling the excavated stuff in trenches 6" thick layer i/c. watering ramming to full compaction etc complete.	7534 Cft.		% 0Cft	
11.	Sand Haro or any other source Sand of the same modules of the Finences (Hill Sand).	3520 Cft		% Cft	
12.	Carriage of 100 Cft./5 Tons of all materials like stone aggregate. Spawl, coal, lime, surkhi, etc. B.G Rail fastening points and crossing bridge, Girders, Pipes, Sheet Rail, M.S Bars etc. Nos: 1000 Nos: titles, 12"x16"x2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the contractors. 7 th Mile	4777 Cft		% Cft	
13.	Manufacturing and supplying of 21" dia RCC manhole cover cast in 1:2:4 concrete ration 3 inch deep at center, reinforced with 1/2" dia tor steel bars at 4" c/c welded to 3/6" thick 2" wide MS plate Two hook of 3/8" dia tor bar including compacting i/c. cruing and transportation in 10 miles. 21" Dia	25 Nos.		Each	
				Total	



EXECUTIVE ENGINEER (SEW)
CLIFTON / SADDAR DISTRICT SOUTH
(KW&SB)

I hereby quoted bid amount of Rs. _____ (Rupees in words _____)

Signature of Contractor _____

Address _____