



# KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE EXECUTIVE ENGINEER (SEW)

(CLIFTON / SADDAR DISTRICT SOUTH)

DEFUNT K.D.A OFFICE OPP: BILAWAL HOUSE  
NEAR BILAWAL CHOWRANGI CLIFTON KARACHI.

Cell: 0334-3324756

SUBJECT:- REPLACEMENT OF OLD & UNSERVICEABLE & UNDERSIZE 24" DIA SEWER LINE PROVIDING & LAYING 24" DIA SEWER LINE AT OPP: SALATEEN HOTEL TO BANGLOW D-95, BLOCK-2 SERVICE ROAD CLIFTON / SADDAR, DISTRICT SOUTH.

Estimated Cost	On Item Rate Basis.	Issued to M/S. _____
Time Limit	30 Days	
Tender Cost	Rs.500/=	Pay Order No. _____ Dated: _____
Penalty	Rs.500/=	

### ISSUING AUTHORITY

Sr.	Description	Quantity	Rate	Per	Amount
01.	Excavation for Pipe line in trenches, and pits in all kinds of Soils or murum i/c. trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joint holes and disposal of surplus earth within a one chain as directed by the Engineer Incharge. Providing fence guard's ligs, flags and temporary crossing for non-vehicular traffic where over required lifts upto 5 ft (1.52m) and lead upto one chain (30.5m). Lift 0' - 5'	18000 Cft.		% 0Cft	
02.	Add for additional lift of every three ft or part three of in Item No.1 to 15 (A&B) for excavation for Pipe lines & storage tanks trenches and pits. 5' to 8'	9800 Cft		% 0Cft	
03.	Full Hire Charges of Pumping set per day inclusive of the wages of driver and assistant, fuel and electric energy plate from required for placing the pump etc. at lower depth with suction and delivery pipe for pumping out water pound at various depth from trenches including the cost of erection and dismantling after completion of job of 10HP form 10 Feet Depth.	15 Days.		P/Day	
04.	Providing laying RCC Pipes with (Rubber Ring Joint and fitting i/c. cutting, fitting and jointing with rubber ring i/c. testing with water to specified pressure. 24" Dia	800 Rft		P/Rft	
05.	Cement Concrete plain including placing compacting finishing and curing compact (including screening and washing stone aggregate without shuttering 1:4:8. P/L 1:4:8 for manhole bed.	339.336 Cft		% Cft	
06.	Cement Concrete plain including placing compacting finishing and curing compact (including screening and washing stone aggregate without shuttering 1:4:8. P/L 1:4:8 for manhole bed.	138.78 Cft		% Cft	
07.	Making connection with existing Manholes i/c. her cost of cutting holes in walls making them good in cement concrete 1:2:4 and making the required channel etc complete.	18 Nos.		Each	
08.	Refilling the excavated stuff in trenches 6" thick layer i/c. watering ramming to full compaction etc complete.	33750 Cft.		% 0Cft	

**SUBJECT:- REPLACEMENT OF OLD & UNSERVICEABLE & UNDERSIZE 24" DIA SEWER LINE PROVIDING & LAYING 24" DIA SEWER LINE AT OPP: SALATEEN HOTEL TO BANGLOW D-95, BLOCK-2 SERVICE ROAD CLIFTON / SADDAR, DISTRICT SOUTH.**

Sr.	Description	Quantity	Rate	Per	Amount
09.	Manufacturing and supplying of ring slab 21" Dia (inside) and 36" dia (outside) 7 1/2" width and 6" thick i/c 3/8" dia for steel bars two concrete rings with 3/8" dia 8 Nos. cross linked bars welded and tow sunk type hooks casted in 1:1 1/2: 3 concrete with embedded 15 Kg C.I frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town officers. (Amount of 25 slabs per trip will be transported)	9 Nos.		Each	
10.	Shifting to the site and fixing 36" dia (outer) ring slab in perfect position on damaged manholes i/c cutting of the position of damaged manhole in proper shape laying in layer of CM in 2" thick and disposal of the debris. As per site	09 Nos.		Each	
11.	Manufacturing & supplying of 21" dia RCC manhole cover cast in 1:2:4 concrete ratio 3 inch deep at centre reinforced with 1/2" dia tor steel bars at 4" c/c welded to 3/16" thick 2" wide M.S plate two hook of compacting i/c curing and transportation in 10 Miles. 21" Dia	09 Nos.		Each	
				<b>Total</b>	

  
 EXECUTIVE ENGINEER (SEW)  
 CLIFTON / SADDAR DISTRICT SOUTH  
 (KW&SB)

I hereby quoted bid amount of Rs. \_\_\_\_\_ (Rupees in words) \_\_\_\_\_

Signature of Contractor \_\_\_\_\_

Address \_\_\_\_\_