


OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.

ESTIMATE COST	9,98,267/-	TIME LIMIT	01 MONTH
TENDER COST	1500/-	SECURITY DEPOSIT	49,913/-
PANELTY PER DAY	1500/-		

SUBJECT:- P/L 2" thick C.C Topping at Sector 5-G, different street in Saeedabd UC-05 D.M.C (West), Baldia Zone.

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of Trenches to correct lever and grade, surplus eartch within a one chain as directed by Eng Incharge.	1350	4650.00	%0cft	6278/-
02	P/L reinforced cement concrete ppes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan RCC pipe Co, M/S Pakistan const (Pvt.) Ltd. M/S Kamal RCC Pipe Co. 12" dia.	100	367.00	P/Rft	36700/-
03	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.1 frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	04 Nos	9307.86	Each	37231/-
04	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 2	1609.15	P/Rft	(-) 2318/-
05	Refilling excavation stuff & surplus earth etc complete.	1215	2760.00	%0Cft	3353/-
06	Dismantling Block Masonry.	1500	1134.38	%Cft	17016/-
07	Dismantling cement concrete plain 1:4:8.	7000	1663.75	%Cft	116463/-
08	P/L cement concrete brick or stone 6 allast 1 1/2" to 2" gauge 1:4:8.	4620	9416.28	%Cft	435032/-
09	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and diving into panels etc complete	14000	3275.50	%Sft	458570/-
10	Carriage of 100 cft tons of all kinds material like cole bricks i/c loading unloading 10 mile.	8635	595.80	%Cft	51447/-
11	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 wirth and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks costed in a 1-182:3 concrete with empeded 15 kg C-1frame in perfect position i/c transportation charges for on every lead of 20 km per arip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	02 Nos	1906.60	Each	3813/-
12	Manufacturing and supplying R.C.C Main Hole covers cast in situ 1:2:4 C.C. 3" inch deep in center reinforced with 3/8" dia M.S. Bars welded on M.S. sheet i/c curing transportation 21" dia 24" dia.	03 Nos	913.63	Each	2741/-
13	Rate analysis for shifting to the site and fixing 26" dia ring slab in perfect position on damage manhole i/c cutting of damage portion of mentioned in past shape and lying of cement concrete mortar of 2" thickness and disport.	02	563.09	Each	1126/-

Nomenclature, quantities and rates
Etc checked and found correct.

M. F. C. 
A.E (B&R)


A.E.E (B&R)

I/We hereby quoted rate@.....% above/below the schedule of rates.

Contractor's Signature.....

Address.....

OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.					
ESTIMATE COST	9,98,347/-	TIME LIMIT	01 MONTH		
TENDER COST	1500/-	SECURITY DEPOSIT	49,917/-		
PANELTY PER DAY	1500/-				
SUBJECT:- P/L 2" thick C.C Topping at Khaja Baba Street to Shahansha Katchi Muslim Mujahid Colony In UC7, D.M.C (West), Baldia Zone.					
S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of Trenches to correct lever and grade, surplus earth within a one chain as directed by Eng Incharge.	675	4650.00	%0cft	3139/-
02	P/L reinforced cement concrete pps with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan RCC pipe Co, M/S Pakistan const (Pvt.) Ltd. M/S Kamal RCC Pipe Co. 12" dia.	50	412.00	P/Rft	18350/-
03	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.1 frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	02 Nos	9307.86	Each	18616/-
04	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 1	1609.15	P/Rft	(-) 1909/-
05	Refilling excavation stuff & surplus earth etc complete.	607	2760.00	%0Cft	1675/-
06	Dismantling Block Masonry.	1800	1134.38	%Cft	20419/-
07	Dismantling cement concrete plain 1:4:8.	7250	1663.75	%Cft	120622/-
08	P/L cement concrete brick or stone 6 allast 1 1/2" to 2" gauge 1:4:8.	4785	9416.28	%Cft	450569/-
09	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and diving into panels etc complete	14500	3275.50	%Sft	474948/-
10	Carriage of 100 cft tons of all kinds material like cole bricks i/c loading unloading 10 mile.	9118	595.80	%Cft	54325/-
11	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 width and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks costed in a 1-182:3 concrete with empeded 15 kg C-1frame in perfect position i/c transportation charges for on every lead of 20 km per arip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	03 Nos	1906.60	Each	5720/-
12	Manufacturing and supplying R.C.C Main Hole covers cast in situ 1:2:4 C.C. 3" inch deep in center reinforced with 3/8" dia M.S. Bars welded on M.S. sheet i/c curing transportation 21" dia 24" dia.	03 Nos	913.63	Each	2741/-
13	Rate analysis for shifting to the site and fixing 26" dia ring slab in perfect position on damage manhole i/c cutting of damage portion of mentioned in past shape and lying of cement concrete mortar of 2" thickness and disport.	03	563.09	Each	1689/-

Nomenclature, quantities and rates
Etc checked and found correct.


A.E (B&R)


A.E. (B&R)


I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____

OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.					
ESTIMATE COST	9,97,712/-	TIME LIMIT	01 MONTH		
TENDER COST	1500/-	SECURITY DEPOSIT	49,886/-		
PANELTY PER DAY	1500/-				
SUBJECT:- P/L 2" thick C.C Topping at different street Jam Nagar Mohallah Shahansha Katchi Colony in UC-7, D.M.C (West), Baldia Zone.					
S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of Trenches to correct lever and grade, surplus earth within a one chain as directed by Eng Incharge.	675	4650.00	%0cft	3139/-
02	P/L reinforced cement concrete ppes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan RCC pipe Co, M/S Pakistan const (Pvt.) Ltd. M/S Kamal RCC Pipe Co. 12" dia.	50	412.00	P/Rft	18350/-
03	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.1 frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	02 Nos	9307.86	Each	18616/-
04	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 1	1609.15	P/Rft	(-) 1909/-
05	Refilling excavation stuff & surplus earth etc complete.	607	2760.00	%0Cft	1675/-
06	Dismantling Block Masonry.	1800	1134.38		20419/-
07	Dismantling cement concrete plain 1:4:8.	7200	1663.75		119790/-
08	P/L cement concrete brick or stone 6 allast 1 1/2" to 2" gauge 1:4:8.	4752	9416.28		447462/-
09	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and diving into panels etc complete	14400	3275.50		471672/-
10	Carriage of 100 cft tons of all kinds material like cole bricks i/c loading unloading 10 mile.	9068	595.80		54027/-
11	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 wirth and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks costed in a 1-182:3 concrete with empeded 15 kg C-1frame in perfect position i/c transportation charges for on every lead of 20 km per arip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	05 Nos	1906.60	Each	9533/-
12	Manufacturing and supplying R.C.C Main Hole covers cast in situ 1:2:4 C.C. 3" inch deep in center reinforced with 3/8" dia M.S. Bars welded on M.S. sheet i/c curing transportation 21" dia 24" dia.	05 Nos	913.63	Each	4568/-
13	Rate analysis for shifting to the site and fixing 26" dia ring slab in perfect position on damage manhole i/c cutting of damage portion of mentioned in past shape and lying of cement concrete mortar of 2" thickness and disport.	05 Nos	563.09	Each	2815/-

Nomenclature, quantities and rates
Etc checked and found correct.


A.E. (B&R)


A.E. (B&R)

I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____

OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.					
ESTIMATE COST	9,98,804/-	TIME LIMIT	01 MONTH		
TENDER COST	1500/-	SECURITY DEPOSIT	49,940/-		
PANALTY PER DAY	1500/-				
SUBJECT:- P/L 2" thick C.C Topping at Yousaf Dada House Ghanchi Mohallah Anjam Colony in UC-7, D.M.C (West), Baldia Zone.					
S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Dismantling Block Masonry.	2250	1134.38		25524/-
02	Dismantling cement concrete plain 1:4:8.	7500	1663.75		124781/-
03	P/L cement concrete brick or stone 6 allast 1 1/2" to 2" gauge 1:4:8.	4950	9416.28		466106/-
04	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and diving into panels etc complete	15000	3275.50		491325/-
05	Carriage of 100 cft tons of all kinds material like cole bricks i/c loading unloading 10 mile.	9750	595.80		58091/-
06	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 wirth and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks costed in a 1-182:3 concrete with empeded 15 kg C-1frame in perfect position i/c transportation charges for on every lead of 20 km per arip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	03 Nos	1906.60	Each	5720/-
07	Manufacturing and supplying R.C.C Main Hole covers cast in situ 1:2:4 C.C. 3" inch deep in center reinforced with 3/8" dia M.S. Bars welded on M.S. sheet i/c curing transportation 21" dia 24" dia.	02 Nos	913.63	Each	1827/-
08	Rate analysis for shifting to the site and fixing 26" dia ring slab in perfect position on damage manhole i/c cutting of damage portion of mentioned in past shape and lying of cement concrete mortar of 2" thickness and disport.	03 Nos	563.09	Each	1689/-

Nomenclature, quantities and rates
Etc checked and found correct.

W. F. A. C. B. K.
A.E (B&R)

[Signature]
A.E.E (B&R)

I/We hereby quoted rate @ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____

OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.					
ESTIMATE COST	9,93,867/-	TIME LIMIT	01 MONTH		
TENDER COST	1500/-	SECURITY DEPOSIT	49,693/-		
PANELTY PER DAY	1500/-				
SUBJECT:- P/L 2" thick C.C Topping at different street Madina Colony in UC-07 Baldia Zone, D.M.C (West).					
S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of Trenches to correct lever and grade, surplus eartch within a one chain as directed by Eng Incharge.	4050	4650.00	%0cft	18833/-
02	Excavation for pipe line in trenches and pits in hard rock by chiseling trimming and dressing alignment & shape leaving up to one chain.	600	24150.00	%0cft	14490/-
03	P/L reinforced cement concrete ppes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan RCC pipe Co, M/S Pakistan const (Pvt.) Ltd. M/S Kamal RCC Pipe Co. 12" dia.	300	229.00	P/Rft	68700/-
04	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.I frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	12 Nos	9307.86	Each	111694/-
05	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 6	1609.15	Pft	(-) 9655/-
06	Refilling excavation stuff & surplus earth etc complete.	4185	2760.00	%Cft	11551/-
07	Dismantling cement block masonry	1350	1134.28		15314/-
08	Dismantling cement concrete plane.	5400	1663.75		89843/-
09	P/L cement concrete bricks or stone bllast 1 1/2" to 2" gauge 1:4:8.	3564	9416.28		335596/-
10	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and dividing into panels etc.	10800	3275.50		353754/-
11	Carriage of 100 cft tane of all kinds material like cell bricks i/c loading unloading 10 miles.	7215	595.80		42987/-
12	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 wirth and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks costed in a 1-182:3 concrete with empeded 15 kg C-1frame in perfect position i/c transportation charges for on every lead of 20 km per arip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	28 Nos	1906.60	Each	53385/-
13	Manufacturing and supplying of R.C.C Ring Slab of 21" Manhole cover cast in 1:2:4 concrete ratio 3 inch deep at center reinforced with 1/2" dia tor steel bars at two 4" c/c welded to 3/16" thick 2" wide M.S plate two hook at 3/8" dia tor bar including compacting i/c curing and transportation with in 10 Miles. 21" dia	28 Nos	913.63	Each	25582/-
14	Rate analysis for shifting to the site and fixing 26" dia Ring Slab in perfect position on damage manhole i/c cutting of damage portion of mentioned in past shape and lying of cement concrete mortar of 2" thickness and disport.	28 Nos	563.09	Each	15767/-

Nomenclature, quantities and rates
Etc checked and found correct.

m. Re. M. S.
A.E (B&R)


A.E.E (B&R)

I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____

OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.

ESTIMATE COST	9,93,429/-	TIME LIMIT	01 MONTH
TENDER COST	1500/-	SECURITY DEPOSIT	49,671/-
PANELTY PER DAY	1500/-		

SUBJECT:- P/L R.C.C Slab i/c clearance of Nallah at Chowrd wala near Noor Masjid in UC-06 Baldia Zone, D.M.C (West).

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Dismantling cement concrete reinforced separating reinforcement from concrete clearing and straightening the same.	2039	5445.00	%cft	111024/-
02	Earth work excavation in ashes sand soft soil or silt clearance undressed bad up to soft.	24000	1663.75	%0cft	39930/-
03	Recowark in roof sleb bears columns raft lintel and other structure member laid in situ or precast laid in position complete in all respect. 1. Ratio (1:2:3) 90 lbs. cement. 2. Cft sand 4 cft shingle 1/8" to 1/4" guage.	2039	337.00	P/Cft	687143/-
04	Fabrication of mild steel reinforcement for cement concrete i/c cutting, bending laying in position making joints and fastenings including cast of binding wire (also includes re moved of rust from bars.	2039	4820.20	P/Cwt	687143/-
05	Carriage of 100 cft tons of all kinds material like cole bricks i/c loading unloading 10 miles.	26039	595.80	%cft	155140/-

Nomenclature, quantities and rates
Etc checked and found correct.

M. F. A. S.
A.E (B&R)

[Signature]
A.E.E (B&R)

I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____

OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.					
ESTIMATE COST	7,76,532/-	TIME LIMIT	01 MONTH		
TENDER COST	1500/-	SECURITY DEPOSIT	38,827/-		
PANELTY PER DAY	1500/-				
SUBJECT:- P/L 12" dia R.C.C Pipe Drain i/c 2" thickness c.c flooring at Gali No.4, Chowrd Wala in UC-06, Baldia Zone, D.M.C (West).					
S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of Trenches to correct lever and grade, surplus earth within a one chain as directed by Eng Incharge.	5400	4650.00	%0cft	25110/-
02	P/L reinforced cement concrete pps with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan RCC pipe Co, M/S Pakistan const (Pvt.) Ltd. M/S Kamal RCC Pipe Co. 12" dia.	400	412.00	P/Rft	164800/-
03	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.1 frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	17 Nos	9307.86	Each	158234/-
04	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 8.5	1609.15	P/Rft	(-) 13678/-
05	Refilling excavation stuff & surplus earth etc complete.	4860	2760.00	%0Cft	13414/-
06	Dismantling cement concrete plain 1:4:8	3400	1663.73	%Cft	56568/-
07	Cement concrete brick or stone last 1 1/2" to 2" guage.	2244	9416.78	%Cft	211301/-
08	Providing and laying 2" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels.	6800	3275.50	%Sft	222734/-
08	Manufacturing and supplying of R.C.C Ring Slab of 21" Manhole cover cast in 1:2:4 concrete ratio 3 inch deep at center reinforced with 1/2" dia tor steel bars at two 4" c/c welded to 3/16" thick 2" wide M.S plate two hook at 3/8" dia tor bar including compacting i/c curing and transportation with in 10 Miles. 21" dia	05 Nos	913.63	Fach	4568/-
09	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 wirth and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks costed in a 1-182:3 concrete with empeded 15 kg C-1frame in perfect position i/c transportation charges for on every lead of 20 km per arip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	05 Nos	1906.60	Each	9533/-
10	Shifting to the site and fixing of 36" dia ring slab in perfect position on damaged manholes i/c cutting of damaged portion of manholes in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	05 Nos	563.09	Each	2815/-
11	Filling watering and ramming earth under floor with new earth excavated from out side lead up to one chain and lift up to 5 fit.	1200	3630.00	%Cft	4356/-
12	Carriage of 100 cft tons of all kinds material like cole brick i/c loading un loading 10 miles.	3940	595.80	%Cft	23475/-

Nomenclature, quantities and rates
Etc checked and found correct.

m. Re - A
A.E (B&R)


A.E.F. (B&R)

I/We hereby quoted rate @ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____

OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.					
ESTIMATE COST	9,64,884/-	TIME LIMIT	01 MONTH		
TENDER COST	1500/-	SECURITY DEPOSIT	48,244/-		
PANELTY PER DAY	1500/-				
SUBJECT:- P/L 12" dia R.C.C Pipe Drain i/c c.c. stet at Noor Masjid Wali Gali in UC-06, Baldia Zone, D.M.C (West).					
S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of Trenches to correct lever and grade, surplus earth within a one chain as directed by Eng Incharge.	6750	4650.00	%0cft	31388/-
02	P/L reinforced cement concrete ppes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan RCC pipe Co, M/S Pakistan const (Pvt.) Ltd. M/S Kamal RCC Pipe Co. 12" dia.	500	412.00	P/Rft	206000/-
03	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.I frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	21 Nos	9307.86	Each	195465/-
04	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	10.5	1609.15	P/Rft	(-) 16896/-
05	Refilling excavation stuff & surplus earth etc complete.	6075	2760.00	%0Cft	16767/-
06	Dismantling cement concrete plain 1:4:8	4250	1663.73	%Cft	70709/-
07	Cement concrete brick or stone last 1 1/2" to 2" guage.	2805	9416.78	%Cft	264127/-
08	Providing and laying 2" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels.	8500	3275.50	%Sft	278418/-
09	Manufacturing and supplying of R.C.C Ring Slab of 21" Manhole cover cast in 1:2:4 concrete ratio 3 inch deep at center reinforced with 1/2" dia tor steel bars at two 4" c/c welded to 3/16" thick 2" wide M.S plate two hook at 3/8" dia tor bar including compacting i/c curing and transportation with in 10 Miles. 21" dia	05 Nos	913.63	Each	4568/-
10	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 width and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks costed in a 1-182:3 concrete with empeded 15 kg C-Iframe in perfect position i/c transportation charges for on every lead of 20 km per arip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	05 Nos	1906.60	Each	9533/-
11	Shifting to the site and fixing of 36" dia ring slab in perfect position on damaged manholes i/c cutting of damaged portion of manholes in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	05 Nos	563.09	Each	2815/-
12	Filling watering and ramming earth under floor with new earth excavated from out side lead up to one chain and lift up to 5 fit.	1500	3630.00	%Cft	5445/-
13	Carriage of 100 cft tons of all kinds material like cole brick i/c loading un loading 10 miles.	4925	595.80	%Cft	29343/-

Nomenclature, quantities and rates
Etc checked and found correct.

M. F. A.
A.E (B&R)

A.E.E.
A.E.E (B&R)

I/We hereby quoted rate @ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____


OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.

ESTIMATE COST	8,17,157/-	TIME LIMIT	01 MONTH
TENDER COST	1500/-	SECURITY DEPOSIT	40,858/-
PANELTY PER DAY	1500/-		

SUBJECT:- P/L C.C street i/c 12" dia R.C.C. Pipe Drain at Gali No.3, Chowrd Wala Jamat Khana in UC-06, D.M.C (West), Baldia Zone.

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of Trenches to correct lever and grade, surplus eartch within a one chain as directed by Eng Incharge.	5738	4650.00	%0cft	26682/-
02	P/L reinforced cement concrete ppes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan RCC pipe Co, M/S Pakistan const (Pvt.) Ltd. M/S Kamal RCC Pipe Co. 12" dia.	425	412.00	P/Rft	175100/-
03	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.1 frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	18 Nos	9307.86	Each	167541/-
04	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 9	1609.15	P/Rft	(-) 14482/-
05	Refilling excavation stuff & surplus earth etc complete.	5164	2760.00	%0Cft	14253/-
06	Dismantling cement concrete plain 1:4:8	3613	1663.75	%Cft	60111/-
07	Cement concrete brick or stone last 1 1/2" to 2" guage.	2384	9416.78	%Cft	224484/-
08	Providing and laying 2" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels.	7225	3275.50	%Sft	236655/-
09	Manufacturing and supplying of R.C.C Ring Slab of 21" Manhole cover cast in 1:2:4 concrete ratio 3 inch deep at center reinforced with 1/2" dia tor steel bars at two 4" c/c welded to 3/16" thick 2" wide M.S plate two hook at 3/8" dia tor bar including compacting i/c curing and transportation with in 10 Miles. 21" dia	05 Nos	913.63	Each	4568/-
10	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 wirth and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks costed in a 1-182:3 concrete with empeded 15 kg C-lframe in perfect position i/c transportation charges for on every lead of 20 km per arip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	05 Nos	1906.60	Each	9533/-
11	Shifting to the site and fixing of 36" dia ring slab in perfect position on damaged manholes i/c cutting of damaged portion of manholes in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	05 Nos	563.09	Each	2815/-
12	Filling watering and ramming earth under floor with new earth excavated from out side lead up to one chain and lift up to 5 fit.	1200	3630.00	%Cft	4356/-
13	Carriage of 100 cft tons of all kinds material like cole brick i/c loading un loading 10 miles.	2958	595.80	%Cft	17624/-

Nomenclature, quantities and rates
Etc checked and found correct.


A.E. (B&R)


A.E. (B&R)

I/We hereby quoted rate @ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____


OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.


ESTIMATE COST	9,98,196/-	TIME LIMIT	01 MONTH
TENDER COST	1500/-	SECURITY DEPOSIT	49,910/-
PANALTY PER DAY	1500/-		

SUBJECT:- P/L 12" dia R.C.C Pipe Drain at different street in Sector 4/A, Saeedabad in UC-04, Baldia Zone, D.M.C (West).

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of Trenches to correct lever and grade, surplus earth within a one chain as directed by Eng Incharge.	10800	4650.00	%0cft	50220/-
02	Excavation for pipe line in trenches and pits in hard rock by chiseling trimming and dressing alignment & shape leaving up to one chain.	2700	24150.00	%0cft	65205/-
03	P/L reinforced cement concrete ppes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan RCC pipe Co, M/S Pakistan const (Pvt.) Ltd. M/S Kamal RCC Pipe Co. 12" dia.	1000	412.00	P/Rft	412000/-
04	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.I frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	52 Nos	9307.86	Each	484009/-
05	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 26	1609.15	Pft	(-) 41838/-
06	Refilling excavation stuff & surplus earth etc complete.	12150	2760.00	%0Cft	33534/-
07	Carriage of 100 cft tons of all kinds material like cole bricks i/c loading unloading 10 miles.	1350	595.80	%Cft	8043/-
08	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 wirth and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks coated in a 1-182:3 concrete with empeded 15 kg C-1frame in perfect position i/c transportation charges for on every lead of 20 km per arip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	10 Nos	1906.60	Each	19066/-
09	Manufacturing and supplying of R.C.C Ring Slab of 21" Manhole cover cast in 1:2:4 concrete ratio 3 inch deep at center reinforced with 1/2" dia tor steel bars at two 4" c/c welded to 3/16" thick 2" wide M.S plate two hook at 3/8" dia tor bar including compacting i/c curing and transportation with in 10 Miles. 21" dia	50 Nos	913.63	Each	45682/-
10	Rate analysis for shifting to the site and fixing 26" dia Ring Slab in perfect position on damage Manhole i/c cutting of damage portion of mentioned in past shape and lying of cement concrete mortar of 2" thickness and disport.	10 Nos	563.09	Each	5631/-

Nomenclature, quantities and rates
Etc checked and found correct.


A.E (B&R)


A.E.E (B&R)

I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____

OFFICE OF THE TOWN OFFICER (I&S) D.M.C (WEST) BALDIA ZONE.

ESTIMATE COST	9,95,449/-	TIME LIMIT	01 MONTH
TENDER COST	1500/-	SECURITY DEPOSIT	49,772/-
PANELTY PER DAY	1500/-		

SUBJECT:- P/L 12" dia R.C.C Pipe Drain House No.233 in different street Block-C Musharraf Colony, in UC-03, Baldia Zone, D.M.C (West).

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of Trenches to correct lever and grade, surplus earth within a one chain as directed by Eng Incharge.	10800	4650.00	%0cft	50220/-
02	Excavation for pipe line in trenches and pits in hard rock by chiseling trimming and dressing alignment & shape leaving up to one chain.	2400	24150.00	%0cft	57960/-
03	P/L reinforced cement concrete ppes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan RCC pipe Co, M/S Pakistan const (Pvt.) Ltd. M/S Kamal RCC Pipe Co. 12" dia.	1000	412.00	P/Rft	412000/-
04	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.I frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	40 Nos	9307.86	Each	372314/-
05	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 20	1609.15	P/Rft	(-) 32183/-
06	Refilling excavation stuff & surplus earth etc complete.	11880	2760.00	%0Cft	32789/-
07	Carriage of 100 cft tons of all kinds material like cole bricks i/c loading unloading 10 miles.	1320	595.80	%Cft	7865/-
08	Manufacturing and supplying of R.C.C Ring Slab of 21" Manhole cover cast in 1:2:4 concrete ratio 3 inch deep at center reinforced with 1/2" dia tor steel bars at two 4" c/c welded to 3/16" thick 2" wide M.S plate two hook at 3/8" dia tor bar including compacting i/c curing and transportation with in 10 Miles. 21" dia	50 Nos	913.63	Each	45682/-
09	Manufacturing and supplying of R.C.C ringslab of 21" dia inside 36" dia outside 7.5 wirth and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks costed in a 1-182:3 concrete with empeded 15 kg C-Iframe in perfect position i/c transportation charges for on every lead of 20 km per arrip fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	49 NOS	1900.00	Each	93423/-
10	Shifting to the site and fixing of 36" dia ring slab in perfect position on damaged manholes i/c cutting of damaged portion of manholes in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	49 Nos	563.09	Each	27591/-
11	Filling watering and ramming earth under floor with new earth excavated from out side lead up to one chain and lift up to 5 fit.	28500	3630.00	%0Cft	103455/-

Nomenclature, quantities and rates
Etc checked and found correct.

m. P.C. AC
A.E (B&R)

[Signature]
A.E.E (B&R)

I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____

OFFICE OF THE XEN (B&R) D.M.C (WEST) BALDIA ZONE.

ESTIMATE COST	5,00,641/- + O/R	TIME LIMIT	01 MONTH
TENDER COST	1500/-	SECURITY DEPOSIT	25,032/- + 5% O/R
PANELTY PER DAY	1500/-		

SUBJECT:- Improvement work of Kumar Wala Park in UC-8, Baldia Zone, D.M.C (West).

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01.	Excavation in foundation of Building Bridge and other structure method including log belting dressing refilling around structure work excavation eith watering and remaing lead up to 5ft orisanry soil.	294	3176.25	%Sft	934/-
02.	Cement concrete 1:2:4 plain including placing compacting, finishing and curing complete.	146	14429.25	%Cft	21067/-
03	Erection and removal of centering for R.C.C on plain cement concrete works of partial wood vertical.	294	3127.41	%Cft	9195/-
04	Providing and laying 1:3:6 cement concrete solid Block masonry wall above 6" inch thickness in 1:6 cement motor in G.F ground floor sub structure including rating out joints & curing etc.	528	14621.44	%Cft	77201/-
05	Distempering three coats	4800	1079.65	%Sft	51823/-
06.	Suppling & spreading cow duck maner.	1389	298.12	P/Cud	414089/-
07	Plantationg of Cow cavpus	300	O/R	Each	O/R
08	Providing & Supply Donkey Pump 1 Hours Power.	1 Nos	O/R	Each	O/R
09	Physical Appliance				
	1. Anany go.	1 Nos	O/R	Each	O/R
	2. See Saw.	1 Nos	O/R	Each	O/R
	3. Slide.	1 Nos	O/R	Each	O/R
	4. Swing.	1 Nos	O/R	Each	O/R
10	Cement Plaster 1:4 up to 12 ft Hight.	588	2496.72	P/Sft	14681/-
11	Providing and Supply inater supply pipe.	100	O/R	P/Rft	O/R

Nomenclature, quantities and rates
Etc checked and found correct.

M. P. A. E.
A.E (B&R)

[Signature]
A.E.E (B&R)

[Signature]
D.T.O (PARK)

I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____