

University Engineer

SPPRA COPY



Phone: 9261366
9261300-6
Ext: 2247

Ref. No. 1231
28/1/2014

Tender Engineering Department
University of Karachi
Karachi-75270

Date of Opening:- 20-02-2014.

Time of Opening:- 02:30 P.M.

Tender # 01

Place of Opening:- Office of Director Finance, University of Karachi.

Work:- Repair & maintenance work at House No.B-11, Staff Town
University of Karachi.

| ITEMS OF WORK. | | QTY. | RATE. | UNIT. | AMOUNT. |
|--|--|---------|-------|-------|---------|
| Roof Screeding works at House No.B-11 | | | | | |
| 01. | Dismantling roof Screeding at 1 st floor roof up to nude roof i/c dispose off the material as directed by in-charge. | 400- | | Sft. | |
| 02. | P/L roof Screeding of 2" thick 1:2:4 C. Cone. Graded bajri + crush and down gauge in 1 st floor slab i/c from work consolidation, finishing and curing etc complete. | 400- | | Sft. | |
| 03. | P/F U. pvc Pipe 3" dia with specials for water spout i/c making holes and making good damages. | 10- | | Rft. | |
| 04. | Hire charges for mixing machine. | L.S | | L.S | |
| 05. | Providing and applying SBR Chemical at existing roof slab's surface for treatment of water proofing work, mixing composition 1 1/2" Kg. neat cement mix in water and added in niro one (1) gallon of SBR Chemical's bottle and applying with paint brushes at required surface, as directed by Engineer In-charge as required at site. | 400- | | Sft. | |
| Glazed Tiles work at House No.B-11 | | | | | |
| 06. | Dismantling of mosaic floor and skirting i/c disposal off the material as directed by In-charge. | 1700- | | Sft. | |
| 07. | P/L floor of 1/4" thick coloured glazed tiles 12" X 12" of master make (Pakistani) 1 graded in ground floor laid over 1" thick C.M 1:2 i/c jointing & washing the tiles with white cement slurry and curing etc complete. | 1700- | | Sft. | |
| Replacement mirror glass, door lock | | | | | |
| 08. | P/F figure glass with beading etc. complete | 50- | | Sft. | |
| 09. | P/F door lock | 06 Nos | | Each | |
| 10. | P/F mirror 24" X 18" with plastic shell. | 03 Nos. | | Each | |
| Electrical Wiring Work | | | | | |
| 11. | P/F Rewiring for light /Fan point with all building C-31 with 2-3/029 wire Fayyaz Cable or equivalent Million supreme in concealed pipe wiring on surface of the wall roof column i/c switch / socket / Dimmer A-99 Aqua China sheet board concealed complete light / Fan point as required. | 54 No. | | Each. | |
| 12. | P/F wiring for circuit line with 2-7/029 Fayyaz cable Million Supreme i/c earth wire 1.5 mm Fayyaz Cable or equivalent as required. | 500 ft. | | Rft. | |
| 13. | P/F Universal plug A99(Aqua with concealed Board. | 12 No. | | Each. | |
| 14. | P/F Power plug A-99 Aqua 13 Amp. with board concealed as required at site. | 3 Nos. | | " | |
| 15. | P/F main D.B box Iron sheet G-20 - 15"X17"X4" connected i/c main circuit breaker Hagar France TP-63 Indicator lamp 3 No i/c a) MCCB Single Phase 10 Amp 3 No, b) Amp 3 No (c) 20 Amp 3 No as required. | 1 Job | | | |
| | | | | TOTAL | |

UNIVERSITY ENGINEER

CAMPUS ENGINEER

CONTRACTOR (With seal)

University Engineer



SPPRA COPY

Phone: 9261366
9261300-6
Ext: 2247

Ref. No. 1231
29/1/2014

Engineering Department
University of Karachi
Karachi-75270

Tender

Date of Opening:- 20-02-2014.
Time of Opening:- 02:30 P.M.
Place of Opening:- Office of Director Finance, University of Karachi.

Tender # 02

Work:- **Electric & Civil Works at House No.C-31, Staff Town, University of Karachi.**

| S. #. | ITEMS OF WORK. | QTY. | RATE. | UNIT. | AMOUNT. |
|-------|--|----------|-------|--------------|---------|
| 01. | P/F Rewiring for light / Fan point. P/F Rewiring for light / Fan point with all building C-31 with 2-3/029 wire Fayyaz Cable Million or equivalent in concealed pipe wiring on surface of the wall roof column i/c switch / socket / Dimmer A-99 Aqua China sheet board concealed complete light / Fan point as required. | 32 No. | | Each. | |
| 02. | P/F wiring for circuit line with 2-7/029 Fayyaz cable or equivalent Million Supreme i/c earth wire copper 1.5 mm as required. | 2500 ft. | | Rft. | |
| 03. | P/F Universal plug A99 Aqua with concealed Board. | 12 No. | | Each. | |
| 04. | P/F Gate light wiring for call bell / Gate light with 2-4/029 Fayyaz Cable or equivalent Million Supreme i/c earth wire Million and PVC Pipe 3/4 have as required. (Not Call bell switch board). | 120 ft. | | Rft. | |
| 05. | P/F Ceiling Fan, Pak Fan Deluxe Plus Copper wire have. | 01 No. | | Each. | |
| 06. | P/F Gate light with Energy Saver lamp 25 watt (Iron sheet) | 02 No. | | " | |
| 07. | P/F main D.B box Iron sheet G-20 - 15"X17"X4" connected i/c main circuit breaker Hagar France TP-63 Indicator lamp 3 No i/c a) MCCB Single Phase 10 Amp 3 No, b) Amp 3 No (c) 20 Amp 3 No as required. | 1 Job | | Job. | |
| 08. | P/F Energy Motor 3 O Phase 25+50 Amp with folding board 12"X15" as required (China Motor) | 01 No. | | Each | |
| 09. | P/F Main service line pole to main energy Motor with 4.7/044 6 mm Fayyaz cable or equivalent Million supreme as required at site. | 30 ft. | | | |
| 10. | RENOVATION OF KITCHEN WORK Dismantling of existing mosaic floor and dado i/c disposal off the material as directed by In-charge. | 160- | | Rft. Sft. | |
| 11. | Dismantling f R.C.C. slab i/c separating reinforcement form concrete as directed by In-charge. | 20- | | Cft. | |
| 12. | P/L floor of 1/4" thick coloured glazed tiles 12"X12" of master make (Pakistani) 1 grade in ground floor laid over 1" thick C.M 1:2 i/c jointing & washing the tiles with white cement slurry and curing etc complete. | 160- | | Sft. | |
| 13. | P/L floor of 2" thick 1:2:4 C. Conc. Using graded screened bajri 3/4" and down gauge in ground floor i/c form work consolidation, finishing and curing etc complete. | 100- | | Sft. | |
| 14. | P/F 3/4" thick marble slab with grinding and polishing i/c cutting holes for sink. | 20- | | Sft. | |
| 15. | P/L 1:3:6 Block masonry 1:2 raking out joints and curing etc complete. | 60- | | Cft. | |
| 16. | 3/4" thick C. plaster 1:4 on walls, column in ground floor i/c making edges, corners, and curing etc complete. | 200- | | Sft. | |
| 17. | P/F 1-1/2" thick solid flush door fixed with side ply i/c iron hinges, handles, door lock etc complete. | 120- | | No. | |
| 18. | P/F Steel sink heavy with bracket, waste, waste pipe, and mixer etc complete. | 1 No. | | No. | |

1231
28/1/2019



SPPRA COPY

Page # 02

| S. #. | ITEMS OF WORK. | QTY. | RATE. | UNIT. | AMOUNT. |
|-------|--|------------------|-------|--------------|---------|
| 19. | P/F Gas Stove town family size fix in line etc Complete. | 1 No. | | No. | |
| 20. | P/F Kitchen Cabinet of Lamination sheet fix with Formica sheet on side i/c brass hinges, catcher, handle etc complete as required at site. | | | Sft. | |
| 21. | Renovation of Toilet work. Dismantling of existing floor dado & Disposal off the material as directed by In-charge. | 260- | | Sft. | |
| 22. | P/L floor of 1/4" thick colored tiles 12"X12" of mastery make (Pakistani) 1 st grade in ground floor laid over 1" thick C.M 1:2 i/c jointing and washing the tiles with white cement slurry and curing et complete. | 260- | | Sft. | |
| 23. | P/L U.Pvc P-Trap 4" dia with trap jail i/c cutting holes and making good damages. | 02 Nos. | | Each. | |
| 24. | P/F U.Pvc pipe 3" dia with specials i/c cutting, joints and making good damages. | 40- | | Rft. | |
| 25. | P/F U.Pvc pipe 4" dia with specials i/c cutting, joints and making good damages. | 40- | | Rft. | |
| 26. | P/F C.Pvc pipe 1/2" dia with specials i/c cutting for concealed piping etc complete. | 60- | | Rft. | |
| 27. | P/F Mirror 24"X18" with plastic shelf. | 01 No. | | Each. | |
| 28. | P/F Towel rail 24"X3/4" with bracket etc complete. | 01 No. | | Each. | |
| 29. | P/F Muslim Shower with 3' long plastic connection. | 01 No. | | Each. | |
| 30. | P/F chrome shower with rod fix in line etc complete. | 01 No. | | Each. | |
| 31. | P/F chrome double bib cock 1/2" dia fix in line. | 01 No. | | Each. | |
| 32. | P/F Chrome bibcock 1/2" dia i/c fix inline. | 03 No. | | Each. | |
| 33. | P/F concealed stop cock 1/2" dia i/c fix in line. | 09 No. | | Each. | |
| 34. | P/F W.C /Commode with low level flush tank (Golden) i/c Pvc flushing pipe suitable for this style with fitting etc. complete. With U. Pvc P-Trap. a) Commode. b) W.C | 01 No. 01 No. | | Each Each | |
| 35. | P/F Wash basin 16"X22" with pedestal, bracket, waste, waste pipe, mixer, plastic connection etc complete. | 01 No. | | Each. | |

UNIVERSITY ENGINEER

CAMPUS ENGINEER

CONTRACTOR (With seal)