

**KARACHI WATER AND SEWERAGE BOARD**



**TENDER DOCUMENTS**


**FOR THE WORK OF**

**REPAIR & MAINTENANCE OF QUARTER NO. E-1,  
COD FILTER PLANT STAFF COLONY.**

**EXECUTIVE ENGINEER-II  
E&M CIVIL (WATER)**

## BIDDING DATA

- |                                                                                                                          |                                                                                       |
|--------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------------------|
| (a) NAME OF PROCURING AGENCY                                                                                             | E.E-11 E&M Civil (Water)KW&SB                                                         |
| (b) Brief Description of works                                                                                           | REPAIR & MAINTENANCE OF<br>QUARTER NO.E-1 COD FILTER<br>PLANT STAFF COLONY<br>KW&SB   |
| (c) Source of fund                                                                                                       |                                                                                       |
| (d) Procuring Agency's Address:-                                                                                         | COD Filter Plant Gulshan-e-Iqbal<br>Karachi                                           |
| (e) Estimate cost                                                                                                        | RS.8,56,433/-                                                                         |
| (f) Amount of security:-                                                                                                 | 2% OF BID COST                                                                        |
| (g) Period of bid validity                                                                                               | (90 days)                                                                             |
| (h) Security Deposit (Including Bid Security)                                                                            | 10% Including Bid Security                                                            |
| (i) Percentage if any to be deducted from bill                                                                           | 7% Income Tax and 1% W/C                                                              |
| (j) Deadline for issuance of Bids allowing with time                                                                     | at 2:00 PM                                                                            |
| (k) Deadline for Submission of Bids allowing with time                                                                   | at 2:30 PM <i>ON 17-03-2014</i>                                                       |
| (l) Venue Time and Bids allowing with time                                                                               | BLOCK " E " Room No 5. 9 <sup>th</sup> mile<br>Karsaz near Awami Markaz,<br>02:30 PM. |
| (m) Time for completion from written order of<br>commence.                                                               | <i>20</i> Days                                                                        |
| (n) Liquidity damages 0.05 of Estimated cost of<br>Bid cost per day of delay but total not<br>Exceeding 10% of bid cost. |                                                                                       |

  
Executive Engineer-II  
E&M Civil(Water),KW&SB

**OFFICE OF THE EXECUTIVE ENGINEER-II**  
**E&M CIVIL (WATER)**

**B.O.Q.**

**SUBJECT: REPAIR & MAINTENANCE OF QUARTER NO. E-1, COD FILTER PLANT STAFF COLONY.**

ITEM NO.	DESCRIPTION OF ITEMS	QTY	RATE	PER	AMOUNT
Item No. 1	Excavation in foundation of building bridge and other structure i/c dag belling dressing, refilling around structure with excavated earth watering and ramming lead upto 5ft in ordinary soil.	2240		%0Cft	
Item No. 2	Cement concrete brick or stone ballast 1 ½" to 2" gauge Ratio 1:4:8	448		%Cft	
Item No. 3 (A)	Cement concrete plain i/c placing compacting finishing and curing complete i/c screened and washing at stone aggregate with out shuttering (H) Ration 1:3:6	1242.50		%Cft	
(B)	Erection / removal of centering of RCC or plain CC vertical (partal wood)	2235		%Sft	
Item No. 4	P/L 1:3:6 cement concrete solid block masonry wall 6" above and below in thickness set in 1:6 cement mortar in graded floor super structure i/c racking out joint by curing etc.	1569.75		%Cft	
Item No. 5	Cement Plaster 1:4 upto 12' hight ¾" thick.	6307		%Sft	
Item No. 6	P/F in position door, windows and ventilator of 2 x 2 ¼" Angle Iron frame and 1" ¾ thick commercial ply wood veneer shutter of deodar wood (3 ply) on both side including hole faste, cheals iron tower bolts, handle hinger and one mortice lock.	24.50		P/Sft	
Item No. 7	Making & fixing steel grated door with 1 1/6" thick shuttering i/c angle iron frame 2 x 2 x 3/8" and ¾" sq. bar 4" centre to centre.	72.50		P/Sft	
Item No. 8	Asbestos cement corrugated sheet roofing i/c necessary over laps and G.I. hook bolts nuts valleys and ridges etc.	169		% Cft	