

WORKS & SERVICE DEPARTMENT

**GOVERNMENT OF SINDH
PROVINCIAL HIGHWAY DIVISION MIRPURKHAS
TENDERS/BIDDING DOCUMENT**

Name Of Work: M&R Mirwah Kot Ghulam Muhammad Road.
Mile:- 0/0 - 0/5 (in Portion)

N.I.T No Date: NIT No TC/G-55/285, Dated: 03-03-2014

Date Of Issue:

Date Of Opening:

Tender Issued To:

D.R No. Date:

And D.R Amount Rs. 3000/-


**EXECUTIVE ENGINEER
PROVINCIAL HIGHWAY DIVISION
MIRPURKHAS**

SCHEDULE " B "

M&R MIRWAH KOT GHULAM MUHAMMAD ROAD .

MILE:.....0/0-0/5. (IN PORTION)

PART " A "

Quantity	No	Item of Work	Rate	Amount
4835 Cft	1	<u>BASE COURSE:-</u> Preparing base course i/c supplying and spreading stone metal of approved quality properly graded to maximum size of 1-1/2" in required thickness of (6" 2 layers) to proper camber and grade including supplying and spreading 15cft screening and non plastic quarry fines. Filling depressions with stone metal after initial rolling including watering and compacting the same so as to achieve 100% density as per modified AASHO specifications (Rate includes providing and using templates. Camber plates, screens.form etc. as directed) rate includes all cost of material . T&P labours and carriage upto site of work	Rs. 10159.66 Per % Cft	Rs. 491220 /=
4158 Sft	2	<u>2 COAT SURFACE DRESSING</u> Providing surface dressing Two coat on new or existing surface with 39 lbs bitumen of 80/100 penetration and 5.0 cft of crush bajri of required size of 3/4"-1/2" . including cleaning the road surface . rolling after each etc complete . Rate includes all cost of materials labours. T&P and carriage upto site .	Rs. 2073.18 Per % Sft	Rs. 86203 /=
13068 Sft	3	<u>THREE COAT SURFACE DRESSING</u> Providing surface dressing Three coat on new or existing surface with 69 lbs bitumen of 80/100 penetration and 7.75 cft of crush bajri of required size of 3/4"-3/8" . including cleaning the road surface . rolling after each etc complete . Rate includes all cost of materials labours. T&P and carriage upto site .	Rs. 3736.28 Per % Sft	Rs. 488257 /=
22000 Sft	4	<u>EARTH WORK ON BERMS:-</u> Earth work for road embankment by bulldozers including ploughing , mixing ciod breaking,dressing & compacting with optimum moisture content lead upto 100ft & left upto 5.0 ft in all type of soil except rock (if earth work is done by other then departmental agency) Sch: of Rate Vol-III Part VI item No.1(3)ii-c ,Page No.1&2	Rs. 2208.37 Per % Sft	Rs. 48584 /=
		TOTAL		Rs. 1114264 /=
4.65 Ton	5	<u>DIFFERENCE COST OF BITUMEN</u>	Rs. 3267.00 Per Ton	Rs. 15192 /=
		G-TOTAL		Rs. 1129456 /=

Note:-

01) No Premium will be allowed on item No.05

02) As a result of subsequent sanction to the estimate should there be any variation in the quantities and rates of sanctioned estimate and these provided in schedule " B" of the tender . the contractor shall abide by the rates & quantities sanctioned estimate.

CONTRACTOR


EXECUTIVE ENGINEER
PROV; HIGHWAY DIVISION
MIRPURKHAS

