

OFFICE OF THE EXECUTIVE ENGINEER (SEWERAGE)
LYARI TOWN, ZONE-II-B, KW&SB.

SUBJECT:- **MANUFACTURING & SUPPLYING RCC RING SLABS IN UC-NO. 01 TO UC-NO. 11, LYARI TOWN (SEW).**

ESTIMATE COST:- On Item Rate Basis. Issued to M/S. _____

TENDER COST:- Rs. 1000/= Pay Order NO: _____

TIME LIMIT:- _____ Days Dated:- _____

PENALTY:- 1000/= Per Day.

SUPERINTENDENT (REVENUE)

S.N.	DESCRIPTION.	QUANTITY	RATE	PER	AMOUNT
01.	Manufacturing & Supplying of 21" dia Ring Slab inside & 36" dia outside dia meter 7.5 width and 6" thick i/c 3/8" dia tor steel bars two concentric ring with 3/8" 8 Nos. cross linked bars welded and two sunk type hooks caste in 1:1-1/2:3 concrete with embedded 15 kg C.I frame in perfect position i/c transportation charges lead of 20 km per trip from casting yard to town office (A minimum of 25 slab per trip will be transported).	240 Nos.		Each	
02.	Shifting to the site and fixing of 36" dia Ring Slab in perfect position on damaged manholes i/c cutting of damage portion of manhole in proper shape and laying cement mortar of 2" thickness & disposal of debris.	240 Nos.		Each	
			TOTAL:-	RS.	


EXECUTIVE ENGINEER (SEW)
LYARI TOWN DIST. (SOUTH)

I hereby quoted Amounting to Rs. _____ (Inwards)

Signature & Stamp of the Contractor:- _____

Address. _____
