

Date: 28-03-2014

FROM :

PHONE NO. :

May. 30 2014 11:56AM P1



Attention Mr. [Name] / [Address]

Health Department  
Government of Sindh

NOTIFICATION

NO.HD (P&E) 3-6 (62) / 2014: The Government of Sindh Health Department is pleased to constitute a Committee under Rules-7 of Sindh Public Procurement Rules 2010 comprising of following Officers to carry out the Maintenance and Repair M&R work at Chandka Medical College Hospital Larkana under M&R funds for the year 2013-14.

- |    |  |          |
|----|--|----------|
| 1. | Dr. Aijaz Ahmed<br>Additional Medical Superintendent<br>Chandka Medical College Hospital Larkana | Chairman |
| 2. | Mr. Shabbir Ahmed Pathan<br>Executive Engineer<br>Buildings Department Division, Larkana         | Member   |
| 3. | Mr. Tariq Hussain Qazi<br>Additional Director (Dev)<br>Chandka Medical College Hospital Larkana  | Member   |

The committee will observe all the codal formalities as per Sindh Public Procurement Rules 2010.

SECRETARY HEALTH  
Government of Sindh

NO.HD (P&E) 3-6 (62) / 2014

Karachi, dated the 29-05-2014.

A copy is forwarded for information and necessary action to:

- o Medical Superintendent, Chandka Medical College Hospital Larkana
- o All Committee Members
- o Accountant General Sindh, / District Account Officer, Larkana
- o Additional Secretary (Dev), Health Department, Government of Sindh, Karachi
- o P.S. to Secretary, Finance & Cooperation Department, Government of Sindh, Karachi
- o PS to Secretary Health Sindh

(SHEERAZ MEMON)  
RESEARCH OFFICER

WORK (1)

ESTIMATE FOR M&R TO UROLOGY DEPARTMENT CMC HOSPITAL LARKANA  
Schedule

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
01.	Removing cement or lime plaster (SINO:52-P-13).	1495 Sft	121/00 Rs:One hundred Twenty one only.	% Sft (hundred)	1,809
02.	Applying floating coat of cement 1/32" thick (SINO:14-P-53).	1495 Sft	660/00 Rs:Six hundred Sixty only.	% Sft (hundred)	9,867
03.	Providing and laying tiles glazed x 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specific action jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4" thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles to proper profile (SINO:60-P-47).	414 Sft	30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only	% Sft (hundred)	126,310
04.	G.I expend actual 1/2" to 3/4" mesh 16 gauge fixed to chowkats without Deodar patti (SINO:65-P-66).	1495 Sft	60/43 Rs: Sixty & Ps Forty three Only.	P. Sft	90,342
05.	Cement plaster ratio (1:3) up to 12' ft height 3/4" thick (SINO:10(c)P-52).	1495 Sft	2795/30 Rs: Two thousand Seven hundred Ninety five & Ps Thirty only.	% Sft (hundred)	41,790
06.	Cement plaster ratio (1:2) up to 12' ft height 1/2" thick (SINO:9(b)P-52).	1495 Sft	2496/72 Rs: Two thousand Four hundred Ninety six & Ps Seventy two only.	% Sft (hundred)	37,325
07.	Scraping (b) Ordinary distemper, oil bound distemper or paint on walls (SINO:54-P-13).	4470 Sft	226/88 Rs: Two hundred Twenty six & Ps Eighty eight Only.	% Sft (hundred)	10,142
08.	Primary coat of chalk distemper (SINO:23-P-54)	<del>7680</del> 8940 Sft	442/75 Rs:Four hundred Forty two & Ps Seventy five only	% Sft (hundred)	<del>34,003</del> 39,582/-

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
09.	Distemping in two coats (SINO:24(b)P- 54).	<del>7680</del> <sup>8940</sup> Sft	1043/90 Rs:One thousand Forty three & Ps Ninety only.	% Sft (hundred)	<del>80,172/-</del> <sup>93325/-</sup>
10.	Painting old surface:-Painting doors and windows any type three coats (SINO:4-(c)P-68).	2918 Sft	1160/06 Rs:One thousand One hundred sixty & Ps Six only.	% Sft (hundred)	33,851
11.	Painting old Surface:-Painting guard bars, gates iron bars grating railings i/c Standard braces (etc) similar open work any type 3-coats(SINO:4(d)P-69).	244 Sft	674/60 Rs:Six hundred Seventy four & Ps Sixty only.	% Sft (hundred)	1,646
12.	Providing and fixing plaster of Paris ceiling border of 8" - 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	142 Rft	104/22 Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	<del>14,799/-</del>
13.	First class deodar wood wrought joinery work in wire guaze door and windows With 22 S.W.G Galvanized wire jointed 144 mesh per square inch iron fitting Completed Glanized wire guaze fixed with 1/2" strips on separate 3/4" deodar Wood frame (SINO:14(d)P-60).	80 Sft	190/72 Rs: One hundred ninety & Ps seventy two only.	P.Sft (single)	15,258
14.	Supplying and fixing false ceiling of plaster of paris, in panels including making frame Work of deodr wood including painting lwith soligia paint (SINO:52-P-64).	352 Sft	25293/42 Rs:Twenty five thousand Two hundred ninety three & Ps forty two only.	% Sft (hundred)	89,033

Total ~~586,346~~<sup>605,079/c</sup>

Issue to M/s: \_\_\_\_\_

Vide D.R No: \_\_\_\_\_

DATED: \_\_\_\_\_

**TENDER FOR WORK**

I/We hereby Tender for the Execution of the work specified in the under written memorandum with in the time specified in the memorandum at the tendered rates specified in the schedule 'B' (Memorandum showing item of work, work to be done) and in accordance on all respects the specification, design, drawing and instructions in written referred to in Rule-1, there of and clauses of the Annexed condition of contract agreement that when the Material for work are provided by Government such material and the rates to be paid of them shall be as provided in schedule 'B' here to:-

**MEMORANDUM**

**General Description:-** \_\_\_\_\_

**Estimated Cost:-** \_\_\_\_\_

**Earnest Money:-** \_\_\_\_\_

**6% I/Tax Conduct:-** \_\_\_\_\_

**03% S/Deposit:-** \_\_\_\_\_

**Completion Period:-** \_\_\_\_\_

Should the tender be accepted I/We hereby agree to abide by & fulfill all terms and conditions of the contract annexed here to so for as applicable and in default there of forfeit & pay to the Governor of Sindh or his successors in office the sum money mentioned in the said condition.

Call deposit No: \_\_\_\_\_ Dated: \_\_\_\_\_ Bank: \_\_\_\_\_  
is hereby forwarded representing the earnest money, the full value of which is to be absolutely forfeited to the Governor of his successor in office should I/We not deposit the full amount of Security Deposit specified in the Memorandum in accordance with clause-1(a) of the said condition other wise Rs:- \_\_\_\_\_ shall be returned by Government as account of security deposit specified in claus-1(b) of the same condition.

I/We agree to execute an agreement on B-1B-2 form in case my/our tender is accepted and I/We shall further be bound to abide by all the terms and condition provided in tender contract agreement.

ESTIMATE FOR M&R TO MEDICAL UNIT - I & III TEACHING CMC HOSPITAL LARKANA  
Schedule

13

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
01.	Removing cement or lime plaster (SINO:52-P-13).	3093 Sft	121/00 Rs:One hundred Twenty one only.	% Sft (hundred)	3,743
02.	Applying floating coat of cement 1/32" thick (SINO:14-P-53).	<sup>454</sup> 3093 Sft	660/00 Rs:Six hundred Sixty only.	% Sft (hundred)	20,414
03.	Cement plaster ratio (1:6) upto 12" ft height 1/2" thick (SINO:13(b)P-52).	3093 Sft	2206/60 Rs:Two thousand Two hundred six & Ps Sixty only.	% Sft (hundred)	68,250
04.	Cement plaster ratio 1:4 upto 12" ht 3/4" thick (SINO:11(a)P-52)	3093 Sft	3015/76 Rs:Three thousand Fifteen & Ps Seventy six Only.	% Sft (hundred)	93,254
05.	Laying floor of approved coloured galzed tiles 1/4" thick laid in white Cement and pigment on a bed of 3/4" thick cement mortar 1:2 (SINO:25-P-43).	144 Sft	27747/06 Rs:Twenty seven thousand Seven hundred forty seven & Ps six only.	% Sft (hundred)	39,956
06.	White glazed tile 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick i/c finishing (SINO:37-P-45).	105 Sft	28253/61 Rs:Twenty eight thousand Two hundred fifty three & Ps Sixty one only.	% Sft (hundred)	29,666
07.	Providing and laying 2" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels (SINO:1(c)P-42).	1400 Sft	3275/50 Rs:Three thousand Two hundred seventy five & Ps Fifty only.	% Sft (hundred)	45857
08.	White washing in two coats (SINO:26(b)P-54).	3093 Sft	425/84 Rs:Four hundred Twenty five & Ps Eight four only.	% Sft (hundred)	13,171
09.	Distemping in two coats (SINO:24(b)P- 54).	<sup>5040</sup> 4320 Sft	1043/90 Rs:One thousand Forty three & Ps Ninety only.	% Sft (hundred)	<del>45,036</del> 52613/c

15

SINO	ITEM OF WORK	QTY	RATE	UNIT	AMOUNT
------	--------------	-----	------	------	--------

10. Painting old surface:-Painting doors and windows any type two coats  
(SINO:4-(c)P-68).

484	Sft	1160/06	% Sft (hundred)	5,614
		Rs:One thousand One hundred sixty & Ps Six only.		

Total 372,538/-  
~~365,021~~

Issue to M/s: \_\_\_\_\_

Vide D.R No: \_\_\_\_\_

DATED: \_\_\_\_\_

**TENDER FOR WORK**

I/We hereby Tender for the Execution of the work specified in the under written memorandum with in the time specified in the memorandum at the tendered rates specified in the schedule 'B' (Memorandum showing item of work, work to be done) and in accordance on all respects the specification, design, drawing and instructions in written referred to in Rule-1, there of and clauses of the Annexed condition of contract agreement that when the Material for work are provided by Government such material and the rates to be paid of them shall be as provided in schedule 'B' here to:-

**MEMORANDUM**

General Description:- \_\_\_\_\_

Estimated Cost:- \_\_\_\_\_

Earnest Money:- \_\_\_\_\_

6% I/Tax Conduct:- \_\_\_\_\_

03% S/Deposit:- \_\_\_\_\_

Completion Period:- \_\_\_\_\_

Should the tender be accepted I/We hereby agree to abide by & fulfill all terms and conditions of the contract annexed here to so for as applicable and in default there of forfeit & pay to the Governor of Sindh or his successors in office the sum money mentioned in the said condition.

Call deposit No: \_\_\_\_\_ Dated: \_\_\_\_\_ Bank: \_\_\_\_\_

is hereby forwarded representing the earnest money, the full value of which is to be absolutely forfeited to the Governor of his successor in office should I/We not deposit the full amount of Security Deposit specified in the Memorandum in accordance with clause-1(a) of the said condition other wise Rs:- \_\_\_\_\_ shall be returned by Government as account of security deposit specified in claus-1(b) of the same condition.

I/We agree to execute an agreement on B-1B-2 form in case my/our tender is accepted and I/We shall further be bound to abide by all the terms and condition provided in tender contract agreement.

ESTIMATE FOR  
Schedule

M&R TO DOCTOR'S RESIDENTIAL BUNGLOW NO:11 & 10 AT MODEL COLONY CMC CIVIL TEACHING HOSPITAL LARKANA (19)

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
01.	Dismantling cement concrete Plain 1:3:6 (SINO:19(b)P-10).	169 Cft	1306/80 Rs:One thousand Three hundred six & Ps Lightly only	% Cft (hundred)	2,208
02.	Removing cement or lime plaster (SINO:52 P-13)	409 Sft	121/00 Rs.One hundred Twenty one only.	% Sft (hundred)	495
03.	Applying floating coat of cement 1/32"thick (SINO:11 P-53).	409 Sft	660/00 Rs:Six hundred Sixty only.	% Sft (hundred)	2,699
04.	Cement concrete plain including placing compacting finishing and Curing complete(including screening and washing of stone aggregate Without shuttering ratio (1:2:4) (SINO:5(D)P-16).	169 Cft	14429/25 Rs:Fourteen thousand Four hundred twenty nine & Ps twenty five only.	% Cft (hundred)	24,385
05.	Providing and laying tiles glazedx 6"x6"x1/2" on floor or wall facing in required Colour and pattern of STILE specific ation jointed in white cement and pigment Over a base of (1:2) grey cement mortar 3/4"thick i/c washing and filling of jointed With slurry of white cement and pigment in desired shape with finishing cleaning & cost of wax polish etc complete i/c cutting tiles toproper profile (SINO 60-P-47)	1467 Sft	30509/77 Rs:Thirty thousand Five hundred nine & Ps Seventy seven only	% Sft (hundred)	447,578
Total					477,365



Issue to M/s: \_\_\_\_\_

Vide D.R No: \_\_\_\_\_

DATED:

**TENDER FOR WORK**

I/We hereby Tender for the Execution of the work specified in the under written memorandum with in the time specified in the memorandum at the tendered rates specified in the schedule 'B' (Memorandum showing item of work, work to be done) and in accordance on all respects the specification, design, drawing and instructions in written referred to in Rule-1, there of and clauses of the Annexed condition of contract agreement that when the Material for work are provided by Government such material and the rates to be paid of them shall be as provided in schedule 'B' here to:-

**MEMORANDUM**

**General Description:-** \_\_\_\_\_

**Estimated Cost:-** \_\_\_\_\_

**Earnest Money:-** \_\_\_\_\_

**6% I/Tax Conduct:-** \_\_\_\_\_

**03% S/Deposit:-** \_\_\_\_\_

**Completion Period:-** \_\_\_\_\_

Should the tender be accepted I/We hereby agree to abide by & fulfill all terms and conditions of the contract annexed here to so for as applicable and in default there of forfeit & pay to the Governor of Sindh or his successors in office the sum money mentioned in the said condition.

Call deposit No: \_\_\_\_\_ Dated: \_\_\_\_\_ Bank: \_\_\_\_\_

is hereby forwarded representing the earnest money, the full value of which is to be absolutely forfeited to the Governor of his successor in office should I/We not deposit the full amount of Security Deposit specified in the Memorandum in accordance with clause-1(a) of the said condition other wise Rs:- \_\_\_\_\_ shall be returned by Government as account of security deposit specified in claus-1(b) of the same condition.

I/We agree to exccute an agreement on B-1B-2 form in case my/our tender is accepted and I/We shall further be bound to abide by all the terms and condition provided in tender contract agreement.

ESTIMATE FOR M&R TO CENTRAL LABORATORY MAIN STORE CITY BLOCK @ CMC  
 Schedule HOSPITAL LARKANA.

23

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
01.	Excavation in foundation of building bridges and other structure i/c Dag belling dressing refilling around structure with excavated earth Watering and ramming lead upto 5'ft In ordinary soil(SINO:18(b)P-4).	256	Cft 3176/25 Rs:Three thousand One thousand seventy six & Ps twenty five only.	%oCft (thousand)	813
02.	Cement concrete brick or stone ballast 1-1/2" to 2" gauge (1:5:10) (SINO::4(c)P-15).	66	Cft 8694/95 Rs:Eight thousand Six hundred Ninety four & Ps Ninety five only.	% Cft (hundred)	5,739
03.	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (SINO::4(e)P-20/31)	145	Cft 11948/36 Rs:One thousandq One hundred forty eight & Ps thirty six only.	% Cft (hundred)	17,325/- <del>24,388</del>
04.	Pacca brick work in other than building in cement sand mortar (1:6) i/c striking Joints (SINO:7(h)P-22).	935	Cft 12346/65 Rs:Twelve thousand Three hundred forty six & Ps sixty five only.	% Cft (hundred)	11544/- <del>128,659</del>
05.	Cement Pointing struck joints on walls Ratio 1:3 (SINO:19(b)P-53)	560	Sft 1213/58 Rs:One thousand Two hundred thirteen & Ps Fifty eight only.	% Sft (hundred)	6,796
06.	Rehandling of earth work upto a lead of 50ft (SINO:9(b)P-2).	1277 <del>1702</del>	Cft 1058/75 Rs:One thousand Fifty eight & Ps Seventy five only.	%oCft (thousand)	1352/- <del>1277</del>
07.	Cement plaster ratio (1:6) upto 12'ht 1/2" thick (SINO:13(b)P-52).	1360	Sft 2206/60 Rs:Two thousand Two hundred six & Ps Sixty only.	% Sft (hundred)	30010/- <del>3111</del>
08.	Cement plaster ratio 1:4 upto 12'ht 3/8" thick (SINO:11(a)P-52)	1360	Sft 2197/52 Rs:Two thousand One hundred ninety seven & Ps Fifty two only.	% Sft (hundred)	29886/- <del>3111</del>

68041P  
207362

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
09.	Supplying and fixing broden glasses on courtyard walls including 1:3:6 cement concrete copping (SINO:61-P-105)	180 Lft	70/44 Rs: Seventy & Ps Forty four only	P.Lft (single)	12 679
10.	Providing and laying single per layer of polythen sheet 0.1mm thick for water Proofing as per specification and instruction of Engineer incharge(SINO:38-P-38).	1702 Sft	10/70 Rs:Ten & Ps Seventy only	P.Sft (single)	18211/- <del>13,364</del>
11.	Mud Plaster on floor or roof 1"thick (SINO:2-P-51).	1702 Sft	555/00 Rs:Five hundred Fifty five only.	% Sft (hundred)	9446/- <del>6,932</del>
12.	Barrow Pit excavation undressed lead upto 100 ft ordinary soil and extra Lead miles (SINO:3(a)P-1).	2700 Cft	2117/50 Rs:Two thousand One hundred seventeen & Ps Fifty only.	%oCft (thousand)	5.717
13.	Supplying and filling sand under floor and plugging-in walls (SINO:29-P-26).	1350 Cft	1141/25 Rs:One thousand One hundred forty one & Ps twenty five only.	% Cft (hundred)	15.406
14.	S/Fixing Girder 4"x8" (SINO:140-P-6).	6.321 Cwt	3850/00 Rs:Three thousand Eighty hundred fifty only.	P.Cwt (single)	24.336
15.	S/Fixing T.Iron (SINO:144-P-6).	1.414 Cwt	3575/00 Rs:Three thousand Five hundred seventy five Only.	P.Cwt (single)	5.055
16.	Second clasws tile roofing consisting of 4"earth and 1"mud plaster with Gobri leeping over 1/2"thick cement plaster 1:6 with 34lbs of hot bitumen coating sand blinded, provided over one layer of 12" x 6"x2" tiles laid in 1:6 cement mortar including 1:2 cement pointing under earth of tiles complete including curing etc (SINO:2-P-33).	72 Sft	7607/25 Rs:Seven thousand Six hundred seven & Ps Twenty five only.	% Sft (hundred)	5.477
17.	Removing cement or lime plaster (SINO:52-P-13).	461 Sft	121/00 Rs:One hundred Twenty one only.	% Sft (hundred)	558

1614927  
304207

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
18.	Applying floating coat of cement 1/32" thick (SINO:14-P-53).	✓ 461 Sft	✓ 660/00 Rs: Six hundred Sixty only.	✓ % Sft (hundred)	✓ 3,043
19.	Cement plaster ratio 1:4 upto 12" ht 3/8" thick (SINO:11(a)P-52)	✓ 461 Sft	✓ 3015/76 Rs: Three thousand Fifteen & Ps Seventy six Only.	✓ % Sft (hundred)	✓ 13,903
20.	Making and fixing barbed wire fencing including R.C.C posts upto 4 horizontal & cross wires (SINO:7-P-95).	✓ 50 Lft	✓ 25283/36 Rs: Twenty five thoud Two hundred eighty three & Ps thirty six only.	✓ % Lft (hundred)	✓ 12,642
21.	Laying floor of approved coloured galzed tiles 1/4" thick laid in white Cement and pigment on a bed of 3/4" thick cement mortar 1:2 (SINO:25-P-43).	✓ 161 Sft	✓ 27747/06 Rs: Twenty seven thousand Seven hundred forty seven & Ps six only.	✓ % Sft (hundred)	✓ 44673/- <del>59,379</del>
22.	White glazed tile 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick i/c finishing (SINO:37-P-15).	✓ 462 Sft	✓ 28253/61 Rs: Twenty eight thousand Two hundred fifty three & Ps Sixty one only.	✓ % Sft (hundred)	✓ 130532/- <del>131,096</del>
23.	Providing and laying 2" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels (SINO:11(c)P-42).	✓ 1800 Sft	✓ 3275/50 Rs: Three thousand Two hundred seventy five & Ps Fifty only.	✓ % Sft (hundred)	✓ 58,959
24.	White washing in two coats (SINO:26(b)P-54).	✓ 1392 Sft	✓ 425/84 Rs: Four hundred Twenty five & Ps Eight four only.	✓ % Sft (hundred)	✓ 5,928
25.	Distempering in two coats (SINO:24(b)P-54).	✓ 5664 Sft	✓ 1043/90 Rs: One thousand Forty three & Ps Ninety only.	✓ % Sft (hundred)	✓ 59,126

623052  
493,379

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
26.	Painting old surface:-Painting doors and windows any type <sup>two</sup> <del>three</del> coats (SINO:4(c) 68)	726	✓ 1160/06 <del>1662/21</del> Rs:One thousand Six hundred Sixty two & Ps Twenty one only.	✓ % Sft (hundred)	✓ 8422/- <del>22,659</del>
27.	Colour washing in two coats over one coat of white washing (SINO:5(b)P-54).	2280	✓ Sft 859/90 Rs:Eight hundred Fifty nine & Ps Ninety only.	✓ % Sft (hundred)	✓ 19,606
Total -					681,081/-

Central Laboratory Main Stork city block

ESTIMATE FOR M&R TO  
Schedule HOSPITAL LARKANA.

@ CMC

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
------	---------------	-----	------	------	--------

**PART (B) W/S & S/FITTING**

01.	Providing, Laying uPVC Pressure pipes of Class "D" (equivalent make) fixing in trench i/c cutting, fitting and jointing with "Z" joint with one rubber Ring i/c testing with water to a head 122meter or 400 ft: 100 mm (2" dia) (SINO:3(d)P-23).	200	Rft	66/00 Rs: Sixty six only.	P.Rft (single)	13.200
02.	Supplying and fixing fibre glass tank of approved quality and design and Wall thickness as specified i/c cost of nut bolts and fixing in plate form of Cement concrete 1:3:6 and making connections for in-let outlet and over Flow inlet-outlet flow pipes etc e complete wall thickness 3.5 mm (SINO:3(b)P-18)(250 Gallon wall thickness 4.0mm)	01	No	21989/61 Rs: Twenty one thousand Nine hundred Eighty nine & Ps Sixty one only.	Each (single)	21.990
03.	Providing and fixing 18"x12" (47.72x30.49cm) lavaroty basin in white glazed Earthen ware complete with & i/c the cost of W.I or C.I cantileverbracketets 6" inches Built to wall painted white in two coats after primary coat of red lead paint a pair of 1/2" dia chrome plated piller taps 1-1/4" rubber plug & chrome plated brass chain 1-1/4" brass Waste of approved pattern 1-1/4" dia malleable iron or x p brass traps malleable iron union & making requisite number of holes in walls, plinth and floor for connections and making Good in cement concrete 1:2:4 (Foreign or superior quality ) (SINO:15-P-5).	03	Nos	5467/00 Rs: Five thousand Four hundred sixty seventy Only.	Each (single)	16.401
04.	Add extra for labour for providing and fixing of earthen ware pedestal white or Coloured glazed (standard pattern) (SINO:9-P-3).	03	Nos	938/47 Rs: Nine hundred Thirty eight & Ps Forty seven only.	Each (single)	2,815
05.	Supplying & fixing in position C.P Bib Cock(b) 1/2" dia C.P bib Cock Standard pattern (SINO:2-P-16).	20	Nos	150/92 Rs: One hundred Fifty & Ps Ninety two only.	Each (single)	3.018
					Total	57,424

OFFICE OF THE MEDICAL SUPERINTENDENT C.M.C HOSPITAL LARKANA

Issue to M/s: \_\_\_\_\_

Vide D.R No: \_\_\_\_\_

DATED:

TENDER FOR WORK

I/We hereby Tender for the Execution of the work specified in the under written memorandum with in the time specified in the memorandum at the tendered rates specified in the schedule 'B' (Memorandum showing item of work, work to be done) and in accordance on all respects the specification, design, drawing and instructions in written referred to in Rule-1, there of and clauses of the Annexed condition of contract agreement that when the Material for work are provided by Government such material and the rates to be paid of them shall be as provided in schedule 'B' here to:-

MEMORANDUM

General Description:- \_\_\_\_\_

Estimated Cost:- \_\_\_\_\_

Earnest Money:- \_\_\_\_\_

6% I/Tax Conduct:- \_\_\_\_\_

03% S/Deposit:- \_\_\_\_\_

Completion Period:- \_\_\_\_\_

Should the tender be accepted I/We hereby agree to abide by & fulfill all terms and conditions of the contract annexed here to so for as applicable and in default there of forfeit & pay to the Governor of Sindh or his successors in office the sum money mentioned in the said condition.

Call deposit No: \_\_\_\_\_ Dated: \_\_\_\_\_ Bank: \_\_\_\_\_

is hereby forwarded representing the earnest money, the full value of which is to be absolutely forfeited to the Governor of his successor in office should I/We not deposit the full amount of Security Deposit specified in the Memorandum in accordance with clause-1(a) of the said condition other wise Rs:- \_\_\_\_\_ shall be returned by Government as account of security deposit specified in claus-1(b) of the same condition.

I/We agree to execute an agreement on B-1B-2 form in case my/our tender is accepted and I/We shall further be bound to abide by all the terms and condition provided in tender contract agreement.

101015

ESTIMATE FOR M&R TO RESIDENTIAL BUNGLOW NEAR CIVIL HOSPITAL CMC HOSPITAL  
Schedule LARKANA ( OCCUPIED BY DR: MUSHTAQUE ALI ABRO )

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
<b><u>PART (A) CIVIL WORK.</u></b>						
01.	S/Fixing Girder 4"x8" (SINO:140-P-6).	26.0	Cwt	3850/00 Rs:Three thousand Eighty hundred fifty only	P.Cwt (single)	100.100
02.	Removing cement or lime plaster (SINO:52-P-13).	1262	Sft	121/00 Rs:One hundred Twenty one only.	% Sft (hundred)	1.527
03.	Applying floating coat of cement 1/32" thick (SINO:14-P-53).	1262	Sft	660/00 Rs:Six hundred Sixty only.	% Sft (hundred)	8.329
04.	Excavation in foundation of building bridges and other structure i/c Dag belling dressing refilling around structure with excavated earth Watering and ramming lead upto 5ft In ordinary soil(SINO:18(b)P-4).	214	Cft	3176/25 Rs:Three thousand One thousand seventy six & Ps twenty five only.	%oCft (thousand)	680
05.	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:4:8 (SINO:4(b)P-15).	128	Cft	9416/28 Rs:Nine thousand Four hundred sixteen & Ps Twenty eight only.	% Cft (hundred)	12 053
06.	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (SINO:4(e)P-20).	78	Cft	11948/36 Rs:One thousand One hundred forty eight & Ps thirty six only.	% Cft (hundred)	9.320
07.	Pacca brick work in ground floor in cement sand mortar (1:6) (SINO:5(e)P-21).	118	Cft	12674/36 Rs:Twelve thousand Six hundred seventy four & Ps thirty six only	% Cft (hundred)	14.956
08.	S/Fixing T Iron (SINO:144-P-6).	1.28	Cwt	3575/00 Rs:Three thousand Five hundred seventy five Only.	P.Cwt (single)	4.576
09.	Providing and fixing venation windows and ventilation of 1st class Deodar wood frame and 1st class deodar wooden louvers (SINO:50-P-64).	06	Sft	698/92 Rs:Six hundred Ninety eight & Ps Ninety two Only	P.Sft (single)	4.194



SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
10.	Second class tile roofing consisting of 4" earth and 1" mud plaster with Gobri leaping over 1/2" thick cement plaster 1:6 with 34lbs of hot bitumen coating sand blinded, provided over one layer of 12" x 6" x 2" tiles laid in 1:6 cement mortar including 1:2 cement pointing under earth of tiles complete including curing etc (SINO:2-P-33).	64	7607/25 Rs: Seven thousand Six hundred seven & Ps Twenty five only.	% Sft (hundred)	1,869
11.	Reinforced cement concrete spout including fixing in position with top & bottom khuas (SINO:27-P-19).	01	524/98 Rs: Five hundred Twenty four & Ps Ninety eight only.	Each (single)	525
12.	First class deodar wood wrought joinery in door and windows etc fixed in position including chowkats hold fasts hinges iron tower belts chocks cleats handles and cords with hooks etc deodar paneled or paneled and glazed or fully glazed 1-3/4" thick (SINO:7(b)P-58).	51	1273/76 Rs: One thousand Two hundred Seventy three & Ps seventy six only.	P.Sft (single)	64,962
13.	Dismantling cement concrete Plain 1:3:6 (SINO:19(b)P-10).	102	1306/80 Rs: One thousand Three hundred six & Ps Eighty only.	% Cft (hundred)	1,333
14.	Cement concrete plain including placing compacting finishing and Curing complete (including screening and washing of stone aggregate Without shuttering ratio (1:2:4) (SINO:5(D)P-16).	151	14429/25 Rs: Fourteen thousand Four hundred twenty nine & Ps twenty five only.	% Cft (hundred)	21,788
15.	Laying floor of approved coloured galzed tiles 1/4" thick laid in white Cement and pigment on a bed of 3/4" thick cement mortar 1:2 (SINO:25-P-43).	72	27747/06 Rs: Twenty seven thousand Seven hundred forty seven & Ps six only.	% Sft (hundred)	19,978
16.	White glazed tile 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick i/c finishing (SINO:37-P-45).	166	28253/61 Rs: Twenty eight thousand Two hundred fifty three & Ps Sixty one only.	% Sft (hundred)	16,901

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
17.	Cement plaster ratio (1:6) upto 12'ft height 1/2" thick (SINO:13(b)P-52).	1538 ✓ Sft	2206/60 Rs:Two thousand Two hundred six & Ps Sixty only	% Sft (hundred)	33.938 ✓
18.	Cement plaster ratio 1:4 upto 12'ht 3/8" thick (SINO:11(a)P-52)	1538 ✓ Sft	2197/52 ✓ Rs:Two thousand One hundred ninety seven & Ps Fifty two only.	% Sft (hundred)	33.798 ✓
19.	First class deodar wood wrought joinery work in wire guaze door and windows With 22 S.W.G Galvanized wire jointed 144 mesh per square inch iron fitting Completed Glanized wire guaze fixed with 1/2" strips on separate 3/4" deodar Wood frame (SINO:14(d)P-60).	192 ✓ Sft	190/72 ✓ Rs: One hundred ninety & Ps seventy two only.	P.Sft (single)	36.618 ✓
20.	Supplying and fixing in position iron / steel grill of 3/4"x1/4" size flat iron of approved Design including painting 3-coats etc complete (weight not to be less than 3.7 Lbs/Sq Foot of finished grill ) (SINO:26-P-93).	48 ✓ Sft	180/50 ✓ Rs:One hundred Eighty & Ps Fifty only.	P.Sft (single)	8.664 ✓
21.	Providing and fixing false ceiling of thermopile in panels of required design & size including frame work of Aluminum T-section hanged with nail wire to ceiling completed (SINO:43-P-39).	1532 ✓ Sft	91/50 ✓ Rs:Ninety one & Ps Fifty only.	P.Sft (single)	140.178 ✓
22.	Providing and fixing plaster of Paris ceiling border of 8" - 10" with of specified Design & thickness i/c fixing besides ceiling with nails / screws with jetties (SINO:44-P-39).	526 ✓ Rft	104/22 ✓ Rs:One hundred Four & Ps Twenty two only.	P.Rft (single)	54.820 ✓
23.	Rehandling of earth work upto a lead of 50ft (SINO:9(b)P-2).	1271 ✓ Cft	1058/75 ✓ Rs:One thousand Fifty eight & Ps Seventy five only.	%Cft (thousand)	1.346 ✓
24.	Providing and laying single per layer of polythen sheet 0.1mm thick for water Proofing as per specification and instruction of Engineer incharge(SINO:38-P-38).	2533 ✓ Sft	10/70 ✓ Rs:Ten & Ps Seventy only	P Sft (single)	27.100 ✓

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
25.	Earth filling over roof including watering remaining with 1" mud plaster Finished with gobri leeping 4"thick earth filling and 1" mud plaster (SINO:11(b)P-35).	2533 Sft	807/29 Rs: Eight hundred Seven & Ps Twenty nine Only.	% Sft (hundred)	20,449
26.	Scraping (b) Ordinary distemper, oil bound distemper or paint on walls (SINIO:54-P-13).	4365 Sft	226/88 Rs: Two hundred Twenty six & Ps Eighty eight Only.	% Sft (hundred)	9,903
27.	Laying white marble flooring fine dressed in the surface without winging set in lime mortar 1:2 including rubbing and polishing of the joints 3/4"thick flooring (SINO:28(a)P-43).	640 Sft	567/48 Rs:Five hundred Sixty seven & Ps Forty eight only	P.Sft (single)	363.187
28.	Providing and fixing 3/8"thick marble tiles of approved quality and colour shade size 8"x4/6"x4" dado skirting and facing removal / tucking of existing plaster surface etc over 1/2"thick base of cement mortar mortar 1:3 setting mortar base including filling the joints and washing the tiles with white cement slurry, current, finishing cleaning and polishing etc complete For new work (SINO:68(i)P-49).	100 Sft	201/07 Rs:Two hundred one & Ps Seven only.	P.Sft (single)	20.107
29.	Pacea brick work in other than building in cement sand mortar (1:6) i.e striking Joints (SINO:7(h)P-22).	90 Cft	12346/65 Rs:Twelve thousand Three hundred forty six & Ps sixty five only.	% Cft (hundred)	11,112
30.	Providing and laying 2"thick topping cement concrete (1:2:4) including surface finishing and dividing into panels (SINO:1(c)P-42).	530 Sft	3275/50 Rs:Three thousand Two hundred seventy five & Ps Fifty only.	% Sft (hundred)	17,361
31.	Distemping in two coats (SINO:24(b)P- 54).	3724 Sft	1043/90 Rs:One thousand Forty three & Ps Ninety only.	% Sft (hundred)	38,875

43

SINO	ITEM OF WORK	QTY	RATE	UNIT	AMOUNT
------	--------------	-----	------	------	--------

32. Colour washing in two coats over one coat of white washing (SINO.5(b)P.51)

4188 ✓ SF

859/90 ✓

Sq. SF ✓

36.013 ✓

Rs: Eight hundred  
Fifty nine & Ps  
Ninety only.

(hundred)

Total 1169,562/-

OFFICE OF THE MEDICAL SUPERINTENDENT C.M.C HOSPITAL LARKANA

Issue to M/s: \_\_\_\_\_

Vide D.R No: \_\_\_\_\_

DATED: \_\_\_\_\_

TENDER FOR WORK

I/We hereby Tender for the Execution of the work specified in the under written memorandum with in the time specified in the memorandum at the tendered rates specified in the schedule 'B' (Memorandum showing item of work, work to be done) and in accordance on all respects the specification, design, drawing and instructions in written referred to in Rule-1, there of and clauses of the Annexed condition of contract agreement that when the Material for work are provided by Government such material and the rates to be paid of them shall be as provided in schedule 'B' here to:-

MEMORANDUM

General Description:- \_\_\_\_\_

Estimated Cost:- \_\_\_\_\_

Earnest Money:- \_\_\_\_\_

6% I/Tax Conduct:- \_\_\_\_\_

03% S/Deposit:- \_\_\_\_\_

Completion Period:- \_\_\_\_\_

Should the tender be accepted I/We hereby agree to abide by & fulfill all terms and conditions of the contract annexed here to so for as applicable and in default there of forfeit & pay to the Governor of Sindh or his successors in office the sum money mentioned in the said condition.

Call deposit No: \_\_\_\_\_ Dated: \_\_\_\_\_ Bank: \_\_\_\_\_

is hereby forwarded representing the earnest money, the full value of which is to be absolutely forfeited to the Governor of his successor in office should I/We not deposit the full amount of Security Deposit specified in the Memorandum in accordance with clause-1(a) of the said condition other wise Rs:- \_\_\_\_\_ shall be returned by Government as account of security deposit specified in claus-1(b) of the same condition.

I/We agree to execute an agreement on B-1B-2 form in case my/our tender is accepted and I/We shall further be bound to abide by all the terms and condition provided in tender contract agreement.

Work 6

ESTIMATE FOR  
Schedule "B"

M&R old Sub-Store at CMC Hospital Lahore.  
(Electric work)

47

SINO	ITEM OF WORK NO:L.B.D	QUANTITY	
<b><u>PART (A) SCHEDULE ITEM</u></b>			
01.	Providing and laying ( MAIN or MAIN ) PVC insulated with size 2-7:029 Copper conductor in 1/2" dia PVC conduit on surface(SINO:3-P-1).	200	Mtrs
	1x200.0		
02.	Providing and laying ( MAIN or SUB MAIN ) PVC insulated with size 2-7:044 ( 6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduit on surface(SINO:5 P-1).	100	Mtrs
	1x100.0		
03.	Wiring for light or fan point with 3/029 PVC insulated wire in 20 mm ( 3/4" ) channel Patti on surface as required (SINO:129-P-15).	55	Nos
	1x55.0		
04.	Wiring for light or fan point with 3/029 PVC insulated wire in 20mm (3/4") Channel patti on surface as required (SINO:130-P-15).	99	Nos
	1x9.0		
05.	Providing and fixing one way SP 10/15 amp switch surface type (SINO:218-P-33).	55	Nos
	1x55.0		
06.	Providing and fixing two pin 5 amp plug & socket (SINO:222 P-33)	99	Nos
	1x9.0		
07.	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227 P-33).	06	Nos
	1x6.0		
08.	Providing and fixing brass ceiling fan 56" (good quality) (SINO:235-P-34).	08	Nos
	1x8.0		

ESTIMATE FOR  
Schedule "B"

49

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
	PART (B) NON-SCHEDULE ITEM				
01.	P/F Energy sever superior quality including fixing on existing holder etc complete				
		35	Nos	497/00	Each
					17,395
				Total	17,395

GENERAL ABSTRACT

01.	PART (A) SCHEDULE ITEM	Rs: 121,132
02.	PART (B) NON-SCHEDULE ITEM	Rs: 17,395
	Total	Rs: 138,527

OFFICE OF THE MEDICAL SUPERINTENDENT C.M.C HOSPITAL LARKANA

Issue to M/s: \_\_\_\_\_

Vide D.R No: \_\_\_\_\_

DATED: \_\_\_\_\_

**TENDER FOR WORK**

I/We hereby Tender for the Execution of the work specified in the under written memorandum with in the time specified in the memorandum at the tendered rates specified in the schedule 'B' (Memorandum showing item of work, work to be done) and in accordance on all respects the specification, design, drawing and instructions in written referred to in Rule-1, there of and clauses of the Annexed condition of contract agreement that when the Material for work are provided by Government such material and the rates to be paid of them shall be as provided in schedule 'B' here to:-

**MEMORANDUM**

General Description:- \_\_\_\_\_

Estimated Cost:- \_\_\_\_\_

Earnest Money:- \_\_\_\_\_

6% I/Tax Conduct:- \_\_\_\_\_

03% S/Deposit:- \_\_\_\_\_

Completion Period:- \_\_\_\_\_

Should the tender be accepted I/We hereby agree to abide by & fulfill all terms and conditions of the contract annexed here to so for as applicable and in default there of forfeit & pay to the Governor of Sindh or his successors in office the sum money mentioned in the said condition.

Call deposit No: \_\_\_\_\_ Dated: \_\_\_\_\_ Bank: \_\_\_\_\_  
is hereby forwarded representing the earnest money, the full value of which is to be absolutely forfeited to the Governor of his successor in office should I/We not deposit the full amount of Security Deposit specified in the Memorandum in accordance with clause-1(a) of the said condition other wise Rs:- \_\_\_\_\_ shall be returned by Government as account of security deposit specified in claus-1(b) of the same condition.

I/We agree to execute an agreement on B-IB-2 form in case my/our tender is accepted and I/We shall further be bound to abide by all the terms and condition provided in tender contract agreement.



ESTIMATE FOR  
Schedule "B"

M & R to Various wards at CMC Hospital City (53)  
Block ~~Langamp~~. (Electrical work)

SINO	ITEM OF WORK NO:L.B.D	QUANTITY
<b><u>PART (A) SCHEDULE ITEM</u></b>		
01.	Providing and laying ( MAIN or MAIN ) PVC insulated with size 2-7/0.29 Copper conductor in 1/2" dia PVC conduit on surface(SINO:3-P-1).	200 Mtrs
	1x200.0	
02.	Providing and laying ( MAIN or SUB MAIN ) PVC insulated with size 2-7/0.44 ( 6mm <sup>2</sup> ) copper conductor in 1" dia PVC conduit on surface(SINO:5-P-1).	100 Mtrs
	1x100.0	
03.	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20 mm (3/4") channel Patti on surface as required (SINO:129-P-15).	52 Nos
	1x55.0	
04.	Wiring for light or fan point with 3/0.29 PVC insulated wire in 20mm (3/4") Channel patti on surface as required (SINO:130-P-15).	09 Nos
	1x9.0	
05.	Providing and fixing one way SP 10/15 amp switch surface type (SINO:218-P-33).	55 Nos
	1x55.0	
06.	Providing and fixing two pin 5 amp plug & socket (SINO:222-P-33).	09 Nos
	1x9.0	
07.	Providing and fixing Three Pin 10/15 amps plug and socket flush type (SINO:227-P-33)	06 Nos
	1x6.0	
08.	Providing and fixing brass ceiling fan 56" (good quality) (SINO:235-P-34).	10 Nos
	1x10.0	

ESTIMATE FOR  
Schedule "B"

55

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT	
PART (B) NON-SCHEDULE ITEM						
01.	P/F Energy sever superior quality including fixing on existing holder etc complete	15	Nos	497/00	Each	22,365
					Total	22,365

GENERAL ABSTRACT

01.	PART (A) SCHEDULE ITEM	Rs: 142,344
02.	PART (B) NON-SCHEDULE ITEM	Rs: 22,365
Total		Rs: 164,709

OFFICE OF THE MEDICAL SUPERINTENDENT C.M.C HOSPITAL LARKANA

Issue to M/s: \_\_\_\_\_

Vide D.R No: \_\_\_\_\_

DATED: \_\_\_\_\_

**TENDER FOR WORK**

I/We hereby Tender for the Execution of the work specified in the under written memorandum with in the time specified in the memorandum at the tendered rates specified in the schedule 'B' (Memorandum showing item of work, work to be done) and in accordance on all respects the specification, design, drawing and instructions in written referred to in Rule-1, there of and clauses of the Annexed condition of contract agreement that when the Material for work are provided by Government such material and the rates to be paid of them shall be as provided in schedule 'B' here to:-

**MEMORANDUM**

General Description:- \_\_\_\_\_

Estimated Cost:- \_\_\_\_\_

Earnest Money:- \_\_\_\_\_

6% I/Tax Conduct:- \_\_\_\_\_

03% S/Deposit:- \_\_\_\_\_

Completion Period:- \_\_\_\_\_

Should the tender be accepted I/We hereby agree to abide by & fulfill all terms and conditions of the contract annexed here to so for as applicable and in default there of forfeit & pay to the Governor of Sindh or his successors in office the sum money mentioned in the said condition.

Call deposit No: \_\_\_\_\_ Dated: \_\_\_\_\_ Bank: \_\_\_\_\_

is hereby forwarded representing the earnest money, the full value of which is to be absolutely forfeited to the Governor of his successor in office should I/We not deposit the full amount of Security Deposit specified in the Memorandum in accordance with clause-1(a) of the said condition other wise Rs:- \_\_\_\_\_ shall be returned by Government as account of security deposit specified in claus-1(b) of the same condition.

I/We agree to execute an agreement on B-1B-2 form in case my/our tender is accepted and I/We shall further be bound to abide by all the terms and condition provided in tender contract agreement.

8

ESTIMATE FOR M&R TO C.C BLOCK FOR GENERATOR PAEDS MEDICINE @ CMC HOSPITAL LARKANA.

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
------	---------------	-----	------	------	--------

PART (A) CIVIL WORK

01.	Excavation in foundation of building bridges and other structure i/c Dag belling dressing refilling around structure with excavated earth Watering and ramming lead upto 5'ft In ordinary soil(SINO:18(b)P-4).	282	Cft	3176/25 Rs:Three thousand One thousand seventy six & Ps twenty five only.	%oCft (thousand)	896
02.	Cement concrete brick or stone ballast 1-1/2" to 2" gauge (1:3:6) (SINO:4(a)P-15).	71	Cft	10770/93 Rs:Ten thousand Seven hundred seventy & Ps: Ninety three only.	% Cft (hundred)	7.647
03.	Pacca brick work in foundation and plinth in cement sand mortar 1:6 (SINO:4(e)P-20).	106	Cft	11948/36 Rs:One thousand One hundred forty eight & Ps thirty six only.	% Cft (hundred)	12.665
04.	Pacca brick work in other than building in cement sand mortar (1:6) i/c striking joints (SINO:7(b)P-22).	106	Cft	12346/65 Rs:Twelve thousand Three hundred forty six & Ps sixty five only.	% Cft (hundred)	13.087
05.	Cement plaster ratio 1:4 upto 12'ht 3/8"thick (SINO:11(a)P-52)	176	Sft	3015/76 Rs:Three thousand Fifteen & Ps Seventy six Only.	% Sft (hundred)	5.308
06.	Filling watering and ramming earth under floor with new earth excavated from Outside lead up to one chain and lift up to 5'ft (SINO:22-P-4).	1969	Cft	3630/00 Rs:Three thousand Six hundred thirty only	%oCft (thousand)	7.147
07.	Cement concrete brick or stone ballast 1 1/2" to 2" gauge 1:6:12 (SINO:4(d)P-11).	263	Cft	8122/95 Rs:Eight thousand One hundred twenty two & Ps ninety five only.	% Cft (hundred)	11.36

(61)

SINO	ITEM OF WORK.	QTY	RATE	UNIT	AMOUNT
08.	Providing and laying 3" thick topping cement concrete (1:2:4) including surface finishing and dividing into panels (SINO:1(b)P-42)	540	4411/82 Rs: Four thousand Four hundred eleven & Ps eighty two only.	Sft Sq. Sft (hundred)	23,821
09.	Making and fixing grating in opening including fixing at site with Flat iron 2"x 3/8" and 3/4" sq; bars at 4" centre to centre (SINO:25-P-92).	165	293/15 Rs: Two hundred Ninety three & Ps Fifteen only.	P.Sft (single)	48,370
				Total	140,307

Issue to M/s: \_\_\_\_\_

Vide D.R No: \_\_\_\_\_

DATED: \_\_\_\_\_

**TENDER FOR WORK**

I/We hereby Tender for the Execution of the work specified in the under written memorandum with in the time specified in the memorandum at the tendered rates specified in the schedule 'B' (Memorandum showing item of work, work to be done) and in accordance on all respects the specification, design, drawing and instructions in written referred to in Rule-1, there of and clauses of the Annexed condition of contract agreement that when the Material for work are provided by Government such material and the rates to be paid of them shall be as provided in schedule 'B' here to:-

**MEMORANDUM**

General Description:- \_\_\_\_\_  
Estimated Cost:- \_\_\_\_\_  
Earnest Money:- \_\_\_\_\_  
6% I/Tax Conduct:- \_\_\_\_\_  
03% S/Deposit:- \_\_\_\_\_  
Completion Period:- \_\_\_\_\_

Should the tender be accepted I/We hereby agree to abide by & fulfill all terms and conditions of the contract annexed here to so for as applicable and in default there of forfeit & pay to the Governor of Sindh or his successors in office the sum money mentioned in the said condition.

Call deposit No: \_\_\_\_\_ Dated: \_\_\_\_\_ Bank: \_\_\_\_\_

is hereby forwarded representing the earnest money, the full value of which is to be absolutely forfeited to the Governor of his successor in office should I/We not deposit the full amount of Security Deposit specified in the Memorandum in accordance with clause-1(a) of the said condition other wise Rs:- \_\_\_\_\_ shall be returned by Government as account of security deposit specified in claus-1(b) of the same condition.

I/We agree to execute an agreement on B-1B-2 form in case my/our tender is accepted and I/We shall further be bound to abide by all the terms and condition provided in tender contract agreement.