


**KARACHI METROPOLITAN CORPORATION**  
**PARKS AND HORTICULTURE DEPARTMENT.**



**STANDARD BIDDING DOCUMENTS**

**(Smaller Work – Rs.2.50 Million Above/Below )**

**(As per PEC & SPPRA Guidelines / Directives)**

**FOR.**

**NAME OF WORK: IMPROVEMENT OF BOUNDARY WALL, GATES, PONDS AND  
PHYSICAL APPLIANCES AT BEACH PARK CLIFTON KMC**

**Tender Reference Sr. No.: DG/P&H/KMC/ 1 /2013-2014**

**In Compliance of PEC & SPPRA Rules 2010**

Estimate Cost: -	Rs.12.825 Million
Bid Security	Rs.2,56,500/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: IMPROVEMENT OF BOUNDARY WALL, GATES, PONDS AND  
PHYSICAL APPLIANCES AT BEACH PARK CLIFTON KMC**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
1	Providing and fixing yellow stone benches in hard stone without seat back as per approved design and shape with two footed fixing in position including the cost of all kinds of loading and unloading and lifting including the cost of chemical polishing etc complete size 6'-0" x 2'-0" x 1'-4" thick slab both side rounded and foots size 2 nos, 1'-6" dia, 1'-3" height etc as per approved by the Officer incharge etc complete.	112 Nos	O/r 16000	Each	1792000
2	S/S and spreading of Yellow murrum from Nooriabad super highway as per approved quality by the officer incharge etc complete	5000 Cft	O/r 40.00	Cft	200000
3	Supplying , stacking and spreading of sweet earth approved garden soil from out side sources including all leads and lifts including cost of spreading in required slopes etc complete	50000 Cft	O/r 32.00	Cft	1600000
4	Supplying , stacking and spreading of well decayed cowdung manure including all leads and lifts from approved out side sources including cost of spreading etc complete	50000 Cft	O/r 30.00	Cft	1500000
5	P/F fiber glass dinasour as per approve quality et complete .	01 Job	O/r 600000	Job	600000
6	Cartage of sand bajri lime and all kinds of soil including all loading and unloading etc complete	50000 Cft	O/r 8.00	Cft	400000
7	Providing and fixing Yellow stone jacket ng with two jacketing including the cost of cutting jointing fixing with cement sand mortar Envicrte or equivalent as per direction by the Engineer incharge etc complete	2476.8 Rft	1000 o/r	Rft	2476800
8	P/F 1' thick envicrate tiles including the cost of jointing fixing etc complete in size 15 1/2" x 7 1/2" x 1" etc complete as per direction by the Engineer incharge etc complete.	214 Sft	O/r 150	Sft	32100
9	Dismantling of stone pillars as per direction by the Engineer incharge etc complete	480 Nos	O/r 90.00	Ech	43200

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
10	P/F stone moulded pillar as per approved design by the officer incharge etc with including the cost of ½" dia milled steel bar and making bole ¾" dia size as under :  a) 5 X 5" x 30" size  b) 6" x 6" x 20"	100 Nos  300 Nos	O/r  1550  1100	Each	155000  330000
11	P/F hollow block masonry encicrate made including the cost of jointing fixing etc complete with cement concrete etc complete	500 Cft	O/r 380	Cft	190000
12	Cutting of hollow block with grinder as per direction by the officer incharge etc complete	1000 Nos	O/r 80.00	Each	80000
13	P/F RCC guarder pre cast 9" x 4" x 11'-0" as per approve by the officer incharge etc complete	300 Rft	O/r 175	Rft	52500
14	Repainting on gate with deco paint with spray machine in any shade and any height in size 20' x 10' feet including scraping filling of old paint size as under :  a) 20' x 10' feet 4 Nos	05 Nos	O/r 70000	Each	350000
15	P/F yellow hard stone tiles in size 2' x 5' x 3" as per direction and approved by the Engineer incharge etc complete.	20 Sft	O/r 250	Sft	5000
16	P/F Mild steel guarder 6" x 3" x ¼" size including the cost of jointing with welding etc complete	100 Kgs	O/r 195	Kg	19500
<b>Total amount (approximately)</b>		<b>Rs.1,28,25,780/- (12.825 Million)</b>			
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(Civil) Rs..... % Above/Below/at par the O/R		Rs.		
B	(Item based of O/R Civil works)Rs..... % Above/Below/at par the O/R		Rs.		
<b>Grand Total amount ( A+B )</b>			Rs.		

Contd.....

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit 180 Days

Penalty per day Rs.1000/-

Typed estimate compared with a checked

Estimate & found correct.

Signature of Contractor \_\_\_\_\_

Address \_\_\_\_\_

\_\_\_\_\_  
(with rubber stamp)


Deputy Director (South)  
(P&H), KMC.

A.E.E. (Civil) P&H,  
(P&H), KMC

Executive Engineer (Civil)  
(P&H) KMC.

Tahid Jamil Durrani  
Director General  
(P&H), K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK: IMPROVEMENT OF JEHangir KOTHARI PRADe AND REPAIRING  
OF BOUNDARY WALL AT BAGH-E-IBNE QASIM CLIFTON KMC**

Tender Reference Sr. No.: DG/P&H/KMC/ 2 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.5.00 Million
Bid Security	Rs.1,00,000 (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: IMPROVEMENT OF JEHANGIR KOTHARI PRADE AND REPAIRING  
OF BOUNDARY WALL AT BAGH-E-IBNE QASIM CLIFTON KMC**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling cement concrete work in any description including the cost of disposal of rubbish upto one chain etc complete	510 Cft	3327.50	%Cft	Rs.16970/-
2	a) Providing and fixing marble tiles 144 sq. inch to 288 sq. inch 1" thick with all side chanfard dado and skirting over a base of ½" thick cement sand mortar 1:3 i/c the jointing and grouting etc complete including the cost of scaffolding for 10' to 12' feet height etc complete.	1500 Sft	O/r 350	Sft	Rs.525000/-
	b) Providing and fixing marble tiles 144 sq. inch to 288 sq. inch ¾" inch thick with all side chanfard dado and skirting over a base of ½" thick cement sand mortar 1:3 including the jointing and grouting etc complete including the cost of scaffolding for 10' to 12' feet height etc complete	1500 Sft	300	Sft	Rs.450000/-
3	P/F stone moulded pillars in size 6" x 6" x 20" as per approved design including the cost of jointing fixing with cement sand mortar etc complete Including using milled steel bars 3/8"	200 Nos	O/r 1100	Each	Rs.220000
4	P/F stone moulded pillars in size 5" x 5" x 30" as per approved design including the cost of jointing fixing with cement sand mortar etc complete	200 Nos	O/r 1550	Each	Rs.310000/-
5	P/F Milled steel square bars grill with flate iron section as per approved design including the cost of welding jointing fixing etc complete	04 Cwt	4928.49 S.R.	Cwt	Rs.19714/-
6	P/F stainless steel screw 2" long 3/16" dia 1 ½" long as per approved design etc complete.	3000 Nos	O/r 40.00	Each	Rs.120000/-
7	Painting on iron work with ready mixed paint at any height in any floor two coats etc complete	36 Cft	896.39 S.R.	%Cft	Rs.323/-
8	P/L Envicrate or its equivalent jacketing with two(2) jacket including the cost of cutting jointing fixing with cement sand mortar etc complete	200 Rft	900 O/r	Rft	Rs.180000/-
9	Supplying, stacking and spreading of sweet earth approved garden soil including the all leads and lifts from approved outside sources in required slopes as per direction by the officer incharge etc complete	10000 Cft	O/r 32.00	Cft	Rs.320000/-

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
10	Supplying and stacking well decayed cowdung manure from approved out side sources including the all leads and lifts including the cost of spreading in uniform thick fine for grassing etc complete	9714 Cft	O/r 30.00	Cft	Rs.291420/-
11	P/F pre cast yellow colour pigment jacketing two nos 12" x 9" x 2" both side tapered including the cost of jointing fixing etc complete as per direction by the Engineer incharge etc complete.	500 Rft	O/r 1000	Rft	Rs.500000/-
12	P/F hallow block masonry colour pigment as per direction by the Engineer incharge etc complete.	2000 Cft	O/r 380	Cft	Rs.760000/-
13	Cutting of hallow block as per direction by the Engineer incharge etc complete.	300 Nos	O/r 80.00	Each	Rs.24000/-
14	Repainting on gate with deco paint with spray machine in any shade and any height in size 20' x 10' feet including scraping filling of old paint including the cost of hardener size as under :  b) 20' x 10' feet  c) 29' x 10' feet	04 Nos  04 Nos	O/r  70000  100000	Each Each	Rs.280000/-  Rs.400000/-
15	Supply of cronocarpus trees in size 4' to 6' feet height as per approve dby the officer incharge	3600 Nos	O/r 150	Each	Rs.540000/-
16	P/F RCC guarder size 9" x 4" x 11"-0" pre cast at as per direction and approved by the Engineer inc ahre etc complete.	110 Rft	O/r 200	Rft	Rs.22000/-
17	P/F yellow hard stone tiles in size 2' x 5' x 3" as per direction and approved by the Engineer inc ahre etc complete.	20 Sft	O/r 300	Sft	Rs.4000/-

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
17	P/F 1' thick envicrate tiles including the cost of jointing fixing etc complete in size 15 1/2" x 7 1/2" x 1" etc complete as per direction by the Engineer inc ahre etc complete.	160 Sft	O/r 150	Sft	Rs.24000/-
<b>Total amount (approximately)</b>		<b>Rs.50,00,029/-(5.00 Million)</b>			
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(Civil) Rs.29606/- _____ % Above/Below/at par the O/R	Rs.			
B	(Item based of O/R Civil works)Rs.4970420/- _____ % Above/Below/at par the O/R	Rs.			
<b>Grand Total amount ( A+B )</b>		Rs.			

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)


For the complete job for all schedule of rates/approved rates/offer rates


I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_


Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)


Time limit 120 Days  
Penalty per day Rs.1000/-  
Typed estimate compared with a checked  
Estimate & found correct.

Signature of Contractor \_\_\_\_\_  
Address \_\_\_\_\_  
(with rubber stamp)

  
Deputy Director (South)  
(P&H),KMC.


  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer (Civil)  
(P&H)KMC.

  
Tahir Jamil Purrani  
Director General  
(P&H),K.M.C.



**KARACHI METROPOLITAN CORPORATION**  
**PARKS AND HORTICULTURE DEPARTMENT.**



**STANDARD BIDDING DOCUMENTS**

**(Smaller Work – Rs.2.50 Million Above/Below )**

**(As per PEC & SPPRA Guidelines / Directives)**

**FOR.**

**NAME OF WORK: IMPROVEMENT OF LIGHTING ARRANGEMENT & IRRIGATION SYSTEM  
AT BAGH-E-IBNE QASIM CLIFTON (P&H)KMC.**

**Tender Reference Sr. No.: DG/P&H/KMC/ 3 /2013-2014**

**In Compliance of PEC & SPPRA Rules 2010**

Estimate Cost: -	Rs.15.00 Million
Bid Security	Rs.300000/-- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: IMPROVEMENT OF LIGHTING ARRANGEMENT & IRRIGATION SYSTEM  
AT BAGH-E-IBNE QASIM CLIFTON (P&H)KMC.**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
	Schedule rates items				
1.	P/F of flood light aluminum dia cast body IP-65 factory fitted wiring with following components :  a) HPIT 400 Watts. b) Ballast for HPIT 400 Watts c) Igniter for HPIT d) Capacitor for HPIT make Philips or Equivalent. Etc	100 Jobs	16980	Job	1698000
2	P/L 35 MM 4 core PVC insulated pvc sheeted as required Pak or Equivalent etc complete	2500 Meters	2529	Mtr	6322500
3	P/L 16 MM 4 core PVC insulated pvc sheeted as required Pak or Equivalent etc complete	1130 Mtrs	1300	Mtr	1469000
4	P/F 400 watts HPIT lamp at the height of 50' feet with the help of hydraulic crane and manual labour as per site required and instruction by the Engineer incharge etc complete	400 Jobs	2380	Job	952000
5	P/F chock etc.	300 Jobs	4375	Job	1312500
6	P/L main or sub main pvc insulated and pvc sheeted 2/7/029 (2.5 mm) etc complete	1500 Meters	118	Mtr	177000
		Total S.R.			Rs.11931000/-
7	P/F motor suitable for non clogging vertical pump set 20 HP siemens electric motor 2800 RPM 440 volts 3 phase complete with all necessary accessories with the help of hydraulic crane and manual labour as required Siemens / equivalent etc complete	04 Jobs	280000	Job	1120000
8	P/F wall mounted panel board size 3' x 2 2/1' x 8" with locking arrangement of the following components :  a) 1-60 AMP TP MCCB Terasaki b) 3 magnetic contractor for 20 HP Siemens electric motor c) 1-EVR best quality d) 1-ECOR best quality e) 1-bush bar1-netural bar f) 3-phase indication lamps g) 2-push butons h) 1-volts meter i) 1-amper meter	06 jobs	50000	Job	300000

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
9	Making excavation for trenches in hard or soft soil after laying cable refilling the excavated material complete as required	65000 Cft	7.00	Rft	455000
10	Painting of 50' feet long octagonal shape and canopy with the help of loader and manual labour including the cost of chipping and scrapping cost of red oxide and two coats of best quality enameled paint complete in all respect as per instruction by the E/I etc complete	31 Jobs	8000	Job	248000
11	P/M/F panel board 3' x 3' x 8" with locking arrangement consisting of the following components :  a) 1-200 AMP TP MCCB Terasaki b) 60 amp tp mccb Terasaki c) 1-bush bar d) 1-neutral bar e) 3-phase indication lamps	07 Jobs	33400	Job	233800
12	Dismantling and repairing of non clogging vertical water pump set KSB size 8' x 6" from pump stole with the help of hydraulic crane 5 tons first of all dismantling the motor 20 HP from vertical pump with the help of hydraulic crane and then dismantling the vertical pump KSB including the cost of making bushes and shaft and required size SKF/NTN and after the repairing the vertical pump refixing the pump set on stole in pit and 20 HP motor on vertical pump with the help of hydraulic crane and manual labour cartage from the site to workshop and back within 30 KM limit etc complete in all respect	06 Jobs	110000	Job	660000
13	P/F connection clamp 125 mm x 38 mm  best quality in GI etc	30 Jobs	350	Each	10500
14	P/F connection clamps 160 mm x 38 mm  GI etc	30 Jobs	400	Job	12000
15	P/F upvc pipe best quality 1 1/2" dia 3' long  one side threaded etc	60 Jobs	132	Job	7920
16	p/f upv BEND 1 1/2" DIA best quality	60 Jobs	80	Job	4800
17	P/F UPVC solution etc	04 Kgs	800	Kg	3200

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
18	P/F making situ around water hydrant 1' x 1' x 2" with ratio 1:2:4 including the cost of roding and curing etc complete	41 Jobs	280	Job	11480
Total amount schedule rates items Total open rates			Rs.11931000/- Rs.3066700/-		
<b>GRAND TOTAL AMOUNT (APPROXIMATELY)</b>			<b>Rs.1,49,97,700/- say (15.00 Million)</b>		
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(M&E) Rs.11931000/- _____ % Above/Below/at par the O/R		Rs.		
B	(Item based of O/R M&E works)Rs.3066700/ _____ % Above/Below/at par the O/R		Rs.		
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)


For the complete job for all schedule of rates/approved rates/offer rates


I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_


Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit \_\_\_\_\_ Days  
Penalty per day Rs.1000/-  
Typed estimate compared with a checked  
Estimate & found correct.


Signature of Contractor \_\_\_\_\_  
Address \_\_\_\_\_  
(with rubber stamp)

  
Asstt. Executive Engineer(M&E)  
(P&H),K.M.C.

  
Executive Engineer(M&E)  
(P&H)K.M.C.

  
Tahir Jan Lurrani  
Director General  
(P&H),K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below)

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK: IMPROVEMENT OF TILES PATHWAYS AT SEA SIDE  
BEACH PARK CLIFTON KMC**

Tender Reference Sr. No.: DG/P&H/KMC/ 4 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.10.47 Million
Bid Security	Rs.2,09,400/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: IMPROVEMENT OF TILES PATHWAYS AT SEA SIDE  
BEACH PARK CLIFTON KMC**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
1	Dismantling cement concrete works in any description including the cost of disposal of rubbish upto one chain etc complete	4950 Cft	3327.50	%Cft	164711
2	P/L 1:2;4 cement concrete cast in situ including the cost of form works its removal compacting curing etc complete	3200 Cft	3275.50	%Cft	104816
3	P/L National tiles as under  a) F/L floor of ¼" thick coloured glazed tiles in size 5 ¼" x 10 ½" National tiles as per approved in floor AND Dado & skirting laid over 1" thick cement sand mortar base 1:2 including the cost of jointing fixing and washing the tiles with white cement slurry of matching colour and curing etc complete.	37000 Sft	30509.77	Sft	11288615
4	P/L 1:4:8 cement concrete foundation basement trenches including the cost of compacting curing etc complete	489.33 cft	11288.75	%Cft	55239
5	P/f encrate pre cast kerb stone plain grey as per approved the quality in size 4" x 6" x 12" x 18" / 2 including the cost of excavation of base of cement concrete upto 2" thick etc complete	505 Rft	297.01	Rft	149990
6	Cartage of sand bajri lime and all kinds of soil including the cost of loading and unloading etc complete	75000 Cft	881.91	%Cft	661432

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
7	Supply of seasonal plants as per approved quality and approved by the officer incharge etc complete (with 12" pots)	7662 Nos	O/r 70.00	Each	536340
Total amount (approximately)		Rs.1,04,76,182/- (10.47 Million)			
I/V/e hereby quoted as following :-					
A	(Item based of schedule rates works )(Civil) Rs.9939842/- _____ % Above/Below/at par the O/R	Rs.			
B	(Item based of O/R Civil works)Rs.536340/- _____ % Above/Below/at par the O/R	Rs.			
Grand Total amount ( A+B )		Rs.			

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates


I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)


Time limit 120 Days  
Penalty per day Rs.1000/-  
Typed estimate compared with a checked  
Estimate & found correct.

Signature of Contractor \_\_\_\_\_  
Address \_\_\_\_\_  
\_\_\_\_\_  
(with rubber stamp)


  
Deputy Director (South)  
(P&H),KMC

  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer (Civil)  
(P&H)KMC.

  
Tahir Jamil Durrani  
Director General  
(P&H),K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK: INSTALLATION OF FOUNTAIN AT GULSHAN-E-JINNAH  
(POLOGROUND) KMC.**

Tender Reference Sr. No.: DG/P&H/KMC/ 5 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.50.00 Million
Bid Security	Rs.10,00,000/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014



**NAME OF WORK: INSTALLATION OF FOUNTAIN AT GULSHAN-E-JINNAH (POLOGROUND)  
K.M.C.**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
1	Providing and fixing of sand stone work for Monumental fountain as per attached detail drawing design and as per direction by the Engineer incharge and as per approved by the Director General (P&H Department, KMC.	Complete Job	17165810	Job	17165810
2	Supply and Installation of electrical works/ accessories as per attached detail drawing and design as per direction by the Engineer incharge and as per approved by the Director General (P&H) Department, KMC	Complete Job	5227685	Job	5227685
3	Supply and installation of plumbing works/ accessories as per attached detail drawing and design as per direction by the Engineer incharge and as per approved by the Director General (P&H) Department, KMC	Complete Job	4642560	Job	4642560
4	Construction of all civil works as per attached detail drawing and design as per direction by the Engineer incharge and as per approved by the Director General (P&H) Department, KMC	Complete Job	16025250	Job	16025250
5	P/F glazed tiles floor dado and skirting as per attached detail drawing and design as per direction by the Engineer incharge and as per approved by the Director General (P&H) Department, KMC	Complete job	6750000	Job	6750000
Total amount		Rs.4,98,11,805/-			
Add 2% contingencies		Rs.996226/-			
Grand total amount (approx.)		Rs.5,08,07,531/- Say 50.00 Million			


I/We hereby quoted as following :-	
(Item based of schedule rates works )(Civil/Elect./Plumbing works ) Rs.50.00 Million _____ % Above/Below/at par the O/R	Rs.


Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)


For the complete job for all schedule of rates/approved rates/offer rates  
I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_  
Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)


Time limit \_\_\_\_\_ Days  
Penalty per day Rs.1000/-  
Typed estimate compared with a checked  
Estimate & found correct.

Signature of Contractor \_\_\_\_\_  
Address \_\_\_\_\_  
\_\_\_\_\_  
(with rubber stamp)


  
Deputy Director-II  
(P&H),K.M.C.

  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer(Civil)  
(P&H)KMC.

  
Tahir Jamil Durrani  
Director General  
(P&H),K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK: PROVIDING & FIXING GRILL FENCING AT GOVERNOR HOUSE  
AWAN-E-SADDAR ROAD KARACHI**

Tender Reference Sr. No.: DG/P&H/KMC/ 6 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.19.99 Million
Bid Security	Rs.3,99,800/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: PROVIDING & FIXING GRILL FENCING AT GOVERNOR HOUSE  
AWAN-E-SADDAR ROAD KARACHI**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
1.	Dismantling cement concrete work in any description including the cost of disposal of rubbish upto one chain etc complete	4725 Cft	3327.50	%Cft	Rs.157224/-
2	Excavation for foundation basement trenches in all kinds of soil excluding the cost of back filling etc complete	11025 Cft	2722.50	%0Cft	Rs.300155/-
3	Providing and laying 1:4:8 cement concrete foundation basement trenches including compacting curing etc complete	2700Cft	9416.28	%Cft	Rs.254240/-
4	Providing and laying 1:2:4 cement concrete cast in situ including the cost of form works its removal compacting curing etc complete	5400 Cft	14429.25	%Cft	Rs.779180/-
5	Providing and laying R.C.C. 1:2:4 work including all labour and material. This rate also all kinds of form moulds lifting shutter ng curing rendering and finishing exposed surface etc complete.	8100 Cft	337.00	Cft	Rs.2729700
6	P/L M S. Reinforcements Bar including the cost of cutting bending binding and binding wire etc complete	289 Cwt	5001.70	Cwt	Rs.1445491/-
7	P/F iron grill fencing with flate iron section and squire bars including the cot of jointing fixing and welding with required section etc complete	15960 Kgs	250.00	Kg	Rs.3990000/-
8	½" inch thick cement plaster with 1:4 cement sand mortar including the cost of making edge corner etc complete.	3600 Sft	2283.93	%Sft	Rs.82221/-
9	Providing and fixing yellow stone benches in hard stone without seat back as per approved design and shape with two footed fixing in position including the cost of all kinds of loading and unloading and lifting including the cost of chemical polishing etc complete size 6'-0" x 2'-0" x 0'-4" thick slab both side rounded and foots size 2 nos, 1'-6" dia, 1-3" height etc as per approved by the Officer incahrge etc complete.	12600 Sft	240.00	Sft	Rs.3024000/-
10	Base plate size 21" x 21" x 2"	120 Nos	3700	Each	444000

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
11	Round ball 13" x 16"	120 Nos	4650	Each	Rs.558000
12	Providing and fixing silver casting pieces as under :				
	a) Jali fencing 24" x 5"	3360 Rft	1000	Rft	3360000
	b) Big arrow	240 Nos	1500	Each	360000
	c) Small arrow	360 Nos	1200	Each	432000
	d) P/F shield plate	623 Nos	5000	Each	3115000
13	Painting on iron work with ready mixed paint at any height in any floor two coats etc complete	8400 Sft	1645.27	%Sft	138203
Total amount (approximately)		Rs.1,99,92,131/- (19.99 Million)			
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(Civil) Rs.4598569/- _____ % Above/Below/at par the O/R		Rs.		
B	(Item based of O/R Civil works)Rs.15283000/- _____ % Above/Below/at par the O/R		Rs.		
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates


I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_


Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)


Time limit 180 Days  
Penalty per day Rs.1000/-  
Typed estimate compared with a checked  
Estimate & found correct.

Signature of Contractor \_\_\_\_\_  
Address \_\_\_\_\_  
\_\_\_\_\_  
(with rubber stamp)


  
Deputy Director  
(P&H),KMC.

  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer(Civil)  
(P&H)KMC.

  
Tahir Jamil Durani  
Director General  
(P&H),K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK: CONSTRUCTION OF ENTRANCE GATE AT GOVERNOR HOUSE KARACHI**

Tender Reference Sr. No.: DG/P&H/KMC/ 7 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.17.00 Million
Bid Security	Rs.3,40,000/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: CONSTRUCTION OF ENTRANCE GATE AT GOVERNOR HOUSE KARACHI**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
1.	Excavation for foundation basement trenches in all kinds of soil excluding the cost of back filling etc complete	18000 Cft	2722.50	%Cft	4901
2	Providing and laying 1:4:8 cement concrete foundation basement trenches including compacting curing etc complete	338Cft	9416.28	%Cft	381665
3	Providing and laying R.C.C. 1:2:4 work including all labour and material. This rate also all kinds of form moulds lifting shuttering curing rendering and finishing; exposed surface etc complete.	1800 Cft	337.00	Cft	606600
4	providing, manufacturing and fixing round moulded plate for foot and top 24" dia and 6" thick with yellow hard stone in hard stone with the help of lath machine including the cost of making 6" dia hole and making edge 2" thick in 13" dia for true alignment and 2" dia making gola surrounding of foots on top and bottom of foot including the cost of loading and unloading, erection in position with the help of heavy crane including the cost of fixing with mixing in colour for matching in marble jelly filling in pours with powder chemical and rubbing & making smooth surface etc complete.	08 Nos.	1000	Each	80000
5	Providing , manufacturing and fixing round columns 16" dia with yellow stone in hard stone with the help of lath machine including the cost of making 6" dia hole and making edge 2" thick in 13" dia for true alignment including the cost of loading and unloading, erection in position with the help of heavy crane including the cost of fixing with mixing in colour for matching in marble jelly filling in pours with powder chemical and rubbing and making smooth surface etc complete including the cost of MS bar and C.C. works in 6" inch dia hole etc completed as per direction by the Engineer incharge etc	53 cft	5500	Rft	291500

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
6	Providing Manufacturing & fixing 9" x 6" x 24" Yellow stone consol with work of hand made carvin moulding /including the cost of loading and unloading erection in position with the help of scaffolding including the cost of fixing with marble Jelli as per drawing etc complete	08 Nos	20000	Each	160000
7	Providing Manufacturing & fixing 3" thick Yellow stone slab with work of hand made moulding /including the cost of loading and unloading erection in position with the help of scaffolding including the cost of fixing with marble Jelli as per drawing etc complete	1295 sft	8000	Sft	10360000
8	Providing Manufacturing & fixing 16" x 24" x 4" Yellow stone plate with work of flower carvin like vaz hand made carvin moulding /including the cost of loading and unloading erection in position with the help of scaffolding including the cost of fixing with marble Jelli as per drawing etc complete	08 Nos	35000	Each	280000
9	Providing Manufacturing & fixing 15" x 80" x 3" fancy border with work of hand made carvin moulding including the cost of loading and unloading erection in position with the help of scaffolding including the cost of fixing with marble Jelli as per drawing etc complete	94 Nos	2250	Each	211500
10	Providing Manufacturing & fixing 12" x 3" Yellow stone strip border with work of hand made carvin moulding /including the cost of loading and unloading erection in position with the help of scaffolding including the cost of fixing with marble Jelli as per drawing etc complete	95 Nos	2250	Each	2144925
11	Providing Manufacturing & fixing 12" x 3" Yellow stone cornes border with work of hand made carvin moulding /including the cost of loading and unloading erection in position with the help of scaffolding including the cost of fixing with marble Jelli as per drawing etc complete	95 Nos	2500	Each	238325
12	Providing Manufacturing & fixing 6" x 3" Yellow stone door beeding with work of hand made carvin moulding /including the cost of loading and unloading erection in position with the help of scaffolding including the cost of fixing with marble Jelli as per drawing etc complete	115 Rft	1000	Each	115000
13	Providing Manufacturing & fixing 24" x 24" x 4" Yellow stone pedestal with work of hand made carvin moulding /including the cost of loading and unloading erection in position with the help of scaffolding including the cost of fixing with marble Jelli as per drawing etc complete	08 Nos	15000	Each	120000
14	P/F milled steel iron gate with aluminum silver casting pieces as per approved design and drawing as per approved by the officer incharge etc complete.	300 Sft	1700	Sft	510000

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
15	Providing and laying Milled steel bars for reinforcement including the cost of cutting bending binding and binding wire using tar bar etc complete	80 Cwt	5001.70	Cwt	400136
16	painting on iron works three coats with ready mixed paint of approved make and shade at any height in any floor etc complete	300 Sft	1645.27	%Sft	4936
Grand total amount (approx.)		Rs.1,69,97,541/- (17.00 Million)			
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(Civil) Rs.843791/- _____ % Above/Below/at par the O/R	Rs.			
B	(Item based of O/R Civil works)Rs.16153750/- _____ % Above/Below/at par the O/R	Rs.			
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit 80 Days

Penalty per day Rs.1000/-

Typed estimate compared with a checked


Estimate & found correct.

Signature of Contractor \_\_\_\_\_


Address \_\_\_\_\_

(with rubber stamp)

  
Deputy Director  
(P&H),KMC.


  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer(Civil)  
(P&H)KMC.

  
Tahir Jamil Durrani  
Director General  
(P&H),K.M.C.



KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK: DEVELOPMENT OF LAWNS, IMPROVEMENT OF GRILL FENCING  
& CONSTRUCTION OF CANOPIES AND GATES AT BURNS GARDEN KMC**

Tender Reference Sr. No.: DG/P&H/KMC/ 8 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.19.95 Million
Bid Security	Rs.3,99,000/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: DEVELOPMENT OF LAWNS, IMPROVEMENT OF GRILL FENCING AND  
CONSTRUCTION OF CANOPIES AND GATES AT BURNS GARDEN KMC**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
1	p/f sand sgtone canopy 20' feet dia including the cost of all cc, rcc and necessary iron work dom of canopy with cast iron fiber coated as per approved drawing and design etc complete in all respect as per direction by the D.G.(P&H),KMC.	03 Nos	800000	Each	2400000
2	P/F moveable gate with 10" dia pipe ¼" thick 20'-0" wide 10'-0" height including the charges of sheesham wood and MS bar 5/8" dia shaft 5" dia and RCC work etc complete	02 Nos	800000	Each	1600000
3	Construction of entrance gate both side entrance burji 48" dia and 16" height pillars both side and bottom box with RCC covered with stone tiles and gola and top box covered with stone tiles and top dom both side including the cost of RCC work etc complete	02 Nos	700000	Each	1400000
4	Excavation for foundation basement trenches in all kinds of soil excluding the cost of back filling etc complete.	1664 Cft	2722.50	%Cft	4530
5	P/L 1:4:8 cement concrete foundation basement trenches including compacting curing etc complete	272 Cft	4319.70	%Cft	11749
6	P/L RCC 1:2:4 work including all labour and material this rate also all kinds of form moulds lifting shuttering curing rendering and finishing exposed surface etc complete	400 Cft	337.00	Cft	134800
7	P/L Milled steel bars for reinforcement including the cost of cutting bending binding and binding wire using tar bar etc complete	17.85 Cwt	5001.70	Cwt	89280
8	Repainting on iron works three coats with ready mixed paint of approved make and shade at any height in any floor etc complete	10400 Sft	1645.27	%Sft	171108
9	Dismantling cement concrete works in any description etc complete	1000 Cft	3327.50	%Cft	33275
10	Cartage of sand bajri lime and all kinds of soil including loading and unloading etc complete	5000 Cft	881.91	%Cft	44096
11	Leveling and dressing the ground including the cutting and filling upto 6" thick etc complete	113000 Sft	181.50	%Sft	205095
12	Grassing fine by dribbling grass roots 3" apart including watering weeding till such time the grass fit for moving etc complete	170000 Sft	6.00	Sft	1020000

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
13	Truffing lawn excluding the cost of turf etc complete	170000 Sft	272.25 S.R.	%Sft	462825
14	Supplying, Stacking and spreading of Sweet earth approved garden soil from outside sources including all leads and lifts i/c cost of spreading in required slopes etc complete	150000 Cft	32.00	cft	4800000
15	Supplying, Stacking and Spreading of well decayed cowdung manure from approved outside sources including leads and lifts and including cost of spreading in uniform thick fine for grassing etc complete.	50000 Cft	30.00	Cft	1500000
16	P/L 1:2:4 cement concrete cast in situ including the cost of forms works its removal compacting curing etc complete	800 Cft	14429	%Cft	115434
17	P/L 1:3:6 cement concrete solid block masonry 4" to 6" thick using graded screened bajri ¾" and down gauge set in lime cement mortar 1:1:6 i/c scaffolding, taking out joints and curing etc. complete in ground floor superstructure etc complete.	600 Cft	14621.14	%Cft	87729
18	½" inch thick cement plaster with 1:4 cement sand mortar including the cost of making edge corner etc complete	1200 Cft	2283.93	%Sft	27407
19	Colour create plaster 3/8" thick as per approved design and colour with white cement and fine sand required shade including the cost of making edge corner etc complete	1200 Cft	6319.50 S.R	%Sft	75834
20	Supply of cronocarups trees in sized 4' to 6' feet height as per approved by the O/I etc	1000 Nos	150	Each	150000
21	Supply of shrub plants as per approved by the O/I etc	8272 Nos	200	Each	1654400
22	Supply of seasonal plants as per approved by the officer incharge etc complete (with 12" pots)	500 Nos	70.00	Each	350000
23	P/F physical appliance unit with fiber glass and wooden frame structure including the cost of fixing as per approved design and drawing and as per approved by the competent authority by DG (P&H)KMC.	01 Unit	985000 O/r	Each	985000
24	P/F swing bridge as per approved by the officer incharge etc complete	02 Nos	100000	Each	200000
25	P/F set saw as per approved by the officer incharge	02 Nos	50000	Each	100000
26	P/F cast iron wooden benches with pan wood battens 6'-0" x 0-2 x 0-1" benches size 6'-0" vertical with three footed of cast iron spiral total weight of foot 65 kgs including the cost of nuts bolts painting with ready mixed paint of approved make and shade as per approve by the Director General (P&H) KMC.	20 Nos	17500 O/r	Each	350000
27	P/F Envicrate Pre Cat Kerb Stone Plain Grey As Per Approved The Quality In Size 4"+6" /2 X12" X 18" Inch including The Cost Of Excavation Of Base Of Cement Concrete Upto 2" Thick Etc Complete	2000 Rft	297.01	Rft	594020

Sl. No.	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT
28	Providing and Fixing Paving Blocks (pavers) of Envicrete make of any type of desired color or shade (60 mm tick approx) over 2 inch thick screened sand, fixing paving block in desired pattern / design filling the joint with fine sand, compacting etc complete including making edges with same pavers and jointing the edge blocks with cement mortar 1:4 curing compacting etc complete as directed by the Engineer Incharge and manufacturer specification. etc complete	10000 Sft	223.97 SR	Sft	2239700
Grand total amount (approx.)			Rs.19946906/- (19.95 Million)		
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(Civil) Rs.3437506/- _____ % Above/Below/at par the O/R	Rs.			
B	(Item based of O/R Civil works)Rs.16509400/- _____ % Above/Below/at par the O/R	Rs.			
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit 80 Days

Penalty per day Rs.1000/-


Typed estimate compared with a checked  
Estimate & found correct.

Signature of Contractor \_\_\_\_\_

Address \_\_\_\_\_

(with rubber stamp)


  
Deputy Director  
(P&H),KMC.

  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer(Civil)  
(P&H)KMC.

  
Tahir Jamil Durrani  
Director General  
(P&H),K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

NAME OF WORK: CONSTRUCTION OF PATH WAYS AT BURNS GARDEN KMC

Tender Reference Sr. No.: DG/P&H/KMC/ 9 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.19.97 Million
Bid Security	Rs.3,99,400/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: CONSTRUCTION OF PATHWAYS AT BURNS GARDEN, KMC.**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
1.	Excavation for foundation basement trenches in all kinds of soil excluding the cost of back filling etc complete	3000 Cft	2722.50	%Cft	8168
2	P/L Dry stone rammed bid stone ballast 1 1/2" to 2" gauge etc complete with compacting as directed by the Engineer Incharge etc complete	1500 Cft	3327.50	%Cft	49913
3	Providing and laying 15 cm thick layer of grular sub base course using hub gravel with sand and silt from 9 to 60 mm laid inlayers including compaction upto 98% of max. dry density determine by AASHTO (T=180 methods) as directed by the Engineer Incharge etc complete	29035	4381.76	%Cft	1272244
4	Providing and laying envicrate or equivalents pavers as per approved design including the cost of preparation of base with fine sand upto 4" thick including the jointing fixing in coloured pigments etc complete	56034 sft	223.97	Sft	12549935
5	Providing and fixing Envicrate pre cast kerb stone plain grey as per approved the quality in size 4"+6"/ 2 x12"x18" inch including the. The cost of excavation of base of cement concrete upto 2" thick etc complete	6000 Rft	297.01	Rft	1782060
6	Supplying and filling earth from approved garden soil approved out side sources including all leads and lifts including loading and unloading etc complete	150000 cft	O/r 12.00	Cft	1800000
7	P/F pre cast dust bin fiber glass dust bins stainless steel pipe as per approved by the officer incarge etc complete.	50 nos	O/r 12000	Each	600000
8	Cartage of sand bajri lime and all kinds of soil including loading and unloading etc complete	148042 cft	881.91	%Cft	1305597
9	Dismantling cement concrete work in any description including the cost of disposal of rubbish upto one chain etc complete	5000 Cft	3327.50	%Cft	166375
10	Providing and fixing Envicrate pre cast kerb stone plain grey as per approved the quality in size 4"+6"/ 2 x12"x18" inch including the. The cost of excavation of base of cement concrete upto 2" thick etc complete	100 Nos	17500 o/r	Each	1750000

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(RS.)
11	Supplying , stacking and spreading of sweet earth approved garden soil including the all leads and lifts from approved out side sources in required slopes as per direction by the officer incharge etc complete	36000 Cft	O/r 32.00	Cft	1152000
12	Supplying and stacking well decayed cowdung manure from approved out side sources including all leads and lifts ncluding the cost of spreading in uniform thick fine for grassing etc complete	24000 Cft	O/r 28.00	Cft	720000
Grand total amount (approx.)		Rs.19979734/- (19.97 Million)			
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(Civil) Rs.12696233/- _____ % Above/Below/at par the O/R	Rs.			
B	(Item based of O/R Civil works)Rs.7283501/- _____ % Above/Below/at par the O/R	Rs.			
Grand Total amount ( A+B )		Rs.			

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit 180 Days


Penalty per da / Rs.1000/-


Typed estimate compared with a checked  
Estimate & found correct.

Signature of Contractor \_\_\_\_\_


Address \_\_\_\_\_

(with rubber stamp)


  
Deputy Director  
(P&H),KMC

  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer(Civil)  
(P&H)KMC.

  
Tahir Janbil Durrani  
Director General  
(P&H),K.M.C.

**KARACHI METROPOLITAN CORPORATION**  
**PARKS AND HORTICULTURE DEPARTMENT.**



**STANDARD BIDDING DOCUMENTS**

**(Smaller Work – Rs.2.50 Million Above/Below )**

**(As per PEC & SPPRA Guidelines / Directives)**

**FOR.**

**NAME OF WORK: ARRANGEMENT OF LIGHTING TOWER AND  
IRRIGATION SYSTEM AT BURNS GARDEN KMC**

Tender Reference Sr. No.: DG/P&H/KMC/ 10 /2013-2014

**In Compliance of PEC & SPPRA Rules 2010**

Estimate Cost: -	Rs.5.00 Million
Bid Security	Rs.100000/-- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014



**NAME OF WORK: ARRANGEMENT OF LIGHTING TOWER AND  
IRRIGATION SYSTEM AT BURNS GARDEN KMC**

Tender Issued to M/s \_\_\_\_\_

Tender cost per order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
	Schedule rates items				
1	P/F of MS octagonal pole as per following specification to be fixed on pre cast foundation with help of hydraulics crane and manual labour 50' feet long with dia of pole at the top 6" and bottom 24" wall thickness 6 mm base plate 8" x 38" x 1" stiffeners 12" by 6" by 1 ½" eight numbers, holes 8 nos making window in the pole required size with "L" key provision .. Two coats red oxide as rust preveritive two coats oil paint as per site requirement and instruction of engineer incahrge etc complete	04 Jobs	166708	Job	666832
2	P/F of flood lights 400 watts HPT having IP65 classification with 400 watts lamp choke capacitor, ignitor and internal wiring, complete in all respect height upto to 50' with help of hydracuic crane and manual labour as per site requirement and instruction of engineer incahrge etc complete	78 Jobs	16980	Job	1324440
3	P/L Main or sub main PVC insulated and pvc sheeted with four core copper conductor 600 / 1000 volts size 35 mm etc complete	270 Mtrs	2529	Mtr	682830
4	Same as item No.3 but 16 mm2	325 Mtrs	1300	Mtr	422500
5	P/L main or sub main pvc insulated and pvc sheeted with single core copper conductor 300 / 500 volts size 2 x 7/.029 (2.5 mm)	360 Mtrs	118	Mtr	42480
6	P/L polythine pipe 90 mm dia as connection clamp size 90 x 8 mm bend, socket union etc including the cost of nipple 1.5" x 1.5" dia GI pipe 1.5" dia long GI bend 1.5" dia 1.5" dia and dead plug 1.5" dia etc complete SDR-17 (PN-10) Dadex / equivalent	650 Mtrs	584	Mtr	379600

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
8	<p>P/M/F wall mounted panel board for 10 HP Siemens electric motor consisting of the following components size 2 ½" x 2 ½" x 8" with locking arrangement :</p> <p>a) 100 AMP TP MCCB  b) 3-Magnetic contractors  c) 2-push buttons  d) 2-indication lamps</p>	02 Jobs	24000	Job	48000
9	<p>Construction of RCC foundation including all materials scaffolding steel shuttering forms faced and others necessary arrangement etc as per following specification and standard approved by the Engineer incharge etc complete as under :-</p> <p>a) Excavation of foundation pit in all kinds of soil rock etc four dimension of 4' x 4' x 10' feet and within 3 chains hiring charges of de-watering pump with labour etc.</p> <p>b) Leaner concreting in the excavated pit with ratio liner then 1:3:6 for the dimension of 3.5' x 3.5' x 6" including the compacting curing etc complete.</p> <p>c) Concreting foundation in the excavated pit with ratio thinner then 1:1.5:3 having cube curing etc i/c providing fixing 4 nos RCC ring 42" dia 1' feet high.</p> <p>d) P/F foundation cage made with MS template having dimension of 32" x 32" 5 mm thick octagonal / round shape with the following comprising :-.....8 Nos 1 ¼" dia MS bolt with a length of 10' feet..... 9 nos MS round bar ½" dia to be welded long bolts with angle iron support inside 2" x 2" x ¼" 4 Nos including 24 nos of nuts 1 ½" and 24 Nos of washer complete as required.</p> <p>e) Back filling the excavated material stuff in the pit etc complete.</p>	04 Jobs	75000	Job	300000
10	<p>M/P/F special type octagonal shape light bracket for High Mast pole suitable for 24 Nos of flood light 400 watts comprising with the following :-</p> <p>a) Angle iron frame 2" x 2" 3/16" 12' feet dia octagonal shape each side 5' feet long 8 nos welded with each other with high frequency BSS standard etc complete.</p> <p>b) Angle iron frame bressing 2" x 2" x 3/16" 6' feet long 8 nos welded with 10" dia pipe 5" long etc.</p> <p>c) Angle iron vertical supporting 1.5" x 1.5" x 1/8" box type 5' long 8 nos welded with top plate 8" 6 mm and 4" dia pipe 1' feet 6" with top plate 8" dia 6 mm and 4" dia pipe 1' feet 6" long etc</p> <p>d) The light of brackets to be painted with anti rust paint and two coats ICI enamel paint the bracket should be installed at the top of high mast pole with hydraulics crane and manual labour complete as required</p>	04 Nos	44000	Each	176000

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
11	P/F Non clogging water pump set size 6" x 5' 1450 RPM 20 HP electric motor 3 phase 440 volts on common base plate including the cost of making cc pad with ratio 1:2:4 nuts and bolts etc complete in all respect Jawaic / Siemens / equivalent etc	02 Nos	196800	Each	393600
12	P/F wall mounted panel board size 2' x 1 ½' x 8" with locking arrangement consisting of the following components :-  a) 60 AMP TP MCCB Terasaki b) 3-magnetic contractor for 20 HP Siemens electric motor c) EVR best quality d) 1-ECOR e) 3-Phase indication lamps f) 1-neutral bar g) 2-push buttons h) 3-volts meter i) 1-ampere meter	02 Jobs	50000	Job	100000
13	P/F GI pipe 6" dia best quality	40 Rft	700	Rft	28000
14	P/F GI pipe 4" dia best quality	30 Rft	500	Rft	15000
15	P/F gate valve 4" dia	05 Nos	2977	Each	14885
16	P/F check valve 6" dia best quality	02 Nos	10000	Each	20000
17	P/F tee GI 4" dia	02 Nos	1200	Each	2400
18	P/F elbow 4" GI dia	02 Nos	1300	Each	2600
19	P/F socket GI 4" dia	02 Nos	600	Each	1200
20	P/F bend 4" dia GI	02 Nos	800	Each	1600
21	Dismantling and rewinding of burnt electric motor 10 HP Siemens on vertical pump set with the help of hydraulics crane 5 tons and manual labour after dismantling, rewinding, varnishing heating drying carried out including the cost of required and shape ball bearing NTN/SKF after testing refixing the motor on vertical pump set with the help of hydraulics crane and cartage of site to workshop and back within 30 KM limit etc complete in all respect	01 Job	40000	Job	40000

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
22	Dismantling and repairing of non clogging vertical water pump set KSB size 6' x 4" from pump stole with the help of hydraulics crane 5 tons and manual labour first of all dismantling motor from vertical pump 10 HP and then dismantling the vertical pump KSB including the cost of making bushes, shaft and required size ball bearing SKF/NTN and after repairing the vertical pump refixing the motor on vertical pump set with the help of hydraulics crane and cartage of site to workshop and back within 30 KM limit etc complete in all respect	01 Job	95000	Job	95000
23	Making situ around water hydrant 1' x 1' x 2' with ratio 1:2:4 including the cost of Roding and curing etc complete	20 Jobs	1200	Job	24000
24	Making excavation for trenches in hard or soft soil 2' x 2' from ground level after laying pipe making good the surfaced by refilling the excavated material etc complete.	8000 Cft	07.00	Cft	56000
25	P/M/F MS main fold for pressure and distribution of water 12" dia long with 2 nos MS 12" ½" thick plate of both ends including cost of making two nos of holes with 3" dia socket welding including cost of 2 Nos 3" dia valves best quality including cost of cutting welding, grinding and finishing work as required complete as per instruction by the Engineer incharge etc complete	02 Jobs	45000	Job	90000
Total amount for schedule rates items(Elect)					Rs.35,18,682/-
Total amount for open rates (Elect.)					Rs.14,54,870/-
<b>Grand total amount (approx.)</b>		<b>Rs.49,73,552/- Say (5.00 Million)</b>			
	I/We hereby quoted as following :-				
A	(Item based of schedule rates works )(M&E) Rs.3518682/- _____ % Above/Below/at par the O/R				Rs.
B	(Item based of O/R M&E works)Rs.1454870/- _____ % Above/Below/at par the O/R				Rs.
	<b>Grand Total amount ( A+B )</b>				Rs.

Contd.....

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)


For the complete job for all schedule of rates/approved rates/offer rates


I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_


Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit \_\_\_\_\_ Days  
Penalty per day Rs.1000/-  
Typed estimate compared with a checked  
Estimate & found correct.


Signature of Contractor \_\_\_\_\_  
Address \_\_\_\_\_  
\_\_\_\_\_  
(with rubber stamp)

  
\_\_\_\_\_  
Asstt. Executive Engineer(M&E)  
(P&H), K.M.C.

  
\_\_\_\_\_  
Executive Engineer(M&E)  
(P&H)K.M.C.

  
\_\_\_\_\_  
Tahir Jamil Durrani  
Director General  
(P&H),K.M.C.

**KARACHI METROPOLITAN CORPORATION**  
**PARKS AND HORTICULTURE DEPARTMENT.**



**STANDARD BIDDING DOCUMENTS**

**(Smaller Work – Rs.2.50 Million Above/Below )**

**(As per PEC & SPPRA Guidelines / Directives)**

**FOR.**

**NAME OF WORK: IMPROVEMENT AND DEVELOPMENT OF ST-10 PARK  
BLOCK-4 CLIFTON KMC**

**Tender Reference Sr. No.: DG/P&H/KMC/ 11 /2013-2014**

**In Compliance of PEC & SPPRA Rules 2010**

Estimate Cost: -	Rs.20.00 Million
Bid Security	Rs.4,00,000/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: IMPROVEMENT AND DEVELOPMENT OF ST-10 PARK BLOCK-4  
CLIFTON KMC.**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT (Rs)
1	Excavation in foundation of building bridges and others structures including debelling dressing refilling around structure with excavated earth watering and ramming lead upto 5' feet (in ordinary soil)	8250 Cft	2722.50 S.R.	%Cft	22460
2	P/L Driv stone rammed bide stone ballast 1 1/2" to 2" gauge etc complete with compacting as directed by the Engineer Incharge etc complete	1000 Cft	3327.50 S.R.	%Cft	33275
3	P/fixing Encicrate or Azhar pre cast kerb stone plain grey as per approved the quality in size 4"+6" x 12" x 18" / 2 including the cost of excavation of base of cement concrete upto 2" thick etc complete	6000 Rft	297.01 S.R.	Rft	1782060
4	Cement plaster 1:4 upto 20' feet height 1/2" thick etc complete	5000 Aft	2283.93	%Sft	114197
5	Colour create plaster 3/8" thick as per approved design and colour with white cement and fine sand required shade including the cost of making edge corner etc complete	19200 Sft	6319.50	%Sft	1213344
6	S/S & spreading yellow murrum from approved quarries to required slope including consolidation by ramming and watering etc complete	6500 Cft	40.00 O/r	Cft	260000
7	Supplying, Stacking and spreading of Sweet earth approved garden soil from outside sources including all leads and lifts i/c cost of spreading in required slopes etc complete	87216.40 cft	32.00 O/r	cft	2790925
8	Supplying, Stacking and Spreading of well decayed cowdung manure from approved outside sources including leads and lifts and including cost of spreading in uniform thick fine for grassing etc com	34255 Cft	30.00 O/r	Cft	1884025
9	P/F Mild steel Gate including the cost of jointing with welding etc com.	1342 kgs	250.00 O/r	Kg	335500
10	P/F wire Mash size 2" x 2" in 10 gauge as per approve by the Engineer incharge etc complete	858 Sft	120.00	Sft	102960
11	Providing and laying 15 cm thick layer of grular sub base course using hub gravel with sand and silt from 9 to 60 mm laid inlayers including compaction upto 93% of max. dry density determine by AASHTO (T=180 methods) as directed by the Engineer Incharge etc complete	81200 sft	4381.76	%Cft	3557989

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT (Rs)
12	Providing and Fixing Paving Blocks (pavers) of Envicrete make of any type of desired color or shade (60 mm tick approx) over 2 inch thick screened sand, fixing paving block in desired pattern / design filling the joint with fine sand, compacting etc complete including making edges with same pavers and jointing; the edge blocks with cement mortar 1:4 curing compacting etc complete as directed by the Engineer Incharge and manufacturer specification. etc complete	10400 Sft	223.97 SR	Sft	2329288
13	Construction of sand stone canopy with heavy 2 1/2" x 3/8" thick angle iron including the cost of mild steel bars fixing with nuts and bolts including the cost of chemical polishing and shape of octagonal use the circle pillar 8 nos size 12" diameter and making foundation for pillar with cement concrete ratio 1:2:4 including the cost of excavation loading and unloading fixing with crane or chain pulley canopy size 20'-0" diameter as per approved by the D.G. (P&H), KMC	01 Nos	750000 O/r	Each	750000
14	P/F physical appliance unit with fiber glass and wooden frame structure including the cost of fixing as per approved design and drawing and as per approved by the competent authority by DG (P&H)KMC.	01 Unit	985000 O/r	Each	985000
15	Providing and fixing see saw (double) with approved design and drawing etc complete As per approve by the competent authority by D.G. (P&H),K.M.C.	02 Nos	50000/- O/r	Each	100000
16	Providing and fixing swing bridge of approved design with three seated with chain links etc complete	02 Nos	100000/- O/r	Each	Rs.200000/-
17	Providing and fixing yellow stone benches in hard stone without seat back as per approved design and shape with two footed fixing in position including the cost of all kinds of loading and unloading and lifting including the cost of chemical polishing etc complete size 6'-0" x 1'-6" x 0'-4" thick slab both side rounded and foots size 2 nos, 1'-3" dia, 1'-3" height etc as per approved by the Officer incharge etc complete	16 nos	16000	Each	256000
18	P/F cast iron wooden benches with pan wood battens 6'-0" x 0-2 x 0-1" benches size 6'-0" vertical with three footed of cast iron spiral total weight of foot 65 kgs including the cost of nuts bolts painting with ready mixed paint of approved make and shade as per approve by the Director Genera (P&H) KMC.	54 Nos	17500	Each	945000



S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT (Rs)
19	P/F GI Pipe railing 2" dia as per approved by the Engineer incharge etc complete	448 Sft	350	Rft	156800
20	Painting on iron work with ready mixed paint at any height in any shade etc complete	180 Sft	1645.27 S.R.	%Sft	2961
21	Oil free distempering with approved make and shade at any height in any floor etc complete	1000 Sft	1762.75	%Sft	17628
22	Manufacturing / Providing and Fixing Dust Bin as per Design DB-2 in fiber glass materia 5 mm thick (approximate) including pedestal in 1-1/2" Dia G.I Pipe 8 SWG molded to shape and fixing in pedestal, including fixing in cement concrete, painting to pedestal etc complete as directed by the E/I etc complete	30 Nos	12000/- O/r	Each	360000
23	Dismantling cement concrete works in any description including the cost of disposal of rubbish upto one chain etc complete.	2500 Cft	3327.50 S.R.	%Cft	83188

## Electrical works

Schedule rates items(electric)					
1	P/F of flood lights 400 watts HPT having IP65 classification with 400 watts lamp choke capacitor, ignitor and internal wiring, complete in all respect height up to 50' with help of hydraulic crane and manual labour as per site requirement and instruction of engineer incharge etc complete	16 Jobs	16980	Job	271680
3	P/L Main or sub main PVC insulated and pvc sheeted with four core copper conductor 600 / 1000 volts size 35 mm etc complete	320 Mtrs	2529	Mtr	809280
4	Same as item No.4 but 16 mm <sup>2</sup>	180 Mtrs	1300	Mtr	234000
5	P/L main or sub main pvc insulated and pvc sheeted with single core copper conductor 300 / 500 volts size 2 x 7/.029 (2.5 mm)	270 Mtrs	118	Mtr	31860
6	P/L and fixing in trenches including fitting, jointing and testing etc complete in all respect the high density polythene pipes PE (HDPE-100 for w/s conforming ISO4427/ DIN8074/8075 BS 3580 PSI 3051-(PN-10) etc complete	500 Mtrs	584	Mtr	292000
7	P/L Main Or Sub Main Pvc Insulated Pvc Sheeted Two Core 7/.036 (4MM <sup>2</sup> ) etc complete	500 Mtrs	170	Mtr	85000
8	Making excavation for trenches or hard sand rock by hammering/ chiseling and spading etc from ground level making good the surface by refilling etc complet.	20760 Cft	7.00	Cft	145320
9	Making situ around 1' x 1' x 3" with ratio 1:2:4 including the cost of roding and	15 Jobs	785	Job	11775

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
10	P/f MS tubular pole 31' feet long with gauge 8 SWG thick all pipes of 6" dia 20' feet long, 5" dia, 5.5' feet long and 4" dia 5 Feet long should be electric welded all together on BSS standard including cost of MS bare plate 18" x 18" x 3/4" with 4 nos of holes size 1" dia electric welded with tubular pole complete within all respect etc . including the cost of hiring hydraulic crane 5 tons	04 Jobs	O/r 36701	Job	146804
11	P/F MS angle iron frame accomm-odate 4 nos 400 watts light size 2' x 4' feet with angle iron size 1 1/2" x 3/16" inch including cost of electric welding cuttinggrinding and finishing complete as required	04 Jobs	O/r 8000	Job	32000
12	Construction of C.C foundation including all materials steel shuttering fairs faced and others necessary arrangement etc as per following specification and standard approved by the Engineer Incharge etc complete as under :-  a) Excavation of foundation pit in all kinds of soil rock etc four dimension of 3' X 3' X 5.5 feet b) Leaner concreting in the excavated pit with ratio liner then 1:3:6 for the dimension of 4' x 4' x 6" including the compacting curing etc complete. c) Concreting foundation in the excavated pit with ratio thinner then 1:2:4 size 2' X 2' X 6.5 feet etc. d) P/F foundation cage made with MS template having dimension of 16" x 16" x 3/4" square shape with the following comprising :-  With 4 nos 3/4" , 5' feet long 4 nos MS round bars 1/2" dia to be welded with 5' feet long bars, 8 Nos of nuts 3/4" size and back filling excavated material as required complete in all respect.	04 Jobs	15168	Job	60672
13	P/F classis lamps post cast iron made 9' feet long with lanter 15" dia as per approved by the Director General (P&H) KMC photo attached complete in all respect with Energy saver bulb 40 watts Philips/Equ. (Hewolt ( Victorians age lamp post cL-01 (Modified)	50 Jobs	48000	JOB	2400000
14	P/F mor o block size 2" x 2" 2 HP single phase 220 volts 2800 RPM with capacitor complete in all respect. (Jawaid/Equ.)	02 Job	21850	Job	43700

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
15	Dismantling of pole 31' feet long from foundation with the help of crane including the cost of dismantling HPIT 400 watts from pole canopy with the help of hydraulics crane as per instruction by the E/I etc complete	04 Jobs	2000	Job	8000
16	P/F foot valve 2" inch dia best quality etc	02 Nos	1000	Each	2000
17	P/F vinyl hose pipe 2" inch dia best quality	30 Rft	120	Rft	3600
18	D/R of split Air conditioner 1.5 tons including the cost of replacement of compressor of required specification replacement of damage copper pipe required size and shape gas charging servicing replacement of control card etc complete as per instruction by the E/I etc complete	06 Jobs	16000	Job	96000
19	Making thrust bore 10' feet across the road at the depth of 5' feet from road level in hard rock area 75' feet long including the cost of making pit size 6' x 6' x 6' feet in hard rock soil at the both ends making a thrust bore etc complete.	01 Job	75000	Job	75000
20	M/P/F for control box floor mounted along-with locking arrangement made from MS 16 SWG sheet the size of the box size 2' x 3' x 10" is to be in accordance with components to be installed as per requirement given below. it must be water proof, dust proof with powder coating and ICI primer coating as per requirement  INCOMMING  a) 1-circuit breaker 200 AMPS (Terasaki or Equivalent) b) 4-base bare 200 AMPS c) 3- Phase indication  OUTGOING  a) 6-30 AMPS circuit breaker TP MCCB Terasaki or equ. b) 4-magnatic contractor suitable for 10 HP with over load relay National green power Japan or equ.	01 Job	56347	Job	56347

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
21	<p>Construction of C.C foundation including all materials steel shuttering fairs faced and others necessary arrangement etc as per following specification and standard approved by the Engineer Incharge etc complete as under :-</p> <p>a) Excavation of foundation pit in all kinds of soil rock etc four dimension of 2' x 2' x 2' feet</p> <p>b) leaner concreting in the excavated pit with ratio 1:4:8 size 2:2:0.5"</p> <p>c) Concreting foundation in excavated pit with ratio 1:2:4 size 2:2:5"</p> <p>d) P/F foundation cage made with 3 Nos MS round bar size 3' long ½" dia "J" shape on sidethread Including the MS nuts 3 nos size ½" and thread MS rings of size ¼" welded, to in bore MS Foundation complete in all respect and back filling excavated material as required .</p>	50 Jobs	3500	Job	175000
	Total amount for civil works		Rs.15019977/-		
	Total amount for electrical works		Rs.4980038/-		
	<b>Grand total amount (approx.)</b>		<b>Rs.2,00,00,015/- (20.00 Million)</b>		
	<b>I/We hereby quoted as following :-</b>				
A	(Item based of schedule rates works )(Civil) Rs.7325112/- _____ % Above/Below/at par the O/R		Rs.		
B	(Item based of O/R Civil works)Rs.7694865/- _____ % Above/Below/at par the O/R		Rs.		
C	(Item based of schedule rates works )(Elect.) Rs.1369760/- _____ % Above/Below/at par the O/R				
D	(Item based of O/R Civil works)(Elect.)Rs..... _____ % Above/Below/at par the O/R				
	<b>Grand Total amount ( A+B+C+D )</b>		Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount

(Name of bank)

Time limit \_\_\_\_\_ Days

Penalty per day Rs.1000/-

Typed estimate compared with a checked


Estimate & found correct.

Signature of Contractor \_\_\_\_\_

Address \_\_\_\_\_


(with rubber stamp)


  
Deputy Director (South)  
(P&H), KMC.

  
A.E.E. (Civil) P&H,  
(P&H), KMC


  
Executive Engineer (Civil)  
(P&H) KMC.

  
Asstt. Executive Engineer  
(M&E) P&H KMC.

  
Executive Engineer  
(M&E) P&H KMC

  
Tahir Jamil Durrani  
Director General  
(P&H), K.M.C.

**KARACHI METROPOLITAN CORPORATION**  
**PARKS AND HORTICULTURE DEPARTMENT.**



**STANDARD BIDDING DOCUMENTS**

**(Smaller Work – Rs.2.50 Million Above/Below )**

**(As per PEC & SPPRA Guidelines / Directives)**

**FOR.**

**NAME OF WORK: CONSTRUCTION OF BOUNDARY WALL AND STONE CANOPIES AT  
ST-28 PARK BLOCK-2 CLIFTON (P&H)KMC.**

**Tender Reference Sr. No.: DG/P&H/KMC/ 12 /2013-2014**

**In Compliance of PEC & SPPRA Rules 2010**

Estimate Cost: -	Rs.19.99 Million
Bid Security	Rs.3,99,800/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: CONSTRUCTION OF BOUNDARY WALL AND STONE CANOPIES AT  
ST-28 PARK BLOCK-2 CLIFTON (P&H)KMC.**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT (Rs)
1	Dismantling cement concrete works in any description including the cost of disposal of rubbish upto one chain etc complete .	27950 Cft	3327.50 S.R.	%Cft	Rs.930036/
2	Excavation in foundation of building bridges and others structures including debellirg dressing refilling around structure with excavated earth watering and ramming lead upto 5' feet (in ordinary soil)	175512 Cft	2722.50 S.R.	%Cft	Rs.477831/-
3	P/L Dry stone rammed bide stone ballast 1 1/2" to 2" gauge etc complete with compacting as directed by the Engineer Incharge etc complete	1250 Cft	3327.50 S.R.	%Cft	Rs.41594/-
4	P/fixing Envicrate or Azhar pre cast kerb stone plain grey as per approved the quality in size 4"+6" x 12" x 18" / 2 including the cost of excavation of base of cement concrete upto 2" thick etc complete	5000 Rft	297.01 S.R.	Rft	Rs.1485050/-
5	Providing and laying 15 cm thick layer of grular sub base course using hub gravel with sand and silt from 9 to 60 mm laid inlayers including compaction upto 98% of max. dry density determine by AASHTO (T=180 methods) as directed by the Engineer Incharge etc complete	10000 Cft	4381.76 S.R.	%Cft	Rs.438176/-
6	Leveling and dressing the ground i/c cutting and filling upto 6" thick etc complete	140000 Sft	181.50 S.R.	%Sft	Rs.254100/-
7	Construction of sand stone canopy with heavy 2 1/2" x 3/8" thick angle iron including the cost of mild steel bars fixing with nuts and bolts including the cost of chemical polishing and shape of octagonal use the circule pillar 8 nos size 12" diameter and making foundation for pillar with cement concrete ratio 1:2:4 including the cost of excavation loading and unloading fixing with crane or chain pulley canopy size 20'-0" diameter as per approved by the D.G. (P&H), KMC	02 Nos	750000 O/r	Each	Rs.1500000/-
8	Cartage of sand bajri lime and all kinds of soil including the cost of loading and unloading etc complete as directed by the Engir eer Incharge etc complete	50000 Cft	881.91	%Cft	Rs.440955/-
9	Supplying earth filling from approved out side sources including all leads and lifts including cost of compacting curing etc complete	24660 Cft	12.00 O/r	Cft	Rs.295920/-
10	Truffing awn excluding the cost of turf etc complete	100000 Sft	272.25 S.R.	%Sft	Rs.272250/-

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT (Rs)
11	Providing and Fixing Paving Blocks (pavers) of Envicrete make of any type of desired color or shade (60 mm tick approx) over 2 inch thick screened sand, fixing paving block in desired pattern / design filling the joint with fine sand, compacting etc complete including making edges with same pavers and jointing the edge blocks with cement mortar 1:4 curing compacting etc complete as directed by the Engineer incharge and manufacturer specification. Etc complete	20000 Sft	223.97 SR	Sft	Rs.4479400/-
12	S/S & spreading yellow murrum from approved quarries to required slope including consolidation by ramming and watering etc complete	5000 Cft	40.00 O/r	Cft	Rs.200000/-
13	Supplying, Stacking and spreading of Sweet earth approved garden soil from outside sources including all leads and lifts i/c cost of spreading in required slopes etc complete	119676 cft	32.00 O/r	cft	Rs.3829632
14	Supplying, Stacking and Spreading of well decayed cowdung manure from approved outside sources including leads and lifts and including cost of spreading in uniform thick fine for grassing etc complete.	25000 Cft	30.00 O/r	Cft	Rs.750000/-
15	Providing and fixing yellow stone benches in hard stone without seat back as per approved design and shape with two footed fixing in position including the cost of all kinds of loading and unloading and lifting including the cost of chemical polishing etc complete size 6'-0" x 1'-6" x 0'-4" thick slab both side rounded and foots size 2 nos, 1'-3" dia, 1'-3" height etc as per approved by the Officer incharge etc complete	08 Nos	O/r 16000	Each	Rs.128000/-
16	Painting on iron work with ready mixed paint at any height in any shade etc complete	3720 Sft	1645.27 S.R.	%Sft	Rs.61204/-
17	Grassing fine by dribbling grass roots 3" apart including watering weeding till such time the grass fit for moving etc complete	100000 Sft	O/r 6.00	Sft	Rs.600000/-
18	Supply of petrol engine lawn mower 5.5 HP in size 20" made in Japan complete in all accessories as per approve by the Director General (P&H)K MC etc complete	01 No	125000/- O/r	Each	Rs.125000/-
19	Supply of manual lawn mower machine in size 16" Made in Germany as per approve by the officer incharge etc complete	01 No.	30000 O/r	Each	Rs.30000/-
20	Providing and fixing see saw with approved design and drawing etc complete	02 Nos	50000/- O/r	Each	Rs.100000/-



S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT (Rs.)
21	Providing and fixing swing bridge of approved design with three seated with chain links etc complete	02 Nos	100000/- O/r	Each	Rs.200000/-
22	Removing of cement plaster as per direction by the Engineer incharge etc complete	10960 Sft	121.00 S.R.	%Sft	Rs.13262/-
23	Colour create plaster 3/8" thick as per approved design and colour with white cement and fine sand required shade including the cost of making edge corner etc complete	10960 Sft	6319.50 S.R	%Sft	Rs.692617/-
24	Manufacturing / Providing and Fixing Dust Bin as per Design DB-2 in fiber glass material 5 mm thick (approximate) including pedestal in 1-1/2" Dia G.I Pipe 8 SWG molded to shape and fixing in pedesta, including fixing in cement concrete, painting to pedestal etc complete as directed by the E/I etc complete.	20 Nos	12000/- O/r	Each	Rs.240000-
25	Supply of mixed shrub plants as per approved by the officer incharge etc complete	2000 Nos	200 O/r	Each	Rs.400000/-
26	Supply of different varieties of trees as per approved by the officer incharge etc complete.	500 Nos	250 O/r	Each	Rs.125000
27	Supply of mixed seasonal plants as per approved by the officer incharge etc complete	3000 Nos	70.00 O/r	Each	Rs.210000/-
28	P/F physical appliance unit with fiber glass and wooden frame structure including the cost of fixing as per approved design and drawing and as per approved by the competent authority by Director General (P&H) KMC.	01 Unit	985000 o/r	Each	985000
29	P/F cast iron wooden benches with pan wood battens 6'-0" x 0-2 x 0-1" benches size 6'-0" vertical with three footed of cast iron spiral total weight of foot 65 kgs including the cost of nuts bolts painting with ready mixed paint of approved make and shade as per approve by the Director General (P&H) KMC.	50 Nos	17500 o/r	Each	875000
30	P/I Cement plaster 1:4 upto 1/2" thick etc complete	2000 Sft	2283.93 S.R.	%Sft	Rs.45679/-

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT (Rs)
31	Providing and laying Milled steel Grill as per approved design / drawing with fate iron section including the cost of jointing fixing with welding etc complete	6500 Kgs	250.00 O/r	Kg	Rs.1625000/-
32	Providing and fixing inauguration stone in size 30" x 42" etc as per approved design including writing as per required complete as per approved design and drawing etc	01 No.	70000 O/r	Each	Rs.70000/-
<b>Grand total amount (approx.)</b>			<b>Rs.1,99,94,275/- (19.99 Million)</b>		
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(Civil) Rs.7705723/- _____ % Above/Below/at par the O/R	Rs.			
B	(Item based of O/R Civil works)Rs.12288552/- _____ % Above/Below/at par the O/R	Rs.			
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit 180 Days

Penalty per day Rs.1000/-


Typed estimate compared with a checked Estimate & found correct.

Signature of Contractor \_\_\_\_\_


Address \_\_\_\_\_

(with rubber stamp)


  
Deputy Director  
(P&H), KMC.

  
A.E.E. (Civil) P&H,  
(P&H), KMC

  
Executive Engineer (Civil)  
(P&H) KMC.

  
Tahir Jamil Durani  
Director General  
(P&H), K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK: IMPROVEMENT OF LIGHTING SYSTEM AND IRRIGATION SYSTEM  
AT DIFFERENT PARKS OF DISTRICT SOUTH (P&H) DEPTT. KMC.**

Tender Reference Sr. No.: DG/P&H/KMC/ 13 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.19.94 Million
Bid Security	Rs.398800/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK: IMPROVEMENT OF LIGHTING SYSTEM AND IRRIGATION SYSTEM  
AT DIFFERENT PARKS OF DISTRICT SOUTH (P&H) DEPTT. KMC.**

Tender issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
	Schedule rates items				
1.	P/F of flood light aluminum dia cast body IP-65 factory fitted wiring with following components :  a) HPIT 400 Watts. b) Ballast for HPIT 400 Watts c) gniiter for HPIT d) Capacitor for HPIT make Philips or Equivalent. Etc	80 Jobs	16980	Job	1358400
2	P/L 35 MM 4 core PVC insulated pvc sheeted as required Pak or Equivalent etc complete.	3000 Meters	2529	Mtr	7587000
3	P/L main or sub main PVC insulated and pvc sheeted with four core copper conductor 600/1000 volts size 150mm2 etc complete	90 Mtrs	10028	Mtr	902520
4	P/L 16 MM 4 core PVC insulated pvc sheeted as required Pak or Equivalent etc complete...	2037 Mtrs	1300	Mtr	2648100
5	P/F 400 watts HPIT lamp at the height of 50' feet with the help of hydraulic crane and manual labour as per site required and instruction by the Engineer incharge etc complete	900 Jobs	2380	Job	2142000
6	P/F chock as required etc.	400 Jobs	4375	Job	1750000
7	P/L main or sub main pvc insulated and pvc sheeted 2/7/.029 (2.5 mm) etc complete	1000 Meters	118	Mtr	118000
8	P/F wall mounted panel board size 3' x 2 2/1' x 8" with locking arrangement of the following components :  a) 1-60 AMP TP MCCB Terasaki b) 3 magnetic contractor for 20 HP Siemens electric motor c) 1-EVR best quality d) 1-ECOR best quality e) 1-bush bar1-netural bar f) 3-phase indication lamps g) 2-push butons h) 1-volts meter i) 1-amper meter	06 jobs	50000	Job	300000
9	Making excavation for trenches in hard or soft soil after laying cable refilling the excavated material complete as required	65000 Cft	7.00	Rft	455000
10	Painting of 50' feet long octagonal shape and canopy with the help of loader and manual labour including the cost of chipping and scrapping cost of red oxide and two cots of ebst quality enemaled paint complete in all respect as per instruction by the E/I etc complete	45 Jobs	8000	Job	360000

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
11	P/M/F panel board 3' x 3' x 8" with locking arrangement consisting of the following components :  a) 1-200 AMP TP MCCB Terasaki b) 60 amp tp mccb Terasaki c) 1 bush bar d) 1-netrual bar e) 3-phase indication lamps	08 Jobs	40000	Job	320000
12	P/F connection clamp 125 mm x 38 mm best qual ty in UPVC	30 Jobs	350	Each	10500
14	P/F connection clamps 160 mm x 38 mm etc	30 Jobs	400	Job	12000
14	P/F upvc pipe best quality 1 1/2" dia 3' long one side threaded etc	60 Jobs	132	Job	7920
15	p/f upv END 1 1/2" DIA best quality	60 Jobs	80	Job	4800
16	P/F UPVC solution etc	05 Kgs	1500	Kg	7500
17	P/F centrifugat Non colloguing pump set size 3" x 2 1/2" open type impeller 2800 RPM coupled with 10 HP 440 volts 50 c/s 2800 RPM coupled Siemens electric motor including cost of making cement concrete foundation and pad with concrete and nuts bolts complete as required as per instruction by the e/l	06 Jobs	113400	Job	1020600
18	P/M/F panel board size 2 1/2" x 2 1/2" with powder coating and locking arrangement consisting of the following components :  a) 1-60 AMP TP MCCB b) 3-Magnatic contractors for 10 Siemens electric motor c) 2-Push bottons d) 3-indicaton lamps e) 1-netrual bar f) 1-bush bar g) 1-EVR for 10 HP motor h) 1-ECOR for 10 HP motor	10 Jobs	50000	Job	500000
19	P/F MS pipe 3" dia heavy duty as per approve by the E/I	100 Rft	266	Rft	26600
20	P/F MS long bend 3" dia heavy duty including MS flanges	10 Jobs	5000	Job	50000
21	P/F Gae vlve 3" dis suitable for sewerage water heavy duty	06 Jobs	800	Job	10800
22	P/F MS heavy duty pipe 2 1/2" dia suitable for sewerage water etc	104 Rft	225	Rft	23400
23	P/f MS long bend 2 1/2" dia hevly duty with flanges etc	12 Jobs	950	Job	11400
24	P/F Gate valve 2 1/2" dia suitable for sewerage water heavy duty best quality	12 Jobs	1225	Job	14700
25	P/F MS check valve heavy duty 3" dia sutiable for sewerage water best quality with flanges	06 Jobs	9000	Job	54000
26	P/F MS nuts bolts heavy duty and bet quality of off size	20 kgs	120	Kg	2400
27	P/F making situ around water hydrant 1' x 1' x 2" with ratio 1:2:4 including the cost of roding and curing etc complete	41 Jobs	280	Job	31980

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT(Rs.)
28	P/F heat proof water proof high quality glass suitable for 400 watts IP65 light at the height of 50' feet with hydraulics crane and manual labour as per instruction by the Engineer incharge etc complete	100 Jobs	2100	Job	435280
Total open rates			Rs.16506020/-		
Total amount schedule rates items			Rs.3433600/-		
<b>GRAND TOTAL AMOUNT (APPROXIMATELY)</b>			<b>Rs.1,99,39,620/- (19.94 Million)</b>		
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(M&E) Rs.3433600/- _____ % Above/Below/at par the O/R	Rs.			
B	(Item based of O/R M&E works)Rs.16506020/- _____ % Above/Below/at par the O/R	Rs.			
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)


For the complete job for all schedule of rates/approved rates/offer rates


I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_


Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit \_\_\_\_\_ Days  
Penalty per day Rs.1000/-  
Typed estimate compared with a checked  
Estimate & found correct.


Signature of Contractor \_\_\_\_\_  
Address \_\_\_\_\_  
(with rubber stamp)

  
Asstt. Executive Engineer(M&E)  
(P&H), K.M.C.

  
Executive Engineer(M&E)  
(P&H)K.M.C.

  
Tahir Janji Durrani  
Director General  
(P&H), K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK: EXCAVATION OF PITS AND SUPPLY OF PLANTS AT  
SAFOORA CHOWRANGI TO UNIVERSITY ROAD KMC**

Tender Reference Sr. No.: DG/P&H/KMC/ 14 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	RS.3.49 MILLION
Bid Security	Rs.69800/-(2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

S.#	DESCRIPTION OF WORKS	QUANTITY.	RATE	PER	AMOUNT(Rs.)
6	Supply and fixing Bamboos size 1 1/2" to 3/4" inch dia and 5'-0" to 7'-0" height for plants bind with jute rope sutly as directed by the officer incharge etc complete	1000 Nos	O/r 60.00	Each	Rs.60000/-
Total amount (approximately)		Rs.34,91,713/- (3.4 Million)			
I/We hereby quoted as following :-					
A	(Item based of schedule rates works )(Civil) Rs.710963/- _____ % Above/Below/at par the O/R			Rs.	
B	(Item based of O/R Civil works)Rs.2780750/- _____ % Above/Below/at par the O/R			Rs.	
Grand Total amount ( A+B )				Rs.	

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from 180 amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit \_\_\_\_\_ Days

Penalty per day Rs.1000/-

Typed estimate compared with a checked


Estimate & found correct.


Signature of Contractor \_\_\_\_\_


Address \_\_\_\_\_

(with rubber stamp)

  
Director  
(P&H), KMC.


  
A.E.E. (Civil) P&H,  
(P&H), KMC

  
Executive Engineer (Civil)  
(P&H) KMC.

  
Tahir Jamil Durrani  
Director General  
(P&H), K.M.C.



KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

Name of work; S/S SWEET EARTH, MANURE AND PLANTS FOR  
DIFFEENT PARKS DIVISION-I KMC.

Tender Reference Sr. No.: DG/P&H/KMC/ 15 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.19.95 MILLION
Bid Security	Rs.399000/-(2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

Name of work; S/S SWEET EARTH, MANURE AND PLANTS FOR  
DIFFEENT PARKS DIVISION-I KMC.

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY.	RATE	PER	AMOUNT(Rs.)
1	Supplying, stacking and spreading of sweet earth approved garden soil including the all leads and lifts from approved out side sources in required slopes as per direction by the officer incharge etc complete	295030 Cft	O/r 32.00	Cft	9440960
2	Supplying and stacking well decayed cowdung manure from approved out side sources including all leads and lifts including the cost of spreading in uniform thick fine for grassing etc complete	186666.66 Cft	O/r 30.00	Cft	5600000
3	Supply of different seasonal plants as per approve by the officer incharge (with 12" pots) etc complete	450000 Nos	70.00 O/r	Cft	3150000
4	Cartage of sand bajri lime and all kinds of soil including the cost of loading and unloading etc complete as directed by the Engineer incharge etc complete	250000 Cft	881.91 S.R.	%Cft	2204775
Total amount			Rs.19954775/- (19.95 Million)		
I/We hereby quoted as following :-					
A	(Item based of S.R. rates works )(Civil) Rs.1763820/- _____ % Above/Below/at par the O/R	Rs.			
B	(Item based of O/R Civil works)Rs.18190955/- _____ % Above/Below/at par the O/R	Rs.			
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit 180 Days


Penalty per day Rs.1000/-


Typed estimate compared with a checked  
Estimate & found correct.


Signature of Contractor \_\_\_\_\_


Address \_\_\_\_\_

(with rubber stamp)


  
D. J. Director  
(P&H),KMC

  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer(Civil)  
(P&H)KMC.

  
Tahir Jamil Durrani  
Director General  
(P&H),K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK; IMPROVEMENT OF LAWNS AND GRASSING IN DIFFERENT PARKS  
AND GREEN BELT OF DIVISION-III KMC.**

Tender Reference Sr. No.: DG/P&H/KMC/ 16 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.19.999 MILLION
Bid Security	Rs.399400/-(2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK; IMPROVEMENT OF LAWNS AND GRASSING IN DIFFERENT PARKS  
AND GREEN BELT OF DIVISION-III KMC.**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY.	RATE	PER	AMOUNT(Rs.)
1	Supplying , stacking and spreading of sweet earth approved garden soil including the all leads and lifts from approved out side sources in required slopes as per direction by the officer incharge etc complete	295030 Cft	O/r 32.00	Cft	9440960
2	Supplying and stacking well decayed cowdung manure from approved out side sources including all leads and lifts including the cost of spreading in uniform thick fine for grassing etc complete	186666.66 Cft	O/r 30.00	Cft	5600000
3	Supply of different seasonal plants as per approve by the officer incharge (with 12" pots) etc complete	450000 Nos	70.00 O/r	Cft	3150000
4	Cartage of sand bajri lime and all kinds of soil including the cost of loading and unloading etc complete as directed by the Engineer Incharge etc complete	250000 Cft	881.91 S.R.	%Cft	2204775
5	Supply of cronocarpus trees size 4' to 6' feet height as per approved by the officer incharge etc complete	300 Nos	150 O/r	Each	45000
Total amount			Rs.19999775/- (19.999 Million)		
I/We hereby quoted as following :-					
A	(Item based of S.R. rates works )(Civil) Rs.1763820/- _____ % Above/Below/at par the O/R		Rs.		
B	(Item based of O/R Civil works)Rs.18235955/- _____ % Above/Below/at par the O/R		Rs.		
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit 180 Days

Penalty per day Rs.1000/-

Typed estimate compared with a checked

Estimate & found correct.

Signature of Contractor \_\_\_\_\_

Address \_\_\_\_\_

(with rubber stamp)


Dy. Director  
(P&H),KMC.

A.E.E. (Civil) P&H,  
(P&H),KMC

Executive Engineer(Civil)  
(P&H)KMC.

Tahir Jamil Durrani  
Director General  
(P&H),K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK; IMPROVEMENT OF LAWNS AND GRASSING IN DIFFERENT  
PARKS AND GREEN BELT OF DIVISION-VI KMC.**

Tender Reference Sr. No.: DG/P&H/KMC/ 17 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.19.999 MILLION
Bid Security	Rs.399400/-(2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK; S/S SWEET EARTH, MANURE AND PLANTS FOR DIFFERENT  
PARKS AND CENTAL ISLAND OF DIVISION-IV (P&H) KMC.**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY.	RATE	PER	AMOUNT(Rs.)
1	Supplying , stacking and spreading of sweet earth approved garden soil including the all leads and lifts from approved out side sources in required slopes as per direction by the officer incharge etc complete	295030 Cft	O/r 32.00	Cft	9440960
2	Supplying and stacking well decayed cowdung manure from approved out side sources including all leads and lifts including the cost of spreading in uniform thick fine for grassing etc complete	186666.66 Cft	O/r 30.00	Cft	5600000
3	Supply of different seasonal plants as per approve by the officer incharge (with 12" pots) etc complete	450000 Nos	70.00 O/r	Cft	3150000
4	Cartage of sand bajri lime and all kinds of soil including the cost of loading and unloading etc complete as directed by the Engineer Incharge etc complete	250000 Cft	881.91 S.R.	%Cft	2204775
5	Supply of cronocarpus trees size 4' to 6' feet height as per approve dby the officer inchrge etc complete	300 Nos	150.00 o/r	Each	45000
<b>Total amount</b>			<b>Rs.19999775/- (19.999 Million)</b>		
I/We hereby quoted as following :-					
A	(Item based of S.R. rates works )(Civil) Rs.1763820- _____ % Above/Below/at par the O/R		Rs.		
B	(Item based of O/R Civil works)Rs.18235955/- _____ % Above/Below/at par the O/R		Rs.		
<b>Grand total amount (A+B )</b>			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)


For the complete job for all schedule of rates/approved rates/offer rates


I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_


Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)


Time limit 180 Days  
Penalty per day Rs.1000/-  
Typed estimate compared with a checked  
Estimate & found correct.

Signature of Contractor \_\_\_\_\_  
Address \_\_\_\_\_  
(with rubber stamp)

  
Dy. Director  
(P&H),KMC.

  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer(Civil)  
(P&H)KMC.

  
Tahir Jamil Durrani  
Director General  
(P&H),K.M.C.

KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



*Handwritten:*  
26  
DP&H

STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

**NAME OF WORK; S/S SWEET EARTH, MANURE AND PLANTS FOR DIFFERENT  
PARKS AND CENTAL ISLAND OF DIVISION-IV (P&H) KMC.**

Tender Reference Sr. No.: DG/P&H/KMC/ 18 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.19.866 MILLION
Bid Security	Rs.397320/-(2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

**NAME OF WORK; S/S SWEET EARTH, MANURE AND PLANTS FOR DIFFERENT  
PARKS AND CENTAL ISLAND OF DIVISION-IV (P&H) KMC.**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY.	RATE	PER	AMOUNT(Rs.)
1	Supplying , stacking and spreading of sweet earth approved garden soil including the all leads and lifts from approved out side sources in required slopes as per direction by the officer incharge etc complete	294479 Cft	O/r 32.00	Cft	9423328
2	Supplying and stacking well decayed cowdung manure from approved out side sources including all leads and lifts including the cost of spreading in uniform thick fine for grassing etc complete	186666.66 Cft	O/r 30.00	Cft	5600000
3	Supply of different seasonal plants as per approve by the officer incharge (with 12" pots) etc complete	450000 Nos	70.00 O/r	Cft	3150000
4	Cartage of sand bajri lime and all kinds of soil including the cost of loading and unloading etc complete as directed by the Engineer Incharge etc complete	240000 Cft	881.91 S.R.	%Cft	2116584
Total amount			Rs.19866584/- (19.866 Million)		
I/We hereby quoted as following :-					
A	(item based of S.R. rates works )(Civil) Rs.1693267/- _____ % Above/Below/at par the O/R	Rs.			
B	(item based of O/R Civil works)Rs.18173317/- _____ % Above/Below/at par the O/R	Rs.			
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit 180 Days

Penalty per day Rs.1000/-


Typed estimate compared with a checked  
Estimate & found correct.


Signature of Contractor \_\_\_\_\_


Address \_\_\_\_\_

(with rubber stamp)

  
Dy. Director,  
(P&H),KMC.


  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer(Civil)  
(P&H)KMC.

  
Tahir Jamil Jurrani  
Director General  
(P&H),K.M.C.



KARACHI METROPOLITAN CORPORATION  
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million Above/Below )

(As per PEC & SPPRA Guidelines / Directives)

FOR.

NAME OF WORK; S/S SWEET EARTH, MANURE AND PLANTS FOR PARKS AND  
NURSERY AT DIVISION-V (P&H) KMC

Tender Reference Sr. No.: DG/P&H/KMC/ 19 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.19.95 MILLION
Bid Security	Rs.399000/- (2%)
Tender Cost: -	Rs.3000/-
Last Date of Sale of Tender	02 / 06 / 2014
Tender submitted & Opened	03 / 06 / 2014

2/6

4/6  
DDE I

**NAME OF WORK: S/S SWEET EARTH, MANURE AND PLANTS FOR PARKS AND NURSERY AT DIVISION-V (P&H) KMC**

Tender Issued to M/s \_\_\_\_\_

Tender cost pay order # \_\_\_\_\_ Rs.3000/- dated \_\_\_\_\_ Sr.No. \_\_\_\_\_ P.No. \_\_\_\_\_

S.#	DESCRIPTION OF WORKS	QUANTITY.	RATE	PER	AMOUNT(Rs.)
1	Supplying , stacking and spreading of sweet earth approved garden soil including the all leads and lifts from approved out side sources in required slopes as per direction by the officer incharge etc complete	281250 Cft	O/r 32.00	Cft	9000000
2	Supplying and stacking well decayed cowdung manure from approved out side sources including all leads and lifts including the cost of spreading in uniform thick fire for grassing etc complete	186666.66 Cft	O/r 30.00	Cft	5600000
3	Supply of different seasonal plants as per approve by the officer incharge etc complete	450000 Nos	70.00 O/r	Cft	3150000
4	Supply of shrub plants as per approve dby the officer incharge etc complete	5000 Nos	200.00 O/r	Each	1000000
5	Supply of different Trees size 10' to 15' feet as per approved by the O/I etc com.	8000 Nos	150.00 O/r	Each	1200000
Total amount			Rs.19950000/-(19.95 million)		
I/We hereby quoted as following :-					
A	(Item based of S.R. rates works )(Civil) Rs..... _____ % Above/Below/at par the O/R	Rs.			
B	(Item based of O/R Civil works)Rs..... _____ % Above/Below/at par the O/R	Rs.			
Grand Total amount ( A+B )			Rs.		

Rs. \_\_\_\_\_ Rupees \_\_\_\_\_  
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # \_\_\_\_\_ dated \_\_\_\_\_

Issued from \_\_\_\_\_ amounting to Rs. \_\_\_\_\_ as 2% Earnest money of bid amount  
(Name of bank)

Time limit 180 Days

Penalty per day Rs.1000/-


Typed estimate compared with a checked


Estimate & found correct.


Signature of Contractor \_\_\_\_\_


Address \_\_\_\_\_

(with rubber stamp)

  
Dy. Director  
(P&H),KMC.

  
A.E.E. (Civil) P&H,  
(P&H),KMC

  
Executive Engineer(Civil)  
(P&H)KMC.

  
Tahir Jamil Durani  
Director General  
(P&H),K.M.C.