

OFFICE OF THE XEN (B&R) D.M.C (WEST) BALDIA ZONE.

ESTIMATE COST 9,97,285/-
 TENDER COST 1500/-
 PENALTY PER DAY 1500/-

TIME LIMIT
 SECURITY DEPOSIT 01 MONTH
 19,946/-


SUBJECT:- Providing and supply sweet earth at Akbar Play Ground in UC-08, D.M.C (West), Baldia Zone.

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Supply and spreading approval Garder soil (sweet earth) free from salt pebbles and grus roots etc approval quarry required grade and slupe and disposal of rubbish with in 3 chain as directed by engineer incharge etc complete in all respect.	58083	2020.00	%Cft.	11,73,277/-

Nomenclature, quantities and rates
 etc checked and found correct.



Sub Engineer (PARK)



D.T.O (PARK)

I/We hereby quoted rate @ _____ % above/below the schedule of rates.

Contractor's Signature

Address

OFFICE OF THE XEN (B&R) D.M.C (WEST) BALDIA ZONE.

3

ESTIMATE COST 9,99,920/-
 TENDER COST 1500/-
 PANELTY PER DAY 1500/-

TIME LIMIT 01 MONTH
 SECURITY DEPOSIT 19,998/-


SUBJECT:- Supply and laying Dacca Gros and supply cow Duk Manure at Akbar Play Ground in, UC-08, D.M.C (West), Baldia Zone.

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01.	Supply and laying dacca cirass.	58083	6.00	P/Sft.	3,48,498/-
02.	Providing and supply cow duck manure	2777	298.12	P/Card	8,27,879/-

Nomenclature, quantities and rates
 Etc checked and found correct.



Sub Engineer (PARK)



D.T.O (PARK)

We hereby quoted rate @

% above/below the schedule of rates.

Contractor's Signature

Address

OFFICE OF THE XEN (B&R) D.M.C (WEST) BALDIA ZONE.


ESTIMATE COST	9,70,043/-	TIME LIMIT	01 Month
TENDER COST	1500/-	SECURITY DEPOSIT	19,401/-
PANELTY PER DAY	1500/-		

SUBJECT:- P/L 2" thick c.c. topping at street No.01/83 to street No.01/84 Sector 5-G Saeedabad in UC No.05, D.M.C (West), Baldia Zone.

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum shape leveling of beds of trenches to correct lever and grade, surplus earth within a oge chain as directed by Engineer Incharge.	1350	4650.00	% 0 cft	6278/-
12	P/L reinforced cement concrete pipes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting jointing with rubber rings etc complete KWSB approved Rate M/S Balochistan R.C.C Pipe Co. M/S Pakistan Const (Pvt.) Ltd. M/S Katta R.C.C Pipe Co. 12" dia.	100	367.00	P/cft	36700/-
13	Construction of 4" manhole inside complete with 21" dia c.c 1:2:4 pre cast C.I frame 12kg i/c the cost of M/S bars reinforcement and two handles 5" clear depth c.c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KWSB) approved rate.	01 Nos	9307.86	Each	37231/-
04	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 2-0	1609.15	P/ft	(-) 3218/-
05	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete.	1215	2760.00	%0cft	3353/-
06	Dismantling cement block masonry.	300	1134.38	%cft	3403/-
07	Dismantling cement concrete plain 1:4:8	555	1663.75	%cft	92338/-
08	Cement concrete bricks or stone ballest 1 1/2" to 2" guage.	3663	9416.28	%cft	344918/-
09	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and diving into panel etc complete.	11100	3275.50	%cft	363581/-
10	Carriage of 100 cft tons at all kinds materials like cole brick i/c loading unloading 10 mfles.	5985	595.80	%cft	35659/-
11	Providing C-I Manhole cover & frame i/c cast of 1 kg materials etc.	80	140	P/Kg	11200/-
12	Manufacturing and surface R.C.C Main hole covers cast in situ 1:2:4 c.c. 3" deeping center reinforced with 3/8" dia M.S steel i/c curing transportation	60 Nos	913.63	Each	54818/-

13	Manufacturing and supplying of R.C.C ring slab of 21" dia inside 36" dia outside 7.5 width and 6" thick i/c 3/8" dia for steel bars two concentric ring with 3/8" dia 8 Nos cross linked bars welded and two suk type hooks casted in a 1-182:3 concrete with empeded 15 kg C-1 frame in perfect position i/c transportation charges for on every lead of 20 km per arip; fram casting yard to town offer (A minimum of 25 slabs per trip will be transported.	60	1906.60	Each	114396/-
14	Rate analysis for shifting to the site and fixing 26" dia Ring Slab in perfect position on damage manhole i/c cutting of damage portion of mentioned in past shape and lying of cement concrete mortar of 2" thickness and disport.	60 Nos	563.09	Each	33785/-

Nomenclature, quantities and rates
Etc checked and found correct.


A.E. (B&R)


A.E. (B&R)

I/We hereby quoted rate@

% above/below the schedule of rates.

Contractor's Signature _____

Address _____