

University Engineer



Phone: 9261366
9261300-6
Ext: 2247

Ref. No. 714

Engineering Department
University of Karachi
Karachi-75270

September 29th, 2014

Tender Notice

Open Tenders in Sealed Cover are invited on Item Rate basis from Reputable Contractors who has experience of such works.

Sr.#	Name of Work	Estimated Cost	Completion Period	Tender Fee
1.	Laying of Cable for Semester Cell to Azadi Chowk, University of Karachi.	Rs.24,37,500/-	60 days	Rs.2500/-
2.	Street lights from Teacher Club to Kancez Fatima Gate University of Karachi.	Rs.29,70,000/-	60 days	Rs.3000/-
3.	Renovation of existing toilets and distempereing / painting of Boys Hostel, University of Karachi.	Rs.19,08,267/-	60 days	Rs.2000/-
4.	Repair of Boundary wall Scout Colony toward PCSIR turning Metrovill Gate, University of Karachi.	Rs.22,95,593/-	45 days	Rs.2300/-

- 1) Tender Documents can be purchased from the Office of the Undersigned with effect from 01-10-2014 on payment of the amount noted above (Non-refundable) between 09:00 a.m till 02:00 Noon on any Working Day except the Day of Opening of Tender.
- 2) Sealed Tender accompanied by Pay Order of Earnest Money @2% of the Bid amount in favour of University of Karachi will be received in the Office of the Director Finance, University of Karachi up to 2:00 p.m. on 23-10-2014 and will be opened on the same day at 2:30 p.m. In presence of the Contractors or their Representatives who will be present at that time. Any Tender not accompanied by Earnest Money or Short Amount of Earnest Money or Conditional Tenders will NOT be considered. No Cheque will be entertained along with Tender as Earnest Money. All Contractors have to submit Proof of Proprietorship of Company along with the CNIC copy and work completion certificate for issuance of Tender "copy of valid NTN". Contractor have to submit copy of work order for execution of work.
- 3) All Bids should be valid for a period of (90) Days.
- 4) The Successful Bidders who refuse to do work after Opening of Tenders, shall be liable to be forfeited their Earnest Money as a Penalty.
- 5) Competent Authority may reject all or any bids subject to relevant provisions of SPPRA Rules.
- 6) In case of any unforeseen situation resulting in closure of office on the date of opening or Government declares holiday the tender shall be submitted / opened on the next working day at the same time and venue.
- 7) Tender notice is also available on SPPRA's and University of Karachi web-site (www.uok.edu.pk).


UNIVERSITY ENGINEER

Copy to :-

01. Advisor to Vice Chancellor.
02. Director Finance
- 03) Deputy Director Finance
- 04) Resident Auditor
- 05) Purchase Officer
- 06) Chief Accountant
- 07) Deputy Executive Engineer (Electrical)
- 08) Sub-Engineer (Electrical)
- 09) University official web-site
- ✓ 10) SPPRA
- 11) PRO
- 12) Notice Board.
- 13) Concerned File.

SPPRA INWARD DIARY

NO: 64263

DATED: 02-10-14

Pi. Horst 490 19
J
2/6
awp



UNIVERSITY OF KARACHI

ENGINEERING DEPARTMENT

University Road, Karachi-75270. Tel: (021) 9926-1386, 9926-1300-08 Ext 2247

TENDER NOTICE

Open Tenders in Sealed Cover are invited on Item Rate basis from Reputable Contractors, who have the Experience of such works.

Sr.No.	Name of Work	Estimated Cost	Completion Period	Tender Fee
1.	Laying of Cable for Semester Cell to Azadi Chowk, University of Karachi	Rs. 24,37,500/-	60-Days	Rs. 2,500/-
2.	Street Lights from Teacher Club to Kameez Fatima Gate, University of Karachi	Rs. 29,70,000/-	60-Days	Rs. 3,000/-
3.	Renovation of Existing Toilets and Distemping/Painting of Boys Hostel, University of Karachi	Rs. 19,08,267/-	60-Days	Rs. 2,000/-
4.	Repair of Boundary Wall Scout Colony towards PCSIR Turning Metroville Gate University of Karachi	Rs. 22,95,593/-	45-Days	Rs. 2,300/-

- Tender Documents can be purchased from the Office of the Undersigned with effect from 1st October 2014 on Payment of Amount noted above (Non-Refundable) between 09:00 am till 02:00 Noon on any Working Day except the Day of Opening of Tender.
- Sealed Tender accompanied by Pay Order of Earnest Money @ 2% of the Bid Amount in favour of University of Karachi, will be received in the Office of the Director Finance, University of Karachi up to 02:00 pm on 23rd October 2014 and will be opened on the Same Day at 02:30 pm in presence of the Contractors or their Representatives who will be present at that time. Any Tender not accompanied by Earnest Money or Short Amount of Earnest Money or Conditional Tenders will NOT be considered. No Cheque will be entertained along with Tender as Earnest Money. All Contractors have to submit Proof of Proprietorship of Company along with the CNIC Copy and Work Completion Certificate for issuance of Tender. "Copy of valid NTN". Contractors have to submit Copy of Work Order for Execution of Work.
- All Bids should be valid for a Period of 90 Days.
- The Successful Bidders who refuse to do work after Opening of Tenders, shall be liable to forfeiture of their Earnest Money as a Penalty.
- Competent Authority may reject all or any Bids subject to relevant Provisions of SPPRA Rules.
- In case of any unforeseen situation resulting in closure of Office on the date of opening or Government declares Holiday, the Tenders shall be submitted/opened on the Next Working Day at the same time and venue.
- This Tender Notice is also available on SPPRA's and University of Karachi Website: www.uok.edu.pk

UNIVERSITY ENGINEER

Wednesday
October 1, 2014
Zilhalaj 5, 1435
KARACHI

Rs 19,00
26 Pages
Vol. LXVIII No. 271
Regd. No. SS-022



DAWN

FOUNDED BY QUAID-E-AZAM MOHAMMAD ALI JINNAH

www.jang.com.pk

پاکستان کے روزنامہ سرگرمی
ABC CERTIFIED
بقاعدہ تصدیق شدہ اشاعت

THE DAILY JANG KARACHI

جنگ

بانی میر ظہیر الرحمن

78 جلد 5 روزی الحسب 1435ھ کے اکتوبر 2014ء 271 نمبر

WEDNESDAY OCTOBER 1, 2014.

UNIVERSITY OF KARACHI
ENGINEERING DEPARTMENT
University Road, Karachi-75270. Tel: (921) 9626-1366, 9926-1300-66 Ext 2247

TENDER NOTICE

Open Tenders in Sealed Cover are invited on Item Rate basis from Reputable Contractors, who have the Experience of such works.

Sr.No.	Name of Work	Estimated Cost	Completion Period	Tender Fee
1.	Laying of Cable for Semester Cell to Azadi Chowk, University of Karachi	Rs. 24,37,500/-	60-Days	Rs. 2,500/-
2.	Street Lights from Teacher Club to Kameez Fatima Gate, University of Karachi	Rs. 29,70,000/-	60-Days	Rs. 3,000/-
3.	Renovation of Existing Toilets and Distemping/Painting of Boys Hostel, University of Karachi	Rs. 19,08,267/-	60-Days	Rs. 2,000/-
4.	Repair of Boundary Wall Scout Colony towards PCSIR Turning Metraville Gate University of Karachi	Rs. 22,95,593/-	45-Days	Rs. 2,300/-

- Tender Documents can be purchased from the Office of the Undersigned with effect from 1st October 2014 on Payment of Amount noted above (Non-Refundable) between 09:00 am till 02:00 Noon on any Working Day except the Day of Opening of Tender.
- Sealed Tender accompanied by Pay Order of Earnest Money @ 2% of the Bid Amount in favour of University of Karachi, will be received in the Office of the Director Finance, University of Karachi up to 02:00 pm on 23rd October 2014 and will be opened on the Same Day at 02:30 pm in presence of the Contractors or their Representatives who will be present at that time. Any Tender not accompanied by Earnest Money or Short Amount of Earnest Money or Conditional Tenders will NOT be considered. No Cheque will be entertained along with Tender as Earnest Money. All Contractors have to submit Proof of Proprietorship of Company along with the CNIC Copy and Work Completion Certificate for issuance of Tender. "Copy of valid NTN". Contractors have to submit Copy of Work Order for Execution of Work.
- All Bids should be valid for a Period of 90 Days.
- The Successful Bidders who refuse to do work after Opening of Tenders, shall be liable to forfeiture of their Earnest Money as a Penalty.
- Competent Authority may reject all or any Bids subject to relevant Provisions of SPPRA Rules.
- In case of any unforeseen situation resulting in closure of Office on the date of opening or Government declares Holiday, the Tenders shall be submitted/opened on the Next Working Day at the same time and venue.

University Engineer



Phone: 9261366
9261300-6
Ext: 2247

Ref. No. _____

Engineering Department
University of Karachi
Karachi-75270

Tender

Date of Opening:- 23-10-2014.
Time of Opening:- 02:30 P.M..
Place of Opening:- Office of Director Finance, University of Karachi.
Work:- Laying of Cable for Semester Cell to Azadi Chowk,
University Of Karachi.

Tender # 01

S. #.	ITEMS OF WORK.	Q T Y.	RATE.	UNIT.	AMOUNT.
01.	Providing & fixing 3 ½ core PVC armored cable 35 sq. mm 3 ½ core with execution / digging 3' with sand red bricks & back filling complete cable laying work as required at site.	2100 Rft.			
02.	Providing & fixing Velocity street light complete 250 watt with 1 ½ dia GI Pipe 3' length on the existing pole complete material Philips or equivalent as required at site.	19 Nos.			
03.	Proving & fixing wire 2-7/036 full gauge with PVC Pipe 1" with complete connection existing poles as required at site.	700 Rft.			

DEPUTY EXECUTIVE ENGINEER(E)

SUB-ENGINEER (E)

UNIVERSITY ENGINEER

CONTRACTDR (With Seal)

University Engineer



Phone: 9261366
9261300-6
Ext: 2247

Ref. No. _____

Tender

Engineering Department
University of Karachi
Karachi-75270
Tender No.02

Date of Opening: 23-10-2014
Time of Opening:- 02:30 P.M.
Place of Opening:- Office of Director Finance, University of Karachi.
Name of work:- Street Lights from Teacher Club to Kaneez Fatima Gate,
University of Karachi.

S. #.	ITEMS OF WORK.	Q T Y.	RATE.	UNIT.	AMOUNT
01.	P/F Mercury blub 110 watt for existing pole & existing shad with chock 110 watt as required at site.	48 Nos.			
02	P/F cable 3 ½ core 35 sq mm 3 ½ core Armored cable with execution 3' feet with sand red bricks & back filling complete cable laying work as required at site.	3300 Rft.			
03.	P/F street light worm type bulb 110 watt Mercury bulb with chock 110 watt complete shad Mercury bulb as required at site with shad GI Pipe 3' long 1 1/2" as required site.	16 Nos			

In words:- (Rupees _____)

DEPUTY EXECUTIV ENGINEER (Electrical)

SUB-ENGINEER (E)

UNIVERSITY ENGINEER

CONTRACTOR (With seal)

University Engineer



Phone: 9261366
9261300-6
Ext: 2247

Ref. No. _____

Date of Opening:- 23-10-2014.
Time of Opening:- 02:30 P.M..
Place of Opening:- Office of Director Finance, University of Karachi.
Work:- Renovation of existing toilets and distempering / painting of Boys
Hostel, University Of Karachi.

Engineering Department
University of Karachi
Karachi-75270

Tender # 03

S. #.	ITEMS OF WORK.	QTY.	RATE.	UNIT.	AMOUNT.
01.	Dismantling glazed tiles / Mosaic floor, dado in any floor including base mortar upto 1 1/2" thick & stacking salvaged material & dispensing of surplus stuff as directed Engineer.	3350'		Sft.	
02.	P/L glazed tiles floor, dado of Master or Equivalent make 6"x6" upto 12"x12" in any floor laid over 1" thick C.M base 1:2 including jointing & washing the tiles with white cement slurry of matching color & curing etc complete.	3350'		Sft.	
03.	Providing and laying 1:3:6 cement concrete solid block masonry 4" to 6" thick using graded screened bajri 3/4" and down gauge set in cement mortar 1:1:6 including scaffolding, raking out joints and curing etc. complete in any floor superstructure.	120'		Cft.	
04.	3/4" thick cement plaster 1:6 on walls, ceiling and columns etc any floor including making edges, corners, and curing etc, complete internal & external surface of room in any floor.	480'		Sft.	
05.	Dismantling C.C. work cast in situ platform foundation, basement, plinth and ground floor including disposing of the material as directed as directed by Engineer In-Charge.	203'		Cft.	
06.	Providing and making platform upto 4' x 4' inside in 1 1/2" thick fine c.c over 4" thick c.c. 1:2:4 kerb in cement concrete 1:2:4 and 1/2" thick cement plaster 1:3 C.M all and to walls upto a height of 2'-6" complete, i/c dismantling existing c.c. platform complete.	9		Each	
07.	P/F un-platisized polyvinyl chloride pipe (c.P.V.C) schedule "80" Dadex make or equivalent with specials and clamps etc i/c cutting, fittings, and jointing (Band,Tee, Y-Tee, cowel etc) complete with and including the cost of breaking through walls and roof and making good damages i/c taking out existing Pipe with fitting i/c cost of taking out existing pipe.				



	A- ¾" dia c. P.V.C For hot & cold Water B- 1" dia c.P.V.C (Water) C- 4" dia Dadex or equivalent make "Nikasi" (Sewerage) i/c cost of cutting, fitting and jointing (Band,Tee,Y-Tee,cowel etc) complete with and including the cost of breaking through walls and roof and making good damages i/c taking out existing Pipe with fitting i/c cost of taking out existing pipe, Excavation & back filling up to required depth & width if required.	730' 100' 430'		Rft. Rft. Rft.	
08.	P/F S.Steel Handle valve approved make, fix in G.I and C.PVC line with all necessary fitting complete etc. ¾" dia. B- 1" dia.	3 2		Each Each	
09.	P/F Making connection with the existing G.I pipe & u.PVC pipe up to 2" dia i/c cutting the pipe and providing fixing necessary fitting.	6		Each	
10.	P/F 22' X 16" lavatory Hand wash basin glazed Master or equivalent make complete with and i/c the cost of pedestal, bracket, waste, waste pipe 1 ¼" dia, side pillar cock Master or equivalent make, plastic connection, stop cock, glazed P-trap with S.S. Jali or equivalent and making requisite number of holes in walls, plinth, ceiling and floor for pipe connection and making good in cement concrete 1:2:4 complete.	9		Each	
11.	P/F 24"x18" beveled edges looking mirror of Belgium glass or equivalent with 1/8" thick hard board and screw fixed to wooden cleats complete i/c taking out existing mirror if any.	9		Each	
12.	P/F glazed oresa W.C pan complete with & i/c the cost of Plastic low level flush tank, P.V.C flushing pipe suitable for squatting type with extra bands and length with fitting, u.PVC p-trap, making requisite of holes in walls, plinth, ceiling & for pipe connection, making good in cement concrete 1:2:4, with all necessary fitting i.e. stop cock, plastic connection etc.	9		Each	
13.	P/F u P.V.C. P-Trap 4" dia with S.S. jali or equivalent i/c cutting hole and making good damages in c.c.	33		Each	
14.	Providing and fixing M.S molded steel frames or equivalent of 6" wide x 2-1/2" (146 mm x 63 mm) manufactured from mild steel or 18 gauge (1.41 mm) conforming to B.S.S 1245 having a double rebate size 1-1/2" x ½" (38 mm x 6 mm) (2 Nos. 6" long welded with frame at not less than 20 points). With holes and threads for fixing steel hinges, fitted with one locking box of same sheet (point welded inside the frame). 6 Nos. 6" long flat iron fixing lugs of 1-1/4" x 3/16" section, treated with special red oxide primer coat or equivalent all around including cutting holes and filling the cavity with cement concrete 1:2:4 etc. in any floor at any height complete as directed by the Engineer In-Charge.	110'		Rft.	



15.	Providing and fixing 1 ½" thick best quality deodar wood solid flush door, fully flush with commercial ply wood (5 ply), approved iron hinges, door lock, sliding bolt complete as required at site. i/c cost of taking out existing door shutters complete. Note: Any flush door would be checked by Engineer In-Charge randomly i.e taking out commercial ply to check the laying to wood properly as directed by Engineer In-charge, This all process's cost bear by contractor.	350'		Sft.	
16.	P/F ½" dia Chrome bib cock of approved make fix in G.I line with all necessary fitting.	30		Each	
17.	P/F ½" dia Chrome plated concealed stop cock, T-stop cock and stop cock with all necessary fitting complete.	66		Sft.	
18.	Providing and fixing side pillar cock /Mixer Master or equivalent make , long neck approved quality with all necessary fitting as required at site.	9		Each	
19.	P/F tower bolt / sliding bolt and door handle fixed on wooden shutter with screw etc complete i/c taking out old tower bolt.	42		Each	
20.	Providing and fixing door (Babar 808) or equivalent as required at site.	21		Each	
21.	P/F aluminum sheet fixed with nails glue on shutter as required at site.	270'		Sft.	
22.	Painting iron /wood work with ready mixed paint of approved make and shade two coats complete at any height in any floor (GOBI'S) or equivalent.	15000'		Sft.	
23.	OIL bound distempering with distemper of approved make and shade in three coats including scraping, sand papering, dusting, and filling the holes, cracks and inequalities, if any at any height in any floor (GOBI'S) or equivalent make.	65000'		Sft.	
24.	Repair of existing outer manhole complete in all respect as required at site.	3		Each	
25.	Providing manhole type "A" 2' x 1'-6" x 2' deep as per approved design and specifications complete for to 12" dia pipes up to 3'-11" depth with cast iron cover and frame 16" dia inside fixed in 4" thick RCC 1:2:4 slab, 8" thick c.c. 1:3:6 c.c. 1:3:6 c.c in hunching, ½" thick cement plaster in 1:3 C.M to all inside & out side wall surface, channels and benching etc. and to top including making requisite number of main and branch channels i/c the cost of excavation back filling and disposal of excavated stuff, manhole cover and frame.	4		Each	
26.	1-1/2" thick cement patch plaster 1:5 in two layers at ceiling, columns etc. in any floor including making edges, and curing etc complete as directed by Engineer In-charge.	1000'		Sft.	
27.	Providing and fixing bath shower with rod approved make as required at site.	12		Each	
28.	Providing and fixing double leaf steel doors made to crittal or equivalent standard and of approved sections fully paneled with M.S sheet or equivalent of 16 gauge painted with two coats of red oxide paint including using approved brass section oxidized fitting iron lugs, cutting holes and making good damages to walls etc. complete as required in any floor. i/c cost of frame.	63'		Sft.	



29.	Providing and laying cement fiber bitumen coated pipe, Dadex or equivalent make for sewer line, including cost of cutting, fitting and jointing with asphalt composition and cement mortar 1:1, including cost of excavation of trench up to required depth and back fills the excavated material in trench including testing with water to a pressure head of 80' feet complete, jointing with existing sewer line as directed by engineer in-charge. 6" dia.	20'		Rft.	
30.	Replacing existing figured / plain glass 44 oz (5.40 mm) approx. with iron nails and putty including removing broken ones if required in any floor.	50'		Sft.	
31.	Cartage of sand, bajri, lime, surkhi, murum, manure, earth, building rubbish including loading, unloading and stacking etc. at site: 1 mile (1.6 km) lead, as directed by Engineer.	1		Job	

UNIVERSITY ENGINEER


ASSISTANT EXECUTIVE ENGINEER (CIVIL)

CONTRACTOR (WITH SEAL)

University Engineer



Phone: 9261366
9261300-6
Ext: 2247

Ref. No. _____

Engineering Department
University of Karachi
Karachi-75270


Tender

Date of Dpening:- 23-10-2014.
Time of Opening:- 02:30 P.M..
Place of Opening:- Office of Director Finance, University of Karachi.
Work:- Repair of Boundary wall Scout Colony toward PCSIR turning, Metrovill Gate,
University of Karachi.

Tender # 04

S. #.	ITEMS OF WDRK.	QTY.	RATE.	UNIT.	AMOUNT.
01.	Cleaning jungle (dense) by cutting, removing all shrubs, trees, up to 6" girth etc. and taking out their entire roots and filling the hollows with earth complete with dressing, consolidating and watering the filling including stacking the serviceable materials and disposal of useless materials as directed, lead up to 10 chains, cost of earth included.	43250'		Sft.	
02.	Providing and laying 1:3:6 cement concrete solid block masonry 4" to 6" thick using graded screened bajri ¾" and down gauge set in cement mortar 1:1:6 including scaffolding, raking out joints and curing etc. complete in any floor superstructure.	15330'		cft.	

UNIVERSITY ENGINEER


ASSISTANT EXECUTIVE ENGINEER (CIVIL)

CONTRACTOR (WITH SEAL)