

OFFICE OF THE XEN (B&R) D.M.C (WEST) BALDIA ZONE.

ESTIMATE COST	2,76,414/-	TIME LIMIT	01 Month
TENDER COST	1500/-	SECURITY DEPOSIT	5,528/-
PANELTY PER DAY	1500/-		

SUBJECT:- P/L 2" thickness c.c Topping at House No:209 To 218 street No:02 sector 12/C in UC No3, D.M.C (West), Baldia Zone,

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Filling watering & Ramming Earth under floor with new Earth (Excavated from outside) Load up to one chain & lift up to 5 feet.	4425cft	3630.00	% cft	16,063/-
02	Carriage of 100cft tons of all kinds material like cole bricks i/c Loading Unloading 10miles.	4425cft	595.80	% cft	26364/-
03	Cement Concert bricks or stone ballast 1 1/2" to 2" gauge.	1287cft	9416.28	% cft	121188/-
04	P/L thick topping cement concrete 1:2:4 i/c surface finishing & diving in to panel E.T.C complete	3900cft	3275.50	%cft	127745/-
05	Manufacturing & supply of R.C.C ring slab of 21" dia inside 36" out side 7.5" with & 6" thick i/c 3/8" dia for steel bars two concentric ring with 3/8" dia 8 Nos cross l'nk'd bar welded & two sunk type hooks easted in(1:1/2:3)cons with embedded 15kg C.I Frame in Perfect position i/c transportation charges for as average lead of 20KM per trip from casting yard to town office (A minimum of 25 slabs per trip will be transported.)	10 NOS	1906.60	Each	19066/-
06	Manufacturing supplying R.C.C main hole covers cast in situ 1:2:3 C.C 3" inch deep in center reinforced with 3/8" dia M.S bars welded on M.S sheet i/c curing transportation 21" dia 24" dia	10 NOS	913.63	Each	913/-
07	Rate analysis for shifting to the site & fixing 26"dia ring slab in perfect position on damage manhole i/c cutting of damage portion of mentioned in past shape & lying of cement concrete mortar of 2"thickness & disport.	10NOS	563.09	Each	5631/-

Nomenclature, quantities and rates
Etc checked and found correct.

M. Farid
A.E (B&R)


A.E.E (B&R)

I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____


OFFICE OF THE XEN (B&R) D.M.C (WEST) BALDIA ZONE.

ESTIMATE COST	9,50,340/-	TIME LIMIT	01 Month
TENDER COST	1500/-	SECURITY DEPOSIT	19,007/-
PANELTY PER DAY	1500/-		

SUBJECT:- P/L 2" thick C.C Topping at Gali No: 20 Block D Ittehad Town in UC No2, D.M.C (West). Baldia Zone,

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Dismantling cement concrete plain 1:4:8.	7500 cft	1663.75	% cft	124781/-
02	Cement concrete bricks or stone ballest 1 1/2" to 2" gauge	4950 cft	9416.28	%cft	466106/-
03	P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and diving into panal etc complete.	1500cft	3275.50	%cft	491325/-
04	Carriage of material 100 cft tons of all kinds material like bricks i/c loading unloading 10 miles.	6000cft	595.80	%cft	35748/-

Nomenclature, quantities and rates
Etc checked and found correct.


A.E (B&R)


A.E. (B&R)

I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____


OFFICE OF THE XEN (B&R) D.M.C (WEST) BALDIA ZONE.

ESTIMATE COST	5,15,201/-	TIME LIMIT	01 Month
TENDER COST	1500/-	SECURITY DEPOSIT	10,304/-
PANELTY PER DAY	1500/-		

SUBJECT:- P/L 12" dia R.C.C pipe line at Gali No: 20 Block D Ittehad Town in UC No2, D.M.C (West), Baldia Zone.

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches & pits in all kinds of soils for Murum shape leveling of beds of trenches to correct lever & great surplus Earth with in a one chain as directed by Eng In charge.	8775cft	4650.00	%0cft	40804/-
02	Excavation for pipe line in trenches & pits in hard rock by chiseling trimming & dressing alignment & shape leaving up to one chain.	2400cft	24150.00	%0cft	57960/-
03	P/L reinforced cement concrete pipe with rubber ring i/c cartyage,loading unloading at site of work fixing in trench cutting fitting . jointing with rubber rings etc. Complete KWSB approved rate . M/S Baluchistan R.C.C pipe Co, M/S Pakistan Constraction Pvt Ltd, M/S Kamal R.C.C pipe Co.	650rft	367.00	P/rft.	238550/-
04	Constraction Of 4" dia mainhole inside complete with 21" dia C.C 1:2:4 precast C.I frame 12 kg i/c the cost of M.S bars reinforcement and two handles 5" clear depth e e 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c banding and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus staff (KWSB) approved rate.	25 Nos	9307.86	Each	232697/-
05	Extra depth beyond 5" ft or less than 5 deducted at the same rate (KWSB) approved rate.	(-)12.5ft	1605.50	Pft	(-)20114/-
06	Refilling excavation stuff and surplus earth etc complete.	10058 cft	2760.00	%cft	5993/-
07	Carriage of 100 cft tons of all kinds material like coal bricks i/c loading unloading 10 miles	1117 cft	595.80	%cft	6655/-

Nomenclature, quantities and rates
Etc checked and found correct.


A.E (B&R)


A.E.E (B&R)

I/We hereby quoted rate@ _____ % above/below the schedule of rates.

Contractor's Signature _____

Address _____



DISTRICT MUNICIPAL CORPORATION (WEST)
BALDIA ZONE, KARACHI.

No.DMC/(W)/XEN/B.Z/414 /2014

Dated: 28/10/2014

To,

The Deputy Director (ENF-I)
Government of Sindh
Sindh Public Procurement Regulatory Authority
Karachi.

Subject: NIT NO.XEN/B.Z/DMC/WEST/410/2014, DATED 15.10.2014 (Sr.No.21607).


Corrigendum

Ref: Your Letter No.Dir(Enf-I)/0133/SPPRA/37-I(KMC)/14-15/4547 dated 21.10.2014.

The bidding documents shall be issued from 26.11.2014 during office hours and on the date of opening i.e. 11.12.2014 bidding documents shall be issued up to 12:00 a.m.

Timing for dropping of Tender will be 11:00 a.m. dated 11.12.2014 Tenders will be opened on at 11:00 a.m.

As advised, corrigendum is issued from further necessary action please.


EXECUTIVE ENGINEER
Baldia Zone, DMC (West)

Copy forwarded for information to:

1. The Administrator, DMC (West).
2. The Superintending Engineer, DMC (West).

SPPRA INWARD DIARY
NO: 2235
DATED: 28-10-14