

KARACHI METROPOLITAN CORPORATION
PARKS AND HORTICULTURE DEPARTMENT.



STANDARD BIDDING DOCUMENTS

(Smaller Work – Rs.2.50 Million or Below)

(As per PEC & SPPRA Guidelines / Directives)

FOR

**NAME OF WORK; CONSTRUCTION OF STONE CANOPY IN PARK AT
CLIFTON BLOCK-3 KMC KARACHI.(Re-invited)**

Tender Reference Sr. No.: DG/P&H/KMC/ 1 /2013-2014

In Compliance of PEC & SPPRA Rules 2010

Estimate Cost: -	Rs.9,94,000/-
Bid Security	Rs.19,880/- (2%)
Tender Cost: -	Rs.1000/-
Last Date of Sale of Tender	12 / 11 /2014
Tender submitted & Opened	13 / 11 /2014

**NAME OF WORK; CONSTRUCTION OF STONE CANOPY IN PARK AT
CLIFTON BLOCK-3 KMC KARACHI**

Tender issued to M/s _____

Tender cost pay order # _____ Rs.1000/- dated _____ Sr.No. _____ P.No. _____

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT (In Rs.)
1	Construction of sand stone canopy with heavy 2 ½" x 3/8" thick angle iron including the cost of mild steel bars fixing with nuts and bolts including the cost of chemical polishing and shape of octagonal use the circule pillar 8 nos size 12" diameter and making foundation for pillar with cement concrete ratio 1:2:4 including the cost of excavation loading and unloading fixing with crane or chain pulley canopy size 20'-0" diameter as per approved by the D.G. (P&H), KMC	01 No.	800000	Each	800000
2	P/fixing Envicrete or Azhar pre cast kerb stone plain grey as per approved the quality in size 4"x6" x 12" x 18" / 2 including the cost of excavation of base of cement concrete upto 2" thick etc complete	70 Rft	297.01	Rft	20791
3	Providing and Fixing Paving Blocks (pavers) of Envicrete make of any type of desired color or shade (60 mm tick approx) over 2 inch thick screened sand, fixing paving block in desired pattern / design filling the joint with fire sand, compacting etc complete including making edges with same pavers and jointing the edge blocks with cement mortar 1:4 curing compacting etc complete as directed by the Engineer Incharge and manufacturer specification. etc complete 20% ceiling	314 Sft	223.97 44.79 179.17	Sft	56261
4	Providing and laying 15 cm thick layer of grular sub base course using hub gravel with sand and silt from 9 to 60 mm laid inlayers including compaction upto 98% of max. dry density determine by AASHTO (T=180 methods) as directed by the Engineer Incharge etc complete	157 Cft	3341	%Cft	5245
5	Excavation in foundation of building bridges and others structures including debelling dressing refilling around structure with excavated earth watering and ramming lead upto 5' feet (in ordinary soil)	52 Cft	2722.50 S.R.	%0Cft	141

S.#	DESCRIPTION OF WORKS	QUANTITY	RATE	PER	AMOUNT (In Rs.)
6	Cartage of sand bajri lime and all kinds of soil including the cost of loading and unloading etc complete as directed by the Engineer Incharge etc complete	52 Cft	881.91	%Cft	459
7	Supply of seasonal plants as per approved by the officer incahrge etc complete	1600 Nos	69.93	Each	Rs.111903/-
Grand total amount					Rs.9,94,000/-

Total amount

Rs.9,94,000/-

I/we hereby quoted as follows :

1.	Item Based on S/R amounting to Rs. _____ _____ % Above/Below/at par the O/R	Rs.
2	Item Based on O/R amounting to Rs. _____ _____ % Above/Below/at par the O/R	RS.
TOTALA AMOUNT A + B		RS.

Total amount is:

Rs. _____ Rupees _____
(in figure) (in words)

For the complete job for all schedule of rates/approved rates/offer rates

I/We have attached a pay order bearing # _____ dated _____

Issued from _____ amounting to Rs. _____ as 2% Earnest money of bid amount
(Name of bank)Time limit 60 Days

Penalty per day Rs.1000/-


Typed estimate compared


With checked and found correct


Signature of Contractor _____


Address _____

(with rubber stamp)


Executive Engineer(Civil)
(P&H),KMC


Deputy Director
(P&H),KMC


Director
(P&H),K.M.C.


Director General
(P&H),K.M.C