

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drain & C.C Block @ west side of main Naukot Road including Jagdish colony Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAIN & C.C BLOCK @ WEST SIDE OF MAIN NAUKOT ROAD INCLUDING JAGDISH COLONY MITHI

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drain & C.C Block at Lohana and Sonara Mohallah Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAIN & C.C BLOCK @ LOHANA & SONARA
MOHALLAH MITHI TOWN

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drain & C.C Block at East Bajeer Mohallah Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAIN & C.C BLOCK @
EAST BAJEER MOHALLAH MITHI TOWN

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drain & C.C Block at West Bajeer, Kunbhar, Pinjara, Khatri and Meghwar Mohallah Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
**REPAIR/CONSTRUCTION OF OPEN SURFACE DRAIN & C.C BLOCK @ WEST BAJEER,
KUNBHAR, PINJARA, KHATRI & MEGHWAR MOHALLAH MITHI TOWN.**

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drain & C.C Block at Darzi and Nai Mohallah Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAIN & C.C BLOCK @ DARZI & NAI
MOHALLAH MITHI TOWN

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drain & C.C Block at Meghwar Mohallah West side of Water Supply Scheme No.3 Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAIN & C.C BLOCK @
MEGHWAR MOHALLAH WEST SIDE OF W/S SCHEME NO: 3 MITHI TOWN

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drain & C.C Block at Maheshwari and Maharaj Mohallah near Murlidhar Temple Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAIN & C.C BLOCK @
MAHESHWARI AND MAHARAJ MOHALLAH NEAR MURLIDHAR TEMPLE MITHI TOWN.

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drain & C.C Block at Bachal Shah Colony Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAIN & C.C BLOCK @
BACHAL SHAH COLONY MITHI.

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drains & C.C Block @ Siran Colony Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAIN & C.C BLOCK @
SIRAN COLONY MITHI.

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drains in Suthar Paro near Holi Ground Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAINS IN SUTHAR PARO NEAR
HOLI GROUND MITHI TOWN

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Open Surface Drains @ Soomra Colony Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR/CONSTRUCTION OF OPEN SURFACE DRAINS @ SOOMRA COLONY MITHI

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 474.0 Cft @ Rs. 2722/50 P% Cft	Rs. 1,290/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1161.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 788.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,31,062/= Rs.1,13,702/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1693.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,02,286/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating cost of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). Type-A 200.0 Rft @ Rs. 94/= P.Rft	Rs. 18,800/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3625.00 Sft @ Rs. 2283/93 P% Sft	Rs. 82,792/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
Total		Rs. 6,84,351/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of C.C Road @ main Bazar Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

CONSTRUCTION OF C.C. ROAD @ MAIN BAZAR MITHI TALUKA MITHI .

1.	Excavation in foundation of building bridges and other structures including dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 feet. (in ordinary soil) (G.S.I.No.18 (b) P-4). 1200.0 Cft @ Rs. 3176/25 P%o Cft	Rs. 3,812/=
2.	Borrow pit excavation undressed lead upto100 ft (a) ordinary soil. (G.S.I.No.3 (a) P-1). 6694.0 Cft @ Rs. 2117/50 P%o Cft	Rs. 14,175/=
3.	Dressing and leveling of earth work to design section etc complete (b) ordinary or hard soil) (G.S.I.No. 11 (b) P-3). 6694.0 Cft @ Rs. 187/55 P%o Cft	Rs. 1,255/=
4.	Extra for every 50 ft additional lead or part there of for earth work (soft ordinary hard and very hard). (G.S.I.No. 8 (a) P-2). 6694.0 Cft @ Rs. 4837/44 P%o Cft	Rs. 32,382/=
5.	Cement concrete brick or stone ballast 1 1/2" to 2" gauge <u>Ratio 1:4:8</u> (G.S.I.No. 4 (B) P-14). 2114.0 Cft @ Rs. 9416/28 P% Cft	Rs.1,99,060/=
6.	Erection & removal of centering for R.C.C. or plain cement concrete works of partial wood (vertical). (G.S.I.No. 19 (b)-ii P-17). 561.0 Sft @ Rs. 3127/41 P% Sft	Rs. 17,545/=
7.	Cement concrete plain i/c placing, compacting, finishing and curing, complete including screening and washing of stone aggregate without shuttering.(Ratio 1:2:4) (G.S.I.No. 5 (f) P-15). 1964.0 Cft @ Rs. 14429/25 P% Cft	Rs.2,83,390/=
8.	Pucca brick work in foundation and plinth in cement sand mortar (1:6) (G.S.I.No. 4 (e) P-19). 675.0 Cft @ Rs. 11948/36 P% Cft	Rs. 80,651/=
9.	Cement plaster (1:4) up to 12' height 1/2" thick.(G.S.I.No. 11 (b) P-51). 900.0 Sft @ Rs. 2283/93 P% Sft	Rs. 20,555/=
	Total	Rs. 6,52,825/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of Black Top Carpet Road @ Kashmir Chowk Mithi & surrounding.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

CONSTRUCTION OF BLACK TOP CARPET ROAD @ KASHMIR CHOWK MITHI & SURROUNDING

S.NO.	ITEM OF WORK	QTY:	RATE	UNIT	AMOUNT
1.	<u>EARTH WORK</u> Earth work for road embankment by bulldozers, including plugging, mixing, clod breaking dressing, compacting with optimum moisture content. Lead upto 100 ft and lift up to 5.0 ft in all types of soil except rock (If earth work is done by other than departmental agency). As per modified AASHO specifications. (95% Density).	3500.0 Cft	@ Rs. 11977/82	P%o Cft	Rs. 41,922/=
2.	<u>SUB-BASE COURSE.</u> Preparing sub-base course by supplying and spreading stone metal of 1-1/2-2" gauge of approved quality from approved quarry in required thickness (6" in 2 layers) to proper camber and grade, including hand packing, filling voids with 20 cft pit sand and non-plastic quarry fines of approved quality and gauge from approved source, watering and compacting to achieve 98-100% density as per modified AASHO specifications (Rate includes all cost of materials T& P and carriage to site of work).	3090.0 Cft	@ Rs. 11837/01	P% Cft	Rs.3,65,763/=
3.	<u>BASE COURSE.</u> Preparing base course by supplying and spreading stone metal of 1-1/2 gauge of approved quality from approved quarry in required thickness (3" in 2 layers) into proper camber and grade, including hand packing filling voids with 15 cft screening and non plastic quarry fines of approved quality and gauge from approved source, watering and compacting to achieve 98-100% density as per modified AASHO specifications (Rate includes all cost of materials T&P and carriage upto site of work).	1545.0 Cft	@ Rs. 13548/48	P% Cft	Rs.2,09,324/=
4.	<u>TWO COAT</u> Providing surface dressing 2 coats on new or existing surface with (39) lbs of bitumen 80/100 penetration and (4.25) cft crush bajri of 3/4"-3/8" gauge including cleaning the road surface rolling after each coat etc complete. Rate including all costs of materials, labour of T&P and carriage upto the site of work.	6180.0 Sft	@ Rs. 2160/93	P% Sft	Rs.1,33,545/=
5.	<u>1" THICK CARPET.</u> Providing 1" thick (consolidate) premix carpet in proper camber and grade i/c supply of 10 cft Cursh Bajri and 4 cft hill sand of approved quarry and gauge with 67 LBS of bitumen 80 to 100 penetration i/c missing in mechanical mixture in required protection i/c heating the material cleaning the road surface (Hill sand 3 cft for mixing and 2.0 cft for dusting) rate i/c all cost of materials T&P and carriage up to site of work.	6180.0 Sft	@ Rs. 4871/53	P% Sft	Rs. ,01,060/=
				Total	Rs.10,51,614/=
	Ded: 20% Below			(-)	Rs.2,10,322/=
				Net	Rs. 8,41,291/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair of Black Top Carpet road from Kashmir Chowk to Bilal Mosque.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

REPAIR OF BLACK TOP CARPET ROAD FROM KASHMIR CHOWK TO BILAL MOSQUE

S.NO.	ITEM OF WORK	QTY:	RATE	UNIT	AMOUNT
1.	<u>BASE COURSE.</u> Preparing base course i/c supplying and spreading stone metal of approved quality properly graded to maximum size of 1 ½" - 2" gauge in required thickness to proper cambers and grade i/c supplying and spreading 15 cft screenings and non plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering and compacting the same so as to achieve 100% density as per modified AASHO specifications. Rate i/c providing and using the templates camber plates, screens, forms as directed. Rate i/c all cost of materials T&P and carriage to site of work.				
	792.0 Cft	@ Rs. 12970/21	P% Cft		Rs.1,02,724/=
2.	<u>1-1/2" THICK PREMIXED CARPET.</u> Providing 1-1/2" Thick (Consolidate) premix Carpet in proper chamber and grade i/c supply of 15 Cft crush bajri and 5 cft hill sand of approved quality and gauge with 93 LBS of Bitumen of 80/100 penetration i/c mixing in mechanical mixture in required proportion i/c heating the material and cleaning the road surface rate i/c cost of material to site of work. (with Paver machine)				
	11400.0 Sft	@ Rs. 7490/72	P% Sft		<u>Rs.8,53,942/=</u>
				Total	Rs. 9,56,666/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair of Black Top Carpet road @ Dargah Siddique Shah Mithi (Part-I).**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

REPAIR OF BLACK TOP CARPET ROAD @ DARGAH SIDDIQUE SHAH MITHI (PART-I).

S.NO.	ITEM OF WORK	QTY:	RATE	UNIT	AMOUNT
1.	<u>BASE COURSE.</u> Preparing base course i/c supplying and spreading stone metal of approved quality properly graded to maximum size of 1 ½" - 2" gauge in required thickness to proper cambers and grade i/c supplying and spreading 15 cft screenings and non plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering and compacting the same so as to achieve 100% density as per modified AASHO specifications. Rate i/c providing and using the templates camber plates, screens, forms as directed. Rate i/c all cost of materials T&P and carriage to site of work.				
	792.0 Cft	@ Rs. 12970/21	P% Cft		Rs.1,02,724/=
2.	<u>1-1/2" THICK PREMIXED CARPET.</u> Providing 1-1/2" Thick (Consolidate) premix Carpet in proper chamber and grade i/c supply of 15 Cft crush bajri and 5 cft hill sand of approved quality and gauge with 93 LBS of Bitumen of 80/100 penetration i/c mixing in mechanical mixture in required proportion i/c heating the material and cleaning the road surface rate i/c cost of material to site of work. (with Paver machine).				
	11400.0 Sft	@ Rs. 7490/72	P% Sft		<u>Rs.8,53,942/=</u>
			Total		Rs. 9,56,666/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair of Black Top Carpet road @ Dargah Siddique Shah Mithi (Part-II).**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

REPAIR OF BLACK TOP CARPET ROAD @ DARGAH SIDDIQUE SHAH MITHI (PART-II).

S.NO.	ITEM OF WORK	QTY:	RATE	UNIT	AMOUNT
1.	<u>BASE COURSE.</u> Preparing base course i/c supplying and spreading stone metal of approved quality properly graded to maximum size of 1 ½" - 2" gauge in required thickness to proper cambers and grade i/c supplying and spreading 15 cft screenings and non plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering and compacting the same so as to achieve 100% density as per modified AASHO specifications. Rate i/c providing and using the templates camber plates, screens, forms as directed. Rate i/c all cost of materials T&P and carriage to site of work.				
	792.0 Cft	@ Rs. 12970/21	P% Cft		Rs.1,02,724/=
2.	<u>1-1/2" THICK PREMIXED CARPET.</u> Providing 1-1/2" Thick (Consolidate) premix Carpet in proper chamber and grade i/c supply of 15 Cft crush bajri and 5 cft hill sand of approved quality and gauge with 93 LBS of Bitumen of 80/100 penetration i/c mixing in mechanical mixture in required proportion i/c heating the material and cleaning the road surface rate i/c cost of material to site of work. (with Paver machine).				
	11400.0 Sft	@ Rs. 7490/72	P% Sft		Rs.8,53,942/=
				Total	Rs. 9,56,666/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Black Top Carpet road & C.C Block near Municipal Committee Office Mithi and surrounding.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

REPAIR/ CONSTRUCTION OF BLACK TOP CARPET ROAD & C.C BLOCK NEAR MUNICIPAL COMMITTEE OFFICE MITHI & SURROUNDING.

ABSTRACT OF COST

1.	Part -A	Repair/Construction of Black Top Road	Rs. 5,11,657/=
2.	Part-B	Repair/Construction of C.C Block	<u>Rs. 2,97,407/=</u>
		Total	Rs. 8,09,064/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

SCHEDULE "B"

PART-A REPAIR/CONSTRUCTION OF BLACK TOP ROAD

S.NO.	ITEM OF WORK	QTY:	RATE	UNIT	AMOUNT
1.	<u>BASE COURSE.</u>				
	Preparing base course i/c supplying and spreading stone metal of approved quality properly graded to maximum size of 1 ½" - 2" gauge in required thickness to proper cambers and grade i/c supplying and spreading 15 cft screenings and non plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering and compacting the same so as to achieve 100% density as per modified AASHO specifications. Rate i/c providing and using the templates camber plates, screens, forms as directed. Rate i/c all cost of materials T&P and carriage to site of work.				
	480.0 Cft	@ Rs. 12970/21	P% Cft		Rs. 62,257/=
2.	<u>1-1/2" THICK PREMIXED CARPET.</u>				
	Providing 1-1/2" Thick (Consolidate) premix Carpet in proper chamber and grade i/c supply of 15 Cft crush bajri and 5 cft hill sand of approved quality and gauge with 93 LBS of Bitumen of 80/100 penetration i/c mixing in mechanical mixture in required proportion i/c heating the material and cleaning the road surface rate i/c cost of material to site of work. (with Paver machine).				
	6000.0 Sft	@ Rs. 7490/72	P% Sft		Rs.4,49,400/=
				Total	Rs. 5,11,657/=

PART-B REPAIR/CONSTRUCTION OF C.C BLOCK

1.	Borrow pit excavation undressed lead upto 100 ft (a) ordinary soil. (G.S.I.No.3 (a) P-1).	3150.0 Cft	@ Rs. 2117/50	P% Cft	Rs. 68,819/=
2.	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (G.S.I.No. 4 (B) P-14).	924.0 Cft	@ Rs. 9416/28	P% Cft	Rs. 87,006/=
3.	Erection & removal of centering for R.C.C. or plain cement concrete works of partial wood (vertical). (G.S.I.No. 19 (b)-ii P-17).	264.0 Sft	@ Rs. 3127/41	P% Sft	Rs. 8,256/=
4.	Cement concrete plain i/c placing, compacting, finishing and curing, complete including screening and washing of stone aggregate without shuttering. (G.S.I.No. 5 (f) P-15) (Ratio 1:2:4).	924.0 Cft	@ Rs. 14429/25	P% Cft	Rs.1,33,326/=
				Total	Rs. 2,97,407/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair/ Construction of Black Top Carpet road @ different streets of Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

REPAIR/CONSTRUCTION OF BLACK TOP CARPET ROAD @ DIFFERENT STREETS OF MITHI TOWN.

S.NO.	ITEM OF WORK	QTY:	RATE	UNIT	AMOUNT
1.	<u>BASE COURSE.</u> Preparing base course i/c supplying and spreading stone metal of approved quality properly graded to maximum size of 1 ½" - 2" gauge in required thickness to proper cambers and grade i/c supplying and spreading 15 cft screenings and non plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering and compacting the same so as to achieve 100% density as per modified AASHO specifications. Rate i/c providing and using the templates camber plates, screens, forms as directed. Rate i/c all cost of materials T&P and carriage to site of work.				
	792.0 Cft	@ Rs. 12970/21	P% Cft		Rs.1,02,724/=
2.	<u>1-1/2" THICK PREMIXED CARPET.</u> Providing 1-1/2" Thick (Consolidate) premix Carpet in proper chamber and grade i/c supply of 15 Cft crush bajri and 5 cft hill sand of approved quality and gauge with 93 LBS of Bitumen of 80/100 penetration i/c mixing in mechanical mixture in required proportion i/c heating the material and cleaning the road surface rate i/c cost of material to site of work. (with Paver machine).				
	11400.0 Sft	@ Rs. 7490/72	P% Sft		Rs.8,53,942/=
			Total		Rs. 9,56,666/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Providing, Laying, Jointing and Testing PVC Pipe Line 6", 4", 3" dia for Water Supply Mithi @ different Mohalla of Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 12,00,000/= |
| c. | Earnest Money @ 2% | Rs. 24,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,20,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

PROVIDING, LAYING, JOINTING AND TESTING PVC PIPE LINE 6", 4", 3" DIA FOR WATER SUPPLY MITHI @ DIFFERENT MOHALLA OF MITHI TOWN.

1.	Dismantling and removing road metalling (G.S.I.No.51 P-13).			
	113.00 Cft	@ Rs. 605/=	P% Cft	Rs. 684/=
2.	Providing PVC pipe of Class "B" equivalent make fixing in trenches i/c cutting, fitting and jointing with Z-joint with one rubber ring i/c testing with water to head of 61 meter or 200 ft. (P.H.S.I.No.1 P-22).			
	<u>6" dia</u>			
	1000.0 Rft	@ Rs. 262/=	P.Rft	Rs.2,62,000/=
	<u>4" dia</u>			
	2000.0 Rft	@ Rs. 137/=	P.Rft	Rs.2,74,000/=
	<u>3" dia</u>			
	2000.0 Rft	@ Rs. 90/=	P.Rft	Rs.1,80,000/=
3.	C.I sluice valve heavy pattern test pressure 21 kg/sq:cm or 300 lbs/sq: inch. . (P.H.S. of Mat: Item No: 2 P-9).			
	<u>6" dia</u>			
	1 No:	@ Rs. 9360/=	Each	Rs. 9,360/=
	<u>4" dia</u>			
	1 No:	@ Rs. 5460/=	Each	Rs. 5,460/=
	<u>3" dia</u>			
	2 No:	@ Rs. 4290/=	Each	Rs. 8,580/=
4.	PVC "Z" Joint fittings. (P.H.S.O.M.Item No. 16 P-28).			
(i)	<u>PVC Tee 4" dia</u>			
	2 No:	@ Rs. 1181/=	Each	Rs. 2,362/=
(ii)	<u>PVC Tee 3" dia</u>			
	2 No:	@ Rs. 900/=	Each	Rs. 1,800/=
(iii)	<u>PVC Reducer 4" dia</u>			
	1 No:	@ Rs. 225/=	Each	Rs. 225/=
(iv)	<u>Eng Plug 3" dia</u>			
	5 No:	@ Rs. 175/=	Each	Rs. 875/=
(v)	<u>Valve socket 3" dia</u>			
	4 No:	@ Rs. 350/=	Each	Rs. 1,400/=
(vi)	<u>Valve socket 4" dia</u>			
	2 No:	@ Rs. 500/=	Each	Rs. 1,000/=
(vii)	<u>Valve socket 6" dia</u>			
	2 No:	@ Rs. 1650/=	Each	Rs. 3,300/=
(viii)	<u>PVC Bend 4" dia</u>			
	1 No:	@ Rs. 956/=	Each	Rs. 956/=
(ix)	<u>PVC Bend 3" dia</u>			
	1 No:	@ Rs. 731/=	Each	Rs. 731/=
5.	Cast iron special for A.C pressure pipe (Standard Weight A.C.I.L "B" Class) (P.H.S. of Mat: Item No: 10 P-12).			
(i)	<u>Short Piece/Tail Piece</u>			
	<u>6" dia</u>			
	2 No:	@ Rs. 618/75	Each	Rs. 1,238/=
	<u>4" dia</u>			
	2 No:	@ Rs. 487/50	Each	Rs. 975/=
	<u>3" dia</u>			
	4 No:	@ Rs. 375/=	Each	Rs. 1,500/=

6.	Jointing C.I/M.S flanged pipes and specials flanged inside trenches i/c supplying rubber packing of the required thickness nuts & bolts with washers etc and other tools required for jointing and testing the joints to the specified pressure etc complete. (P.H.S.I.No. 1 P-40).			
	<u>6" dia</u>			
	2 Joints	@ Rs. 938/=	P.Joint	Rs. 1,876/=
	<u>4" dia</u>			
	2 Joints	@ Rs. 513/=	P.Joint	Rs. 1,026/=
	<u>3" dia</u>			
	4 Joints	@ Rs. 499/=	P.Joint	Rs. 1,996/=
7.	Making joints to PVC specials fitting including laying of specials and cost of solvent cement of required diameter and testing the joints along with PVC pipe line "B", "C" and "D" class to the specified pressure and making good to all leaky joints etc complete (P.H.S.I.No. 1 P-41).			
	<u>4" dia</u>			
	5 Joints	@ Rs. 70/=	P.Joint	Rs. 350/=
	<u>3" dia</u>			
	5 Joints	@ Rs. 59/=	P.Joint	Rs. 295/=
8.	Excavation for pipe line in trenches and pits in sandy soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade. Cutting joint holes and disposal of surplus earth within a one chain as direct by Engineer Incharge providing fence guards lights, flags and temporary crossings for non-vehicular traffic wherever required lift up to 5 ft. (1.52 meter) lead upto one chain (30.5 m) (P.H.E.S.I.No. 2 P-60).			
	31000.00 Cft	@ Rs. 3750/=	P%o Cft	Rs.1,16,250/=
9.	Refilling the excavated stuff in trenches in 6" layers i/c watering and ramming to full compacting etc complete. (P.H.S.I.No 24 P-53).			
	27900.00 Cft	@ Rs. 2760/=	P%o Cft	Rs. 77,004/=
10.	Providing chamber 3' x 2' (915 x 615 mm) inside dimension 4 ½' (1372 mm) deep as per approved design for sluice valve 3" to 12" dia with 18" (457 mm) dia inside cast iron cover and frame (wt = 1 cwt 3 qr) fixed in RCC 1:2:4 (102 mm) thick (with 5 Lbs steel per cft) 9" (299 mm) thick brick masonry wall set in 1:6 cement mortar 6" (1152 mm) thick cement concrete 1:3:6 in foundation 1" (25 mm) thick cement concrete 1:2:4 flooring ½" (12.5 mm) thick cement plaster 1:3 to all inside wall surface and to top i/c providing and fixing M.S foot rest at every one foot beyond 2 ½ ft depth curing, excavation, back filling and disposal of surplus earth etc complete. (P.H.S.I.No. 1 P-49).			
	2 Nos:	@ Rs. 18820/=	Each	Rs. 37,640/=
			Total	Rs. 9,92,883/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BETWEEN RS. 2.5 MILLION TO RS. 50.0 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Providing, Laying, Jointing and Testing PVC Pipe Line 10” dia for Drainage Scheme No. 1 Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule “B” memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule “A” here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 40,00,000/= |
| c. | Earnest Money @ 2% | Rs. 80,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 4,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule “A”NIL.....

Schedule “B” attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

PROVIDING, LAYING, JOINTING AND TESTING PVC PIPE LINE 10" DIA FOR DRAINAGE SCHEME NO. 1 MITHI.

- | | | |
|-------|--|----------------|
| 1. | Dismantling and removing road metalling (G.S.I.No.51 P-13).
135.00 Cft @ Rs. 605/= P% Cft | Rs. 817/= |
| 2. | Providing PVC pipe of Class "B" equivalent make fixing in trenches i/c cutting, fitting and jointing with Z-joint with one rubber ring i/c testing with water to head of 61 meter or 200 ft. (P.H.S.I.No.1 P-22).
<u>10" dia</u>
4000.0 Rft @ Rs. 721/= P.Rft | Rs.28,84,000/= |
| 3. | C.I sluice valve heavy pattern test pressure 21 kg/sq:cm or 300 lbs/sq: inch. . (P.H.S. of Mat: Item No: 2 P-9).
<u>10" dia</u>
1 No: @ Rs. 27690/= Each | Rs. 27,690/= |
| 4. | Reflex valve heavy pattern (Test pressure 21.0 kg/sq:cm or 300 lbs/sq: inch) (imported). (P.H.S. of Mat: Item No: 6 P-10).
<u>10" dia</u>
2 No: @ Rs. 18687/50 Each | Rs. 37,375/= |
| 5. | Cast iron specials UPVC/AC pressure pipes cast iron specials for PVC/A.C pressure pipe (Standard Weight for A.C.I.L "B" Class) (P.H.S. of Mat: Item No: 14 P-12). | |
| (i) | <u>Bend 90° 10" dia</u>
1 No: @ Rs. 6662/50 Each | Rs. 6,663/= |
| (ii) | <u>Bend 45° 10" dia</u>
2 No: @ Rs. 5037/50 Each | Rs. 10,075/= |
| (iii) | <u>Short Piece 10" dia</u>
6 No: @ Rs. 2212/50 Each | Rs. 13,275/= |
| 6. | C.I Tee flange ends with holes i/c curing and facing of flanged for all size (P.H.S.I.No. 11 P-12).
1.003 Cwt @ Rs. 6096/= P.Cwt | Rs. 6,114/= |
| 7. | Jointing C.I/M.S flanged pipes and special flange inside trenches i/c supplying rubber packing of the required thickness nuts & bolts with washers etc and other tools required for jointing and testing the joints to the specified pressure etc complete. (P.H.S.I.No. 1 P-40).
<u>10" dia</u>
6 Joints @ Rs. 1576/= P.Joint | Rs. 9,456/= |
| 8. | Making joints to PVC specials fitting including laying of specials and cost of solvent cement of required diameter and testing the joints along with PVC pipe line "B", "C" and "D" class to the specified pressure and making good to all leaky joints etc complete (P.H.S.I.No. 1 P-41).
<u>10" dia</u>
3 Joints @ Rs. 138/= P.Joint | Rs. 414/= |

9.	Excavation for pipe line in trenches and pits in sandy soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade. Cutting joint holes and disposal of surplus earth within a one chain as direct by Engineer Incharge providing fence guards lights, flags and temporary crossings for non-vehicular traffic wherever required lift up to 5 ft. (1.52 meter) lead upto one chain (30.5 m) (P.H.E.S.I.No. 2 P-60). <u>10" dia</u>	40000.00 Cft	@ Rs. 3750/=	P%o Cft	Rs.1,50,000/=
10.	Refilling the excavated stuff in trenches in 6" layers i/c watering and ramming to full compacting etc complete. (P.H.S.I.No 24 P-77).	36000.00 Cft	@ Rs. 2760/=	P%o Cft	Rs. 99,360/=
11.	Providing chamber 3' x 2' (915 x 615 mm) inside dimension 4 ½' (1372 mm) deep as per approved design for sluice valve 3" to 12" dia with 18" (457 mm) dia inside cast iron cover and frame (wt = 1 cwt 3 qr) fixed in RCC 1:2:4 (102 mm) thick (with 5 Lbs steel per cft) 9" (299 mm) thick brick masonry wall set in 1:6 cement mortar 6" (1152 mm) thick cement concrete 1:3:6 in foundation 1" (25 mm) thick cement concrete 1:2:4 flooring ½" (12.5 mm) thick cement plaster 1:3 to all inside wall surface and to top i/c providing and fixing M.S foot rest at every one foot beyond 2 ½ ft depth curing, excavation, back filling and disposal of surplus earth etc complete. (P.H.S.I.No. 1 P-49).	2 Nos:	@ Rs. 18820/=	Each	<u>Rs. 37,640/=</u>
Total					Rs. 32,82,879/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BETWEEN RS. 2.5 MILLION TO RS. 50.0 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Supply/Fixing of pumping machinery Pump KSB Made and Motor 60 HP Siemens including all accessories for Drainage Scheme No-1.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 40,00,000/= |
| c. | Earnest Money @ 2% | Rs. 80,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 4,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
SUPPLYING/ FIXING OF PUMPING MACHINERY PUMP KSB MADE AND MOTOR 60 HP
SIEMENS INCLUDING ALL ACCESSORIES FOR DRAINAGE SCHEME NO.1

1.	Providing, installing and testing in position including transportation to site of work at Mithi. KSB Non-Clogging Pump type KWPZ 80/400 with flange intermediate piece and initial soft gland packing directly coupled through a flexible coupling of size 3BN-H to a SIEMENS induction totally enclosed fan cooled 60 HP/1470 RPM Electric Motor suitable for 400+/-5%/3PH/50 Hz mounted on a common base steel frame with foundation bolts mounted on common steel frame or base plate capable to give discharge 500 IGPM against a head of 180 ft i/c installing of pumping set on cement concrete foundation ratio 1:2:4 with M.S nuts and bolts of 5/8" dia to be embedded in C.C foundation including P/F star delta starter 50 ampere (Green Power) with motor control unit consist of circuit breaker main switch 40/50 amperes (Siemens) automatic star delta starter under over voltage relay, phase failure relay, ampere meter 30 amperes, volt meter 500 volts indicating lights all fixed in metallic nypere proof box. Providing internal wiring for mains with 2-7/0.044 PVC insulated wire 660 volts grade in 25 mm (1") PVC conduit fitted on surface as required including providing/fixing earthen set with 0.6 M x 0.6 M x 6.3 mm (2 ft x 2 ft x 1/4") copper plate buried in the ground at a depth of 3.7 M (12 ft) or less as per PWD specification and testing the pumping set against the required head and discharge for 72 hours etc complete.	1 Set	@ Rs. 21,89,307/=	P.Set	Rs.21,89,307/=
2.	Providing G.I Pipe, specials and clamps etc i/c fixing, cutting and fitting complete with end i/c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc with white zinc paint with pigment to match the colour of the building and testing with water to a pressure head of 200 ft and handling (P.H.S.I. No. 1 P-12). <u>4" dia</u>	26.0 Rft	@ Rs. 896/17	P.Rft	Rs. 23,300/=
3.	Providing M.S flanges made out 3/8" (10 mm) thick sheet cutting, drilling holes etc complete (R.A.A). <u>4" dia</u>	04 No:	@ Rs. 596/75	Each	Rs. 2,387/=
4.	Supplying/fixing foot valve heavy pattern with cone type gate (G.S.I.No. 4 P-12). <u>4" dia</u>	01 No:	@ Rs. 893/75	Each	Rs. 894/=
5.	C.I bend with flanged end with holes including turning and facing flanges for all size (S.M.I.No. 8P-11). <u>4" dia</u>	0.187 Cwt	@ Rs. 6096/=	P.Cwt	Rs. 1,140/=
6.	Jointing C.I/M.S flanged pipe and special and in jointing trenches i/c supply rubber packing of the required thickness nuts bolts with washier etc and other tools required for jointing and testing joint to the specified etc complete (P.H.I No. 1 P-40). <u>4" dia</u>	02 Joints	@ Rs. 513/=	P.Joint	Rs. 1,026/=
				Total	Rs. 22,17,354/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of B-Type Drain from Phuloo Chowk to Qasam Shah Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 12,00,000/= |
| c. | Earnest Money @ 2% | Rs. 24,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,20,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

CONSTRUCTION OF B-TYPE DRAIN FROM PHULOO CHOWK TO QASAM SHAH MITHI TOWN.

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 3919.0 Cft @ Rs. 2722/50 P% Cft	Rs. 10,669/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 946.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 281.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,06,792/= Rs. 40,546/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1959.0 Cft @ Rs. 11948/36 P% Cft	Rs.2,34,068/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating coat of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). 950.0 Rft @ Rs. 174/= P.Rft	Rs.1,65,300/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 4512.00 Sft @ Rs. 2283/93 P% Sft	Rs.1,03,051/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
	Total	Rs. 7,94,845/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair of Bilawal Bhutto Public Park & Replacement of Park Articles.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

REPAIR OF BILAWAL BHUTTO PUBLIC PARK & REPLACEMENT OF PARK ARTICLES.

ABSTRACT OF COST

1.	Part -A	Civil Work	Rs. 85,849/=
2.	Part-B	Replacement of Park Articles	<u>Rs. Quoted Rate</u>
		Total	Rs. 85,849/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

SCHEDULE "B"

PART-A CIVIL WORK

1.	Providing and fixing iron steel grill using solid square bars of size ½" x ½" placed at 4" i/c and frame of flat iron patti of ¾" x ¾" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3 coats with 1 st coat of red oxide paint etc. (G.S.I.No. 30 P-94).	120.0 Sft	@ Rs. 194/16	P.Sft	Rs. 27,587/=
2.	Glazed tile dado ¼" thick laid in pigment over 1:2 cement sand mortar ¾" thick including finishing. (G.S.I.No. 38 P-45).	168.0 Sft	@ Rs. 28299/30	P% Sft	Rs. 47,543/=
3.	Cement plaster (1:4) upto 12' height 3/8" thick. (G.S.I.No.11 (a) P-52).	80.00 Sft	@ Rs. 2197/52	P% Sft	Rs. 1,758/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20).	75.0 Cft	@ Rs. 11948/36	P% Cft	Rs.8,961/=
Total					Rs. 85,849/=

PART-B REPLACEMENT OF PARK ARTICLES.

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01	Slider	01 No:			
02	Swing	01 No:			
03	Bench	10 No:			
04	Horse Fiber	01 No:			
05	Double Swing	01 No:			
06	Grassing	01 Job			
07	Flower Buckets	50 No:			
08	Dust Bin	08 No:			
09	Suction Pump, Electric Motor ½ HP	01 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair & rehabilitation of Civil Work @ Drainage Scheme No: 1 Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

REPAIR & REHABILITATION OF CIVIL WORK @ DRAINAGE SCHEME NO: 1 MITHI.

1. Excavation in foundation of building bridges and other structures including dagbelling dressing, refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5 feet in sandy soil. (G.S.I.No. 18 (b) P-5).
379.00 Cft @ Rs. 2722/50 P%o Cft Rs. 1,032/=
2. Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering). (G.S.I.No. 5 P-18).
Ratio 1:4:8
924.00 Cft @ Rs. 11288/75 P% Cft Rs.1,04,308/=
- Ratio 1:2:4
569.00 Cft @ Rs. 14429/25 P% Cft Rs. 82,102/=
3. Pucca Brick work in foundation and plinth in cement sand mortar ratio (1:6) (G.S.I.No. 4 (e) P-21).
480.0 Cft @ Rs. 11948/36 P% Cft Rs. 57,352/=
4. Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also i/c of forms moulds lifting shuttering curing rendering and finishing the exposed surfaces i/c screening and washing of shingle. (c) R.C.C work in roof slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respect ratio (1:2:4) 90 lbs cement 2 cft sand and 4 cft shingles 1/8" gauge. (G.S.I.No. 6 (i) P-19).
71.30 Cft @ Rs. 337/= P.Cft Rs. 24,028/=
5. Fabrication of mild steel reinforcement for cement concrete including cutting bending, laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars. (G.S.I.No. 8 (b) P-17).
2.864 Cwt @ Rs. 5001/70 P.Cwt Rs. 14,325/=
6. Pucca brick work in ground floor in cement sand mortar (1:4) (G.S.I.No.1 (b) P-24).
138.0 Cft @ Rs. 13227/41 P% Cft Rs. 18,254/=
7. Pucca brick work other than building i/c struck joints up to 12' height in cement sand mortar (1:4). (G.S.I.No: 7 (c) P-21).
Ratio (1:4)
143.00 Cft @ Rs. 12899/70 P% Cft Rs. 18,447/=
8. Making and fixing steel grated doors with 1/16" thick sheeting i/c angle iron frame 2" x 2" x 3/8" and 3/4" squire bars 4" center to center with locking arrangement (G.S.I.No. 24 P-97).
89.50 Sft @ Rs. 726/72 P.Sft Rs. 65,041/=

9.	Dry brick on edge paving sand grouted i/ c preparation of bed by watering, ramming and brining the same to proper camber by ½" thick mud plaster (G.S.I.No: 5 P- 46).	1560.0 Sft	@ Rs. 3823/57	P% Sft	Rs. 59,648/=
10.	Cement plaster (1:6) upto 12' height ½" thick. (G.S.I.No.13 (b) P-52).	1793.00 Sft	@ Rs. 2206/60	P% Sft	Rs. 39,564/=
11.	Cement plaster (1:4) upto 12' height 3/8" thick. (G.S.I.No.11 (a) P-52).	1793.00 Sft	@ Rs. 2197/52	P% Sft	Rs. 39,402/=
12.	Providing and laying 2" thick topping concrete ratio (1:2:4) surface finishing and dividing into panels 2" thick. (G.S.I.No. 16 (c) P-42).	1090.00 Sft	@ Rs. 3275/50	P% Sft	Rs. 35,703/=
13.	Painting new surface doors and windows three coats. (G.S.I.No. 5 P-68).	300.00 Sft	@ Rs. 2116/41	P% Sft	Rs. 6,349/=
14.	White washing (a) one-coat (G.S.I.No. 26 (b) P-59).	1793.00 Sft	@ Rs. 416/63	P% Sft	Rs. 7,470/=
	(b) <u>Three Coats.</u>	120.00 Sft	@ Rs. 829/95	P% Sft	Rs. 996/=
15.	Distempering three coats (G.S.I.No.24 P-59).	2515.0 Sft	@ Rs. 1681/90	P% Sft	<u>Rs. 42,300/=</u>
				Total	Rs. 6,16,321/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair & rehabilitation of Civil Work @ Drainage Scheme No: 2 & Drainage Scheme Peetho Dargah.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"
REPAIR & REHABILITATION OF CIVIL WORK @ DRAINAGE SCHEME NO: 2 &
DRAINAGE SCHEME PEETHO DARGAH

1.	Excavation in foundation of building bridges and other structures including dagbelling dressing, refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5 feet in sandy soil. (G.S.I.No. 18 (b) P-5).	379.00 Cft	@ Rs. 2722/50	P% Cft	Rs. 1,032/=
2.	Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering). (G.S.I.No. 5 P-18). <u>Ratio 1:4:8</u>	924.00 Cft	@ Rs. 11288/75	P% Cft	Rs.1,04,308/=
	<u>Ratio 1:2:4</u>	569.00 Cft	@ Rs. 14429/25	P% Cft	Rs. 82,102/=
3.	Pucca Brick work in foundation and plinth in cement sand mortar ratio (1:6) (G.S.I.No. 4 (e) P-21).	480.0 Cft	@ Rs. 11948/36	P% Cft	Rs. 57,352/=
4.	Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also i/c of forms moulds lifting shuttering curing rendering and finishing the exposed surfaces i/c screening and washing of shingle. (c) R.C.C work in roof slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respect ratio (1:2:4) 90 lbs cement 2 cft sand and 4 cft shingles 1/8" gauge. (G.S.I.No. 6 (i) P-19).	71.30 Cft	@ Rs. 337/=	P.Cft	Rs. 24,028/=
5.	Fabrication of mild steel reinforcement for cement concrete including cutting bending, laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars. (G.S.I.No. 8 (b) P-17).	2.864 Cwt	@ Rs. 5001/70	P.Cwt	Rs. 14,325/=
6.	Pucca brick work in ground floor in cement sand mortar (1:4) (G.S.I.No.1 (b) P-24).	138.0 Cft	@ Rs. 13227/41	P% Cft	Rs. 18,254/=
7.	Pucca brick work other than building i/c struck joints up to 12' height in cement sand mortar (1:4). (G.S.I.No: 7 (c) P-21). <u>Ratio (1:4)</u>	143.00 Cft	@ Rs. 12899/70	P% Cft	Rs. 18,447/=
8.	Making and fixing steel grated doors with 1/16" thick sheeting i/c angle iron frame 2" x 2" x 3/8" and 3/4" squire bars 4" center to center with locking arrangement (G.S.I.No. 24 P-97).	89.50 Sft	@ Rs. 726/72	P.Sft	Rs. 65,041/=

9.	Dry brick on edge paving sand grouted i/ c preparation of bed by watering, ramming and brining the same to proper camber by ½" thick mud plaster (G.S.I.No: 5 P- 46).	1560.0 Sft	@ Rs. 3823/57	P% Sft	Rs. 59,648/=
10.	Cement plaster (1:6) upto 12' height ½" thick. (G.S.I.No.13 (b) P-52).	1793.00 Sft	@ Rs. 2206/60	P% Sft	Rs. 39,564/=
11.	Cement plaster (1:4) upto 12' height 3/8" thick. (G.S.I.No.11 (a) P-52).	1793.00 Sft	@ Rs. 2197/52	P% Sft	Rs. 39,402/=
12.	Providing and laying 2" thick topping concrete ratio (1:2:4) surface finishing and dividing into panels 2" thick. (G.S.I.No. 16 (c) P-42).	1090.00 Sft	@ Rs. 3275/50	P% Sft	Rs. 35,703/=
13.	Painting new surface doors and windows three coats. (G.S.I.No. 5 P-68).	300.00 Sft	@ Rs. 2116/41	P% Sft	Rs. 6,349/=
14.	White washing (a) one-coat (G.S.I.No. 26 (b) P-59).	1793.00 Sft	@ Rs. 416/63	P% Sft	Rs. 7,470/=
	(b) <u>Three Coats.</u>	120.00 Sft	@ Rs. 829/95	P% Sft	Rs. 996/=
15.	Distempering three coats (G.S.I.No.24 P-59).	2515.0 Sft	@ Rs. 1681/90	P% Sft	<u>Rs. 42,300/=</u>
				Total	Rs. 6,16,321/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair & Rehabilitation of Pumping Machinery including Replacement of Pipe & Cable for Drainage Scheme No: 1 Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

**REPAIR & REHABILITATION OF PUMPING MACHINERY INCLUDING REPLACEMENT OF
PIPE & CABLE FOR DRAINAGE SCHEME NO: 1 MITHI**

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01	Repair of Motor 50 HP.	02 No:			
02	G.I Pipe 6" dia	60 ft			
03	Cable 4-core 19/52	50 ft			
04	Bearing SKT for Motor	04 No:			
05	Screening Chamber Jali 6' x 8'	02 No:			
06	Greasing of Pump Motor	02 Job			
07	Repair of Panel Board	02 No:			
08	Non-Return Valve 6" dia	03 No:			
09	C.I Sluice valve 6" dia	03 No:			
10	C.I Bend 6" dia	06 No:			
11	C.I Flung 6" dia	24 No:			
12	Rubber Packing	60 No:			
13	Galvanized Nut Bolts	01 Job			
14	C.I foot valve 6" dia	02 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair & Rehabilitation of Pumping Machinery including Replacement of Pipe & Cable for Drainage Scheme No: 2 Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

**REPAIR & REHABILITATION OF PUMPING MACHINERY INCLUDING REPLACEMENT OF
PIPE & CABLE FOR DRAINAGE SCHEME NO: 2 MITHI**

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01	Repair of Motor 50 HP.	02 No:			
02	G.I Pipe 6" dia	60 ft			
03	Cable 4-core 19/52	50 ft			
04	Bearing SKT for Motor	04 No:			
05	Screening Chamber Jali 6' x 8'	02 No:			
06	Greasing of Pump Motor	02 Job			
07	Repair of Panel Board	02 No:			
08	Non-Return Valve 6" dia	03 No:			
09	C.I Sluice valve 6" dia	03 No:			
10	C.I Bend 6" dia	06 No:			
11	C.I Flung 6" dia	24 No:			
12	Rubber Packing	60 No:			
13	Galvanized Nut Bolts	01 Job			
14	C.I foot valve 6" dia	02 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair & Rehabilitation of Civil Work @ Water Supply Schemes in Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

REPAIR & REHABILITATION OF CIVIL WORK @ WATER SUPPLY SCHEMES MITHI TOWN.

1. Excavation in foundation of building bridges and other structures including dagbelling dressing, refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5 feet in sandy soil. (G.S.I.No. 18 (b) P-5).
379.00 Cft @ Rs. 2722/50 P%o Cft Rs. 1,032/=
2. Cement concrete plain including placing, compacting, finishing and curing complete (including screening and washing of stone aggregate without shuttering). (G.S.I.No. 5 P-18).
Ratio 1:4:8
924.00 Cft @ Rs. 11288/75 P% Cft Rs.1,04,308/=
- Ratio 1:2:4
569.00 Cft @ Rs. 14429/25 P% Cft Rs. 82,102/=
3. Pucca Brick work in foundation and plinth in cement sand mortar ratio (1:6) (G.S.I.No. 4 (e) P-21).
480.0 Cft @ Rs. 11948/36 P% Cft Rs. 57,352/=
4. Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also i/c of forms moulds lifting shuttering curing rendering and finishing the exposed surfaces i/c screening and washing of shingle. (c) R.C.C work in roof slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respect ratio (1:2:4) 90 lbs cement 2 cft sand and 4 cft shingles 1/8" gauge. (G.S.I.No. 6 (i) P-19).
71.30 Cft @ Rs. 337/= P.Cft Rs. 24,028/=
5. Fabrication of mild steel reinforcement for cement concrete including cutting bending, laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars. (G.S.I.No. 8 (b) P-17).
2.864 Cwt @ Rs. 5001/70 P.Cwt Rs. 14,325/=
6. Pucca brick work in ground floor in cement sand mortar (1:4) (G.S.I.No.1 (b) P-24).
138.0 Cft @ Rs. 13227/41 P% Cft Rs. 18,254/=
7. Pucca brick work other than building i/c struck joints up to 12' height in cement sand mortar (1:4). (G.S.I.No: 7 (c) P-21).
Ratio (1:4)
143.00 Cft @ Rs. 12899/70 P% Cft Rs. 18,447/=
8. Making and fixing steel grated doors with 1/16" thick sheeting i/c angle iron frame 2" x 2" x 3/8" and 3/4" squire bars 4" center to center with locking arrangement (G.S.I.No. 24 P-97).
89.50 Sft @ Rs. 726/72 P.Sft Rs. 65,041/=

9.	Dry brick on edge paving sand grouted i/ c preparation of bed by watering, ramming and brining the same to proper camber by ½" thick mud plaster (G.S.I.No: 5 P- 46).	1560.0 Sft	@ Rs. 3823/57	P% Sft	Rs. 59,648/=
10.	Cement plaster (1:6) upto 12' height ½" thick. (G.S.I.No.13 (b) P-52).	1793.00 Sft	@ Rs. 2206/60	P% Sft	Rs. 39,564/=
11.	Cement plaster (1:4) upto 12' height 3/8" thick. (G.S.I.No.11 (a) P-52).	1793.00 Sft	@ Rs. 2197/52	P% Sft	Rs. 39,402/=
12.	Providing and laying 2" thick topping concrete ratio (1:2:4) surface finishing and dividing into panels 2" thick. (G.S.I.No. 16 (c) P-42).	1090.00 Sft	@ Rs. 3275/50	P% Sft	Rs. 35,703/=
13.	Painting new surface doors and windows three coats. (G.S.I.No. 5 P-68).	300.00 Sft	@ Rs. 2116/41	P% Sft	Rs. 6,349/=
14.	White washing (a) one-coat (G.S.I.No. 26 (b) P-59).	1793.00 Sft	@ Rs. 416/63	P% Sft	Rs. 7,470/=
	(b) <u>Three Coats.</u>	120.00 Sft	@ Rs. 829/95	P% Sft	Rs. 996/=
15.	Distempering three coats (G.S.I.No.24 P-59).	2515.0 Sft	@ Rs. 1681/90	P% Sft	<u>Rs. 42,300/=</u>
				Total	Rs. 6,16,321/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair & Rehabilitation of Pumping Machinery for Water Supply Scheme No: 1, 2 & 3 Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

**REPAIR & REHABILITATION OF PUMPING MACHINERY FOR
WATER SUPPLY SCHEME NO: 1, 2 & 3 MITHI TOWN**

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01	Repair of Supply Motor: 30 HP	03 No:			
	20 HP	04 No:			
	10 HP	02 No:			
02	Repair of Panel Board	06 No:			
03	G.I Pipe 6" dia	120 ft			
	4" dia	60 ft			
04	Foot valve Brass 4" dia	06 No:			
05	M.S Valve 6" dia	06 No:			
	4" dia	10 No:			
	3" dia	12 No:			
06	Supplying/fixing KSB Pump 65/20 ETA complete	03 No:			
07	Repair of Tube Well Panel Boards	06 No:			
08	Supplying/fixing Tube Well G.I Pipe 2" dia i/c Nut Bolts & flange welded packing.	90 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Repair & Rehabilitation of Pumping Machinery for Water Supply Scheme No: 4, 5 & 6 Mithi Town.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

**REPAIR & REHABILITATION OF PUMPING MACHINERY FOR
WATER SUPPLY SCHEME NO: 4, 5 & 6 MITHI TOWN**

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01	Repair of Supply Motor: 30 HP	01 No:			
	20 HP	02 No:			
02	Supplying/fixing KSB Pump 65/20 ETA complete	02 No:			
03	Repair of Panel Board	04 No:			
04	G.I Pipe 6" dia	120 ft			
	4" dia	60 ft			
05	Foot valve	04 No:			
06	Non-Return valve 6" dia	02 No:			
	4" dia	04 No:			
	3" dia	06 No:			
07	Supplying/fixing Tube Well G.I Pipe 2" dia i/c Nut Bolts & flange welded packing.	50 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of Screening Chamber including Pipe line at Drainage Scheme No.1 Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

CONSTRUCTION OF SCREENING CHAMBER INCLUDING PIPE LINE @ DRAINAGE SCHEME NO: 1 MITHI

- | | | | | | |
|----|--|------------|----------------|---------|---------------|
| 1. | Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to one chain lift up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). | 1944.0 Cft | @ Rs. 2722/50 | P%o Cft | Rs. 5,293/= |
| 2. | Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-18).
<u>(1:4:8)</u> | 81.0 Cft | @ Rs. 11288/75 | P% Cft | Rs. 9,144/= |
| 3. | Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). | 708.0 Cft | @ Rs. 337/= | P.Cft | Rs.2,38,596/= |
| 4. | Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.8 (b) P-17). | 28.446 Cwt | @ Rs. 5001/70 | P.Cwt | Rs.1,42,278/= |
| 5. | Cement plaster (1:3) up to 12' height 1/2" thick.(G.S.I.No.10 P-52). | 520.00 Sft | @ Rs. 2344/59 | P% Sft | Rs. 12,192/= |
| 6. | Fabrication of heavy steel work with angles, tees, flat iron, iron and sheet iron for making trusses, girders, tanks etc, including cutting riveting, handing assembling and fixing but eluding erection in position. (G.S.I.No.2 P-91). | 1.67 Cwt | @ Rs. 4928/49 | P.Cwt | Rs. 8,231/= |
| 7. | Erection and fitting in position of iron tresses, staging of water tank etc. (G.S.I.No.3 P-91). | 1.67 Cwt | @ Rs. 271/04 | P.Cwt | Rs. 453/= |
| 8. | Excavation for pipe line in trenches and pits in sandy soils i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade. Cutting joint holes and disposal of surplus earth within a one chain as direct by Engineer Incharge providing fence guards lights, flags and temporary crossings for non-vehicular traffic wherever required lift up to 5 ft. (1.52 meter) lead upto one chain (30.5 m) (P.H.E.S.I.No. 2 P-60). | 168.00 Cft | @ Rs. 3750/= | P%o Cft | Rs. 630/= |

9.	Providing R.C.C pipes of A.S.T.M-C-76-62 T/C-76-70 Class-II Wall B and fixing in trenches i/c cutting, fitting and jointing with rubber ring i/c testing with water to specified pressure. (P.H.E.S.I.No. 1 (b) P-17). <u>12" dia</u> 16.0 Rft	@ Rs. 412/=	P.Rft	Rs. 6,592/=
10.	Supplying and embedding .CI foot steps of approved design weight not less than 15 Lbs (R.A Approved). 19 No:	@ Rs. 181/65	Each	Rs. 3,451/=
11.	Refilling the excavated stuff in trenches 6" thick layer i/c watering, ramming, to full compaction etc complete. (P.H.S.I No. 24 P-77). 151.0 Cft	@ Rs. 2760/=	P%o Cft	<u>Rs. 417/=</u>
Total				Rs. 4,27,277/=
Schedule-B Amount of 01 No: Screening Chamber = Rs. 4,27,277/=				
Schedule-B Amount of 02 No: Screening Chamber				
02 No:				Rs. 8,54,554/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of Waiting Shed and Wizu Khana at Markazi Imam Bargah Shoaib-Abu-Talib (A.S) Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

**CONSTRUCTION OF WAITING SHED AND WIZU KHANA @
MARKAZI IMAM BARGAH SHOAB ABU TALIB (A.S) MITHI.**

1. Excavation in foundation of building bridges and other structures including dagbelling dressing, refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5 feet in sandy soil. (G.S.I.No. 18 (b) P-4).
522.00 Cft @ Rs. 3176/25 P%o Cft Rs. 1,658/=
2. Cement concrete brick or stone ballast 1 ½"to 2" gauge Ratio 1:6:12 (G.S.I.No. 4 (d) P-15).
249.00 Cft @ Rs. 8122/25 P% Cft Rs. 20,226/=
3. Pucca Brick work in foundation and plinth in cement sand mortar ratio (1:6) (G.S.I.No. 4 (e) P-21).
415.0 Cft @ Rs. 11948/36 P% Cft Rs. 49,586/=
4. Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also i/c of forms moulds lifting shuttering curing rendering and finishing the exposed surfaces i/c screening and washing of shingle. (c) R.C.C work in roof slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respect ratio (1:2:4) 90 lbs cement 2 cft sand and 4 cft shingles 1/8"guage. (G.S.I.No. 6 (i) P-19).
131.00 Cft @ Rs. 337/= P.Cft Rs. 44,147/=
5. Earth filling, watering and ramming earth under floor with new earth excavated from outside lead up to one chain and lift up to 5 feet (G.S.I.No. 22 P-5).
243.00 Cft @ Rs. 3630/= P%o Cft Rs. 882/=
6. Pucca brick work in ground floor in cement sand mortar (1:6) (G.S.I.No.1 (b) P-24).
583.0 Cft @ Rs. 11948/36 P% Cft Rs. 69,659/=
7. Fabrication of mild steel reinforcement for cement concrete including cutting bending, laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars. (G.S.I.No. 8 (b) P-17).
5.26 Cwt @ Rs. 5001/70 P.Cwt Rs. 26,309/=
8. Supplying & Fixing M.S Girder size 8" x 4" (Sch: of Mat: Item No: 140 P-72).
8.25 Cwt @ Rs. 3850/= P.Cwt Rs. 31,763/=
9. Supplying & fixing T-Iron. (S.M. I. No. 144 P-72).
7.52 Cwt @ Rs. 3575/= P.Cwt Rs. 26,884/=

10.	Erecting rolled steel beams or rails erection for posts etc (other than in roof). (G.S.I.No. 6 P-09).	15.77 Cwt	@ Rs. 186/34	P.Cwt	Rs. 2,939/=
11.	1 st class tile roofing consisting of 4" earth and 1" mud plaster with gobri leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand witched layer of 1:6 cement pointing under side of tiles complete including curing etc. (G.S.I.No. 1 P-33).	420.00 Sft	@ Rs. 11443/10	P% Sft	Rs. 48,061/=
12.	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proofing as per specification and instructions of Engineer Incharge. (G.S.I.No. 41 P-38).	420.00 Sft	@ Rs. 10/70	P.Sft	Rs. 4,494/=
13.	Cement plaster (1:6) upto 12' height 1/2" thick. (G.S.I.No.13 (b) P-52).	1886.00 Sft	@ Rs. 2206/60	P% Sft	Rs. 41,616/=
14.	Cement plaster (1:4) upto 12' height 3/8" thick. (G.S.I.No.11 (a) P-52).	1886.00 Sft	@ Rs. 2197/52	P% Sft	Rs. 41,445/=
15.	Providing and laying 2" thick topping concrete ratio (1:2:4) surface finishing and dividing into panels 2" thick. (G.S.I.No. 16 (c) P-42).	340.00 Sft	@ Rs. 3275/50	P% Sft	Rs. 11,137/=
16.	White washing three coats (G.S.I.No. 26 (c) P-54).	340.00 Sft	@ Rs. 829/95	P% Sft	Rs. 2,822/=
17.	Primary coat of chalk distemper (G.S.I.No.23 P-34).	1886.00 Sft	@ Rs. 442/75	P% Sft	Rs. 8,350/=
18.	Distemping three coats (G.S.I.No.24 P-54).	1886.0 Sft	@ Rs. 2116/=	P% Sft	Rs. 39,908/=
19.	Painting new surface preparing surface and painting guard bars (G.S.I.No.4 P-68).	361.00 Sft	@ Rs. 1489/68	P% Sft	Rs. 5,378/=
20.	Providing G.I Pipes, specials, and clamps etc including fixing cutting & fitting complete with and i/c the cost of breaking through walls and roof, making good etc painting two coats after cleaning the pipe etc with white zink paint with pigment to match the colours of the building and testing with water to a pressure head of 200 feet and handling. (W/Sant. Sch: I No. 1 P-12).				
	<u>3/4" dia</u>	150.0 Rft	@ Rs. 95/79	P.Rft	Rs. 14,368/=
	<u>1/2" dia</u>	50.0 Rft	@ Rs. 73/21	P.Rft	Rs. 1,860/=
	<u>2" dia</u>	10.0 Rft	@ Rs. 233/=	P.Rft	Rs. 2,330/=

21.	Painting of G.I Pipe with 2 coats of zink paint for internal fittings. (W/Sant. Sch: I No. 3 P-13).			
	<u>3/4" dia</u>			
	150.0 Rft	@ Rs. 4/=	P.Rft	Rs. 600/=
	<u>1/2" dia</u>			
	50.0 Rft	@ Rs. 3/=	P.Rft	Rs. 150/=
	<u>2" dia</u>			
	10.0 Rft	@ Rs. 7/=	P.Rft	Rs. 70/=
22.	Supplying and fixing bib cock (W/Sant. Sch: I No. 2 (I) (a) P-16).			
	10 No:	@ Rs. 150/92	Each	Rs. 1,509/=
23.	Providing & fixing full way gun metal valves with wheels, threaded or flanged ends with rubber washing (W/Sant. Sch: I No. 4 (A) P-17).			
	<u>3/4" dia</u>			
	01 No:	@ Rs. 197/12	Each	Rs. 197/=
			Total	Rs. 4,98,348/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of Water Tank and Wash Rooms at Markazi Imam Bargah Shoaib-Abu-Talib (A.S) Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

**CONSTRUCTION OF WATER TANK AND WASH ROOMS @
MARKAZI IMAM BARGAH SHOAB ABU TALIB (A.S) MITHI.**

1. Excavation in foundation of building bridges and other structures including dagbelling dressing, refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5 feet in sandy soil. (G.S.I.No. 18 (b) P-4).
163.00 Cft @ Rs. 3176/25 P%o Cft Rs. 518/=
2. Cement concrete brick or stone ballast 1 ½"to 2" gauge Ratio 1:6:12 (G.S.I.No. 4 (d) P-15).
46.00 Cft @ Rs. 8122/25 P% Cft Rs. 3,736/=
3. Pucca Brick work in foundation and plinth in cement sand mortar ratio (1:6) (G.S.I.No. 4 (e) P-21).
125.0 Cft @ Rs. 11948/36 P% Cft Rs. 14,935/=
4. Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also i/c of forms moulds lifting shuttering curing rendering and finishing the exposed surfaces i/c screening and washing of shingle. (c) R.C.C work in roof slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respect ratio (1:2:4) 90 lbs cement 2 cft sand and 4 cft shingles 1/8"guage. (G.S.I.No. 6 (i) P-19).
69.00 Cft @ Rs. 337/= P.Cft Rs. 23,253/=
5. Earth filling, watering and ramming earth under floor with new earth excavated from outside lead up to one chain and lift up to 5 feet (G.S.I.No. 22 P-5).
71.00 Cft @ Rs. 3630/= P%o Cft Rs. 258/=
6. Pucca brick work in ground floor in cement sand mortar (1:6) (G.S.I.No.1 (b) P-24).
259.0 Cft @ Rs. 11948/36 P% Cft Rs. 30,946/=
7. Fabrication of mild steel reinforcement for cement concrete including cutting bending, laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars. (G.S.I.No. 8 (b) P-17).
2.77 Cwt @ Rs. 5001/70 P.Cwt Rs. 13,855/=
8. Supplying & fixing T-Iron. (S.M. I. No. 144 P-72).
1.22 Cwt @ Rs. 3575/= P.Cwt Rs. 4,361/=
9. Erecting rolled steel beams or rails erection for posts etc (other than in roof). (G.S.I.No. 6 P-09).
1.22 Cwt @ Rs. 186/34 P.Cwt Rs. 227/=

10.	1 st class tile roofing consisting of 4" earth and 1" mud plaster with gobi leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand witched layer of 1:6 cement pointing under side of tiles complete including curing etc. (G.S.I.No. 1 P-33).	71.00 Sft	@ Rs. 11443/10	P% Sft	Rs. 8,125/=
11.	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proofing as per specification and instructions of Engineer Incharge. (G.S.I.No. 41 P-38).	71.00 Sft	@ Rs. 10/70	P.Sft	Rs. 760/=
12.	Cement plaster (1:6) upto 12' height 1/2" thick. (G.S.I.No.13 (b) P-52).	613.00 Sft	@ Rs. 2206/60	P% Sft	Rs. 13,526/=
13.	Cement plaster (1:4) upto 12' height 3/8" thick. (G.S.I.No.11 (a) P-52).	613.00 Sft	@ Rs. 2197/52	P% Sft	Rs. 13,471/=
14.	Providing and laying 2" thick topping concrete ratio (1:2:4) surface finishing and dividing into panels 2" thick. (G.S.I.No. 16 (c) P-42).	48.00 Sft	@ Rs. 3275/50	P% Sft	Rs. 1,572/=
15.	White washing three coats (G.S.I.No. 26 (c) P-54).	48.00 Sft	@ Rs. 829/95	P% Sft	Rs. 398/=
16.	Primary coat of chalk distemper (G.S.I.No.23 P-34).	613.00 Sft	@ Rs. 442/75	P% Sft	Rs. 2,714/=
17.	Distempering three coats (G.S.I.No.24 P-54).	613.0 Sft	@ Rs. 2116/=	P% Sft	Rs. 12,971/=
18.	Painting new surface preparing surface and painting guard bars (G.S.I.No.4 P-68).	92.00 Sft	@ Rs. 1489/68	P% Sft	Rs. 1,371/=
19.	P/F European white glazed earthenware wash dawn W.C pan complete with and i/c the cost of white back plastic seat (Best Quality) and lid with C.P brass hinges and buffers, 3 gallon white glazed earthenware low level foushing cistern with Sighon fitting 1/2" dia white porcelain enameled flush band 3/4" dia and making required number etc complete (W/Sant. Sch: I No. 1 A P-1).	2 No:	@ Rs. 5044/60	Each	Rs. 10,089/=
20.	Providing G.I Pipes, specials, and clamps etc including fixing cutting & fitting complete with and i/c the cost of breaking through walls and roof, making good etc painting two coats after cleaning the pipe etc with white zink paint with pigment to match the colours of the building and testing with water to a pressure head of 200 feet and handling. (W/Sant. Sch: I No. 1 P-12).	<u>3/4" dia</u> 50.0 Rft	@ Rs. 95/79	P.Rft	Rs. 4,789/=
		<u>1/2" dia</u> 30.0 Rft	@ Rs. 73/21	P.Rft	Rs. 2,196/=

21.	Painting of G.I Pipe with 2 coats of zink paint for internal fittings. (W/Sant. Sch: I No. 3 P-13).			
	<u>3/4" dia</u>			
	50.0 Rft	@ Rs. 4/=	P.Rft	Rs. 200/=
	<u>1/2" dia</u>			
	30.0 Rft	@ Rs. 3/=	P.Rft	Rs. 90/=
22.	Supplying and fixing bib cock (W/Sant. Sch: I No. 2 (I) (a) P-16).			
	2 No:	@ Rs. 150/92	Each	Rs. 302/=
23.	Providing & fixing full way gun metal valves with wheels, threaded or flanged ends with rubber washing (W/Sant. Sch: I No. 4 (A) P-17).			
	<u>3/4" dia</u>			
	01 No:	@ Rs. 197/12	Each	Rs. 197/=
24.	Supplying/fixing 1 st class deodar wood wrought joinery in doors and windows etc fixed in position i/c chowkats hold fasts hinges iron tower bolts chocks cleats, handles and cords with hooks etc (G.S.I.No. 7 (b) P-58).			
	40.0 Sft	@ Rs. 1273/76	P.Sft	<u>Rs. 50,950/=</u>
			Total	Rs. 2,15,810/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of Office Rooms in Municipal Committee Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

REPAIR/CONSTRUCTION OF OFFICE ROOMS IN MUNICIPAL COMMITTEE MITHI.

1. Dismantling pucca brick work in lime or cement mortar. (G.S.I.No. 13 P-10).
1488.0 Cft @ Rs. 1285/63 P% Cft Rs. 19,130/=
2. Pucca Brick work in foundation and plinth in cement sand mortar ratio (1:6) (G.S.I.No. 4 (e) P-21).
780.0 Cft @ Rs. 11948/36 P% Cft Rs. 93,197/=
3. Providing and laying 2" thick topping concrete ratio (1:2:4) surface finishing and dividing into panels 2" thick. (G.S.I.No. 16 (c) P-42).
1432.00 Sft @ Rs. 3275/50 P% Sft Rs. 46,905/=
4. 1st class tile roofing consisting of 4" earth and 1" mud plaster with gobri leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand witched layer of 1:6 cement pointing under side of tiles complete including curing etc. (G.S.I.No. 1 P-33).
1588.00 Sft @ Rs. 11443/10 P% Sft Rs.1,81,716/=
5. Providing and laying single per layer of polythene sheet 0.13 mm thick for water proofing as per specification and instructions of Engineer Incharge. (G.S.I.No. 41 P-38).
1488.00 Sft @ Rs. 10/70 P.Sft Rs. 15,922/=
6. Supplying & Fixing M.S Girder size 8" x 4" (Sch: of Mat: Item No: 140 P-72).
39.50 Cwt @ Rs. 3850/= P.Cwt Rs.1,52,075/=
7. Supplying & fixing T-Iron. (S.M. I. No. 144 P-72).
17.27 Cwt @ Rs. 3575/= P.Cwt Rs. 61,740/=
8. Cement plaster (1:4) upto 12' height 1/2" thick. (G.S.I.No.11 (b) P-52).
3520.00 Sft @ Rs. 2283/93 P% Sft Rs. 80,394/=
9. Cement plaster (1:4) upto 12' height 3/8" thick. (G.S.I.No.11 (a) P-52).
3520.00 Sft @ Rs. 3015/76 P% Sft Rs.1,06,155/=
10. Supplying & fixing in position Aluminum channels framing for hinged doors or Alcop made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan) locks i/c handles stoppers etc. (b) Dlux model (Bronze). (G.S.I.No. 83 P-108).
56.00 Sft @ Rs. 1507/66 P.Sft Rs. 84,426/=
11. Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen, i/c handles stoppers & locking arrangement etc complete. (b) Dlux model (Bronze). (G.S.I.No. 84 P-108).
36.00 Sft @ Rs. 1647/69 P.Sft Rs. 59,317/=

12.	Laying floors of approved coloured glazed tiles ¼" thick laid in white cement and pigment on a bed of ¾" thick cement mortar 1:2 (G.S.I.No. 25 P-43).	230.00 Sft	@ Rs. 27747/06	P% Sft	Rs. 63,818/=
13.	Providing and fixing iron steel grill door with angle iron frame of 1 ½" x 1 ½" x ¼" and flat iron ¾" x ¼" with approved design and locking arrangement embedded in masonry as per instruction of Engineer Incharge. (G.S.I.No. 30 P-93).	88.0 Sft	@ Rs. 194/16	P.Sft	<u>Rs. 17,086/=</u>
				Total	<u>Rs. 9,81,881/=</u>

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of A-Type Drain @ East Bajeer & Rajar Paro Mithi**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

CONSTRUCTION OF A-TYPE DRAIN @ EAST BAJEER & RAJAR PARO MITHI.

1.	Dismantling of brick work in cement mortar (G.S.I.No.13 P-10). 38.0 Cft @ Rs. 1285/63 P% Cft	Rs. 489/=
2.	Excavation in foundation of building bridges and other structures including Dag belling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (in sand, ashes or loose sand). (G.S.I.No.18 (a) P-4). 2609.0 Cft @ Rs. 2722/50 P% Cft	Rs. 7,103/=
3.	Cement concrete plain i/c placing, compacting, finishing and curing complete including screening and washing of stone aggregate without shuttering. Ratio (1:4:8) (G.S.I.No.5 (i) P-15). <u>(1:4:8)</u> 1078.0 Cft @ Rs. 11288/75 P% Cft <u>(1:2:4)</u> 312.0 Cft @ Rs. 14429/25 P% Cft	Rs.1,21,693/= Rs. 45,019/=
4.	Pucca brick work in foundation and plinth in cement sand mortar (1:6).(G.S.I.No.4, P-20). 1576.0 Cft @ Rs. 11948/36 P% Cft	Rs.1,88,306/=
5.	Constructing of standard open drain connote block of cement concrete (1:2:4) in situ to the design profile including cost of mould as per drawing including applying floating coat of cement 1/32" thick to the exposed face finished smooth curing etc complete as per detailed drawing. (P.H.S.I.No. (D) P-44). 1100.0 Rft @ Rs. 94/= P.Rft	Rs.1,03,400/=
6.	Cement plaster (1:4) up to 12' height 1/2" thick. (G.S.I.No.11 (b) P-51). 3025.00 Sft @ Rs. 2283/93 P% Sft	Rs. 69,089/=
7.	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). (a) R.C. work in roof slab, beams columns rafts. Lintels and other structural members laid in situ or pre-cast laid in position completed in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft sand 4 Cft shingle 1/8" to 1/4" gauge. (G.S.I.No. 6 P-16). 249.0 Cft @ Rs. 337/= P.Cft	Rs. 83,913/=
8.	Fabrication of mild steel reinforcement for cement concrete including cutting, bending, Laying in position making joints and fastenings including cost of binding wire (also i/c removal of rust from bars (G.S.I.No.7 (ii) P-16). 10.00 Cwt @ Rs. 5001/70 P.Cwt	Rs. 50,017/=
	Total	Rs. 6,69,029/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of Officer Residence @ Water Supply Scheme No: 7 By-Pass Road Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

CONSTRUCTION OF OFFICER RESIDENCE @ WATER SUPPLY SCHEME NO: 7 BY-PASS ROAD MITHI.

1. Excavation in foundation of building bridges and other structures including dagbelling dressing, refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5 feet in sandy soil. (G.S.I.No. 18 (b) P-4).
1168.00 Cft @ Rs. 3176/25 P% Cft Rs. 3,710/=
2. Cement concrete brick or stone ballast 1 ½"to 2" gauge Ratio 1:4:8 (G.S.I.No. 4 (b) P-14).
405.00 Cft @ Rs. 9416/28 P% Cft Rs. 38,136/=
3. Pucca Brick work in foundation and plinth in cement sand mortar ratio (1:6) (G.S.I.No. 4 (e) P-21).
1542.0 Cft @ Rs. 11948/36 P% Cft Rs.1,84,244/=
4. Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also i/c of forms moulds lifting shuttering curing rendering and finishing the exposed surfaces i/c screening and washing of shingle. (c) R.C.C work in roof slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respect ratio (1:2:4) 90 lbs cement 2 cft sand and 4 cft shingles 1/8"guage. (G.S.I.No. 6 (i) P-19).
304.00 Cft @ Rs. 337/= P.Cft Rs.1,02,448/=
5. Fabrication of mild steel reinforcement for cement concrete including cutting bending, laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars. (G.S.I.No. 8 (b) P-17).
12.21 Cwt @ Rs. 5001/70 P.Cwt Rs. 61,071/=
6. Pucca brick work in ground floor in cement sand mortar (1:6) (G.S.I.No.5 (i) (c) P-20).
1574.0 Cft @ Rs. 12674/36 P% Cft Rs.1,99,494/=
7. Supplying & Fixing M.S Girder size 8" x 4" (Sch: of Mat: Item No: 140 P-72).
16.0 Cwt @ Rs. 3850/= P.Cwt Rs. 61,600/=
8. Supplying & fixing T-Iron. (S.M. I. No. 144 P-72).
12.46 Cwt @ Rs. 3575/= P.Cwt Rs. 44,545/=
9. Erecting rolled steel beams or rails erection for posts etc (other than in roof). (G.S.I.No. 6 P-09).
28.46 Cwt @ Rs. 186/34 P.Cwt Rs. 5,303/=
10. Supplying & fixing in position Aluminum channels framing for hinged doors or Alcop made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan) locks i/c handles stoppers etc. (b) Dlux model (Bronze). (G.S.I.No. 83 P-108).
91.00 Sft @ Rs. 1507/66 P.Sft Rs.1,37,197/=

11.	Supplying & fixing in position Aluminum channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminum fly screen, i/c handles stoppers & locking arrangement etc complete. (b) Dlux model (Bronze). (G.S.I.No. 84 P-108). 96.00 Sft @ Rs. 1647/69 P.Sft	Rs.1,58,178/=
12.	Laying floors of approved coloured glazed tiles ¼" thick laid in white cement and pigment on a bed of ¾" thick cement mortar 1:2 (G.S.I.No. 25 P-43). 520.00 Sft @ Rs. 27747/06 P% Sft	Rs.1,44,285/=
13.	Glazed tile dado ¼" thick laid in pigment over 1:2 cement sand mortar ¾" thick including finishing. (G.S.I.No. 38 P-45). 288.00 Sft @ Rs. 28299/30 P% Sft	Rs. 81,502/=
14.	Cement plaster (1:4) upto 12' height ½" thick. (G.S.I.No.11 (b) P-52). 3561.00 Sft @ Rs. 2283/93 P% Sft	Rs. 81,331/=
15.	Cement plaster (1:4) upto 12' height 3/8" thick. (G.S.I.No.11 (a) P-52). 3561.00 Sft @ Rs. 2197/52 P% Sft	Rs. 78,254/=
16.	Providing and laying 3" thick topping concrete ratio (1:2:4) surface finishing and dividing into panels 2" thick. (G.S.I.No. 16 P-42). 260.00 Sft @ Rs. 4411/82 P% Sft	Rs. 11,471/=
17.	1 st class tile roofing consisting of 4" earth and 1" mud plaster with gobi leeping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand witched layer of 1:6 cement pointing under side of tiles complete including curing etc. (G.S.I.No. 1 P-33). 588.00 Sft @ Rs. 11443/10 P% Sft	Rs. 67,285/=
18.	Providing and laying single per layer of polythene sheet 0.13 mm thick for water proofing as per specification and instructions of Engineer Incharge. (G.S.I.No. 41 P-38). 588.00 Sft @ Rs. 10/70 P.Sft	Rs. 6,292/=
19.	White washing three coats (G.S.I.No. 26 (c) P-54). 4081.00 Sft @ Rs. 829/95 P% Sft	Rs. 33,870/=
20.	Distempering three coats (G.S.I.No.24 P-54). 4081.0 Sft @ Rs. 2116/= P% Sft	Rs. 86,354/=
21.	Painting new surface preparing surface and painting guard bars (G.S.I.No.4 P-68). 598.00 Sft @ Rs. 1489/68 P% Sft	Rs. 8,908/=
22.	Providing and fixing iron steel grill door with angle iron frame of 1 ½" x 1 ½" x ¼" and flat iron ¾" x ¼" with approved design and locking arrangement embedded in masonry as per instruction of Engineer Incharge. (G.S.I.No. 30 P-93). 234.0 Sft @ Rs. 194/16 P.Sft	Rs. 45,433/=

23. P/F European white glazed earthenware wash dawn W.C pan complete with and i/c the cost of white back plastic seat (Best Quality) and lid with C.P brass hinges and buffers, 3 gallon white glazed earthenware low level foushing cistern with Sighon fitting ½" dia white porcelain enameled flush band ¾" dia and making required number etc complete (W/Sant. Sch: I No. 1 A P-1).
2 No: @ Rs. 5044/60 Each Rs. 10,089/=
24. Supplying/fixing wash basen mixture of each superior quality with C.P head ½" dia (W/Sant. Sch: I4 (a) No. P-19).
2 No: @ Rs. 2882/= Each Rs. 5,764/=
25. Supplying/fixing C.P Muslim Shower with double bib cock with ring pipe etc complete (W/Sant. Sch: 19 (a) No. P-19).
2 No: @ Rs. 3432/= Each Rs. 6,864/=
26. Supplying/fixing jet shower with rod of superior quality single c.p head ½" dia (W/Sant. Sch: 15 No. P-19).
2 No: @ Rs. 1142/24 Each Rs. 2,285/=
27. Supplying/fixing concealed tee-stop cock of superior quality with C.P head ½" dia (W/Sant. Sch: 12 No. P-18).
6 No: @ Rs. 843/92 Each Rs. 5,064/=
28. Supplying/fixing Bath room accessories set 7 pieces i/c towel rod, brush holder soaptray shelf of approved design i/c cost of screws, nuts etc complete. (Master Brand) (W/Sant. Sch: 23 No. P-19).
2 No: @ Rs. 8122/40 Each Rs. 16,245/=
29. Supplying/fixing in position C.P Bib cock standard pattern ½" dia (W/Sant. Sch: No: 2 (1) (b) P-16).
6 No: @ Rs. 150/92 Each Rs. 906/=
30. Providing G.I Pipes, specials, and clamps etc including fixing cutting & fitting complete with and i/c the cost of breaking through walls and roof, making good etc painting two coats after cleaning the pipe etc with white zink paint with pigment to match the colours of the building and testing with water to a pressure head of 200 feet and handling. (W/Sant. Sch: I No. 1 P-12).
½" dia
200.0 Rft @ Rs. 73/21 P.Rft Rs. 14,642/=
31. Providing PVC pipe of Class "B" equivalent make fixing in trenches i/c cutting, fitting and jointing with Z-joint with one rubber ring i/c testing with water to head of 61 meter or 200 ft. (P.H.S.I.No.1 P-22).
4" dia
50.0 Rft @ Rs. 137/= P.Rft Rs. 6,850/=

32.	Providing and fixing squatting type white glazed earthen ware w.c pan with front flush inter and complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls plinth and floor for pipe connection and making good in cement concrete 1:2:4 (W/Sant. Sch: I No. 2 A (i) P-01).			
	02 No:	@ Rs. 5728/80	Each	Rs. 11,458/=
33.	Providing and fixing full way gun metal valves with wheels, threaded or flanged ends with rubber washing. (W/Sant. Sch: I. No. 4 A P-17). <u>½" dia</u>			
	02 No:	@ Rs. 134/42	Each	<u>Rs. 269/=</u>
			Total	Rs. 17,21,347/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **SUPPLY OF 6 NO: REFUSE RICKSHAW FOR SANITATION BRANCH MITHI.**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|--|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 20,000/= |
| d). | Total Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e). | Percentage, if any to be deducted from Bills: | 8% |
| f). | Time allowed for the work from the date of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

SUPPLY OF 6 NO: REFUSE RICKSHAW FOR SANITATION BRANCH MITHI.

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Supply of Chingchi Rickshaw with Refuse Collecting Box for Refuse Collection in Mithi Town.	06 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **SUPPLYING/FIXING FURNITURE FOR BILAWAL BHUTTO LIBRARY MITHI.**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|--|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 20,000/= |
| d). | Total Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e). | Percentage, if any to be deducted from Bills: | 8% |
| f). | Time allowed for the work from the date of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

SUPPLYING/FIXING FURNITURE FOR BILAWAL BHUTTO LIBRARY MITHI.

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Wooden Reading Chairs with net on back seat	50 No:			
02.	Office Table (3 x 5)	02 No:			
03.	Library Table (10 x 4) Talhi Wood Farmica Top	02 No:			
04.	Revolving Chair	02 No:			
05.	Plastic Chair Good Quality	20 No:			
06.	A.C 1.5 Ton with stabilizer	02 No:			
07	Almirah Iron 6' x 4'	06 No:			
08	Digital UPS 8 x 8 with Battery	02 No:			
09	Ceiling Fan	10 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **SUPPLY OF 6 NO: TYRES AND P.T.O FOR FIRE BRIGADE VEHICLE
NO: GS-9005.**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|---|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 16,000/= |
| d). | Total Security Deposit i/c Earnest
Money @ 10%: | Rs. 80,000/= |
| e). | Percentage, if any to be deducted
from Bills: | 8% |
| f). | Time allowed for the work from the date
of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

SUPPLY OF 6 NO: TYRES AND P.T.O FOR FIRE BRIGADE VEHICLE NO: GS-9005

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Tyre General 1000/20/16 Ply Rating for Fire Brigade Vehicle GS-9005	06 Nos:			
02	P.T.O including all accessories for Fire Brigade vehicle GS-9005.	01 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **SUPPLY OF 12 NO: TYRES FOR FIRE BRIGADE VEHICLE MASTER AND LOADER MASTER.**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|--|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 20,000/= |
| d). | Total Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e). | Percentage, if any to be deducted from Bills: | 8% |
| f). | Time allowed for the work from the date of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

SUPPLY OF 12 NO: TYRES FOR FIRE BRIGADE VEHICLE MASTER AND LOADER MASTER.

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Tyre General 6/50/16 ply Rating for Fire Brigade Vehicle Master & Loader Master.	12 Nos:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **SUPPLY OF 4-CORE CABLE 37/83 COPPER 500 METERS FOR PIPE LINE W/S SCHEME MITHI-NAUKOT.**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|--|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 10,000/= |
| d). | Total Security Deposit i/c Earnest Money @ 10%: | Rs. 50,000/= |
| e). | Percentage, if any to be deducted from Bills: | 8% |
| f). | Time allowed for the work from the date of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

**SUPPLY OF 4-CORE CABLE 37/83 COPPER 500 METERS FOR
PIPE LINE WATER SUPPLY SCHEME MITHI-NAUKOT**

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Supplying and fixing 4-core cable 37/83 Copper.	500 Meter			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **SUPPLYING OF 10 NO: SUBMERSIBLE MOTOR 5.5 HP WITH PUMP FOR TUBE WELL W/S SCHEMES MITHI.**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|--|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 20,000/= |
| d). | Total Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e). | Percentage, if any to be deducted from Bills: | 8% |
| f). | Time allowed for the work from the date of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

**SUPPLYING OF 10 NO: SUBMERSIBLE MOTOR 5.5 HP WITH PUMP FOR
TUBE WELL W/S SCHEMES MITHI**

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Supply of submersible Motor 5.5 HP with pump etc complete	10 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **SUPPLYING AND FIXING OF 2 NO: SUPPLY MOTOR SIEMENS 40 HP
2800 RPM FOR W/S SCHEMES MITHI TOWN.**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|---|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 20,000/= |
| d). | Total Security Deposit i/c Earnest
Money @ 10%: | Rs. 1,00,000/= |
| e). | Percentage, if any to be deducted
from Bills: | 8% |
| f). | Time allowed for the work from the date
of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

**SUPPLYING AND FIXING OF 2 NO: SUPPLY MOTOR SIEMENS 40 HP 2800 RPM FOR
W/S SCHEMES MITHI TOWN.**

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Supplying/fixing of water Supply Motor Siemens 40 HP 2800 RPM	02 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **REPAIR OF 04 NO: PANEL BOARDS (200 HP) FOR PIPE LINE W/S
SCHEME MITHI-NAUKOT.**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|---|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 10,000/= |
| d). | Total Security Deposit i/c Earnest
Money @ 10%: | Rs. 50,000/= |
| e). | Percentage, if any to be deducted
from Bills: | 8% |
| f). | Time allowed for the work from the date
of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

REPAIR OF 04 NO: PANEL BOARDS (200 HP) FOR PIPE LINE W/S SCHEME MITHI-NAUKOT

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Repair of Panel Board (200 HP) etc complete.	04 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **SUPPLY OF TEE JOINTER MACHINE FOR PIPE LINE MITHI**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|--|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 10,000/= |
| d). | Total Security Deposit i/c Earnest Money @ 10%: | Rs. 50,000/= |
| e). | Percentage, if any to be deducted from Bills: | 8% |
| f). | Time allowed for the work from the date of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

SUPPLY OF TEE JOINTER MACHINE FOR PIPE LINE MITHI

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Tee Jointer Machine with all components for jointing P.E Pipe	1 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

NAME OF WORK: **SUPPLY OF 08 NO: REFUSE VAN CONTAINERS.**

NAME OF CONTRACTOR TO WHOM TENDER ISSUED: _____

TENDER FEE _____ RECEIVED VIDE D.R. NO: _____ Dated: _____

MEMORANDUM

- | | | |
|-----|--|-----------------|
| a). | General Description: | As above. |
| b). | Estimated Cost: | Rs. Quoted Rate |
| c). | Earnest Money @ 2% | Rs. 20,000/= |
| d). | Total Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e). | Percentage, if any to be deducted from Bills: | 8% |
| f). | Time allowed for the work from the date of written order to commence is: | 6-Months |

1. I/We hereby tender for the execution for the Government of Sindh of the work specified in the under written memorandum within the time specified in such memorandum of the tendered rates specified in Schedule-B (Memorandum showing items of work to be carried out) and in accordance in all respects with the specifications, designs, drawings and instructions in writing referred to in Rule I here of and in clause of the annexed conditions of contract and agrees that when materials for the work are provided by Government such materials and the rates to be paid for them shall be as provided schedule-A hereto.

2. I/We shall not withdraw and ask for the return of earnest money before expiry of the period shown, as under, commencing from the date of opening of the tender and that if it is withdrawn in violation of this conditions earnest money shall be forfeited.

When the sanctioning authority for the tender is:

1. One Month.
2. Two Months.
3. Three Months.
4. Government Six Months.

3. All terms and conditions will be applicable as per Printed Standard Bidding Document
4. The successful tendered shall have to sign the agreement in printed Standard Bidding Document

(CONTRACTOR)

SCHEDULE "B"

SUPPLY OF 08 NO: REFUSE VAN CONTAINERS.

Sr. No.	Name of Item	Quantity	Rate	Unit	Amount
01.	Supply of Refuse van garbage collecting container of approved shape & quality.	08 No:			
				Total	

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI

(STANDARD BIDDING DOCUMENT BELOW RS. 2.500 MILLION)

Issued to M/S _____

& Charged Rs. _____ Tender Fee _____

Vide D.R.No. _____ Dated: _____

MUNICIPAL COMMITTEE MITHI

Percentage rate Tender and Contract work issued for the work: **Construction of Handicraft Centre near Tarachand Community Hall North Colony Mithi.**

I/We hereby tender for the execution, for the Government of Sindh (here in before) and herein-after referred to as Government of the work specified in the under written memorandum within the time specified in each memorandum @ Rs. _____ percent, above/below/estimate schedule of rate entered in the Schedule "B" memorandum showing items of work to be carried out and in accordance in all respects with the specification designs, drawing and instruction in written referred to in Rule-I here of and in Clause-12 of the annex condition of the contract and agree that when materials for the work are provided by the Government such materials at the rate to be paid for shall be as provide in Schedule "A" here to.

MEMORANDUM

- | | | |
|----|---|-----------------|
| a. | General Description: | As Above |
| b. | Estimated Cost: | Rs. 10,00,000/= |
| c. | Earnest Money @ 2% | Rs. 20,000/= |
| d. | Security Deposit i/c Earnest Money @ 10%: | Rs. 1,00,000/= |
| e. | Percentage, if any to be deducted from the bills: | Rs. 8% |
| f. | Time allowed for completion of the work is: | 6-Months |

CONTRACTOR UNDERTAKING

I/We have referred the above rates after taking into consideration all the terms and conditions as per printed Standard Bidding Document so as to complete the agreement. In case of failure the Department will be as liberty to take action against/as per clause of agreement printed in Standard Bidding Document, which has been read by me and accepted by me.

Schedule "A"NIL.....

Schedule "B" attached herewith.

C.D.NO: _____ Dated: _____

Of _____

CONTRACTOR

SCHEDULE "B"

**CONSTRUCTION OF HANDCRAFT CENTER NEAR TARACHAND COMMUNITY HALL
NORTH COLONY MITHI.**

1. Excavation in foundation of building bridges and other structures including dagbelling dressing, refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5 feet in sandy soil. (G.S.I.No. 18 (b) P-4).
578.00 Cft @ Rs. 3176/25 P% Cft Rs. 1,836/=
2. Cement concrete brick or stone ballast 1 ½"to 2" gauge Ratio 1:4:8 (G.S.I.No. 4 (b) P-14).
931.00 Cft @ Rs. 9416/28 P% Cft Rs. 87,666/=
3. Pucca Brick work in foundation and plinth in cement sand mortar ratio (1:6) (G.S.I.No. 4 (e) P-21).
451.0 Cft @ Rs. 11948/36 P% Cft Rs. 53,887/=
4. Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also i/c of forms moulds lifting shuttering curing rendering and finishing the exposed surfaces i/c screening and washing of shingle. (c) R.C.C work in roof slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete in all respect ratio (1:2:4) 90 lbs cement 2 cft sand and 4 cft shingles 1/8"guage. (G.S.I.No. 6 (i) P-19).
394.00 Cft @ Rs. 337/= P.Cft Rs.1,32,778/=
5. Fabrication of mild steel reinforcement for cement concrete including cutting bending, laying in position making joints and fastenings including cost of binding wire (also includes removal of rust from bars. (G.S.I.No. 8 (b) P-17).
15.83 Cwt @ Rs. 5001/70 P.Cwt Rs. 79,177/=
6. Pucca brick work in ground floor in cement sand mortar (1:6) (G.S.I.No.5 (i) (c) P-20).
909.0 Cft @ Rs. 12674/36 P% Cft Rs.1,15,210/=
7. Supplying & fixing in position Aluminum channels framing for hinged doors & windows or Alcop made with 5 mm thick tinted glass glazing (Belgium) and Alpha (Japan) locks i/c handles stoppers etc. (b) Dlux model (Bronze). (G.S.I.No. 83 P-108).
151.00 Sft @ Rs. 1507/66 P.Sft Rs.2,27,657/=
8. Providing and fixing iron steel grill door with angle iron frame of 1 ½" x 1 ½" x ¼" and flat iron ¾" x ¼" with approved design and locking arrangement embedded in masonry as per instruction of Engineer Incharge. (G.S.I.No. 30 P-93).
125.0 Sft @ Rs. 194/16 P.Sft Rs. 24,270/=
9. Cement plaster (1:4) upto 12' height ½" thick. (G.S.I.No.11 (b) P-52).
2338.00 Sft @ Rs. 2283/93 P% Sft Rs. 53,398/=

10.	Cement plaster (1:4) upto 12' height 3/8" thick. (G.S.I.No.11 (a) P-52).	2338.00 Sft	@ Rs. 2197/52	P% Sft	Rs. 51,378/=
11.	Providing and laying 3" thick topping concrete ratio (1:2:4) surface finishing and dividing into panels 2" thick. (G.S.I.No. 16 P-42).	1400.00 Sft	@ Rs. 4411/82	P% Sft	Rs. 61,765/=
12.	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2 (G.S.I.No. 25 P-43).	784.00 Sft	@ Rs. 27747/06	P% Sft	Rs.2,17,537/=
13.	White washing three coats (G.S.I.No. 26 (c) P-54).	2517.00 Sft	@ Rs. 829/95	P% Sft	Rs. 20,890/=
14.	Distempering three coats (G.S.I.No.24 P-54).	2338.0 Sft	@ Rs. 2116/=	P% Sft	Rs. 49,472/=
15.	Making and fixing steel grated doors with 1/16" thick sheeting i/c angle iron frame 2" x 2" x 3/8" and 3/4" squire bars 4" center to center with locking arrangement (G.S.I.No. 24 P-97).	60.00 Sft	@ Rs. 930/76	P.Sft	Rs. 55,846/=
16.	P/F European white glazed earthenware wash dawn W.C pan complete with and i/c the cost of white back plastic seat (Best Quality) and lid with C.P brass hinges and buffers, 3 gallon white glazed earthenware low level foushing cistern with Sighon fitting 1/2" dia white porcelain enameled flush band 3/4" dia and making required number etc complete (W/Sant. Sch: I No. 1 A P-1).	2 No:	@ Rs. 5044/60	Each	Rs. 10,089/=
17.	Supplying/fixing wash basen mixture of each superior quality with C.P head 1/2" dia (W/Sant. Sch: I4 (a) No. P-19).	2 No:	@ Rs. 2882/=	Each	Rs. 5,764/=
18.	Supplying/fixing concealed tee-stop cock of superior quality with C.P head 1/2" dia (W/Sant. Sch: 12 No. P-18).	2 No:	@ Rs. 843/92	Each	Rs. 1,688/=
19.	Supplying/fixing in position C.P Bib cock standard pattern 1/2" dia (W/Sant. Sch: No: 2 (1) (b) P-16).	6 No:	@ Rs. 150/92	Each	Rs. 906/=
20.	Providing G.I Pipes, specials, and clamps etc including fixing cutting & fitting complete with and i/c the cost of breaking through walls and roof, making good etc painting two coats after cleaning the pipe etc with white zink paint with pigment to match the colours of the building and testing with water to a pressure head of 200 feet and handling. (W/Sant. Sch: I No. 1 P-12).				
	<u>1/2" dia</u>	60.0 Rft	@ Rs. 73/21	P.Rft	Rs. 4,393/=
	<u>3/4" dia</u>	50.0 Rft	@ Rs. 95/79	P.Rft	Rs. 4,790/=

21.	Providing and fixing full way gun metal valves with wheels, threaded or flanged ends with rubber washing. (W/Sant. Sch: I. No. 4 A P-17).			
	<u>1/2" dia</u>			
	02 No:	@ Rs. 134/42	Each	Rs. 269/=
	<u>3/4" dia</u>			
	02 No:	@ Rs. 197/12	Each	Rs. 394/=
22.	Providing PVC pipe of Class "B" equivalent make fixing in trenches i/c cutting, fitting and jointing with Z-joint with one rubber ring i/c testing with water to head of 61 meter or 200 ft. (P.H.S.I.No.1 P-22).			
	<u>4" dia</u>			
	50.0 Rft	@ Rs. 137/=	P.Rft	<u>Rs. 6,850/=</u>
			Total	Rs. 12,67,910/=

CONTRACTOR

MUNICIPAL ENGINEER
MUNICIPAL COMMITTEE
MITHI

CHIEF MUNICIPAL OFFICER
MUNICIPAL COMMITTEE
MITHI