



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/1

01-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: Construction of cc street in Patah mohallah Balloch mohallah Rind mohallah and Bapra mohallah in Orangi zone

BILL OF QUANTITIES

ESTIMATED COST

RS. 7,75,563.00 + OR

BID SECURITY

RS. 25,511.00

TENDER COST

RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,
Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)

ORANGI ZONE



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Construction of cc street in Patah mohallah Balloch mohallah Rind mohallah and Bapra mohallah in Orangi zone

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Preparing of sub grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller	20400	sft	526.28% sft	107361.00
02	P/L RCC 2" thick topping CC 1:2:4 i/c surface finishing and dividing in to penels 2" thick topping	20400	Sft	3275.50 % sft	668202.00
SUB TOTAL PART-A					775563.00 + OR

SIGNATURE OF CONTRACTOR _____

ADDRESS : _____

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/L Aggregate base course material over the prepared sub grade in conformity with lines grade thickness and typical cross section shown in drawing for new pavement using well graded granular crushed stoen with asan dand silt having a smooth gradation curve with tin the limit for grading A or B as per AASHTO M 142-62 and compacting to 100% of the minimum dry density according to AASHTO-T 180 method D using approved m\chanical means of i/c watering with all lead and lift as per specification and as per directed by engineer in charge	5100 cft	OR Rs.	
02	Extra for using SR cement in place of OPC	598 cwt	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR _____



4/1

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT Construction of cc street in Patah mohallah Balloch mohallah Rind mohallah and Bapra mohallah in Orangi zone

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	FART-A (ITEM RATES BASES ON SR) (@ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____





4/2

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

02-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: P/L RCC PIPE FROM BALLOCH PARA TO NALLAH IN ORANGI ZONE

BILL OF QUANTITIES

ESTIMATED COST
BID SECURITY
TENDER COST

RS. 8,36,200.00 + OR
RS. 16,724.00
RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,

Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)

ORIGINAL



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE FROM BALLOCH PARA TO NALLAH IN ORANGI ZONE

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete 1:3:6 plain	1083 cft	cft	3327.50 % cft	36037.00
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	4263	cft	4650.00 0%cft	19823.00
03	Excavation for pipe line in trenches and pits in all soft by hammering and chiseling i/c alignment dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	1109	cft	10770.00 0%,cft	11944.00
04	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 12" dia pipe	975 Rft	Rft	367.00	357825.00
05	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	36 Nos	Each	13064.00	470304.00
06	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-)65.50	Rft	1540.00	(-) 100870.00
07	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	3444 cft	Cft	2760.01 0%cft	9505.00
08	Cartage of sand bajri lime surki murum i/c building rubbish loading and unloading and stacking at site	1083 cft	cft	1065.00 % cft	11534.00
09	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB 3/4" and d/g etc complete 21" dia	22 Nos	Each	913.63 each	20100.00
SUB TOTAL PART-A					836200.00 + OR

SIGNATURE OF CONTRACTOR

ADDRESS : _____



4/2

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE FROM BALLOCH PARA TO NALLAH IN ORANGI ZONE

SUBJECT:
PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	S/F mported earth with in the radius of 5 miles i/c digging loading and unloading and stacking at site i/c leveling compacting etc	5200 cft	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

D.M.C. KARACHI WEST



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE FROM BALLOCH PARA TO NALLAH IN ORANGI ZONE

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



03-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: FILLING OF POTHoles AND DAMAGE PORTION OF ROAD BY CARPETING
FROM MAGSI HOUSE TO MAIN ROAD AND NEAR KHALID HOUSE IN
ORNAGI ZONE.

BILL OF QUANTITIES

ESTIMATED COST	RS. 4,79,700.00 + OR
BID SECURITY	RS. 9594.00
TENDER COST	RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,

Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)



**DISTRICT MUNICIPAL CORPORATION, KARACHI WEST ,
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519**

SUBJECT: FILLING OF POTHoles AND DAMAGE PORTION OF ROAD BY CARPETING
FROM MAGSI HOUSE TO MAIN ROAD AND NEAR KHALID HOUSE IN
ORNAGI ZONE.

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	492	cft	3327.50	16371.00
02	Earth work, excavation of roadside nails forming its bank or putting the same on the embankment as directed breaking clods dressing its complete in ordinary soil	8400	Cft	1437.00 0% cft	12071.00
03	Cartage of sand bajri lime surki murum and building rubbish i/c loading and unloading and stacking at site 10 miles	8892	cft	1065.04 % cft	94733.00
04	Providing 1" thick consolidated premixed carpet in proper camber and grade i/c supplying 10 cft Bajri 4 cft hill sand of approved quality and grade bitumen of 8/100 penetration i/c missing in a mechanical mixer in required proportion i/c heating material and cleaning the road surface rate i/c all cost of material T&P and carrying up to 3 chain using crushed Bajri Laing premixed carpet	7482	cft	4765.11	356526.00
SUB TOTAL PART-A					4,79,700.00

SIGNATURE OF CONTRACTOR

ADDRESS :



4/3

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT:

FILLING OF POTHoles AND DAMAGE PORTION OF ROAD BY CARPETING
FROM MAGSI HOUSE TO MAIN ROAD AND NEAR KHALID HOUSE IN
ORNAGI ZONE.

SUBJECT:

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/L Aggregate base course material over the prepared sub grade in conformity with lines grade thickness and typical cross section shown in drawing for new pavement using well graded granular crushed stone with sand and silt having a smooth gradation curve within the limit for grading A or B as per AASHTO M 142-62 and compacting to 100% of the minimum dry density according to AASHTO-T 180 method D using approved mechanical means of i/c watering with all lead and lift as per specification and as per directed by engineer in charge	2806 cft	OR Rs.	
02	Distemping of approved make and shade of as per direction of Engineer in charge	31600 sft	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: FILLING OF POTHoles AND DAMAGE PORTION OF ROAD BY CARPETING
FROM MAGSI HOUSE TO MAIN ROAD AND NEAR KHALID HOUSE IN
ORNAGI ZONE.

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____
TOTAL RS. _____ RUPEES		

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/4

04-*

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: P/L RCC SEWERAGE LINE 12" IN QAYYUM BLOCK WORK IN GALI # 07
IN ORNAGI


BILL OF QUANTITIES

ESTIMATED COST	RS. 8,92,510.00
BID SECURITY	RS. 17,850.00
TENDER COST	RS. 1000.00


Issued to M/S _____

Video pay order / Challan # _____ dated _____ Rs. _____

Signature and stamp


Executive Engineer B&R Orangi zone,

Executive Engineer
Building & Roads
Orangi Zone (D.M.C (West))





4/6

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC SEWERAGE LINE 12" IN QAYYUM BLOCK WORK IN GALI # 07
IN ORNAGI

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:3:6 plain	1400	cft	1306.80	18295.00
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	2806	cft	4650.00 0 %cft	13048.00
03	Excavation for pipe line in trenches and pits in all kind hard rock by hammering and chiseling to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	2250	Cft	24510.00 0 % cft	55148.00
04	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 12" dia pipe	/00	Rft	367.00 Rft	256900.00
05	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	45 Nos	Each	13064.00 each	557868.00
06	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-)69.64	Rft	1540.00 Rft	(-)107246.00
07	P/L 1:3:6 Sc using GSB ¾" and d/g i/c consolidation curing etc complete in all respect	192 cft	Cft	12595.00 % cft	2418.00
08	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	2806 cft	Cft	2760.00 0%cft	7745.00
09	P/L 1:2:4 FCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	20 Nos	Each	913.63 each	18273.00



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

10	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	3950 cft	cft	1065.04 % cft	42069.00
SUB TOTAL PART-A					8,92,510.00 + OR

SIGNATURE OF CONTRACTOR

ADDRESS :

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	15 Nos	OR Rs.	
02	S/F improvement earth from borrow pits i/c digging and loading unloading and leveling and dressing etc compaction curing etc complete	3000 cft	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC SEWERAGE LINE 12" IN QAYYUM BLOCK WROK IN GALI # 07
IN ORNAGI

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART -A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART -B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____





DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/5

05- ✓

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: P/L RCC PIPE NEAR GHOUSIA HOTEL AND BOLOSOM BEAUTY PARLOR IN
GULSIAN-E-BEHAR IN ORANGI ZONE.

BILL OF QUANTITIES

ESTIMATED COST

BID SECURITY

TENDER COST

RS. 8,79,070.00 + OR

RS. 17,581.00

RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

D
C
W
E
T

Signature and stamp

Executive Engineer B&R Orangi zone,

Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE NEAR GHOUSIA HOTEL AND BOLOSOM BEAUTY PARLOR IN
GULSHAN-E-BEHAR IN ORANGI ZONE.

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:3:6 plain	1400	cft	1306.80	18295.00
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	2806	cft	4650.00 0 %cft	13048.00
03	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	2250	Cft	10770.00 0% CFT	27464.00
04	Excavation for pipe line in trenches and pits in all kind hard rock by hammering and chiseling to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	2250	CFT	24510.00 0% CFT	55148.00
05	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 12" dia pipe	850	Rft	367.00 Rft	311950.00
06	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and beding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	38 Nos	Each	13064.00 each	493540.00
07	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-)72	Rft	1540.00 Rft	(-)110880.00
08	P/L 1:3:6 Cc using GSB ¾" and d/g i/c consolidation curing etc complete in all respect	192 cft	Cft	12595.00 % cft	2418.00



4P

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

09	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	2806 cft	Cft	2760.00 0% cft	7745.00
10	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	20 Nos	Each	913.63 each	18273.00
11	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	3950 cft	cft	1065.04 % cft	42069.00
SUB TOTAL PART-A					8,79,078.00 + OR

SIGNATURE OF CONTRACTOR

ADDRESS :

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	15 Nos	OR Rs.	
02	S/F improvement earth from borrow pits i/c digging and loading unloading and leveling and dressing etc compaction curing etc complete	3000 cft	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE NEAR GHOUSIA HOTEL AND BOLOSOM BEAUTY PARLOR IN
GULSHAN-E-BEHAR IN ORANGI ZONE.

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/6

06

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: Reconstruction of slab near house # 187 zia ul haq colony in UC-10

BILL OF QUANTITIES

ESTIMATED COST

BID SECURITY

TENDER COST

RS. 4,24,334.00 + OR

RS. 8,487.00

RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,

Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)

D C W S



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Reconstruction of slab near house # 187 zia ul haq colony in UC-10

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	1200	cft	4650.00 0%cft	5580.00
02	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 12" dia pipe	200 Rft	Rft	367.00	73400.00
02	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	10 Nos	Each	13064.00	130640.00
03	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-)17	Rft	1540.00	(-) 26180.00
04	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	989 cft	Cft	2760.00 0%cft	2730.00
05	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	58 Nos	Each	913.63 each	52991.00
06	Dismantling of RCC separating reinforcement bars from concrete cleaning and straightening same	1106	cft	5445.00 % cft	60222.00
07	Dismantling of cement concrete 1:2:4 plain	344 cft	cft	3327.50 % cft	11447.00
08	Earth work excavated in ashes, soft soil or scaled clearance undressed lead upto 50 ft	8000 cft	cft	1663.75 % cft	13310.00
09	Cartage of sand bajri lime surki murum i/c building rubbish loading and unloading and stacking at site	9450 cft	cft	1065.00% cft	100643.00
SUB TOTAL PART-A					4,24,334.00 + OR

SIGNATURE OF CONTRACTOR

ADDRESS : _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/6

SUBJECT: Reconstruction of slab near house # 187 zia ul haq colony in UC-10

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC precast slab of required size and shap and racking of joints with CM curing etc complete as per direction of engineer in charge	1150 Sft	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

MET



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Reconstruction of slab near house # 187 zia ul haq colony in UC-10.

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



07-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: Supplying and fixing of manhole covers and ring in the jurisdiction of PS-95 Orangi zone

BILL OF QUANTITIES

ESTIMATED COST	RS. 7,30,904.00 + OR
BID SECURITY	RS. 14,618.00
TENDER COST	RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,
Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Supplying and fixing of manhole covers and ring in the jurisdiction of PS-95 Orangi zone

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	800 Nos	Each	913.63 each	7,30,904.00
SUB TOTAL PART-A					7,30,904.00 + 0%

SIGNATURE OF CONTRACTOR

ADDRESS : _____

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer-in-charge	100 Nos	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

ADDRESS : _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/7

SUBJECT: Supplying and fixing of manhole covers and ring in the jurisdiction of PS-95 Orangi zone

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____

2

)



418

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

08-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: RE-CONSTRUCTION OF ROAD NEAR MUSLIMZADA HOUSE AND BILAL CLINIC ALIABAD AND BABOO HOTEL AND QASIM HOUSE IN UC-13

BILL OF QUANTITIES

ESTIMATED COST

RS. 7,32,860.00 + OR

BID SECURITY

RS. 14,657.00


TENDER COST

RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp


Executive Engineer B&R Orangi zone,
Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: RE-CONSTRUCTION OF ROAD NEAR MUSLIMZADA HOUSE AND BILAL CLINIC ALIABAD AND BABOO HOTEL AND QASIM HOUSE IN UC-13

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	492	cft	3327.50	16371.00
02	Earth work, excavation of roadside nails forming its bank or putting the same on the embankment as directed breaking clods dressing its complete in ordinary soil	8400	Cft	1437.00 0% cft	12071.00
03	Cartage of sand bajri lime surki murum and building rubbish i/c loading and unloading and stacking at site 10 miles	12567	cft	1065.00 % cft	133796.00
04	Providing 1" thick consolidated premixed carpet in proper camber and grade i/c supplying 10 cft Bajri 4 cft hill sand of approved quality and grade bitumen of 8/100 penetration i/c missing in a mechanical mixer in required proportion i/c heating material and cleaning the road surface rate i/c all cost of material T&P and carrying up to 3 chain using crushed Bajri Laing premixed carpet	11975	cft	4765.11 / 8ft	570622.00
SUB TOTAL PART-A					7,32,860.00 + OR

SIGNATURE OF CONTRACTOR

ADDRESS :



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: RE-CONSTRUCTION OF ROAD NEAR MUSLIMZADA HOUSE AND BILAL CLINIC ALIABAD AND BABOO HOTEL AND QASIM HOUSE IN UC-13

SUBJECT:
PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/L Aggregate base course material over the prepared sub grade in conformity with lines grade thickness and typical cross section shown in drawing for new pavement using well graded granular crushed stoen with asan dand silt having a smooth gradation curve with tin the limit for grading A or B as per AASHTO M 142-62 and compacting to 100% of the minimum dry density accorign to AASHTO-T 180 method D using approved m\chanical means of i/c watering with all lead and lift as per specification and as per directed by engineer in charge	4491 cft	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

(Faint diagonal watermark or stamp)



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: RE-CONSTRUCTION OF ROAD NEAR MUSLIMZADA HOUSE AND BILAL CLINIC ALIABAD AND BABOO HOTEL AND QASIM HOUSE IN UC-13

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



4/8

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

09-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: P/L RCC SLAB NEAR MASJID UMER KHATAB AND GOVERNMENT SCHOOL
IN ORANGI ZONE

BILL OF QUANTITIES

ESTIMATED COST	RS. 8,82,700.00 ✓
BID SECURITY	RS. 17,654.00
TENDER COST	RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp

D.M.C. KARACHI WEST

Executive Engineer B&R Orangi zone,

Executive Engineer .
Building & Roads
Orangi Zone D.M.C (West)



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC SLAB NEAR MASJID UMER KHATAB AND GOVERNMENT SCHOOL
IN ORANGI ZONE

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	2844 cft	cft	3327.50 % cft	94634.00
02	Earth work excavation in ashes sand soft soil or scaled clearance undressed lead up to 50 ft	7106 cft	cft	2420.00% cft	19197.00
03	Cement concrete plain 1:2:4 i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shuttering	2009 cft	cft	14429.25 % cft	289883.00
04	RCC work i/c all labour and materials except the cost of reinforcement and its labour for bending binding with will be paid separately This rate also i/c all kind of forms molds lifting shuttering cutting rendering and finishing the expose surface i/c screening and washing of singles ratio 1:2:4	697 cft	cft	337.00	234889.00
05	Fabrication of tor steel reinforcement concrete i/c cutting bending binding and laying in position making joints and fastening i/c all lead and removal of rust from the bars	28 cwt	cwt	5001.70	140048.00
06	Cartage of sand bajri ljme surki murum and building rubbish i/c loading and unloading and stacking at site 10 miles	9958 cft	cft	1065.00 % cft	106052.00
SUB TOTAL PART-A					8,82,700.00 + OR

SIGNATURE OF CONTRACTOR

ADDRESS :



4/9

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC SLAB NEAR MASJID UMER KHATAB AND GOVERNMENT SCHOOL
IN ORANGI ZONE

SUBJECT:
PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	40 Nos	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

DRAFT



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC SLAB NEAR MASJID UMER KHATAB AND GOVERNMENT SCHOOL
IN ORANGI ZONE

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/10

10-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: P/L RCC PIPE GULSHAN-E-AHBAB DOUBLE PMT AND GALI # 07 IN ORANGI ZONE ✓

BILL OF QUANTITIES

ESTIMATED COST	RS. 8,61,273.00 ✓
BID SECURITY	RS. 17,225.00 ✓
TENDER COST	RS. 1000.00 ✓

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,
Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/10

10	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	3800 cft	cft	1065.04 % cft	40472.00
2SUB TOTAL PART-A					8,61,273/-+OR

SIGNATURE OF CONTRACTOR

ADDRESS : _____

SUBJECT: P/L RCC PIPE GULSHAN-E-AHBAB DOUBLE PMT AND GALI # 07 IN ORANGI ZONE

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	24 Nos ✓	OR Rs.	
02	S/F improvement earth from borrow pits i/c digging and loading unloading and leveling and dressing etc compaction curing etc complete	2800 cft ✓	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE GULSHAN-E-AHBAB DOUBLE PMT AND GALI # 07 IN
ORANGI ZONE

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:3:6 plain	1400 ✓	cft	1306.80 ✓	18295.00 ✓
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	2806 ✓	cft	4650.00 0 %cft ✓	130218.00 ✓
03	Excavation for pipe line in trenches and pits in all kind hard rock by hammering and chiseling to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	2250 ✓	Cft	24510.00 0 % cft ✓	55148.00 ✓
04	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 12" dia pipe	650 ✓	Rft	367.00 Rft ✓	238550.00 ✓
05	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	42 Nos ✓	Each	13064.00 each ✓	548688.00 ✓
06	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-) 69.00 ✓	Rft	1540.00 Rft ✓	(-)106260.00 ✓
07	P/L 1:3:6 Cc using GSB ¾" and d/g i/c consolidation curing etc complete in all respect	190 cft ✓	Cft	12595.00 % cft ✓	2393.00 ✓
08	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	2700 cft ✓	Cft	2760.00 0%cft ✓	7452.00 ✓
09	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	48 Nos ✓	Each	913.63 each ✓	43487.00 ✓



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE GULSHAN-E-AHBAB DOUBLE PMT AND GALI # 07 IN
ORANGI ZONE

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

11-

SUBJECT: Rehabilitation of 9" and 12" dia RCC pipe drain in sector 1-B near Balloch goth in Orangi zone

BILL OF QUANTITIES


ESTIMATED COST	RS. 8,99,240.00 +OR
BID SECURITY	RS. 17,985.00
TENDER COST	RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated _____ Rs. _____

Signature and stamp

ORANGI ZONE


Executive Engineer B&R Orangi zone,
Executive Engineer
Building & Roads
Orangi Zone D.M.C. (West)



4/4

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Rehabilitation of 9" and 12" dia RCC pipe drain in sector 1-B near Balloch goth in Orangi zone ✓

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	35 Nos	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

ORIGINAL

4/11

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Rehabilitation of 9" and 12" dia RCC pipe drain in sector 1-B near Balloch goth in Orangi zone ✓

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	35 Nos	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

DRAFT



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Rehabilitation of 9" and 12" dia RCC pipe drain in sector 1-B near Balloch goth in Orangi zone

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR-11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/12

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

12-

SUBJECT: P/L RCC PIPE DRAIN IN SECTOR 8/L NEAR QATAR HOSPITAL IN ORANGI ZONE

BILL OF QUANTITIES

ESTIMATED COST

RS. 7,88,610.00 + OR

BID SECURITY

RS. 15,772.00

TENDER COST

RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,

Executive Engineer

Building & Road

Orangi

DISTRICT MUNICIPAL CORPORATION



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE DRAIN IN SECTOR 8/L NEAR QATAR HOSPITAL IN ORANGI ZONE

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	2025 ✓	cft	3327.50 % cft ✓	67382.00 ✓
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	4950 ✓	cft	4650.00 ✓ 0%cft	23018.00 ✓
03	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 9" & 12" dia pipe	400 Rft ✓ 500 Rft ✓	Rft Rft	206.00 ✓ 367.00 ✓	82400.00 ✓ 183500.00 ✓
04	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	35 Nos ✓	Each	13064.00 ✓	457240.00 ✓
05	Add for extra depth beyond 5' depth less the 5 ft deduct the same rate	(-)70.0744 ✓	Rft	1540.00 ✓	(-) 107915.00 ✓
06	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	4108 cft ✓	Cft	2760.00 ✓ 0%cft	11338.00 ✓
07	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	45 Nos ✓	Each	913.63 each ✓	41113.00 ✓
08	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	2867 ✓	cft	1065.00% cft	30534.00 ✓
SUB TOTAL PART-A					7,88,610.00 + OR ✓

SIGNATURE OF CONTRACTOR

ADDRESS : _____



4/12

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE DRAIN IN SECTOR 8/L NEAR QATAR HOSPITAL IN ORANGI ZONE

SUBJECT:
PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	75 Nos	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

DRAFT



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L RCC PIPE DRAIN IN SECTOR 8/L NEAR QATAR HOSPITAL IN ORANGI ZONE

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



17

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

13-

SUBJECT: Rehabilitation of 12" and 18" dia RCC pipe near Ibrahim Ali Bhai school in Orangi zone

BILL OF QUANTITIES

ESTIMATED COST

RS. 9,18,640.00+OR

BID SECURITY

RS. 18,373.00

TENDER COST

RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated _____ Rs. _____

DUPLICATE

Signature and stamp

Executive Engineer B&R Orangi zone,

Executive Engineer

Building & Roads

Orangi Zone D.M.C (West)



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Rehabilitation of 12" and 18" dia RCC pipe near Ibrahim Ali Bhai school in Orangi zone

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	2815 ✓	cft	3327.50 % cft ✓	93603.00 ✓
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	4800 ✓	cft	4650.00 ✓ 0% cft	22320.00 ✓
03	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 12" & 15" dia pipe	200 Rft ✓ 600 Rft ✓	Rft Rft	367.00 ✓ 436.00 ✓	73400.00 ✓ 261600.00 ✓
04	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	31 Nos ✓	Each	13064.00 ✓	404984.00 ✓
05	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-)53.159 ✓	Rft	1540.00 ✓	(-) 81,865.00 ✓
06	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	3529 cft ✓	Cft	2760.00 ✓ 0% cft	9740.00 ✓
07	P/L 1:2:4 RCC manhole covers i/c for bar frame using GSB ¾" and d/g etc complete 21" dia	100 Nos ✓	Each	913.63 each ✓	91363.00 ✓
08	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	4084 ✓	cft	1065.00% cft ✓	43495.00 ✓
SUB TOTAL PART-A					918640.00 + OR ✓

SIGNATURE OF CONTRACTOR

ADDRESS : _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/13

SUBJECT: Rehabilitation of 12" and 18" dia RCC pipe near Ibrahim Ali Bhai school in Orangi zone

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	30 Nos	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

ORANGI



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Rehabilitation of 12" and 18" dia RCC pipe near Ibrahim Ali Bhai school in Orangi zone

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITFM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



14

14-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: P/L 12" DIA RCC PIPE DRAIN IN SECTOR 1-D AND PARK IN ORNAGI ZONE

BILL OF QUANTITIES

ESTIMATED COST

RS. 9,20,210.00 + OR

BID SECURITY

RS. 18,404.00

TENDER COST

RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,
Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)

DUPLICATE



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762319

SUBJECT: P/L 12" DIA RCC PIPE DRAIN IN SECTOR 1-D AND PARK IN ORNAGI ZONE

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
02	Dismantling of cement concrete flooring 1:2:4 plain	2813	cft	3327.50 % cft	93603.00
03	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	4800	cft	4650.00 0%cft	22320.00
0	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 12" dia pipe	800	Rft	367.00	293600.00
05	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	35 Nos	Each	13064.00	457240.00
06	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-)57.011	Rft	1540.00	(-) 87797.00
07	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	3954 cft	Cft	2760.00 0%cft	10913.00
08	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	3659	cft	1065.00% cft	38968.00
09	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	100 Nos	Each	913.63 each	91363.00
SUB TOTAL PART-A					920210.00 + OR

SIGNATURE OF CONTRACTOR _____

ADDRESS : _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/14

SUBJECT: P/L 12" DIA RCC PIPE DRAIN IN SECTOR 1-D AND PARK IN ORNAGI ZONE

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	25 Nos	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

DECLARATION



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L 12" DIA RCC PIPE DRAIN IN SECTOR 1-D AND PARK IN ORNAGI ZONE

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/15

15-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: Rehabilitation of 9" and 12" dia RCC pipe near UC-12 Office in Orangi zone

BILL OF QUANTITIES

ESTIMATED COST	RS. 8,88,620.00 + OR
BID SECURITY	RS. 17,772.00 ✓
TENDER COST	RS. 1000.00 ✓

Issued to M/S

Video pay order / Challan # _____ dated _____ Rs. _____

Signature and stamp

Executive Engineer-B&R-Orangi zone,

Executive Engineer
 Building & R/W
 Orangi Zone (M.C. Orangi)

District Municipal Corporation
 Karachi West
 Sector 11-E
 Shahrah-e-Orangi
 Orangi Town
 Karachi West



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Rehabilitation of 9" and 12" dia RCC pipe near UC-12 Office in Orangi zone

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	2944	cft	3327.50 % cft	97962.00
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	4950	cft	4650.00 0%cft	23018.00
03	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 12" dia pipe	400 500	Rft "	206.00 367.00	82400.00 183500.00
04	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	40 Nos	Each	13064.00	522560.00
05	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-) 76.728	Rft	1540.00	(-) 118161.00
06	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	4108 cft	Cft	2760.00 0%cft	11338.00
07	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	3786	cft	1065.00% cft	40321.00
08	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	50 Nos	Each	913.63 each	45682.00
SUB TOTAL PART-A					8,88,620.00 + OR

SIGNATURE OF CONTRACTOR

ADDRESS : _____

4/16



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

16-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: REPAIRING AND RENOVATION OF DIFFERENT ROOMS AND OTHER
WORKS ON MAIN BUILDING OF ORANGI ZONE.

BILL OF QUANTITIES

ESTIMATED COST	RS. 4,78,240.00 + OR
BID SECURITY	RS. 9,565.00
TENDER COST	RS. 1,000.00

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp


Executive Engineer B&R Orangi zone,



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: REPAIRING AND RENOVATION OF DIFFERENT ROOMS AND OTHER
WORKS ON MAIN BUILDING OF ORANGI ZONE.

PART-A ITEM BASED ON SCHEDULE RATES.

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	P/L 1:3:6 cement concrete solid block masonry wall 6" and below in thickness set in 16 cement mortar in ground floor super structure i/c racking out joints and curing etc complete	695 cft	cft	15771.01 % cft	109609.00
02	Cement plaster 1:4 up to 20 ft height ½ " thick	2780 sft	sft	2283.93 % sft	63493.00
03	Dismantling on plaster surface	10758 sft	sft	1646.15 % sft	177093.00
04	Repairing the surface and painting with plastic emulsion of approved make and shade	4560 sft	sft	1402.23 % sft	63942.00
05	P/F 24" X 18" lavatory basin white glazed i/c all respect and pedestal complete	1 No	Each	5192.17 each	5192.00
06	P/F European type with glazed earthen wear wash down WC pan complete with and i/c the cost of seat and all fitting etc complete	2 Nos	No	11477.40 Each	22955.00
07	Supplying and fixing widow printed blinder with plain design as per color and fitting etc complete in respect	392 sft	sft	91.11 sft	35720.00
09	P/F fulway gunmetal valave 1" dia	1 No	No	260.92 each	260.00
SUB TOTAL PART-A					

SIGNATURE OF CONTRACTOR

ADDRESS : _____



4/16

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: REPAIRING AND RENOVATION OF DIFFERENT ROOMS AND OTHER WORKS ON MAIN BUILDING OF ORANGI ZONE.

PART-B ITEM BASED ON OFFER RATES.

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/L tiles glazed 18" x 18" x 14" on floor or wall facing in required color and pattern jointed with cement pigment i/c washing and fitting etc complete	768 sft	OR RS.	
02	P/F glass of 5 mm in place of broken window etc	320 sft	OR Rs.	
03	P/F wooden partition of lasani ply wood i/c all accessories etc complete	320 sft	OR RS.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

SUBJECT:





17-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: P/L AND FIXING OF DIFFERENT SIZES OF RCC PIPE NER NOORANI PARK
IN ORNAGI ZONE

BILL OF QUANTITIES

ESTIMATED COST	RS. 7,78,980.00 + OR
BID SECURITY	RS. 15,580.00 ✓
TENDER COST	RS. 1000.00 ✓

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,
Executive Engineer
Building & Roads
Orangi Zone D.M.C (West)

D.M.C. (West)



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L AND FIXING OF DIFFERENT SIZES OF RCC PIPE NER NOORANI PARK
IN ORNAGI ZONE

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	2025	cft	3327.50 % cft	67382.00
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	3850	cft	4650.00 0%cft	17903.00
03	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 9", 15" & 12" dia pipe	200 300 200	Rft Rft Rft	206.00 367.00 436.00	41200.00 110100.00 87200.00
04	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	30 Nos	Each	13064.00	391920.00
05	Add for extra depth beyond 5'ft depth less the 5 ft deduct the same rate	(-) 43.38	Rft	1540.00	(-) 66805.00
06	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	3025 cft	Cft	2760.00 0%cft	8343.00
07	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	2852	cft	1065.00% cft	30374.00
08	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	100 Nos	Each	913.63 each	91363.00
SUB TOTAL PART-A					7,78,980/- +OR

SIGNATURE OF CONTRACTOR

ADDRESS :



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/17

SUBJECT: P/L AND FIXING OF DIFFERENT SIZES OF RCC PIPE NER NOORANI PARK
IN ORNAGI ZONE

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	80 Nos	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

ORIGINAL



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: P/L AND FIXING OF DIFFERENT SIZES OF RCC PIPE NER NOORANI PARK
IN ORNAGI ZONE

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



18-
TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: Replacement of broken RCC pipe near Cardio center in Orangi zone

BILL OF QUANTITIES

ESTIMATED COST	RS. 7,75,480.00 + OR
BID SECURITY	RS. 15,510.00 ✓
TENDER COST	RS. 1000.00 ✓

Issued to M/S

Video pay order / Challan # _____ dated _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,

ORANGI TOWN
MUNICIPAL CORPORATION
KARACHI WEST



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Replacement of broken RCC pipe near Cardio center in Orangi zone ✓

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	2025 ✓	cft	3327.50 % cft	67382.00 ✓
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	4950 ✓	cft	4650.00 ✓ 0%cft	23018.00 ✓
03	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 9", & 12" dia pipe	400 ✓ 500 ✓	Rft Rft	206.00 ✓ 367.00 ✓	82400.00 ✓ 183500.00 ✓
04	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	36 Nos ✓	Each	13064.00 ✓	470304.00 ✓
05	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-)90.0504	Rft	1540.00 ✓	(-) 138678.00 ✓
06	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	4108 cft ✓	Cft	2760.00 ✓ 0%cft	11338.00 ✓
07	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	2867 ✓	cft	1065.00% cft ✓	30534.00 ✓
08	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	50 Nos ✓	Each	913.63 each	45682.00 ✓
SUB TOTAL PART-A					7,75,480.00 + OR ✓

SIGNATURE OF CONTRACTOR

ADDRESS :



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/18

SUBJECT: Replacement of broken RCC pipe near Cardio center in Orangi zone

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	80 Nds	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

Handwritten signature



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Replacement of broken RCC pipe near Cardio center in Orangi zone

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

4/19

19- ✓

TENDER REFERENCE # NIT/04/2015 ✓

Dated: 30-03-2015 ✓

SUBJECT: CONSTRUCTION AND IMPROVEMENT OF CC STREET AND PIPE DRAIN
AND OTHER WORKS IN FAQIR COLONY ORANGI ZONE ✓

BILL OF QUANTITIES

ESTIMATED COST
BID SECURITY
TENDER COST

RS. 6,66,440.00 + OR ✓
RS. 13,329.00 ✓
RS. 1000.00 ✓

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,
Building & Roads
Orangi Zone D.M.C (West)

ORIGINAL



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: CONSTRUCTION AND IMPROVEMENT OF CC STREET AND PIPE DRAIN AND OTHER WORKS IN FAQIR COLONY ORANGI ZONE

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	2868 ✓	cft	3327.50 % cft ✓	95433.00 ✓
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	1150 ✓	cft	4650.00 ✓ 0%cft	5348.00 ✓
03	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 9", & 12" dia pipe	200 ✓	Rft	367.00 ✓	73400.00 ✓
04	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	12-Nos ✓	Each	13064.00 ✓	156768.00 ✓
05	Add for extra depth beyond 5 ft depth less the 5 ft deduct the same rate	(-)18.1598 ✓	Rft	1540.00 ✓	(-) 27966.00 ✓
06	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	920 cft ✓	Cft	2760.00 ✓ 0%cft	2539.00 ✓
07	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	2868 ✓	cft	1065.00% cft ✓	30544.00 ✓
08	Preparing of sub grade i/c earth excavation leveling to an average depth of 9" dressing to camber and consolidation with power roller	8690 ✓	sft	526.28% sft ✓	45734.00 ✓
09	P/L RCC 2" thick topping CC 1:2:4 i/c surface finishing and dividing in to penels 2" thick topping	8690 ✓	Sft	3275.50 % sft ✓	284641.00 ✓
SUB TOTAL PART-A					6,66,440/- +OR

SIGNATURE OF CONTRACTOR

ADDRESS : _____



4/18/17

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: CONSTRUCTION AND IMPROVEMENT OF CC STREET AND PIPE DRAIN AND OTHER WORKS IN FAQIR COLONY ORANGI ZONE

PART-B ITEM BASED ON OFFER RATES.

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	Distemping on walls of approved shade two coats etc complete	16250 sft	OR RS.	
02	P/L Aggregate base course material over the prepared sub grade in conformity with lines grade thickness and typical cross section shown in drawing for new pavement using well graded granular crushed stone with asan dand silt having a smooth gradation curve with in the limit for grading A or B as per AASHTO M 142-62 and compacting to 100% of the minimum dry density accorign to AASHTO-T 180 method D using approved m\chanical means of i/c watering with all lead and lift as per specification and as per directed by engineer in charge	2172 cft	OR RS.	
03	S/F imported earth within the radius of 5 miles digging loading and unloading and stacking at site and leveling and consolidation with power roller	2160 cft	OR RS.	
04	Extra for using SR cement in place of ORC	251 cwt	OR RS.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: CONSTRUCTION AND IMPROVEMENT OF CC STREET AND PIPE DRAIN
AND OTHER WORKS IN FAQIR COLONY ORANGI ZONE

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



20-

TENDER REFERENCE # NIT/04/2015

Dated: 30-03-2015

SUBJECT: Construction / Improvement of RCC pipe drain in sector 7-A near Haji hotel in Orangi zone

BILL OF QUANTITIES

ESTIMATED COST	RS. 8,78,680.00 + OR
BID SECURITY	RS. 17,574.00
TENDER COST	RS. 1000.00

Issued to M/S

Video pay order / Challan # _____ dated: _____ Rs. _____

Signature and stamp

Executive Engineer B&R Orangi zone,

DISCLAIMER



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Construction / Improvement of RCC pipe drain in sector 7-A near Haji hotel in Orangi zone

PART-A ITEM BASED ON SCHEDULE RATES

S #	DESCRIPTION	QUANTITY	UNIT	RATES	AMOUNT
01	Dismantling of cement concrete flooring 1:2:4 plain	2813	cft	3327.50 % cft	93603.00
02	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by engineer in charge	4800	cft	4650.00 0%cft	22320.00
03	P/L RCC rubbing ring pipe of class A and fixing in trenches i/c cutting fitting and jointing with rubber ring etc 9", & 12" dia pipe	800	Rft	367.00	293600.00
04	Construction of manhole 4' dia inside i/c RCC ring slab 39" dia with manhole cover 21" dia of 5' clear depth in 1:2:4 in 9" thick wall and bedding cast in situ with fair face steel shuttering i/c excavation back filling and disposal of surplus stuff up to one chain etc complete	35 Nos	Each	13064.00	457240.00
05	Add for extra depth beyond 5ft depth less the 5 ft deduct the same rate	(-)60.248	Rft	1540.00	(-) 92782.00
06	Refilling of excavation stuff in trenches 6" this compacting at all lead and lift	3954 cft	Cft	2760.00 0%cft	10913.00
07	Cartage of sand bajri lime surki murum building rubbish i/c loading and unloading and stacking at site	3659	cft	1065.00% cft	38968.00
08	P/L 1:2:4 RCC manhole covers i/c tor bar frame using GSB ¾" and d/g etc complete 21" dia	60 Nos	Each	913.63 each	54818.00
SUB TOTAL PART-A					8,78,680.00 + OR

SIGNATURE OF CONTRACTOR

ADDRESS : _____



4/20

DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762512

SUBJECT: Construction / Improvement of RCC pipe drain in sector 7-A near Haji hotel in Ornagi zone

PART-B ITEM BASED ON OFFER RATES

S #	DESCRIPTION	QUANTITY	RATES	AMOUNT
01	P/F RCC ring slab 39" dia with RCC manhole cover of 21" dia as per direction of engineer in charge	45 Nos	OR Rs.	
SUB TOTAL PART-B				

SIGNATURE OF CONTRACTOR

ORIGINAL



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST
SECTOR 11-E SHAHRAH-E-ORANGI, ORANGI TOWN, KARACHI
PTCL # 36697869 / 36660102 & FAX # 36762519

SUBJECT: Construction / Improvement of RCC pipe drain in sector 7-A near Haji hotel in Orangi zone

I / WE HEREBY QUOTED RATES AS FOLLOWS:-

01	PART-A (ITEM RATES BASES ON SR) @ _____ % ABOVE / BELOW SR I/C THE COST OF CARRIAGE OF MATERIALS AND DIFFERENCE OF COST OF BITUMEN	RS. _____
02	PART-B (ITEM RATE BASES ON OFFER RATES / ITEM RATES THE ITEMS OTHER THEN SCHEDULE RATES	RS.- _____
GRAND TOTAL PART-A & B		RS. _____

TOTAL RS. _____ RUPEES

NOTE:-

- The rates must be quoted in words and figures both clearly readable.
- Any correction / cutting must be initialed and stamped by the bidder.

Signature of contractor _____

Address : _____

Cell # _____ / PTCL # _____



DISTRICT MUNICIPAL CORPORATION, KARACHI WEST

NAME OF WORK:

INSTRUCTION TO BIDDERS / PROCURING AGENCIES GENERAL RULES AND GUIDANCE TO CONTRACTORS

This section of the bidding documents should provide the information necessary for bidders to prepare responsive bids, in accordance to the requirement of the procuring agency. It should also give information on bid, submission, opening and evaluation, and on the award of contract. Matter governing the performance or the contract or payment under the contract or matters affecting the risks, rights and obligations of the payment under the contract is included as conditions of contract and bidding Data.

The instruction to bidders will not be part of the contract and will cease to have effect once the contract is signed.

1-Notice in viting / invitation for bid: All work proposed to be executed by contract shall be notified in a form of notice inviting tender (NIT) / Invitation to bid (IFB) hosted on the web site of authority and procuring of work and also in newspapers wherever require as per Rules. NIT must state the description of work, dates, time and place issuing tenders, submission, opening bids, completion time, cost of bidding documents and bid security either in lump sum or a percentage of estimated cost /bid cost. The interested bidders must have valid NTN also. 2-Content of bidding documents: it must include, but not limited to: Conditions of contract, **contract data, specification or its reference with premium to be filled in the form of percentage above / below or on item rates to be quoted, form of agreement and drawings.**

v

3-Fixed price contracts: The bid price and rates are fixed during the currency of the contract and under no circumstance shall any be entitled to claim enhance rates for any terms in this contract.

4- **Right to rejection:** The procuring agency shall have the right of rejecting all or any of the tender / bid as per provision of SPP Rules-2010 (amended-2013).

5- **Conditional offer:** Any person who submits a tender shall fill up the usual printed form stating at what percentage above or below on the rates specified in the bill of quantities for an item or work to be carried out he is willing to undertake the work and also quoted the rates for those items which are based on market rates. Only one rats of such percentage on all the scheduled rates shall be framed, The tender which proposes time, allowing for carrying out, eh work or which contain any other conditions will be liable to rejection, No printed form of tender shall include a tender for more than one work, but if contractor wish to tender for two or more works, they shall submit a separate tender for each, The envelope containing his tender documents shall refer the name and number of the work.

6-**Measurements:** All works shall be measured by standardized instruments according to the rules.

7-**Evidence of eligibility:** Bidders shall provide evidence of their eligibility as and when requested by the procuring agency. Experience of relevant works / turnover of at least last three years, managerial capability, resources, details who to execute the work and cop with technical difficulties, available machineries, Registration of Board, income tax department valid NTN number, registration in sale tax in case the procurement of goods and services, Registration of Sindh Revenue board and registration of Pakistan Engineering council and any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44.

8-**Late submission of bids:** any bid received by the agency after the deadline for submission of bids shall be rejected and returned unopened to the bidder.

9- **Bid security:** Bid without the security of required amount and prescribed form shall be rejected.

10-Arithmetical errors: Bids determined to be substantially responsive shall be checked for any arithmetic errors. Arithmetical errors shall be rectified on the following basis:-

- In case of schedule rates, the amount of percentage quoted above or below will be checked and added or subtracted from the amount of bill of quantities to arrive the final bid cost.
- In case of item rates: if there is a discrepancy between the unit rates and the total cost that is obtained by multiplying the unit and quantities the unit rate shall prevail and the total cost will be corrected unless in the opinion of the agency there is any obvious misplacement of the decimal point in the unit rates, in which case the total cost as quoted will govern and the unit rates be corrected. If there is a discrepancy between the total bid amount and the sum of total costs the sum of the total cost shall prevail and the total bid amount shall be corrected.
- Where there is a discrepancy between the amounts in figures and in words the amount in words shall be governed.

CONDITION OF CONTRACT.

Clause-1: Commencement and completion dates of the work: The contractor shall not enter upon or commence any portion of the work except with the written authority and instructions of the Engineer in charge or its subordinate officer / official of the work failing which authority the contract shall have no claim to ask for measurement or its payment the work executed by him on site.

Clause-2: Liquidated damages: The contractor shall pay liquidated damages to the agency at The contractor shall proceed with the work with due expedition and with delay and complete in the time allowed for carrying out the work as entered in the tender shall be strictly observed by the contractor and shall reckon from the date on which the order to commence the work, the contractor shall be bound, In all in which the time allowed for completion of at any work exceeds one month to achieve progress on the prorated basis.

The rate devastated in bidding data for each day that the completion date is later than the intended completion date the amount of liquidated damage paid by the contractor to the agency shall not exceed 10 percent of the contract amount / cost / price. Payment of liquidated damages does not affect the contractor's liabilities.

Clause-3: Termination of the contract.

Procuring agency / Executive Engineer may terminate the contract if either of the following conditions exist:-

- 1- Contractor causes a breach of any clause of the contract:
- 2- The progress of any particular portion of the work is unsatisfactory and notice of 10 days has expired.
- 3- in case of abandonment of the work owing to the serious illness or death of a contractor or any other cause.
- 4- contractor can also request for termination of contract if a payment certified by the Engineer in charge is not paid to the contractor within 60 days of the date of submission of the bill.

(B) The Executive Engineer / Procuring agency has power to adopt any of the following courses as may deem fit:

- 1- to forfeit the security deposit available except conditions mentioned at A(3) and (4) above.
- 2- to finalize the work by measuring the work done by the contractor.

(C) - In the event of any the above courses being adopted by the Engineer / procuring agency the contractors Have :-

- No claim to compensation for any loss sustained by him by reason of his having purchased or procured any materials or entered into any engagements or made any advances on account of or with a view to the execution of work or the performance of the contract.
- However, the contractor can claim for the work done on site duly certified by the Executive Engineer in writing regarding the performance of such work and has not been paid. The procuring Agency / Engineer may invite fresh bid for remaining work.

Clause-4: Possession of the site and claims for compensation for delay. The Executive Engineer shall give possession of all parts of the site to the contractor. If possession of the site is not given by the date stated in commencement order no compensation shall be allowed for any delay caused by starting to work on account of any acquisition of land water standing in borrow pits compartments or in accordance sanction to estimates. In such case, either date of commencement will be changed or period of completion is to be extended accordingly.

Clause -5: Extension of intended completion date: The procuring agency either on its initiative before the date of completion or on desired of the contractor may extend the intended from the completion date, if any event which hindrance the execution of contract accordance or a variation order if issued which make it impossible to complete the work by the intended completion date for such period as he may think necessary or proper. The decision of the Executive Engineer in this matter shall be final. Where time has been extended under this or any other clause of this agreement, the date of completion of the work shall be date fixed by the order given in the extension or by the aggregate of such orders, make under this agreement. When time has been extended as for said, it shall continue to be essence of the contract and all clauses of the contract shall continue to be operative during the extended period.

Clause-6: **Specification:** The contractor shall execute the whole or every part of the work in the most substantial and workman like manner and both as regard material or all other matters strict accordance with the specification lodge in the office the Executive Engineer and initialed by the parties, the said specification being a part of the contract. The contractor shall also confirm fully and faithfully to the design, drawing and instruction in writing relating to the works signed by the Executive Engineer in-charge and lodge in his office in to which the contractor shall be entitled to have access as such office or on the site of work for the purpose of inspection during office hours and the contractor shall, if he so required be entitled at his own expense to make or cost to be made copy of the specification, and all such design, drawing, and instruction as aforesaid.

Clause-7 **Payment:** (A) Interim fresh running bill a bill shall be submitted by the contractor as frequently as the progress of work may justified for all the work executed and not included any previous bill atleast one in a month and the Engineer in-charge shall take or cost to be taken requisite measurement for the purpose of having the same verified and the claim, as far as admissible, adjusted, if possible before the expiry of 10 days from the presentation from the bill, at any time depute a subordinate to measure up the said work in the presence of the contractor or his authorized agent, whose counter signature to the measurement list will be sufficient to warrant and the Engineer in-charge may prepare a bill from such list which shall be binding on the contractor in all respect. The engineer procuring agency shall pass/ certify the amount to be paid to the contractor, which he consider due and payable in respect thereof, subject to deduction of security deposit, advance payment if any make to him and taxes. All such intermediate payment shall be regarded as payment by way of advance against the final payment only and not as payment for work actually done and completed and shall not preclude the engineer in-charge from the recoveries from final bill and rectification of defects and unsatisfactory items of work pointed out to him during the defect liability period.

(B)- Final bill : A bill shall be submitted by the contractor within one month of the day fixed for the completion of work otherwise the Engineer in charge certificate of re-measurement and of the total amount payable for the work shall be final and binding on all parties.

Clause - 8 : **Reduced rates.** In cases where the items of works are not accepted as so completed, the engineer-in-charge may make payment on account of such items at such reduced rates as he may consider reasonable in the preparation of final or on running account bills with reasons recorded in writing.

Clause -9: **Issuance of variation and repeat orders.**

- (A) Agency may issue a variation order for procurement of works, physical services from the original contractor to cover any increase or decrease in quantities, including the introduction of new work items that are either due to change of plan, design or alignment to suit actual field conditions, within the general scope and physical boundaries of the contract.
- (B) Contractor shall not perform a variation until the procuring agency has authorized the variation in writing subject to the limit not exceeding the contract cost by of %15 on the same conditions in all respects on which he agreed to do item in the work, and at the same rates, as are specified in the tender for the main work. The contractor has no right to claim for compensation by reason of alterations and curtailment of the work.
- (C) In case the nature of the work in the variation does not correspond with items in the bill of quantities, the quotation by the contractor is to be in the form of few rates for the relevant item of work, and the engineer-in-charge is satisfied that the rate quoted is within the rate worked out by him on detailed rate analysis, and then only he shall allow him that rate after approval from higher authority.
- (D) The time of the work shall be extended in the proportion that the additional work bear to the original contract work. The price to be exceeded by more than 15% and then engineer can adjust the rates for those quantities causing excess the cost of contract beyond 15% after approval for superintending engineer.
- (E) Repeat order: Any cumulative beyond 15 % of initial contract amount shall be subject of any other contract to be tendered of if the works are separable from the original contract.

5

Clause 10: Quality control:

- A- Identifying defects if at any time before the security deposit is refunded to the contractor / during defect liability period mentioned in bid data, the Engineer in charge for his subordinate in charge of the work may instruct the contractor to uncover and test any part of the work which he considered may have a defect due to use of un sound material and un skilled full workman ship and the contractor has to carry out a test at his own cost irrespective of work already approved or paid
- B- Correction of defect the contractor shall be bound forthwith to rectified or removed and re construct the work so specified in whole or in part, as the case may require. The contractor shall correct the notified defect within the defect correction period mentioned in notice.
- C- UN corrected defects 1- in the case of any such failure, the Engineer incharge shall give the contractor at least 14 days' notice of in intention to use the third party correct the defect. He may rectify and remove and re execute the work or remove or replace material or articles complain of as the case may be as the risk and expense in all respect of the contractor.
2- if the engineer consider that the correction of the defect is not essential and it may be accepted or make use of, it shall be within his discretion to accept the same at such reduce rates as he may fixed there forth.

Clause 11: A- Inspection of operations. The Engineer and his subordinate, shall at all reasonable time have access to the site for supervision and inspection of work under or in course of execution in pursuance of the contract and contractor shall afford every facility /assistance in obtaining the right to such access

B- Date for inspection: The Engineer shall give the contractor give a reasonable notice of the intention of the Engineer in-charge or his subordinate staff to visit the work shall have given to the contractor, then he either himself be present to receive orders and instructions or have responsible agent duly accredited in writing present for that purpose orders given to the contractor's duly authorized agent shall be considered to have the same force an effect as if they had been given to the contractor himself.

Clause- 12: Examination of work before covering up:

A-No part of the work shall be covered up or put out of view / beyond the reach without giving notice of no less then days to the Engineer in charge when ever any such part of the works or foundation is or are ready or about to be ready for examination and the Engineer shall without delay unless he considers it unnecessary and advises the contractor accordingly, attend for the purpose of examining and measuring such part of the works or of examining such foundations.

B- If any work is cover up or placed beyond the reach of measurement without such notice having been given: the same shall be uncovered on the contractor's expenses and in default thereof no payment or allowance shall be made for such work or for the materials with which the same was executed.

Clause- 13: Risk: The contractor shall be responsible for all risks of loss of or damage to physical property or facilities or the related services at the premises and of personal injury and death without arise during and in consequence of its performance of the contractor. If any damage is caused while the work is in progress or become apparent within months of the grant of the certificate of completion, final or otherwise the contractor shall make good the same at this own expense or in default the Engineer may cause the same to be made good by other workman and deduct the expenses from retention money laying with the Engineer.

Clause- 14: Measures for prevention of fire and safety measures: The contractor shall not set fire to any standing jungle, trees bush wood or grass without a written permit from the Executive Engineer. When such permit is given, and also in a l cases when destroying cutting or uprooting trees bush wood grass etc by fire, the contractor shall take necessary measures to prevent such fire of all its activities including protection of the environment on and off the site.

5

5

Compensation of all damage done intentionally or in intentionally on the site by the contractor's labors shall be paid by him.

Clause 15: **Sub contracting:** The contractor shall not subcontract the whole of the works except where otherwise provided by the contract. The contractor shall not subcontract any part of the works without the prior consent of the Engineer in-charge. Any such consent shall not relieve the contractor from any liability or obligation under the contract and he shall be responsible for the acts, default or neglects were those of the contractor his agent servants or workman. The provisions of this contractor shall apply to such subcontract or his employees as if he or it were employees of the contractor.

Clause- 16: **Disputes:** All disputes arising in connection with the present contract, and which cannot be amicably settled between the parties, the decision of the Superintending Engineer of the circle / officer one grade higher to awarding authority shall be final, conclusive and binding on all parties to the contractor upon all questions relating to the meaning of the specifications, designs, drawings and work or as to any other questions\, claim, rights, matter or things whatsoever in any way arising out of or relating to the contract design, drawings, specifications, estimates, instructions, orders or these conditions or otherwise concerning the works or the execution of failure to execute the same whether arising during the progress of the work or after the completion or abandonment thereof.

Clause- 17: **Site clearance:** On completion of the work the contractor shall furnish the certificate by the Engineer in-charge (hereinafter called the Engineer in-charge) of such completion, but neither such certificate shall be given nor shall the work be considered to be complete until the contractor shall have removed all temporary structures and materials brought at the site either fails to comply with the requirements of this clause then Engineer in-charge may on the expense of the contractor remove and dispose off the same as he thinks fit and shall deduct the amount of all expenses so incurred from the contractor retention money. The contractor shall have no claim in respect of any surplus materials as aforesaid except for any such actually realized by the sale thereof.

Clause-18: **Financial assistance / advance payment:**

- A- Mobilization advance in any condition, situation is not allowed.
- B- Secure advance against materials brought at site.
 - 1- Secured advance may be permitted only against imperishable materials/ quantities anticipated / utilized on the work within a period of three months from the date of issue of secured advance and definitely not full quantities of materials for the entire work/ contract. The sum payable for such material on site shall not exceed 75% of the materials of the market price of materials.
 - 2- Recovery of secured advance paid to the contractor under above provision shall be affected from the monthly payments on actual consumption basis but not later then period more the three months (even if unutilized).

Clause-19: **Recovery of arrears of land Revenue:** Any sum due to the government by the contractor shall liable for recovery as arrears of land Revenue.

Clause-20: **Refund of security Deposit / Retention Money :** On completion of the whole of the works (a work should be considered as complete for the purpose of refund of security deposit to a contractor from the last date on which its final measurement are checked by and competent authority, if such check is necessary otherwise from the last date of recording the final measurements, the defects notice period has also passed and the Engineer in-charge has certified that all defects notified to the contractor before the end of this period have been corrected, the security deposit lodged by a contractor in cash or recovered in installments from his bills) shall be refunded to him after the expiry of three months from the date on which the work is completed.

Divisional Accountant

Executive Engineer / Procuring Agency

Contractor _____