

NAME OF WORK: - PROVIDING LAYING C.C TILE FLOORING QUAIDABAD QUARTER
MADINA COLONY & INTERNAL STREETS UC-QUAIDABAD BIN QASIM ZONEBILL OF QUANTITIES

(A) Description an rate of Items based on Composite Schedule of Rates.

S.No	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	6498.00	Preparing sub grade including earth excavation for filling to an average depth of 9" dressing to camber and consolidation with power roller etc...complete.	526.28	% Sft	34198.00
2.	2437.00	Providing and laying aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting by approved mechanical means (Motor grader, Vibrator roller and smooth wheel roller etc watering to maintain the moisture content the compaction of each layer shall 100 percent to the mix dry density (Rate i/c all cost of material T&P and carriage upto(H.W.Sch.P/4 I/13(b))	7606.09	% Cft	185360.00
3.	212.00	P/L cement concrete plain i/c placing compacting finishing and curing complete (including screening and washing at stone aggregate without. 1:2:4 etc...complete.(G.Sch.P/15 I/5(f)	14429.25	%Cft	30590.00
4.	5650.00Sft	Providing and laying Cement concrete Plain 1:2:4 ratio Gray Cement pigmented Tiles 2" Thick (50mm) 12"x 12" size (305mmx305mm) crushing strength including curing with steam curing additive laid over 3" thick sand cession (Consolidate) compaction with mechanical means including levelling required camber and grade with sand cussion joint including curing and finishing complete as Directed by Engineer In charge.	123.20	P.Sft	696080.00
5.	17 Nos	Manufacturing and supplying R.C.C Ring slab 21"dia out side 7.5"widthand 6"thick i/c 3/8"dia to steel bar to concentric ring with 3/8"dia 8 Nos cross link bars 1/c curing staking and transportation with in 10 Miles etc complete.(W S Schedule P-27 It-2)	1906.60	Each	32412.00

5.	23 Nos	Manufacturing and supplying R.C.C manhole covers cast in 1:2:4 concrete ratio 3" deep at center to center reinforcement with 3/8" dia for steel bars at 4" center to center welded to 1/8" thick 2.5" deep M.S Plate 1/c curing staking and transportation with in 10 Miles etc complete.(W S Schedule P-27 It-1) 21" dia	913.63	Each	Rs.21927/-
----	--------	---	--------	------	------------

Amount Total (a) Rs: 9,99,653/-

_____ %Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A)= a + b in words & Figures:

Contractor

Executive Engineer / Procuring Agency

Summary of Bill of Quantities

Cost of Bid	Amount
1 (A) Cost based on composite Schedule of Rate	_____
2 (B) Cost of based on Non / Offered Schedule of Rates.	_____
TOTAL COST OF BID (C) = TOTAL (A) + Total (B)	_____

Contractor

Executive Engineer / Procuring Agency

NAME OF WORK: -

PROVIDING LAYING C.C TILE FLOORING MARVI GOTH
& MUSLIM TANOL COLONY UC-QUAIDABAD BIN QASIM ZONEBILL OF QUANTITIES

(A) Description an rate of Items based on Composite Schedule of Rates.

S.NO	Quantities	Description of item to be executed at site	Rate	Unit	Amount in Rupees
1.	2.	3.	4.	5.	6.
1.	6498.00	Preparing sub grade including earth excavation for filling to an average depth of 9" dressing to camber and consolidation with power roller etc...complete.	526.28	% Sft	34198.00
2.	2437.00	Providing and laying aggregate base course in proper grade and camber having CBR 80% as per AASHTO standard specification i/c spreading and compacting by approved mechanical means (Motor grader, Vibrator roller and smooth wheel roller etc watering to maintain the moisture content the compaction of each layer shall 100 percent to the mix dry density (Rate i/c all cost of material T&P and carriage upto(H.W.Sch.P/4 I/13(b))	7606.09	% Cft	185360.00
3.	212.00	P/L cement concrete plain i/c placing compacting finishing and curing complete (including screening and washing at stone aggregate without. 1:2:4 etc...complete.(G.Sch.P/15 I/5(f)	14429.25	%Cft	30590.00
4.	5650.00Sft	Providing and laying Cement concrete Plain 1:2:4 ratio Gray Cement pigmented Tiles 2" Thick (50mm) 12"x 12" size (305mmx305mm) crushing strength including curing with steam curing additive laid over 3" thick sand cession (Consolidate) compaction with mechanical means including levelling required camber and grade with sand cussion joint including curing and finishing complete as Directed by Engineer In charge.	123.20	P.Sft	696080.00
5.	17 Nos	Manufacturing and supplying R.C.C Ring slab 21" dia out side 7.5" widthand 6"thick i/c 3/8" dia to steel bar to concentric ring with 3/8" dia 8 Nos cross link bars 1/c curing staking and transportation with in 10 Miles etc complete.(W S Schedule P-27 It-2)	1906.60	Each	32412.00

5.	23 Nos	Manufacturing and supplying R.C.C manhole covers cast in 1:2:4 concrete ratio 3" deep at center to center reinforcement with 3/8" dia for steel bars at 4" center to center welded to 1/8" thick 2.5" deep M.S Plate 1/c curing staking and transportation with in 10 Miles etc complete.(W S Schedule P-27 It-1) 21" dia	913.63	Each	Rs.21927/-
----	--------	---	--------	------	------------

Amount Total (a) Rs: 9,99,653/-

_____ %Above/Below On The Schedule Rates of CSR.

Amount to be Added/Deducted on the basis of premium quoted Total (b)

Total (A)= a + b in words & Figures:

Con ractor

Executive Engineer / Procuring Agency

Summary of Bill of Quantities

Cost of Bid

Amount _____

1 (A) Cost based on composite Schedule of Rate _____

2 (B) Cost of based on Non / Offered Schedule of Rates. _____

TOTAL COST OF BID (C) = TOTAL (A) + Total (B) _____

Contractor

Executive Engineer / Procuring Agency