

OFFICE OF THE EXECUTIVE ENGINEER (SEWERAGE)
LYARI TOWN, DIST. (SOUTH), KW&SB.

SUBJECT:- R / R OF 12" & 8" DIA RCC SEWER PIPE IN UMER LANE,
PHOTO LANE, SHANSHAHI ROAD AND KALA KOT
STREETS IN LYARI TOWN (SEWERAG), KW&SB.

ESTIMATE COST:- On Item Rate Basis. Issued to M/S. _____

TENDER COST:- Rs. 1000/= Pay Order NO: _____

TIME LIMIT:- _____ Days Dated:- _____

PENALTY:- 1000/= Per Day.

SUPERINTENDENT (REVENUE)

S.N.	DESCRIPTION.	QUANTITY	RATE		PER	AMOUNT
			In Figure	In Words		
01.	Dismantling and removing road metalling.					
		3500 Cft.			%Cft	
02.	Excavation for pipe line in trenches, and pits in all kind of soils of murum i/c trimming and dressing sides ;to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth within a one chain as directed by Engineer Incharge. Providing fence guards , lights, flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft. (1.52m) and lead upto one chain (30.5m). (0' to 5').					
	Up to 0' to 5'	13500 Cft.			%0Cft	
03.	Add every (03) three ft. additional lift in all execution					
	Up to 5' to 8'	3000 Cft.			%0Cft	
	Cont...Page... 02.					

Page... 02.						
04.	Providing, Laying RCC pipes with (Rubber Ring Joint and fitting in trench i/c cutting, fitting and jointing with rubber ring i/c testing with water to specified pressure.					
	200 mm (8" Dia).	200 Rft.			P/Rft	
	300 mm (12" Dia).	1000 Rft.			P/Rft	
05.	Full hire charges of the pumping set per day inclusive of wage of driver and Assistant fuel or electric energy plate forms required for placing pumps etc. at lower depth with suction and delivery pipes for pumping out water found at various depths from trenches i/c the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping o / w from 10 ft deep trench.	16 Days.			P/Day	
06.	Providing manholes 4 ft. inside with C.I Frame (15 kg) 5 feet clear depth 1:2:4 cast in situ in 9" thick wall 1:4:8 c.c in 6ft. dia and 6" thick in foundation, 1:2:4 c.c in benching ½" thick C.P 1:3 mortar on inside walls & surface of channel / benching i/c making required nos of main and branch channels, ¾' dia bars M.S foot rest at 12" c/c including cost of excavation of all kinds of soil, backfilling and disposal of excavated stuff etc complete, as per design and instruction of the engineer in-charge.	27 Nos.			Each	
Cont...Page... 03.						

Page... 03.						
07.	Add / deduct per ft depth.	(+) 8 Ft.			P/Ft.	
08.	Making connection with the existing m/hole i/c the cost of cutting holes in walls making them good in cement concert 1:2:4 and making the required channel etc. complete.	28 Nos.			Each	
09.	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc. complete.	15164 Cft			%0Cft	
				TOTAL:-	RS.	

Aahid
EXECUTIVE ENGINEER (SEW)
LYARI TOWN DIST. (SOUTH)

I hereby quoted Amounting to Rs. _____ (Inwards) _____

 Signature & Stamp of the Contractor:-
 Address. _____

EVALUATION CRITERIA OF THE TENDER UPTO 1.00 MILLION.

SUBJECT:- R / R OF 12" & 8" DIA RCC SEWER PIPE IN UMER LANE, PHOTO LANE, SHANSHAHI ROAD AND KALA KOT STREETS IN LYARI TOWN (SEWERAGE).

Bid shall be evaluated on the basis of following information are available with the bid:-

01. Bid shall be in sealed Cover.
02. Bid shall be properly signed by the Contractor with Stamp.
03. Name of firm, postal address, telephone number, Fax number, E-mail address must be written.
04. Rate must be quoted in figures and words.
05. NTN and Sales Tax (Where applicable).
06. Contractor should be registered with Sindh Revenue Board in terms of Rule-45-46(I)(iii) of SPP Rules, 2010 (amended 2014).
07. Relevant Experience of work (03) Three Years.
08. Turnover at least (03) Years.
09. Bid Security of required amount.
10. Conditional bid will not be considered.
11. Bid will be evaluated accordingly to SPPR-2010 (Amended 2013).
12. Debarred Contractors bid cannot be accept.



**EXECUTIVE ENGINEER (SEW)
LYARI TOWN (SOUTH)
KW&SB.**

ANNEXTURE-II
PROCUREMENT PLAN (NON-DEVELOPMENT)
LYARI TOWN, DISTRICT SOUTH KW&SB (FINANCIAL YEAR 2014-2015)

SR. NO.	FUND HEAD & SUB HEAD	NAME OF WORK AND BREAK UP	ALLOCATED FUNDS AND BREAK UP FOR DIFFERENT LOCATIONS / SITES	ITEMS TO BE EXECUTED	METHOD OF PROCUREMENT	ANTICIPATED/ ACTUAL DATE OF ADVERTISEMENT	ANTICIPATED / ACTUAL DATE OF START	ANTICIPATED / ACTUAL DATE OF COMPLETION	REMARKS
A	B	C	D	E	F	G	H	I	J
01.	E-023-32	R / R OF 12" & 8" DIA RCC SEWER PIPE IN UMER LANE, PHOTO LANE, SHANSHAHI ROAD AND KALA KOT STREETS IN LYARI TOWN (SEWERAG), KW&SB.	5.00 MILLION	R / R OF 12" & 8" DIA RCC SEWER PIPE IN UMER LANE, PHOTO LANE, SHANSHAHI ROAD AND KALA KOT STREETS IN LYARI TOWN (SEWERAG), KW&SB.	Single stage one Envelope Procedure.	07-05 - 2015	2 nd Week of May - 2015	4 th Week of May -2015	

Ashid
EXECUTIVE ENGINEER (SEW)
LYARI TOWN DIST: (SOUTH)