



BIDDING DATA

This Section should be filled in by the Executive Engineer Education Works Division Sukkur, before issuance of the Bidding Documents.

- (a) Name of Procuring Agency Executive Engineer, Education Works Division Sukkur
- (b) Brief Description of Works CONSTRUCTION OF 05 ROOMED RIVER SIDE SCHOOL OF EXCELLENCE AT VILLAGE MUHAMMAD LAIK BHUTTO NEAR PUNJ NALKA ACHYOON QUBYOON ROHRI. UNDER MNA PRIORITY PROGRAMME NA-199 2014-15
- (c) Procuring Agency Address Near Shikarpur Phatak Golimar Road Sukkur
- (d) Estimated Cost 8700000
- (e) Amount of Bid Security 174000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (if bid Security) 870000
- (h) Percentage, if any, to be deducted from bills 8%
- (i) Deadlines for submission of bids along with times 14.05.2015 (1:00 PM)
- (j) Venue, Time and Date of Bid Opening 14.05.2015 (2:00 PM)
- (k) Time for completion from written order of commences 03 Months
- (L) Liquidly Damages _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No. _____ Date _____ Amount _____

(c) Tender Issued to (Mr. / M/S)


DIVISIONAL ACCOUNTS OFFICER
EDUCATION WORKS DIVISION
SUKKUR


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SUKKUR

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- CONSTRUCTION OF 05 ROOMED RIVER SIDE SCHOOL OF EXCELLENCE AT VILLAGE MUHAMMAD LAIK BAHITO NEAR DUDHAIYA RIVER, DISTRICT SHERKOT, FATA. BYCCO, KORI, UNDER TANA PRIORITY PROGRAMME. NA-199 2014 PROGRAMME

Item No.	Quantity	Description of item to be executed at site	Rate	Unit	Amount
PART 'A' SCHEDULE ITEMS					
1	9,042	Excavation in foundation of building, bridges and other structures including dressing retaining around structure with excavated earth watering and ramming lead upto one chain and lift upto 5ft (b) in ordinary soil (C.S.I No:18 (b) P.5).	3,176.26	%CR	28,720
2	3,560	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9,416.28	%CR	335,220
3	3,202	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6 (C.S.I No:4 (e) P.21).	11,948.36	%CR	1,099,488
4	1,995	Reinforced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately this rate also includes all kinds of forms moulds lifting clearing curing rendering and finishing the exposed surface (including screening and washing of shingles) (a) RC work in slabs beams columns raft lintels and other structural members laid in situ or pre cast laid in position complete in all respects. (b) Ratio (1:2:4) for 1:1 cement 2:1:3 sand 4:1:1 shingles 180 to 174 gauge (c) 1:1:6 (A (1) P.17).	337.00	P.Cit	658,835
5	127	Fabrication of iron steel reinforcement for cement concrete including cutting bending and laying in position making joints and finishes including cost of binding wire also includes removal of rust from bars (C.S.I No:17).	3,081.70	P.Cit	611,158
6	1,009	Pacca brick work in upper floor in cement sand mortar ratio. (C.S.I No. 4 (e) Page No: 21)	12,074.36	%CR	1,021,553
7	1,600	Pacca brick work other than building including striking of joints up to feet height (C.S.I No: 7 (c) Page No: 22)	12,346.65	%CR	444,479
8	120	Making & fixing steel grated door with 1/16" thick sheeting including angle iron frame 2" x 2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangement. (C.S.I No:24 P-92)	726.72	P.Sit	87,206
9	398	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for windows using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary bolts fast filling with cement sand slurry of ratio 1:6 and repairing the joints. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:28 P.93).	240.50	P.RR	95,719
10	187	Providing and fixing G.I frames /Chowkates 7"2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c welded hinges and fixing at site with necessary bolts fast filling with cement sand slurry of ration 1:6 and repairing the joints. Cost also i/c all carriage tools and plants used in making and fixing (C.S.I No:29 P.93).	226.90	P.RR	42,804
11	8,492	Filling watering and ramming earth under floor with new earth excavated from outside lead upto one chain and lift upto 5ft. (C.S.I No: 22 P.4).	3,030.00	%CR	23,500
12	8,492	Extra lead three miles.	579.41	%CR	37,615
13	13,572	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b) Page No: 52).	2,206.60	%Sft	365,678
14	13,572	Cement plaster upto 20' height 3/8" thick ratio 1:4 (C.S.I No: 11 (a) Page No: 52).	2,197.52	%Sft	354,173
15	4,800	Cement pointing striking of joints of walls ratio 1:2 (C.S.I No: 19 (a) Page. 53)	1,287.44	%Sft	61,797
16	223	Supplying and fixing in position iron steel grill of 3/4"x 1/4" size flat iron of approved design i/c painting three coats etcomplete weightg not less than 3.7 lbs of finished grill (C.S.I No:26 P.93).	180.50	P.Sit	40,252
17	163	Notice board made with cement (C.S.I No:1 P.95).	59.11	P.Sit	9,298
18	463	First class deodar wood wrought joinery in doors and windows etcted in position i/c in chwoakts holds fasts hinges iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paned are fully glazed 1/3/4"only shutter (C.S.I No:7 (b) P.58).	902.93	P.SR	418,057

Quantities	Description of item to be executed at site	Rate	Units	Amount
10	107 Laying in one (top) 1/2 inch thick in patches of approved any pattern of 1 part of WHITE cement 2 parts of rubble chips of required shape and size of approved pigment in the ratio of 1:12 of cement used in topping including rubbing and polishing etc. complete. (S.I No55 Page 47)	12,346.40	%Sqft	81,442
20	7 400 1/2" Order of tiles of work	3,200.00	Each	79,400
21	100 1/2" Floor of tiles of work	3,575.00	Each	101,700
22	1 400 1/2" floor tiled steel floor on old rails in roof etc. connection and fixing in position (S.I No: 1 (a) (i))	180.34	Each	180,340
23	1075 1st class tiles roofing consisting of 4" earth and 1" mud plaster with lagging over 1/2" thick cement plaster 1:3 with 34 lbs of hot bitumen mastic and blinding provided over one layer of 12" dia x 1/4" tiles laid in 1/2" cement mortar including 1/2" cement pointing under eaves of floor complete including caning etc (C.S.I No: 1 (a) (i))	11,443.10	%Sqft	74,762
24	7 722 White wash three coats (C.S.I No 26 (c) P-54)	820.06	%Sqft	22,501
25	10 572 Primary coat of chalk under distemper (C.S.I No 23 (c) P-54)	442.75	%Sqft	73,973
26	11 572 Distemper three coats (C.S.I No 24 (c) P-54)	1,079.65	%Sqft	170,920
27	1 100 Painting new surface, and painting of doors and windows any type (th edges) 3 coats (C.S.I No:4 (c) P-70).	2,116.41	%Sqft	23,281
28	120 Painting guard bars gate iron bars grating railing including standard braces etc and smaller open work three coat (C.S.I No:4 (d) (i) P-70).	1,270.83	%Sqft	1,525
TOTAL :-				7,366,512

PART "B" SCHEDULE ITEMS

1	3	Providing & fixing squaring type white glazed or flusco cistern with internal fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connection & making good in cement concrete 1:2:4. W.C not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia C.I trap with C.I thumb. (S.I No:1 (b) P-No:1)	4802.60	Each	14,408
2	3	Providing & fixing 24" x 18" lavatory basin in white glazed earthen ware complete with & 1/2 the cost of W.I or C.I counter bracket. 6 inches built into wall, painted white in two coats after a primary coat of red lead paint, a pair of 1/2" dia rubber plug & chrome plate brass chain 1-1/4" dia malleable iron or C.P brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete 1: 2: 4 (Standard pattern). (S.I No:9 P-No:3).	4253.70	Each	12,761
3	3	Add: extra labour for providing and fixing of earthen ware pedestal white or colored glass standard pattern (S.I No:9 P-No:3).	938.47	Each	2,815
4	6	P/F in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection (S.I No:23 P-No:6).	447.15	Each	2,683
5	3	P/F 6" x 4" c.c gully trap with 4" dia out let complete with 4" thick 1:2:4 c.c for bed and 1/2" thick cement plaster 1:3 to the kerb c.I caning 6" x 6" and c.I cover and frame 12" x 12" in side etc complete (S.I No:1(a-i) P-No:21).	1193.17	Each	3,580
6	50	P/F 4" dia C.I soil and vent pipes including cutting and filling and extra painting to match the colour of the building (S.I No:1 P-No:9).	333.29	P.Rft	16,665
7	1	RCC pipe with collar class "D" and dipping the traches to the required depth and fixing in position 1/2 cutting fitting and jointing with max phalt composition and cement mortar 1:1 and testing with water pressure to head of 4 Ft above the top of the height			
	100	4" dia			
	50	6" dia	146.57	P.Rft	14,657
8	3	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & 1/2 making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No: 20 Page No.3).	199.25	P.Rft	9,963
			2042.43	P.Rft	6,127
9	1	Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and 1/2 the cost of breaking through walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zinc paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)			

Quantities	Description of item to be executed at site	Rate	Units	Amount
99	1/2" dia			
150	3/4" dia	73.21	P.Rft	7,321
50	1" dia	95.79	P.Rft	4,369
50	1-1/4" dia	128.55	P.Rft	7,713
	Add: Extra labor for concealed CI pipe and filling w/c making recess in the wall for pipe and making good in Cement mortar etc Complete	153.19	P.Rft	7,600
50	1/2" dia			
50	3/4" dia	7.82	P.Rft	391
	Providing and fixing full way gun metal valves with wheels threaded or Banged ends with rubber washing (b) standard pattern (Photo attachment Manufacture by M/S Anwar Technical works (S.I No:4 (b) P- No:17).	8.45	P.Rft	423
	3/4" dia	161.92	Each	486
	1/2" controlled stop cock of superior quality with crystal head head 1/2" dia (S.I No:11 (b) P- No:18).	227.92	Each	684
	5/8" long bib cock of crystal head with c.p head 1/2" dia (S.I No:13 (b) P- No:19).	478.28	Each	2,970
	5/8" wash basin mixture of superior quality with c.p head 1/2" dia with crystal head (S.I No:16 (b) P- No:15).	1109.40	Each	6,057
	1 Supplying & fixing Bath room accessories set (7 pieces i/c towel rod, brush holder, soap tray, shelf of approved quality and design etc complete. (S.I No: 22 P- No:19)	2882.00	Each	2,882
	P/F handle valves (China) (S.I No:7 P- No:14).	10322.40	Each	10,322
3	3/4" dia			
3	1" dia	271.92	Each	816
	P/F in position floor grass tank with approved design and wall thickness as specified i/c cost of nuts bolts and fixing in plate forum of c.c 1:3:6 and making connections for inlets out late and over flow inlets out flow pipes etc complete (S.I No:3 P- No:13	365.42	Each	1,096
	250 Gallons	21989.61	Each	11,990
TOTAL :-				1,00,336

PART "C" SCHEDULE ITEMS

1	Providing PVC Pipes of class D equivalent (make) fixing in trench i/c cutting, fitting and jointing with "Z" joint with one rubber Ring i/c testing with water to head of 122 meters or 400ft. (S.I No:3 Page No:23)	137.00	P.Rft	1,700
	Construction of manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) depth with walls of BB in cement mortar 1:3 cement plaster 1:3, 1/2" thick inside of walls and 1" (25 mm) thick over benching and channel i/c fixing CI manhole cover with frame of clear opening 1-1/2' x 1, 1/2' (457x457 mm) of 1.75 Cwt. (38.9 Kg) embedded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) wide projecting 4" (102 mm) from the face of wall at 12" (305 mm) C.C dully painted etc. complete as per specification and drawing (S.I No. P Page No. 46). (PHE)	226.00	P.Rft	1,600
2		14748.00	Each	14,244
TOTAL :-				1,0,544

Amount Total (CSR)

Part "A" % Above / Below _____

Part "B" % Above / Below _____

Part "C" % Above / Below _____

Total Amount _____

Total Amount _____

Total Amount _____

Total "A+B+C" _____

CONTRACTOR

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SUKKUR

This form should be filled in for the purpose of registration of bids for the works mentioned below
submitted to the District Engineer.

- (a) Name of Procuring Agency Executive Engineer, Education Works Division Sikkur
- (b) Brief Description of Works CONSTRUCTION OF 05 ROOMED RIVER SIDE SCHOOL OF EXCELLENCE AT VILLAGE MUHAMMAD LAIK BHUTTO NEAR PUNJ NALKA ACHYOGH GUBBYON RORKE UNDER MNA PRIORITY PROGRAMME NA-199 2014-15 PROGRAMME (INTERNAL ELECTRIFICATION).
- (c) Procuring Agency Address No. 21/22/23/24/25/26/27/28/29/30/31/32/33/34/35/36/37/38/39/40/41/42/43/44/45/46/47/48/49/50/51/52/53/54/55/56/57/58/59/60/61/62/63/64/65/66/67/68/69/70/71/72/73/74/75/76/77/78/79/80/81/82/83/84/85/86/87/88/89/90/91/92/93/94/95/96/97/98/99/100/101/102/103/104/105/106/107/108/109/110/111/112/113/114/115/116/117/118/119/120/121/122/123/124/125/126/127/128/129/130/131/132/133/134/135/136/137/138/139/140/141/142/143/144/145/146/147/148/149/150/151/152/153/154/155/156/157/158/159/160/161/162/163/164/165/166/167/168/169/170/171/172/173/174/175/176/177/178/179/180/181/182/183/184/185/186/187/188/189/190/191/192/193/194/195/196/197/198/199/200/201/202/203/204/205/206/207/208/209/210/211/212/213/214/215/216/217/218/219/220/221/222/223/224/225/226/227/228/229/230/231/232/233/234/235/236/237/238/239/240/241/242/243/244/245/246/247/248/249/250/251/252/253/254/255/256/257/258/259/260/261/262/263/264/265/266/267/268/269/270/271/272/273/274/275/276/277/278/279/280/281/282/283/284/285/286/287/288/289/290/291/292/293/294/295/296/297/298/299/300/301/302/303/304/305/306/307/308/309/310/311/312/313/314/315/316/317/318/319/320/321/322/323/324/325/326/327/328/329/330/331/332/333/334/335/336/337/338/339/340/341/342/343/344/345/346/347/348/349/350/351/352/353/354/355/356/357/358/359/360/361/362/363/364/365/366/367/368/369/370/371/372/373/374/375/376/377/378/379/380/381/382/383/384/385/386/387/388/389/390/391/392/393/394/395/396/397/398/399/400/401/402/403/404/405/406/407/408/409/410/411/412/413/414/415/416/417/418/419/420/421/422/423/424/425/426/427/428/429/430/431/432/433/434/435/436/437/438/439/440/441/442/443/444/445/446/447/448/449/450/451/452/453/454/455/456/457/458/459/460/461/462/463/464/465/466/467/468/469/470/471/472/473/474/475/476/477/478/479/480/481/482/483/484/485/486/487/488/489/490/491/492/493/494/495/496/497/498/499/500/501/502/503/504/505/506/507/508/509/510/511/512/513/514/515/516/517/518/519/520/521/522/523/524/525/526/527/528/529/530/531/532/533/534/535/536/537/538/539/540/541/542/543/544/545/546/547/548/549/550/551/552/553/554/555/556/557/558/559/560/561/562/563/564/565/566/567/568/569/570/571/572/573/574/575/576/577/578/579/580/581/582/583/584/585/586/587/588/589/590/591/592/593/594/595/596/597/598/599/600/601/602/603/604/605/606/607/608/609/610/611/612/613/614/615/616/617/618/619/620/621/622/623/624/625/626/627/628/629/630/631/632/633/634/635/636/637/638/639/640/641/642/643/644/645/646/647/648/649/650/651/652/653/654/655/656/657/658/659/660/661/662/663/664/665/666/667/668/669/670/671/672/673/674/675/676/677/678/679/680/681/682/683/684/685/686/687/688/689/690/691/692/693/694/695/696/697/698/699/700/701/702/703/704/705/706/707/708/709/710/711/712/713/714/715/716/717/718/719/720/721/722/723/724/725/726/727/728/729/730/731/732/733/734/735/736/737/738/739/740/741/742/743/744/745/746/747/748/749/750/751/752/753/754/755/756/757/758/759/760/761/762/763/764/765/766/767/768/769/770/771/772/773/774/775/776/777/778/779/780/781/782/783/784/785/786/787/788/789/790/791/792/793/794/795/796/797/798/799/800/801/802/803/804/805/806/807/808/809/810/811/812/813/814/815/816/817/818/819/820/821/822/823/824/825/826/827/828/829/830/831/832/833/834/835/836/837/838/839/840/841/842/843/844/845/846/847/848/849/850/851/852/853/854/855/856/857/858/859/860/861/862/863/864/865/866/867/868/869/870/871/872/873/874/875/876/877/878/879/880/881/882/883/884/885/886/887/888/889/890/891/892/893/894/895/896/897/898/899/900/901/902/903/904/905/906/907/908/909/910/911/912/913/914/915/916/917/918/919/920/921/922/923/924/925/926/927/928/929/930/931/932/933/934/935/936/937/938/939/940/941/942/943/944/945/946/947/948/949/950/951/952/953/954/955/956/957/958/959/960/961/962/963/964/965/966/967/968/969/970/971/972/973/974/975/976/977/978/979/980/981/982/983/984/985/986/987/988/989/990/991/992/993/994/995/996/997/998/999/1000
- (d) Estimated Cost 500000
- (e) Amount of Bid Security 100000
- (f) Period of Bid Validity (Days) 30 Days
- (g) Security Deposit (in bid Security) 100000
- (h) Percentage, if any, to be deducted from bills 8%
- (i) Deadline for submission of bids along with bills 14.05.2015 (11.00 PM)
- (j) Venue, Time and Date of Bid opening 14.05.2015 (12.00 PM)
- (k) Name of Applicant Mr. [Signature]
- (l) Designation Area [Signature]
- (m) District [Signature]
- (n) D/R No. _____ Date _____ Amount _____
- (o) Tender issued to Mr. [Signature]


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SIKKUR


[Signature]
EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SIKKUR

BIDDING DATA

This Section should be filled in by the Executive Engineer Education Works Division Sukkur, before issuance of the Bidding Documents.

- (a) Name of Procuring Agency Executive Engineer, Education Works Division Sukkur
- (b) Brief Description of Works RENOVATION / REHABILITATION OF EXISTING
ELEMENTARY / SECONDARY / COLLEGES
BUILDINGS (RAIN DAMAGES) 2012-13 @ QUARTER
NO. 1 HANDI CAPPED CHILDREN SCHOOL SUKKUR.
- (c) Procuring Agency Address Near Shikarpur Phatak Golimar Road Sukkur
- (d) Estimated Cost 1900000
- (e) Amount of Bid Security 38000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 190000
- (h) Percentage, if any, to be deducted from bills 8%
- (i) Deadlines for submission of bids along with times 14.05.2015 (1:00 PM)
- (j) Venue, Time and Date of Bid Opening 14.05.2015 (2:00 PM)
- (k) Time for completion from written order of commences 02 Months
- (l) Liquidity Demogon _____
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D.R No. _____ Date _____ Amount _____
- (o) Tender Issued to (Mr./M/S) _____


DIVISIONAL ACCOUNTS OFFICER
EDUCATION WORKS DIVISION
SUKKUR


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SUKKUR

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- RENOVATION / REHABILITATION OF EXISTING ELEMENTARY / SECONDARY / COLLEGES BUILDINGS (RAIN DAMAGES) 2012-13 @ QUARTER NO. 1 HANDI CAPPED CHILDERN SCHOOL SUKKUR.

Item No	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1.	438	Dismantling cement concrete reinforced separating reinforcement from concrete clearing and straighting the same (C.S.I No:20 P-10).	5445.00	%Cft	23849
2	3	Removing doors with chowkats (C.S.I No:33 (a) P-12).	142.18	Each	427
3	300	Dismantling brick work in line or cement plaster (C.S.I No:13 P-10).	1285.63	%Cft	3857
4	277	Dismantling cement concrete plain 1:3:6 (C.S.I No. 19 (b) P-10).	1306.80	%Cft	3620
5	1639	Removing cement or lime plaster (C.S.I No:53 P-13).	121.00	%Sft	1983
6	2654	Disposal of Dibries	579.41	%Cft	15378
7	264	Excavation in foundation of building bridges and other structure including dressing refeling around structure with excavated earth watering and ramming lead upto one chain and lift upto 5ft (b) in ordinary soil(C.S.I No:18 (b)P.5.	3176.25	%Cft	839
8	68	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9416.28	%Cft	6403
9	340	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6(C.S.I No:4 (c) P.21).	11948.36	%Cft	40624
10	666	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepreately; this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slabe bams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (i)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft. shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.19).	337.00	P.Cft	224442
11	32.705	Fabrication of Tor steel reinforcement for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:7 B P.20).	5001.70	P.Cwt	163581
12	1809	Filling watering and raming earth under floor with new earth excavated from outside lead upto on chain and lift upto 5ft. (C.S.I No: 22 P.4).	3630.00	%Cft	6567
13	1809	Extra lead three miles	579.41	%CR	10482
14	533	Pacca brick work in ground floor in cement sand mortar ratio: (C.S.I No: 5 (e) Page No: 21)	12674.36	%CR	67554
15	751	Pacca brick work other then building including striking of joints up to feet height (C.S.I No: 7 (e) Page No: 22)	12346.65	%Cft	92723
16	1639	Applying & Flooting coat of cement 1/32" thick (C.S.I No:14 P-53).	660.00	%Sft	10817
17	1639	Cement plaster upto 20' height 3/4" thick ratio 1:4 (C.S.I No: 11 (c) Page No: 52)	3015.76	%Sft	49428
18	686	Providing and lying 2" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels(C.S.I No:16 (c) P-42).	3275.50	%Sft	32296
19	630	Providing and lying 3" thick topping cement concrete 1:2:4. Including surface finishing dividing into panels (C.S.I No:16 (d) P-42).	4411.82	%Sft	27794
20	3426	Cement plaster upto 20' height 1/2" thick ratio 1:6 (C.S.I No: 13 (b)Page No: 52).	2206.60	%Sft	75598
21	3426	Cement plaster upto 20' height 3/8" thick ratio 1:4 (C.S.I No: 11 (a) Page No: 52).	2197.52	%Sft	75287
22	76	Making & fixing steel grated door with 1/16" thick sheeting including angle iron frame 2" x 2" 3/8"and 3/4" square bars 4" centre to centre with locking arrangemnt. (C.S.I No:24 P-92)	726.72	P.Sft	55231
23	15	First class deodar wood wrought joinery in doors and windos etcfied in position l/c in ciwoakts holds fasts hinges iron tower bolts chowks cleats handles and cards with hooks etc Deodar paneled or paneed are fully glazed 1/3/4"only shutter (C.S.I No:7 (b) P.58).	902.93	P.Sft	13544

Sl. No.	Qty	Description of item to be executed at site	Rate	Units	Amount
76		Galvanized wire gauze fixed to chowkats with 3/4" deodar strips and screws. (C.S.I No. 14 (d) P-60).	190.72	P.Sft	14495
58		First class deodar wood wrought joinery in wire glazed door and windows with 22. S.W.G galvanized wire glazed 144 mesh per squarer inch iron fitting complete 1 1/2" thick deodar wood framing including wire gauze with ordinary hinges. (C.S.I No:14 (B) P.67).	562.98	P.Sft	32653
205		Cement Concrete plain including placing compacting finishing and curing complete including screening complete and washing of stone aggregate without churning Ratio: 1:2:4 (C.S.I No: 5 (d) Page No:16)	14429.25	%Cft	29580
7	214	Excision and removal of cutting for R.C.C or plain Cement concrete work for plinth wall Horizontal (C.S.I No. 18 (a) (i) Page No:21)	3598.58	%Sft	7680
28	5,000	1/2" Circular Site of Work	3850.00	P.Cwt	19250
29	2,893	1/2" Linear Site of Work	3575.00	P.Cwt	10342
30	7,893	Excision rooted steel beam or old rails in roof etc erection and fixing in position (C.S.I No:6 P-91).	186.34	P.Cwt	1471
31	428	2nd class tiles roofing consisting of 4" earth and 1" mud presles with leaping over 1/2" thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2" tiles laid in 1" G cement mortar including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.33).	7607.25	%Sft	9737
32	4	Fixing doors including chowkats (C.S.I No:44 (a) P-63).	279.51	P.No	1118
33	45	Providing & fixing deodar almirah 9" - 12" depth including boxing with back shelves shutters brass fitting complete (CSI No:23 P-61)	1778.50	P.Sft	80033
34	214	Supplying and fixing broden glasses on courtyard walls including 1: 3: 6 cement concrete coping.	70.44	P.Sft	15074
35	1527	Providing and laying non-glazed 6" x 6" x 1/4" on floor or wall facing in required colour and optom of STILE specification jointed in white cement and pigment over a base of 1:2 grey cement mortar 3/4" thick including washing and filling of joints with slaurry of white cement and pigment in desired shape with finishing, clearing and cost of wax polish etc. complete including cutting tiles to proper profile. (C.S.I No:60 P-47).	30509.77	%Sft	465884
36	128	1/2" barbed wire fencing with 12 gauge -4 points @ 6" apart barbed wire /2 strengthening & fixing in angle iron vertical posts (C.S.I No: 9 P-96).	8.38	P.Sft	1073
37	24	Providing & Fixing angle iron vertical posts of barbed wire fencing of size 2" x 2" 1/4" embedded in RCC / Masonary pillars i/c fixing in pillars by chiseling and filling the with cement sand mortar repairing and finishing the surface (C.S.I No. 8 P-56).	169.18	P.Sft	4060
38	132	Supplying & Fixing false ceiling of plaster paris, in panels including making frame work of deodar wood including painting with softlight paint (C.S.I No: 52 P-64).	25293.42	%Sft	33387
38	5255	Destember three coats (C.S.I No:24 (c) P-54).	1079.65	%Sft	56736
39	1816	Preparing surface and painting with Emulsion paint three coat (CSI No. 21 (c) Page No. 72)	1762.75	%Sft	32012
40	439	Painting new surface, and puting of doors and windows any type (i/c e gyes) 3 coats (C.S.I No:4 (c) P-76).	2116.41	%Sft	9291
41	424	Painting guard bars gats iron bars grating railing including standard braces etc and smiler open work three coat (C.S.I No:4 (d) (ii) P-70).	1270.83	%Sft	5388
TOTAL :-					1831586

Amount Total (CSR)

Part "A"

% Above / Below

Total Amount

Total "A"

NON SCHEDULE ITEMS

1	1	P/F piston pump set 1 H.P single phase 220 volts with 1/1/4" x 1/1/4" suction and delivery (Local made) (Electric)		Each	
2		P/F Union check walls 3/4"		Each	
3		P/F Ball walls 3/4"		Each	

No	Description of item to be executed at site	Rate	Units	Amount
	Supplying and fixing Gas burner & pipes etc as required		Each	
	Supplying and fixing 1/2" ball valve of Gas burner & pipes etc as required		Each	
	Gas compressor etc as required		Each	
TOTAL :-				


Cost of Bid

Amount Position

1. (A) Cost Based on Composite Schedule of Rates
2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)


CONTRACTOR



 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 SUKKUR

BIDDING DATA

This Section should be filled in by the Executive Engineer Education Works Division Sukkur, before issuance of the Bidding Documents.

- (a) Name of Procuring Agency Executive Engineer, Education Works Division Sukkur
- (b) Brief Description of Works RENOVATION / REHABILITATION OF EXISTING
ELEMENTARY / SECONDARY / COLLEGES
BUILDINGS (RAIN DAMAGES) 2012-13 @ QUARTER
NO. 2 HANDICAPPED CHILDREN SCHOOL SUKKUR.
- (c) Procuring Agency Address Near Shikarpur Phatak Golimar Road Sukkur
- (d) Estimated Cost 1000000
- (e) Amount of Bid Security 20000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (i/c bid Security) 100000
- (h) Percentage, if any, to be deducted from bills 8%
- (i) Deadlines for submission of bids along with times 14.05.2015 (1:00 PM)
- (j) Venue, Time and Date of Bid Opening 14.05.2015 (2:00 PM)
- (k) Time for completion from written order of commences 02 Months
- (L) Liquidity Damages _____
- (m) Deposit Receipt | _____ Date _____ Amount _____
- (n) D.R No: _____ Date _____ Amount _____
- (o) Tender Issued to (Mr. / M/S) _____


DIVISIONAL ACCOUNTS OFFICER
EDUCATION WORKS DIVISION
SUKKUR


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SUKKUR

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates:

OF WORK :- RENOVATION / REHABILITATION OF EXISTING ELEMENTARY / SECONDARY / JESUIT COLLEGE BUILDINGS (RAIN DAMAGES) 2012-13 @ QUARTER NO. 2 HANDI CAPPED CHILDREN'S COLLEGE JOL SUKKUR.

Item No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1	376	Dismantling cement concrete reinforced separating reinforcement from concrete clearing and straighting the same (C.S.I No:20 P-10)	5,445.00	%Cft	20,473
2		Removing doors with chowkats (C.S.I No:33 (a) P-12).	142.18	Each	142
3	198	Dismantling cement concrete plain 1:3:6 (C.S.I No. 19 (b) P-10).	1,306.80	%Cft	2,587
4	962	Removing cement or lime plaster (C.S.I No:53 P-13).	121.00	%Sft	1,164
5	72	Excavation in foundation of building bridges and other structure including dressing refeling around structure with excavated earth watering and ramming lead upto one chain and lift upto 5ft (b) in ordinary soil(C.S.I No:18 (b)P:5.	3,170.25	%CCft	229
6	107	Cement concrete brick or stone ballast 1 1/2" to 2" guage ratio 1:4:8 (C.S.I No: 4 (b) Page No:15)	9,416.28	%Cft	10,075
7	357	Rein forced cement concrete work including all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid sepreately this rate also includes all kinds of forms moulds:lifting shuttering curing rending and finishing the exposed surface (including screening and washing of shingle) (a) RC work in slab: beams columns rafts lintels and other structural members laid in situ or pre cost laid in position complete in all respects. (b)Ratio (1:2:4) 90 Lbs cement 2 Cft. sand 4 Cft. shingle 1/8" to 1/4" guage.(C.S.I No:6 A (1) P.19).	337.00	P.Cft	120,309
8	18	Fabrication of Tor steel reinforcement for cement concrete including cutting bending and laying in position making joints and fastings including cost of binding wire also includes removal of rust from bars (C.S.I No:7 P.19)	5,001.70	P.Cwt	87,685
9	172	Pucca brick work in ground floor in cement sand mortar ratio: (C.S.I No. 5 (c) Page No: 21)	12,674.36	%Cft	21,800
10	962	Applying & flooring coat of cement 1/32" thick (C.S.I No:14 P.53).	600.00	%Sft	6,349
11	1,622	Cement plaster upto 20' height 3/4" thick ratio 1:4 (C.S.I No: 11 (c) Page No: 52).	3,015.76	%Sft	48,916
12	2,148	Providing and lying 2" thick topping cement concrete 1:2:4. including surface finishing dividing into panels(C.S.I No:16 (c) P-42).	3,275.50	%Sft	70,358
13	124	Making & fixing steel grated door with 1/16" thick sheeting including angle iron frame 2" x 2" 3/8"and 3/4" square bars 4" centre to centre with locking arragemnt. (C.S.I No:24 P-92)	726.72	P.Sft	90,113
14	18	First class deodar wood wrought joinery in doors and windows etc fixed insition i/c in chwoakts holds fasts hinges iron lower bolts chowkats cleats handles and cards with hooks etc deodar paneled or paned are fully glazed 1:3:4 (C.S.I No: 7 (b)Page No: 58).	1,273.76	P.Sft	22,928
15	10	S/F Girder at Site of Work	3,850.00	P.Cwt	38,157
16	6	S/F T.Iron at Site of Work	3,575.00	P.Cwt	21,704
17	16	Erection rooled steel beam or old rails in roof etc erection and fixing in position (C.S.I No:6 P-91).	186.34	P.Cwt	2,978
18	270	2nd class tiles roofing consisting of 4"earth and 1" mud plaster with leaping over 1/2"thick cement plaster 1:6 with 34 lbs of hot bitumen coating sand blinded provided over one layer of 12"x6"x2"tiles laid in 1"6 cement mortar including 1:2 cement pointing under neath of tiles complete including curing etc (C.S.I No:2 P.33).	7,607.25	%Sft	20,540
19	128	Asbestos cement corrugated sheet roofing including necessary over laps and G.I hook bolts nuts screws washers and bitumen washers etc. (excluding valleys and ridges etc. (C.S.I No:28 P.37).	12,141.25	%Sft	15,541
20	1	Fixing doors including chowkats (C.S.I No:41 (a) P.53).	279.51	P.No	280
21	54	Supplying and fixing broden,glasses on courtyard walls including 1: 3: 6 cement concrete coping.	70.44	P.Sft	3,804
22	12	Providing & fixing deodar almirah 9" - 12" deep including boxing with back shelves shutters brass fitting complete (CS: No.23 P-61)	1,778.50	P.Sft	21,342
23	625	White wash three coats (C.S.I No:26 (c) P-54).	1,079.65	%Sft	6,748

Sl. No.	Description of item to be executed at site	Rate	Units	Amount
352	Decorative three coats (C.S.I No:24 (c) P-54).	1,079.65	%Sft	37,270
384	Painting new surface, and painting of doors and windows any type (w/c edges) 3 coats (C.S.I No:4 (c) P-70).	2,116.41	%Sft	10,243
368	Painting guard bars girts iron bars grating railing including standard braces etc and smaller open work three coat (C.S.I No:4 (d) (ii) P-70).	1,270.83	%Sft	4,677
TOTAL :-				686,411

PART "B" SCHEDULE ITEMS

1	1	Providing and fixing squatting type white glazed earthen ware w.c pan with front flush inlet & complete with including the cost of flushing design with internal fitting and flush Pipe with bend and making requisite number of holes in walls, plinth & floor for Pipe connection & making good in cement concrete 1:2:4. (Foreign Equivalant) W.C pan 18" earthen ware low level flush tank 3 gallons. With 4" dia C.I Trap.	6,014.80	Each	6,015
2	2	Providing & fixing 4" diameter white glazed earthen ware wash down w.c pan complete with and including cost of substitute plastic seat (Dura) 18" x 14" and 18" dia. 1" brass hinges and buffers. 3 gallons white glass of earthen ware low level flushing cistern with apron fitting 1-1/2" dia waste porcelain enameled flush bend 3/4" dia and making requisite number of holes in walls, plinth and floor for Pipe connections and making good in cement concrete 1:2:4. (Foreign Quality).	11,477.40	Each	22,955
3	7	W.C in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection	447.15	Each	3,130
4	3	Providing & fixing 6" x 2" or 6" x 3" C.I floor trap of the approved self cleaning design with a C.I screwed down grating with or without a vent arm complete with & 1/c making requisite number of holes in walls, plinth & floor for Pipe connections & making good cement concrete 1:2:4. (S.I No.. 20 Page No.3).	2,042.43	P.Rit	6,127
5		Providing G.I Pipes, specials, and clamps etc, including fixing cutting & fitting complete with and 1/c the cost of breaking through walls and roof, making good etc. painting two coats after cleaning the Pipe etc. with white zinc paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (SI No. 1 Page No.12)			
1	20)	1/2" dia	73.21	P.Rit	14,642
1	20)	3/4" dia	95.79	P.Rit	19,158
6		Add : Extra labor for concealed G.I pipe and Fitting 1/c making recess in the wall for pipe and making good in Cement motor etc Complete			
	50)	1/2" dia	7.82	P.Rit	391
7	1	S/Fixing long bib- cock of crystal head with 1/2" dia.	1,384.24	Each	4,153
8	2	Supplying/Fixing wash basen mixture of superir quality with c.p head 1/2" dia.	2,882.00	Each	5,764
9	1	Supplying & fixing sink mixture cock of superior quality with c.p head etc complete.	2,745.60	Each	2,746
10	2	Supplying & fixing C.I Muslim Showerer with double Bib cock & ring Pipe etc complete.	3,432.00	Each	6,864
11	1	Supplying & fixing Bath room accessories set (7 Piece) 1/c towel rod, brush holder soaptray shelf bf approved design 1/c cost of screws, nuts etc Complete. (Master Brand).	10,322.40	Each	10,322
12	3	Constructiong manhole or inspection chamber for the required dia of circular sewer and 3'-6" (1067 mm) dpth with walls of BB in cement motor 1:3 cement plaster 1:3, 1/2" thick inside of walls and 1" (25 mm) thick over benching and channel 1/c fixing CI manhole cover with frame of clear opening 1-1/2' x 1., 1/2' (457x457 mm) of 1.75 Cwt. (80.9 Kg) embedded in plain C.C 1:2:4 and fixing 1" (25 mm) dia M.S steps 6" (150 mm) waide projecting 4" (102 mm) from the face of wall at 12" (305 mm) C.C dully painted etc. complete as per specification and drawing (SI No. 1 Page No. 46). (P.R.L)	14,748.00	Each	44,244
13	2	Providing & fixing 4" x 4" dia C.I branch of the required degree with access doors, rubber washer 3/8" thick and bolts and nuts and extra painting to match the colour of the building.	704.00	Each	1,408
14	3	Providing & fixing 4" dia C.I terminal guard including extra painting to match the colour of the building.	389.70	Each	1,169

Items	Description of item to be executed at site	Rate	Units	Amount
TOTAL :-				149,088

Total CSR)

7/10/10 / Below

Total Amount

7/10/10 / Below

Total Amount

Total "A+B"

NON SUPPLIED ITEMS

1	2	Providing & fixing 2" x 16" heavy beam in white glazed earthen ware complete with 8/16 the cost of W.I or C.I cantilever brackets 6 inches built into wall, painted white on the outside and a primary coat of red lead paint on the inside of 1/2" dia rubber plug & chromia plate base chain 1/4" dia malleable iron or C.I brass traps malleable iron or brass unions and making requisite number of holes in walls, plinth & floor for pipe connection and making good in cement concrete		P.No
2	5	1/2" dia standard water tap		
3	1	Supplying and fixing stop cock of superior quality with c.n head 1/2" dia.		P.No
4	1	Providing & fixing steel sinks stainless local make complete with cast iron or wrought iron brackets 6 inches built in wall 1/2" c.p rubber plug chrome		P.No
5	2	Supplying and fixing wall showery red stop cock complete (M.A.D.E)		P.No
6	10	Providing PVC Pipes of class D equivalent make to supply in trench for outdoor fitting and jointing with "Z" joint with one rubber ring for testing with water to		
	14)	4" dia		R.F.I
	6)	6" dia		R.F.I
	10	Supplying and fixing PVC MADE		
	9	Tees 4" dia		Each
	4	Elbow 4" dia		Each
	3	Clip 4" dia		Each
	3	End Cape 4" dia		Each
TOTAL :-				

Cost of Bid


Amount Position

1. (A) Cost Based on Composite Schedule of Rates

2. (B) Cost Based on Non/Offered Schedule of Rates

TOTAL COST OF BID (C) = TOTAL (A) + TOTAL (B)


CONTRACTOR



 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 SUKKUR

BIDDING DATA

This Section should be filled in by the Executive Engineer Education Works Division Sukkur, before issuance of the Bidding Documents.

- (a) Name of Procuring Agency Executive Engineer, Education Works Division Sukkur
- (b) Brief Description of Works RENOVATION / REHABILITATION OF EXISTING
ELEMENTARY / SECONDARY / COLLEGES
BUILDINGS (RAIN DAMAGES) 2012-13 @ QUARTER
NO. 1+2 AT COMPLEX FOR HANDI CAPPED
CHILDREN SUKKUR (INTERNAL)
- (c) Procuring Agency Address Near Shikarpur Phatak Golimar Road Sukkur
- (d) Estimated Cost 400000
- (e) Amount of Bid Security 10000
- (f) Period of Bid Validity (Days) 28 Days
- (g) Security Deposit (w/ Bid Security) 40000
- (h) Percentage, if any, to be deducted from bills 8%
- (i) Deadlines for submission of bids along with times 14.05.2015 (1:00 PM)
- (j) Venue, Time and Date of Bid Opening 14.05.2015 (3:00 PM)
- (k) Time for completion from written order of commences 02 Months
- (l) Liquidity Damages -
- (m) Deposit Receipt _____ Date _____ Amount _____
- (n) D₂R No. _____ Date _____ Amount _____
- (o) Tender Issued to (Mr. / M/S) _____


DIVISIONAL ACCOUNTS OFFICER
EDUCATION WORKS DIVISION
SUKKUR


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SUKKUR

BILL OF QUANTITIES

Description and Rate of Items based on Composite Schedule of Rates

NAME OF WORK :- RENOVATION / REHABILITATION OF EXISTING ELEMENTARY / SECONDARY / COLLEGES BUILDINGS (RAIN DAMAGES)- 2012-13 @ QUARTER NO. 1+2 AT COMPLEX FOR HANDICAPPED CHILDREN SUKKUR. (INTERNAL ELECTRIFICATION).

Sl. No.	Quantities	Description of item to be executed at site	Rate	Units	Amount
PART "A" SCHEDULE ITEMS					
1	65	Wiring for light or fan point with 7/0.29 PVC insulated wire in 25mm (3/4") PVC conduit recessed in the wall or column as required. (S.I.No:111 P- No:15)	1130	per point	73,450
2	14	Wiring for plug point with 7/0.29 PVC insulated wire in 25mm (3/4") PVC conduit recessed in the wall or column as required. (S.I.No:112 P- No:15)	985	per point	13,790
3	2	Wiring for call bell point with 7/0.29 PVC insulated wire in 20mm (3/4") PVC conduit recessed in the wall or column as required. (S.I.No:126 P- No:15)	1761	per point	3,528
4	150	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.29 copper conductor in 1/2" dia PVC conduit recessed in the wall or column as required. (S.I.No:10 P- No:2)	222	per Meter	33,300
5	55	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.36 copper conductor in 3/4" dia PVC conduit recessed in the wall or column as required. (S.I.No:11 P- No:2)	252	per Meter	13,860
6	150	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.44 copper conductor in 1/2" dia PVC conduit recessed in the wall or column as required. (S.I.No:11 P- No:2)	341	per Meter	51,150
8	15	Providing & fixing circuit breaker 6,10,15,20, 30,40,50 & 63amp SP (1B-5S) on prepared board as required (S.I.No:202 P- No:30)	916	Each	13,740
9	2	Providing & fixing circuit breaker 15,20,30, 40,50,60,75 & 100amp 1P (XS-100NS) on prepared board as required (S.I.No:207 P- No:31)	9261	P.No	18,522
10	12	Providing & fixing two pin 10/15amp plug & flush type (S.I.No:225 P- No:33)	83	P.No	996
11	3	Providing & fixing three pin 10/15amp plug & socket flush type (S.I.No:222 P- No:33)	162	P.No	486
12	65	Providing & fixing one way SP 5amp switch flush type(S.I.No:219 P- No:33)	54	P.No	3,510
13	25	Providing & fixing Bakelite ceiling rose with two terminals (S.I.No:228 P- No:33)	72	P.No	1,800
14	6	Providing & fixing Brass Ceiling fan 56" (good quality) (S.I.No:235 P- No:34)	3185	P.No	19,110
15	20	Providing & fixing Brass Pattern holder (S.I.No:232 P- No:33)	70	P.No	1,400
16	100	Providing & laying (MAIN or SUB MAIN) PVC insulated with size 2-7/0.52 (10 mm ²) copper conductor in 1" dia PVC conduit on surface (S.I.No:8 P- No:1).	428	P.Mtr	42,800
17	2	Providing & fixing Brass Bracket fan 18" (good quality) (S.I.No:236 P- No:34)	2791	P.Mtr	5,582
18	2	Providing & Fixing of flood light 400 watts (HPI) having IP65 classification with 400w lamp, choke, capacitor, igniter & Internal wiring complete in all respect at the height up to 40ft with the help hydraulic crane and manual labour as per site requirement and instruction of EI (S.I.No:164 P- No:26)	16980	P.No	33,960
TOTAL :-					330,984

PART "B" SCHEDULE ITEMS

1	3	P/P distribution metal board double shutter to accommodate circuit breakers including painting with enamel paint and for other similar job on surface (S.I.No:18 P- No:13)	1426.33	P.Sh	4,279
2	34	P/P wall bracket light fancy type superior quality including necessary electric connection and fixing on wall or ceiling etc complete.(S.I.No:5 P- No:33)	497.00	Each	16,898
3	50	P/P energy saver superior quality including fixing on existing holder etc complete.(S.I.No:6 P- No:33)	497.00	Each	24,850

(Signature)