


OFFICE OF THE TOWN COMMITTEE JAM NAWAZ ALI




TALUKA JAM NAWAZ ALI

District Sanghar

TENDER / BIDDING DOCUMENTS


Assistant Engineer
Town Committee
Jam Nawaz Ali


Town Officer
Town Committee
Jam Nawaz Ali

NOTICE INVITING TENDERS

Dated: _____

Local Government (OZT) Funds/Own Sources: _____

Bid Reference No.: _____

1. The **Town Committee Jam Nawaz Ali** has received funds from Government of Sindh, OZT Share for the Annual Development Plan 2014-2015 towards the cost for construction of surface drains, c.c. topping, brick pavements, earth filling, excavation & repair/rehabilitation water supply/drainage schemes and bidding is open for all bidders who fulfill the criteria.
2. The **Town Committee Jam Nawaz Ali** invites sealed bids from interested bidders who have experience in above works and registered with the relevant tax authorities.
3. Bidders may obtain information by acquiring the bidding document (BD) from the office of the procuring agency upto date **29-5-2015** time **12:00 Noon** and opening same date 01:00 pm at office of the Assistant Engineer, Town Committee Jam Nawaz Ali, District Sanghar.
4. A complete set of BD may be purchased by an interested bidders on submission of a written application to the above office and upon payment of a non-refundable fee of Rs. 500 upto 0.5 Million & Rs. 1,000 for more than 0.50 Million/-.
5. All bids must be accompanied by a bid security 2% of bid price or an equivalent amount in freely convertible currency, and must be delivered to **Assistant Engineer, Town Committee Jam Nawaz Ali, District Sanghar**, at or before 01:00 hours on 29-5-2015. Bids will be opened at 02:00 hours on the same day, in the presence of bidder's representatives who choose to attend at the same address.
5. **Town Committee Jam Nawaz Ali** reserves right to annual the bidding process and reject all bids or proposals, as per SPPA Rules 2010.

- 19.2 (a) Procuring Agency's address for the purpose of bid submission
**Office of the Administrator/Town Officer,
Town Committee, Jam Nawaz Ali,
District Sanghar.**
- (b) Name and identification number of the contract.
**Construction of CC Topping, Surface Drains, Brick pavement, earth filling,
excavation and Repair/Rehabilitation of water supply/Drainage Schemes &
procurement of goods such as furniture & staff liveries in Town Committee
Jam Nawaz Ali, 1-51.**
- 20.1 (a) Deadline for submission of bids:
**Date of submission of Bid: From date of publication to 29-5-2015
Time of submission: 12:00 Noon**
- (b) Venue, time and date of bid opening.
**Office of the Administrator/Town Officer, Town Committee, Jam Nawaz Ali,
District Sanghar at 1:00 pm on dated 29-5-2015 2nd date 01-06--2015 at 01:00 pm**
- 32.3 Stamp duty
0.3% will be paid by successful bidder as stamp duty.
- 1.1.9 Time for Completion 03 Months and 02 months.

OFFICE OF THE TOWN COMMITTEE JAM NAWAZ ALI DISTRICT SANGHAR

SCHEDULE-B

S/No	Village's / City	Type of work	Schedule amount
1	Various places in Jam Nawaz Ali	Brick pavemet	542,242
2	Jam Kambhu Khan, Jam Nawaz Ali	Repair Pubic park	150,137
3	Various places in Jam Nawaz Ali	Culverts	67,563
4	Village Hamal Mari	Brick pavement	253,046
5	Village Dad Muhammad Baloch	Brick pavement	180,747
6	Village Gul Hassan Katohar	Brick pavement	542,242
7	Village Dariya Khan Mari	Brick pavement	180,747
8	Village Nabi Bux Makorani.	Brick pavement	198,822
9	Various places in Berani	Brick pavement	542,242
10	Ward No. 1 & 2 Berani city	C.C Block	534,702
11	Ward No. 3 & 4	C.C Block	534,702
12	Ward No. 5	C.C Block	534,702
13	Village Mera Khan Mari	Earth filling	342,420
14	Village Gui Hassan Katohar	Earth filling	315,994
15	Village Haji Shoukat Magsi	C.C Block	440,343
16	Various places in Berani	Culverts	67,563
17	Village Sher Mohd Khaskheli w/supply	Brick pavement	180,747
18	Water supply Berani	Repair drain	816,298
19	Village Khadim Jatt	Culverts	67,563
20	Village Mir Mohd Rind	Brick pavement	126,523
21	Ward No. 1 & 2 Berani city	Surface drain	662,441
22	Ward No. 3 & 4 Berani city	Surface drain	680,571
23	Ward No. 5 Berani city	Surface drain	698,700
24	Village Sawan Mari	Brick pavement	180,747
25	Village Abdul Rasheed Abupoto	Earth filling	506,040
26	Various places in Hoat Wassan	Brick pavement	542,242
27	Various places in Hoat Wassan	Culverts	67,563
28	Village Jan Mohd Kaloi	Brick pavement	542,242
29	Village Hasu Babar	Brick pavement	242,201
30	Village Pariyo Majidano	Waiting shed	257,086
31	Village Jan Mohd Kaloi	Earth filling	134,944
32	various places in Nauabad city Part-A	C.C Block	534,702
33	various places in Nauabad city Part-B	C.C Block	534,702
34	Various places in Nauabad	Culverts	67,563
35	Old Nauabad	C.C Block	188,718
36	Village Salleh Mari	Earth filling	122,012
37	Village Attam Bheel	Brick pavement	112,063
38	Old Nauabad	Brick pavement	542,242
39	Various places in Nauabad city Part-A	Surface drain	662,441
40	Various places in Nauabad city Part-B	Surface drain	686,009
41	Village Misri Shar	Brick pavement	361,494
42	Village Allah Dad Shar	Excivation	286,488
43	Village Chanesar Mahar	Brick pavement	108,448
44	Village Kalo Zardari	Brick pavement	216,897


SCHEDULE-B

**NAME OF WORK: REPAIR OF PUBLIC PARK JAM KAMBHU KHAN
JAM NAWAZ ALI**

1.	Barrow pit excavation undressed lead up to 100'ft. (G.S.I.NO: 3 P/1)			
	2630.0 Cft	Rs.2117/50	P%0 Cft	Rs.5569/-
2.	Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete. (G.S.I.NO:13 P/ 4)			
		Qty Same as item No:1	=2630.0 Cft	
	2630.0 Cft	Rs.354/-	P%0 Cft	Rs.931/-
3.	Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (GSI No: 4 P/17)			
	633.60 Cft	Rs.9416/28	P%0 Cft	Rs.59662/-
4.	Cement concrete plain i/c placing compacting finishing curing complete i/c screening & washing of stone aggregate without shuttering Ratio (1:2:4). (GSI No: 5 P/17)			
1.	480.0 Cft	Rs.14429/25	P%0 Cft	Rs.69260/-
5.	Erection & removing centering for RCC in plain cement concrete work of partial wood 2 nd class vertical (GSI No: 19 P/18)			
2.	96.0 Cft	Rs.3127/41	P%0 Cft	Rs.3002/-
6.	Carriage of bricks (lead 2 miles)			
		Qty Same as item No:1	= 2630.0 Cft	
	2630.0 Cft	Rs.502/52	P%0 Nos.	<u>Rs.13216/-</u>
			TOTAL :-	Rs.150137/-

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor format the firm query and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decide separately.
- 5 No perimum, will be allowed on non schedule items.


Assistant Engineer
T.C JAM NAWAZ ALI

SCHEDULE-B

Name of work: Culverts various places in Jam Nawaz Ali

1. Excavation in foundation of building and other structure i/c dag belling dressing refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5' (In ordinary soil) (GSI No: 18(b)P/5).

336.0 Cft. Rs.3176/25 P% 0 Cft. Rs. 1068/-

2. Cement concrete plain i/c placing compacting finishing curing etc complete i/c screening and washing or stone aggregate without shuttering Ratio 1:4:8 (GSI No:5(i) P-16).

84.0 Cft. Rs:11288/75 P% Cft. Rs: 9483/-

16.0 Cft. Rs:14429/25 P% Cft. Rs:2309/-

3. Pucca brick work in foundation and plinth in cement sand mortar 1:6. (G.S.I.NO: P/).

Name of 211.37 Cft. Rs.11948/36 P% Cft Rs.25256/-

4. Cement plaster 1:4 upto 20' height 3/8" thick. (G.S.I.NO: 11 (b) P/52)

180.46 Sft @Rs.3015/76 P% Sft Rs.5443/-

5. RCC work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms mould lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle) a RCC work in roofs slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete the all respect (I) Ratio 1:2:4 90 lbs cement 2cft sand 4 cft shingle 1/8" to 1/4" gauge. (GSI No: 6 (a) P-17).


44.62 Cft. Rs: 337/- P/Cft. Rs. 15038/-

6. Fabrication of mild steel reinforcement cement concrete i/c cutting bending laying in position and fastening i/c cost of binding wire etc. (GSI No:7(b)P-19)

1.79 Cwt. Rs: 5001/70 P/Cwt. Rs: 8966/-

Terms & Conditions:

1. All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
2. No payment of cartage of material involved in the work will be made to the contractor separately.
3. All construction material will be brought by the contractor format the firm query and specified to the Estimate.
4. Any error mission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decide separately.
5. No perimum, will be allowed on non schedule items.


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work Brick pavement @ Village Hamal Mari Mehboob Street UC Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

15750.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 33351 .00
-------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

15750.0 Cft	@ Rs 354.00	P%0 Cft	Rs 5576 .00
-------------	-------------	---------	-------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)


5600.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 214120 .00
------------	--------------	---------	---------------

Total			Rs 253046 .00
-------	--	--	---------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement @ Village Dad Muhammad Baloch UC Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

11250.0 Cft	@ Rs 2117.50	P%0 Cft	Rs	23822 .00
-------------	--------------	---------	----	-----------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

11250.0 Cft	@ Rs 354.00	P%0 Cft	Rs	3983 .00
-------------	-------------	---------	----	----------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)


4000.0 Sft	@ Rs 3823.57	P%0 Sft	Rs	152943 .00
------------	--------------	---------	----	------------

Total	Rs	180747 .00
-------	----	------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of rates decide separetaly.
- 5 No perimum, will be allowed on non schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: **Brick pavement of Village Gul Hassan Katohar UC Berani**

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

33750.0 Cft @ Rs 2117.50 P%0 Cft Rs 71466 .00

2 Ear h work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 33750.0 Cft

33750.0 Cft @ Rs 354.00 P%0 Cft Rs 11948 .00

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

12000.0 Sft @ Rs 3823.57 P%0 Sft Rs 458828 .00

Total Rs 542242 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.

Contractor


Assistant Engineer
T.C. Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement @ Village Dariya Khan Mari UC Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

11250.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 23822 .00
-------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

11250.0 Cft	@ Rs 354.00	P%0 Cft	Rs 3983 .00
-------------	-------------	---------	-------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)


4000.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 152943 .00
------------	--------------	---------	---------------

Total	Rs 180747 .00
-------	---------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of rates decide separetaly.
- 5 No perimum, will be allowed on non schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: C.C Block in ward No. 1 & 2 Berani City

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

19125.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 40497 .00
-------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 19125.0 Cft

19125.0 Cft	@ Rs 354.00	P%0 Cft	Rs 6770 .00
-------------	-------------	---------	-------------

3 Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Gauge ratio 1:4:8

850 x 8.0 x 0.33 = 2244.0 Cft

2244.0 Sft Cft	@ Rs 9416.28	P%0 Cft	Rs 211301 .00
----------------	--------------	---------	---------------

4 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shattering ratio 1:2:4

850 x 8.0 x 0.25 = 1700.0 Cft


1700.0 Cft	@ Rs 14429.25	P%0 Cft	Rs 245297 .00
------------	---------------	---------	---------------

4 Erection & removing centering for RCC in plain cement concrete work of partial wood 2 class vertical (GSI No. 15 P/18)

2 x 850 x 0.58 = 986.0 Sft

986.0 Sft	@ Rs 3127.41	P%0 Sft	Rs 30836 .00
-----------	--------------	---------	--------------

Total	Rs 534702 .00
-------	---------------


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: C.C Block in ward No. 3 & 4 Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

19125.0 Cft @ Rs 2117.50 P%0 Cft Rs 40497 .00

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 19125.0 Cft

19125.0 Cft @ Rs 354.00 P%0 Cft Rs 6770 .00

3 Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Guage .ratio 1:4:8

Name of work: C.C Block 850 x 8.0 x 0.33 = 2244.0 Cft

2244.0 Sft Cft @ Rs 9416.28 P%0 Cft Rs 211301 .00

1 Barrow pit excavation

4 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shattering ratio 1:2:4

850 x 8.0 x 0.25 = 1700.0 Cft

1700.0 Cft @ Rs 14429.25 P%0 Cft Rs 245297 .00

4 Erection & removing centering for RCC in plain cement concrete work of partial wood 2 class vertical (GSI No. 19 P/18)

Name of work: C.C Block 2 x 850 x 0.58 = 986.0 Sft

986.0 Sft @ Rs 3127.41 P%0 Sft Rs 30836 .00

Total Rs 534702 .00


Assistant Engineer

T.C Jam Nawaz Ali

986.0 Sft

Rs 30836 .00

Rs 534702 .00

SCHEDULE-B

Name of work: C.C Block in Ward No. 5 Berani City

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

19125.0 Cft @ Rs 2117.50 P%0 Cft Rs 40497 .00

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 19125.0 Cft

19125.0 Cft @ Rs 354.00 P%0 Cft Rs 6770 .00

3 Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Guage .ratio 1:4:8

2244.0 Sft Cft @ Rs 9416.28 P%0 Cft Rs 211301 .00

4 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shattering ratio 1:2:4

1700.0 Cft @ Rs 14429.25 P%0 Cft Rs 245297 .00


5 Erection & removing centering for RCC in plain cement concrete work of partial wood 2 class vertical (GSI No. 15 P/18)

986.0 Sft @ Rs 3127.41 P%0 Sft Rs 30836 .00

Total Rs 534702 .00

Termes & Conditions:

- 1 All works shall be carried out a per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cortage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor fromt the firm qury and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of ra tes decide separetaly.
- 5 No pe.imum, will be allowed on non schedule items.


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Earth filling in Village Mera Khan UC Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

138547.5 Cft @ Rs. 2117.50 P%0 Cft Rs. 293374 .00

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

SCHEDULE-B

Qty same item No. 1 = 138548 Cft

138547.5 Cft @ Rs 354.00 P%0 Cft Rs. 49045.8 .00

Name of work: Earth

Total Rs. 342420

1 Terms conditions Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.

2 No payment of cartage of material involved in the work will made to the contractor separately.

3 All construction material will be brought by the contractor fromt the firm qury and specified to the Estimate.


4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of ra tes decide separately.

5 No payment will be allowed on non schedule items. Rs. 49045.8

Total Rs. 342420

Contractor's name

Contractor's name
Address
City



Assistant Engineer Local
T.C Jam Nawaz Ali

Contractor's name
Address
City

Contractor's name
Address
City

Contractor's name
Address
City

Contractor's name

Total Rs. 342420

SCHEDULE-B

Name of work: Earth filling in Village Gul Hassan Katohar UC Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

127855 Cft	@ Rs. 2117.50	P%0 Cft	Rs. 270733 .00
------------	---------------	---------	----------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 127855 Cft

127855.0 Cft	@ Rs 354.00	P%0 Cft	Rs. 45260.7 .00
--------------	-------------	---------	-----------------

Name of work: Earth

Rs 315994

Terms conditions:

Barrow pit excavation

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge. Rs. 27073.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate. (GSI No. 13)
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decide separately.
- 5 No perimum, will be allowed on non schedule items.

Contractor

At work site
Government Department
Engineer Incharge
No payment of cartage

All construction material
Estimate.

Any error or omission


Assistant Engineer
T.C Jam Nawaz Ali

As directed by
separately

to the
works and

Contractor

Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Construction of C.C Block at Village Haji Shoukat Magsi UC Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

15750.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 33351 .00
-------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GS No. 13, P-14)

15750.0 Cft	@ Rs 354.00	P%0 Cft	Rs 5576 .00
-------------	-------------	---------	-------------

3 Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Guage ratio 1:4:8

1848.0 Sft Cft	@ Rs 9416.28	P%0 Cft	Rs 174013 .00
----------------	--------------	---------	---------------

4 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shattering ratio 1:2:4

1400.0 Cft	@ Rs 14429.25	P%0 Cft	Rs 202010 .00
15750.0 Cft			Rs 33351 .00


4 Erection & removing centering for RCC in plain cement concrete work of partial wood 2 class vertical (GSI No. 19 P/18)

812.0 Sft	@ Rs 3127.41	P%0 Sft	Rs 25395 .00
-----------	--------------	---------	--------------

Total	Rs 440343 .00
-------	---------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of rates decide separately.
- 5 No perimum, will be allowed on non schedule items.


Assistant Engineer
T.C Jam Nawaz Ali


SCHEDULE-B

Name of work: Culverts various places in Berani

- | | | | | | |
|----|--|------------|-------------|-----------|-------------|
| 1. | Excavation in foundation of building and other structure i/c dag belling dressing refilling around the structure with excavated earth watering and ramming lead upto one chain andlift upto 5' (In ordinary soil) (GSI No: 18(b)P/5). | 336.0 Cft. | Rs.3176/25 | P% 0 Cft. | Rs. 1068/- |
| 2. | Cement concrete plain i/c placing compacting finishing curing etc complete i/c screening and washing or stone aggregate without shuttering Ratio 1:4:8 (GSI No:5(i) P-16). | 84.0 Cft. | Rs:11288/75 | P% Cft. | Rs: 9483/- |
| | | 16.0 Cft. | Rs:14429/25 | P% Cft. | Rs:2309/- |
| 3. | Pucca brick work in foundation and plinth in cement sand mortor 1:6.
(G.S.I.NO: P/). | 211.37 Cft | Rs.11948/36 | P% Cft | Rs.25256/- |
| 4. | Cement plaster 1:4 upto 20' height 3/8" " thick. (G.S.I.NO: 11 (b) P/52) | 180.46 Sft | @Rs.3015/76 | P% Sft | Rs.5443/- |
| 5. | RCC work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms mould lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle)a RCC work in roofs slabs beams columns rafts lintels and other structural members laid in situ or precast liad in position complete the all respect (I) Ratio 1:2:4 90 lbs cement 2cft sand 4 cft shingle 1/8" to 1/4" guage.(GSI No: 6 (a) P-17). | 44.62 Cft. | Rs: 337/- | P/Cft. | Rs: 15038/- |
| 6. | Fabrication of mild steel reinforcement cement concrete i/c cutting bending laying in position and fastening i/c cost of binding wire etc.(GSI No:7(b)P-19) | 1.79 Cwt. | Rs: 5001/70 | P/Cwt. | Rs: 8966/- |

Terms & Conditions:

- 1 All works shall be carried out a per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cortage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor format the firm query and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will referred to the approval estimate of the works and schedule of ra tes decide separately.
- 5 No perimum, will be allowed on non schedule items.


Assistant Engineer
 T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement at Vill: Sher Mohd Khaskheli UC Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

11250.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 23822 .00
-------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

11250.0 Cft	@ Rs 354.00	P%0 Cft	Rs 3983 .00
-------------	-------------	---------	-------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

Name of work	4000.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 152943 .00
--------------	------------	--------------	---------	---------------

Total	Rs 180747 .00
-------	---------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.


Assistant Engineer
T.C Jam Nawaz Ali


SCHEDULE-B

Name of work: Culverts Village Khadim Jat UC Berani

1. Excavation in foundation of building and other structure i/c dag belling dressing refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5' (In ordinary soil) (GSI No: 18(b)P/5).
336.0 Cft. Rs.3176/25 P% 0 Cft. Rs. 1068/-
2. Cement concrete plain i/c placing compacting finishing curing etc complete i/c screening and washing or stone aggregate without shuttering Ratio 1:4:8 (GSI No:5(i) P-16).
84.0 Cft. Rs:11288/75 P% Cft. Rs: 9483/-
16.0 Cft. Rs:14429/25 P% Cft. Rs:2309/-
3. Pucca brick work in foundation and plinth in cement sand mortar 1:6.
(G.S.I.NO: P/).
211.37 Cft Rs.11948/36 P% Cft Rs.25256/-
4. Cement plaster 1:4 upto 20' height 3/8" thick. (G.S.I.NO: 11 (b) P/52)
180.46 Sft @Rs.3015/76 P% Sft Rs.5443/-
5. RCC work i/c all labour and material except the cost of steel reinforcement and its labour for bedding and binding which will be paid separately. This rate also includes all kinds of forms mould lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle) a RCC work in roofs slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete the all respect (I) Ratio 1:2:4 90 lbs cement 2cft sand 4 cft shingle 1/8" to 1/4" gauge. (GSI No: 6 (a) P-17).
44.62 Cft. Rs: 337/- P/Cft. Rs: 15038/-
6. Fabrication of mild steel reinforcement cement concrete i/c cutting bending laying in position and fastening i/c cost of binding wire etc. (GSI No:7(b)P-19)
1.79 Cwt. Rs: 5001/70 P/Cwt. Rs: 8966/-

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor format the firm query and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decide separately.
- 5 No perimum, will be allowed on non schedule items.


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement @ Village Mir Mohd Rind UC Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

7875.0 Cft	@ Rs 2117.50	P%0 Cft	Rs	16675 .00
------------	--------------	---------	----	-----------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

	Qty same item No. 1	=	7875.0 Cft	
7875.0 Cft	@ Rs 354.00	P%0 Cft	Rs	2788 .00

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

2800.0 Sft	@ Rs 3823.57	P%0 Sft	Rs	107060 .00
------------	--------------	---------	----	------------

		Total	Rs	126523 .00
--	--	-------	----	------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.

Contractor



Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: **Surface drain Ward No. 1 & 2 Berani city**

S. #	Description	Quantity	Rate	Unit	Amount
1	Excavation in foundation of building and other structure i/c dag belling dressing refilling around the structure with excavated earth watering and ramming lead up to one chain and lift up to 5' (In ordinary soil) (GSI No: 18(b)P/4).	4356 Cft	@ Rs. 3176.25	P% Cft	13835.7 .00
2	Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Guage ratio 1:4:8	1089.00 Cft	@ Rs. 11288.75	P% Cft	122934 .00
3	Pucca brick work in foundation and plinth in cement sand mortar (1:6) (GSI No:4(e)P/21)	3375.00 Cft	@ Rs. 11288.75	P% Cft	380995 .00
4	Construction of standard open drains conute block of CC (1:2:4) in situ to design profile i/c cost of mould as per drawing i/c s/f cost of cement 1/32" thick to the exposed surface finishing smooth curing etc complete as detailed drawing (PHSI NO 17 P/58)				
1	Excavation in foundation excavated earth watering	1800.00 Cft	@ Rs. 94.00	P/Rft	1692 .00
5	Cement plaster (1:4) upto 20' height 1/2" thick.(GSI No:11(b)P/52).	5832.00 Sft	@ Rs. 2283.93	P% Sft	133199 .00
6	RCC work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms mould lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle) a RCC work in roofs slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete the all respect (I) Ratio 1:2:4 90 lbs cement 2cft sand 4 cft shingle 1/8" to 1/4" guage.(GSI No: 6 (a) P-17).				
		19.17 Cft	@ Rs. 337.00	P% Cft	6459 .00
7	Fabrication of mild steel reinforcement cement concrete i/c cutting bending laying in position and fastening i/c cost of binding wire etc.(GSI No:8(b)P-17)	0.66 Cft	@ Rs. 5001.70	P / Cft	3326 .00
					662441 .00

Contractor


Assistant Engineer
 T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: **Surface drain Ward No. 3 & 4 Berani city**

S. #	Description	Quantity	Rate	Unit	Amount
1	Excavation in foundation of building and other structure i/c dag belling dressing refilling around the structure with excavated earth watering and ramming lead up to one chain and lift up to 5' (In ordinary soil) (GSI No: 18(b)P/4).	4477 Cft	@ Rs. 3176.25	P%0 Cft	14220.1 .00
2	Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Guage .ratio 1:4:8	1119.25 Cft	@ Rs. 11288.75	P% Cft	126349 .00
3	Pucca brick work in foundation and plinth in cement sand mortar (1:6) (GSINo:4(e)P/21)	3468.75 Cft	@ Rs. 11288.75	P% Cft	391579 .00
4	Construction of standard open drains conute block of CC (1:2:4) in situ to design profile i/c cost of mould as per drawing i/c s/f cost of cement 1/32" thick to the exposed surface finishing smooth curing etc complete as detailed drawing (PHSI NO 17 P/58)	1850.00 Cft	@ Rs. 94.00	P/ Rft	1739 .00
5	Cement plaster (1:4) upto 20' height 1/2" thick.(GSI No:11(b)P/52).	5994.00 Sft	@ Rs. 2283.93	P% Sft	136899 .00
6	RCC work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms mould lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle)a RCC work in roofs slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete the all respect (I) Ratio 1:2:4 90 lbs cement 2cft sand 4 cft shingle 1/8" to 1/4" guage.(GSI No: 6 (a) P-17).	19.17 Cft	@ Rs. 337.00	P% Cft	6459 .00

7 Fabrication of mild steel reinforcement cement concrete i/c cutting bending laying in position and fastening i/c cost of binding wire etc.(GSI No:8(b)P-17)

0.66 Cft	@ Rs. 5001.70	P / Cft	3326 .00
			680571 .00


Termes & Conditions:

- 1 All works shall be carried out a per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cortage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor fromt the firm qury and specified to the Estimate
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of ra tes decide separetaly.
- 5 No perimum, will be allowed on non schedule

17	P / Cft	3326
		680571

Termes & Conditions:

Contractor


Assistant Engineer
 T.C Jam Nawaz Ali

3326
680571

SCHEDULE-B

Name of work: Brick pavement @ Village Sawan Mari UC Berani

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

11250.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 23822.00
-------------	--------------	---------	-------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

	Qty same item No. 1	=	11250.0 Cft
11250.0 Cft	@ Rs 354.00	P%0 Cft	Rs 3983.00

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick multi plaster (GSI No. 5 P/40)

4000.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 152943.00
------------	--------------	---------	--------------

Barrow pit excavation

Total


			Rs 180747.00
--	--	--	--------------

			Rs 23822.00
--	--	--	-------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm query and specified to the Estimate.
- 4 Any error/mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of rates decide separately.
- 5 No perimum, will be allowed on non schedule items.

Contractor


Assistant Engineer
 T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement of various places UC Hoat Wassan

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

33750.0 Cft @ Rs 2117.50 P%0 Cft Rs 71466 .00

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)


33750.0 Cft @ Rs 354.00 P%0 Cft Rs 11948 .00

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

Name of work: 12000.0 Sft Brick @ Rs 3823.57 P%0 Sft Rs 458828 .00
Total Rs 542242 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval of the estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Culverts various places in UC Hoat Wassan

1. Excavation in foundation of building and other structure i/c dag belling dressing refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5' (In ordinary soil) (GSI No: 18(b)P/5).

326.0 Cft.	Rs.3176/25	P% 0 Cft.	Rs. 1068/-
------------	------------	-----------	------------

2. Cement concrete plain i/c placing compacting finishing curing etc complete i/c screening and washing of stone aggregate without shuttering Ratio 1:4:8 (GSI No:5(i) P-16).

84.0 Cft.	Rs:11288/75	P% Cft.	Rs: 9483/-
15.0 Cft.	Rs:14429/25	P% Cft.	Rs:2309/-

3. Pucca brick work in foundation and plinth in cement sand mortar 1:6. (G.S.I.NO: P/).

211.37 Cft	Rs.11948/36	P% Cft	Rs.25256/-
------------	-------------	--------	------------

4. Cement plaster 1:4 upto 20' height 3/8" thick. (G.S.I.NO: 11 (b) P/52)

180.46 Sft	@Rs.3015/76	P% Sft	Rs.5443/-
------------	-------------	--------	-----------

5. RCC work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms mould lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle) a RCC work in roofs slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete the all respect (i) Ratio 1:2:4 90 lbs cement 2cft sand 4 cft shingle 1/8" to 1/4" gauge. (GSI No: 6 (a) P-17).


44.62 Cft.	Rs: 337/-	P/Cft.	Rs: 15038/-
------------	-----------	--------	-------------

6. Fabrication of mild steel reinforcement cement concrete i/c cutting bending laying in position and fastening i/c cost of binding wire etc. (GSI No:7(b)P-19)

1.79 Cwt.	Rs: 5001/70	P/Cwt.	Rs: 8966/-
-----------	-------------	--------	------------

Terms & Conditions:

1. All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
2. No payment of cartage of material involved in the work will be made to the contractor separately.
3. All construction material will be brought by the contractor format the firm query and specified to the Estimate.
4. Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
5. No perimum, will be allowed on non schedule items.


Assistant Engineer
 T.C. Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement of village Jan Muhammad Kaloi UC Hoat Wassan

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

33750.0 Cft	@ Rs 2117.50	P%0 Cft		Rs 71466 .00
-------------	--------------	---------	--	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1			=	33750.0 Cft
33750.0 Cft	@ Rs 354.00	P%0 Cft		Rs 11948 .00

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

12000.0 Sft	@ Rs 3823.57	P%0 Sft		Rs 458828 .00
-------------	--------------	---------	--	---------------

	Total	Rs 542242 .00
--	--------------	---------------

	Rs 71466 .00
--	--------------

Termes & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of rates decide separetaly.
- 5 No perim num, will be allowed on non schedule items.

Termes & Conditions:

1 All works shall be carried out by the **Contractor**

	Rs 458828 .00
	Rs 542242 .00

Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: **Brick pavement @ Village Hasu Babar UC Hoat Wassan**

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

15075.0 Cft	@ Rs 2117.50	P%0 Cft		Rs 31921 .00
-------------	--------------	---------	--	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1		=	15075.0 Cft	
15075.0 Cft	@ Rs 354.00	P%0 Cft		Rs 5337 .00


3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" brick mud plaster (GSI No. 5 P/40)

5360.0 Sft	@ Rs 3823.57	P%0 Sft		Rs 204943 .00
			Total	Rs 242201 .00
				Rs 31921 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately. Rs 5337 .00
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate. Rs 204943 .00
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately. Rs 31921 .00
- 5 No premium will be allowed on non schedule items.

Contractor


Assistant Engineer
T.C. Jam Nawaz Ali

SCHEDULE-B


e of work: Waiting shed Village Periyu Majedano

1. Excavation in foundation of building and other structure i/c dag belling dressing refilling around the structure with excavated earth watering and ramming lead up to one chain and lift up to 5' (In ordinary soil) (GSI No: 18(b)P/5).
305.0 Cft. @Rs.3176/25 P% 0 Cft. Rs. 968/-
2. Cement concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:4:8 (GSI NO 4 (B) P/17)
141.78 Cft @Rs. 9416/28 P% cft Rs. 13350/-
3. Errection and removal of centering for RCC or plain cement concrete work (GSI NO 18 P/21)
330.0 Sft @Rs. 3127/41 P% Sft Rs. 10320/-
4. Cement concrete plain i/c placing compacting finishing curing etc complete i/c screening and washing or stone aggregate without shuttering Ratio 1:3:6 (GSI No:5 P-17)
177.0 SftS @Rs. 12595/- P% Cft Rs. 22293/-
5. Pucca brick work in foundation and plinth in cement sand mortar (1:6) (GSI No:5(e)P/28)
363.75 Cft @Rs. 12674/36 P% cft Rs. 46103/-
6. Providing & fixing arramental cement 2"think (GSI No.11,P/18)
36.0 Sft @Rs. 226/02 P% Sft Rs. 8136/-
7. RCC work i/c all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. This rate also includes all kinds of forms mould lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle)a RCC work in roofs slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete the all respect (I) Ratio 1:2:4 90 lbs cement 2cft sand 4 cft shingle 1/8" to 1/4" guage.(GSI No: 6 (a) P-19).
134.57 Cft @Rs. 337/- P/Cft Rs. 45495/-
8. Fabrication of mild steel reinforcement cement concrete i/c cutting bending laying in position and fastening i/c cost of binding wire etc.(GSI No:7(b)P-19)
4.82 Cwt. @Rs: 5001/70 P/Cwt. Rs. 24108/-
9. Cement plaster (1:6) up to 20' height 1/2" thick.(GSI No:11(b)P/55).
527.0 Sft @Rs. 2206/80 P% Sft Rs. 11630/-
10. Cement pointing stock joint on wall(GSI No.19(b) P/59)
587.75 Sft @Rs. 1213/58 P% Sft Rs. 7133/-

11.	Filling watering and ramming earth in floor(GSI No.21 P/6)			
	323.12 Sft	@Rs. 1512/50	P% Sft	Rs.4885/-
12.	Providing and laying 2: thick topping cement concrete (1;2:4) i/c surface finishing and dividing into panels (GSI NO 16 /47)			
	168.0Sft	@Rs. 3275/50	P/Sft	Rs. 5503/-
13.	Rough cost stucco cement plaster ¾" thick in proportion of 1:1 ½" in cement hill sand and bajri in pattern (GSI NO 16 P/47)			
	118Sft	@Rs. 2306/10	P% Sft	Rs. 2721/-
14.	S/F steel grated Door with 1/16" thick (GSI No.24.P/97)			
	28.0Sft	@Rs. 726/-	P/Sft	Rs. 20348/-
15.	Fabrication of havey steel with angle tees ftal iron roundiron and steel...(GSI No:2 P-96)			
	3.14 Cwt.	@Rs: 4928/48	P/Cwt.	Rs. 15475/-
16.	<u>Painting new Surface</u> Preparing surface and painting of doors and windows any type three coats(GSI No 5/ P/77)			
	56.0 Sft	@Rs. 2116/41	P% Sft	Rs. 1185/-
17.	White washing 3 coats)(GSI NO 26 P/60)			
	800.0 Sft	@Rs. 829/90	P% Sft	Rs. 6639/-
18.	Color washing (GSI NO 25 (b)P/60)			
19.	Supplying fixing in position iron steel grill of ¾" x ¼" size flat iron of approved design i/c painting 3 coats etc complete weight not less then 3.7 Lbs /sq foot of finished grill.(GSI No 26 P/97)			
	32.0 Sft	@Rs. 180/50	P%Sft	Rs. 5776/-
				Total Rs: 257086/-

CONDITIONS.

1. Any erroromission in the specification quantity and unit will be governed by the relevant schedule items.
2. The rates should be inclusive of all taxes i.e. sales tax octori tax etc.
3. No separate carriage will be paid to the contractor.
4. No premium will be allowed for non schedule items.
5. The decision of the Administrator Town Committee Jam Nawaz Ali will be final and biniding the parties if any dispute.


 Assistant Engineer
 TC Jam Nawaz Ali

SCHEDULE-B

Name of work: Construction of C.C Block of Nauabad City.

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)				
19125.0 Cft	@ Rs 2117.50	P%0 Cft		Rs 40497 .00
2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)				
	Qty same item No. 1	=	19125.0 Cft	
19125.0 Cft	@ Rs 354.00	P%0 Cft		Rs 6770 .00
3 Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Guage .ratio 1:4:8				
2244.0 Sft Cft	@ Rs 9416.28	P%0 Cft		Rs 211301 .00
4 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shattering ratio 1:2:4				
1700 0 Cft	@ Rs 14429.25	P%0 Cft		Rs 245297 .00
5 Erection & removing centering for RCC in plain cement concrete work of partial wood 2 class vertical (GSI No. 19 P/18)				
986.0 Sft	@ Rs 3127.41	P%0 Sft		Rs 30836 .00
			Total	Rs 534702 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of rates decide separately.
- 5 No perimum, will be allowed on non schedule items.


Assistant Engineer
 T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: C.C Block in Nauabad City.

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

19' 25.0 Cft @ Rs 2117.50 P%0 Cft Rs 40497 .00

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 19125.0 Cft

19125.0 Cft @ Rs 354.00 P%0 Cft Rs 6770 .00

3 Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Guage .ratio 1:4:8

2244.0 Sft Cft @ Rs 9416.28 P%0 Cft Rs 211301 .00

4 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shattering ratio 1:2:4


17766.0 Cft @ Rs 14429.25 P%0 Cft Rs 254977 .00

5 Erection & removing centering for RCC in plain cement concrete work of partial wood 2 class vertical (GSI No. 19 F/18)

986.0 Sft @ Rs 3127.41 P%0 Sft Rs 30836 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cortage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor fromt the firm qury and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of ra tes decide separetaly.
- 5 No perimum, will be allowed on non schedule items.


 Assistant Engineer
 T.C Jam Nawaz Ali

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cortage of material involved in the work will made to the contractor separately.


SCHEDULE-B

Name of work: Culverts various places in Nauabad

- | | | | | | |
|----|--|------------|-------------|-----------|-------------|
| 1. | Excavation in foundation of building and other structure i/c dag belling dressing refilling around the structure with excavated earth watering and ramming lead upto one chain and lift upto 5' (In ordinary soil) (GSI No: 18(b)P/5). | 336.0 Cft. | Rs.3176/25 | P% 0 Cft. | Rs. 1068/- |
| 2. | Cement concrete plain i/c placing compacting finishing curing etc complete i/c screening and washing or stone aggregate without shuttering Ratio 1:4:8 (GSI No:5(i) P-16). | 84.0 Cft. | Rs:11288/75 | P% Cft. | Rs: 9483/- |
| | | 16.0 Cft. | Rs:14429/25 | P% Cft. | Rs:2309/- |
| 3. | Pucca brick work in foundation and plinth in cement sand mortar 1:6. (G.S.I.NO: P/). | 211.37 Cft | Rs.11948/36 | P% Cft | Rs.25256/- |
| 4. | Cement plaster 1:4 upto 20' height 3/8" thick. (G.S.I.NO: 11 (b) P/52) | 180.46 Sft | @Rs.3015/76 | P% Sft | Rs.5443/- |
| 5. | RCC work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms mould lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle) a RCC work in roofs slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete the all respect (I) Ratio 1:2:4 90 lbs cement 2cft sand 4 cft shingle 1/8" to 1/4" guage. (GSI No: 6 (a) P-17). | 44.62 Cft. | Rs: 337/- | P/Cft. | Rs: 15038/- |
| 6. | Fabrication of mild steel reinforcement cement concrete i/c cutting bending laying in position and fastening i/c cost of binding wire etc. (GSI No:7(b)P-19) | .79 Cwt. | Rs: 5001/70 | P/Cwt. | Rs: 8966/- |

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor format the firm query and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decide separately.
- 5 No perimum, will be allowed on non schedule items.


Assistant Engineer
 T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Construction of C.C Block Old Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

6750.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 14293 .00
------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

6750.0 Cft	@ Rs 354.00	P%0 Cft	Rs 2390 .00
------------	-------------	---------	-------------

3 Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Guage .ratio 1:4:8

792.0 Sft Cft	@ Rs 9416.28	P%0 Cft	Rs 74577 .00
---------------	--------------	---------	--------------

Name of work: Construction

4 Cement concrete plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate without shattering ratio 1:2:4

600.0 Cft	@ Rs 14429.25	P%0 Cft	Rs 86576 .00
-----------	---------------	---------	--------------


5 Erection & removing centering for RCC in plain cement concrete work of partial wood 2 class vertical (GSI No. 19 P/18)

343.0 Sft	@ Rs 3127.41	P%0 Sft	Rs 10883 .00
-----------	--------------	---------	--------------

	Total	Rs 188718 .00
--	-------	---------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cortage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor fromt the firm qury and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of ra tes decide separetaly.
- 5 No perimum, will be allowed on non schedule items.


Assistant Engineer
 T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Earth filling in Village Salleh Mari UC Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

49367.5 Cft @ Rs. 2117.50 P%0 Cft Rs. 104536 .00

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 49368 Cft

49367.5 Cft Earth @ Rs 354.00 P%0 Cft Rs. 17476 .00

1 Barrow pit excavation Total Rs. 122012 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm query and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of ra tes decide separetaly.
- 5 No perimum, will be allowed on non schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work **Brick pavement @ Village Attam Bheel UC Nauabad**

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

6975.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 14770 .00
------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 6975.0 Cft

6975.0 Cft	@ Rs 354.00	P%0 Cft	Rs 2469 .00
------------	-------------	---------	-------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

2480.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 94825 .00
------------	--------------	---------	--------------

Total		Rs 112063 .00
		Rs 14770 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval of the estimate of the works and schedule of rates decided separately.
- 5 No perimum, will be allowed on non schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement at old Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

33750.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 71466 .00
-------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

33750.0 Cft	@ Rs 354.00	P%0 Cft	Rs 11948 .00
-------------	-------------	---------	--------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)


12000.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 458828 .00
-------------	--------------	---------	---------------

Total	Rs 542242 .00
--------------	---------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: **Surface drain in various places in Nauabad city**

S. #	Description	Quantity	Rate	Unit	Amount
------	-------------	----------	------	------	--------

1 Excavation in foundation of building and other structure i/c dag belling dressing refilling around the structure with excavated earth watering and ramming lead up to one chain and lift up to 5' (In ordinary soil) (GSI No: 18(b)P/4).

4356 Cft @ Rs. 3176.25 P% Cft 13835.7 .00

2 Cement Concrete Brick or Stone Ballast 1 1/2 to 2" Guage ratio 1:4:8

1089.00 Cft @ Rs. 11288.75 P% Cft 122934 .00

Name of work: **Surface drain in various places in Nauabad city**

3 Pucca brick work in foundation and plinth in cement sand mortar (1:6) (GSINo:4(e)P/21)

3375.00 Cft @ Rs. 11288.75 P% Cft 380995 .00

S. #	Description	Quantity	Rate	Unit	Amount
------	-------------	----------	------	------	--------

4 Construction of standard open drains conute block of CC (1:2:4) in situ to design profile i/c cost of mould as per drawing i/c s/f cost of cement 1/32" thick to the exposed surface finishing smooth curing etc complete as detailed drawing (PHSI NO 17 P/58)

1800.00 Cft @ Rs. 94.00 P/ Rft 1692 .00

5 Cement plaster (1:4) upto 20' height 1/2" thick.(GSI No:11(b)P/52).

5832.00 Sft @ Rs. 2283.93 P% Sft 133199 .00

6 RCC work i/c all labour and material except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms mould lifting shuttering curing rendering and finishing the exposed surface (i/c screening and washing of shingle) a FCC work in roofs slabs beams columns rafts lintels and other structural members laid in situ or precast laid in position complete the all respect (I) Ratio 1:2:4 90 lbs cement 2cft sand 4 cft shingle 1/8" to 1/4" guage.(GSI No: 6 (a) P-17).

19.17 Cft @ Rs. 337.00 P% Cft 6459 .00

7 Fabrication of mild steel reinforcement cement concrete i/c cutting bending laying in position and fastening i/c cost of binding wire etc.(GSI No:8(b)P-17)


0.66 Cft @ Rs. 5001.70 P / Cft 3326 .00
662441 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of rates decide separately.
- 5 No perimum, will be allowed on non schedule

Terms & Conditions:

Contractor shall be bound by the Local Government Department directed by Engineer incharge.


Assistant Engineer
T.C. Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement Village Misry Shah UC Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

22500.0 Cft	@ Rs 2117.50.	P%0 Cft	Rs	47644 .00
-------------	---------------	---------	----	-----------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 22500.0 Cft

22500.0 Cft	@ Rs 354.00	P%0 Cft	Rs	7965 .00
-------------	-------------	---------	----	----------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

Name of work: Village Misry Shah UC Nauabad

8000.0 Sft	@ Rs 3823.57	P%0 Sft	Rs	305886 .00
------------	--------------	---------	----	------------

Barrow pit excavation

	Total		Rs	361494 .00
--	-------	--	----	------------


22500.0 Cft

Rs 47644 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferred to the approval estimate of the works and schedule of rates decide separately.
- 5 No perimum, will be allowed on non schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: **Exvation Village Allah Dad Shar UC Nauabad**

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

111375 Cft	@ Rs. 2117.50	P%0 Cft	Rs. 235837 .00
------------	---------------	---------	----------------

2 Earth work compaction laying carth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 111375 Cft

111375.0 Cft	@ Rs 354.00	P%0 Cft	Rs. 39427 .00
--------------	-------------	---------	---------------

3 Extra for every 50 ft additional lead or part therof.

111375.0 Cft	@ Rs 100.78	P%0 Cft	Rs. 11224 .00
--------------	-------------	---------	---------------

Total Rs. 286488 .00
Rs. 235837 .00

Termes & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other
- 2 No payment of cortage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor fromt the firm query and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferred to the approval estimate of the works and schedule of ra tes decide separetaly.
- 5 No perimum, will be allowed on non schedule items.


Assistant Engineer
T.C Jam Nawaz Ali

Contractor

SCHEDULE-B

Name of work: Brick pavement Village Chanesar Mahar UC Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

3750.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 14293 .00
------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 6750.0 Cft

6750.0 Cft	@ Rs 354.00	P%0 Cft	Rs 2390 .00
------------	-------------	---------	-------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

Name of work: Brick pavement Village Chanesar Mahar UC Nauabad

2400.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 91766 .00
------------	--------------	---------	--------------


1 Barrow pit excavation

Total	Rs 108448 .00
-------	---------------

Rs 14293 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.


Assistant Engineer
T.C. Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement Village Abdul Malik Mari UC NAUABAD

1 Barrow pit excavation undressed lead up to 100'-ft (GSI No. 3 P/1)
 27000.0 Cft @ Rs 2117.50 P%0 Cft Rs 57173 .00

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 27000.0 Cft
 27000.0 Cft @ Rs 354.00 P%0 Cft Rs 9558 .00

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)


9600.0 Sft @ Rs 3823.57 P%0 Sft Rs 367063 .00

Total
 Rs 433793 .00

Termes & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cortage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor fromt the firm qury and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will fererred to the approval estimate of the works and schedule of ra tes decide separetaly.
- 5 No perimum, will be allowed on non schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Earth filling in Village Allah Jurio Mari UC Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

44362.5 Cft @ Rs. 2117.50 P%0 Cft Rs. 93938 .00

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 44363 Cft

44362.5 Cft @ Rs 354.00 P%0 Cft Rs. 15704 .00
 Name of work: Earth
 Rs. 109642

Terms & Conditions:

- 1 Barrow pit excavation
- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm query and specified to the Estimate.
- 4 Any error mission in the rates and schedule-B will ferferred to the approval estimate of the works and schedule of rates decide separetaly.
- 5 No perimum will be allowed on non schedule items.

Name of work: Earth

Rs. 15704 .00
109642

Terms & Conditions:

Contractor

Assistant Engineer

T.C Jam Nawaz Ali

(Local)

Rs. 93938

Rs. 109642

Assistant Engineer

SCHEDULE-B

Name of work: Brick pavement of Dargah Tilla Shah UC Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

32175.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 68131 .00
-------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 32175.0 Cft

32175.0 Cft	@ Rs 354.00	P%0 Cft	Rs 11390 .00
-------------	-------------	---------	--------------

3 Dry Erick on edge paving sand grouted i/c preparation of b ed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

Name of work: Sft


11440.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 437416 .00
-------------	--------------	---------	---------------

	Total	
		Rs 516937 .00

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement Village Arbab Ali Mahar UC Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

6075.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 12864 .00
------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 6075.0 Cft

6075.0 Cft	@ Rs 354.00	P%0 Cft	Rs 2151 .00
------------	-------------	---------	-------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

2160.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 82589 .00
------------	--------------	---------	--------------


6075.0 Cft		Total	Rs 97603 .00
------------	--	-------	--------------

			Rs 12864 .00
--	--	--	--------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.

Contractor


Assistant Engineer
 T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement Village Setal Bheel UC Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

15075.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 31921 .00
-------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 15075.0 Cft

15075.0 Cft	@ Rs 354.00	P%0 Cft	Rs 5337 .00
-------------	-------------	---------	-------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

5360.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 204943 .00
------------	--------------	---------	---------------


	Total	Rs 242201 .00
--	--------------	----------------------

		Rs 31921 .00
--	--	--------------

Termes & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

NAME OF WORK: BRICK PAVEMENT OF VILL: BHUTTO LISKANI UC NAUABAD

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

4950.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 10482 .00
------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 4950.0 Cft

4950.0 Cft	@ Rs 354.00	P%0 Cft	Rs 1752 .00
------------	-------------	---------	-------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

1760.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 67295 .00
------------	--------------	---------	--------------

	Total		Rs 79529 .00
			Rs 10482

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali

SCHEDULE-B

Name of work: Brick pavement of various places of UC Nauabad

1 Barrow pit excavation undressed lead up to 100' ft (GSI No. 3 P/1)

33615.0 Cft	@ Rs 2117.50	P%0 Cft	Rs 71180 .00
-------------	--------------	---------	--------------

2 Earth work compaction laying earth in 6" layers leveling dressing and watering for compaction etc complete (GSI No. 13, P-14)

Qty same item No. 1 = 33615.0 Cft

33615.0 Cft	@ Rs 354.00	P%0 Cft	Rs 11900 .00
-------------	-------------	---------	--------------

3 Dry Brick on edge paving sand grouted i/c preparation of bed by watering ramming to proper camber 1/2" thick mud plaster (GSI No. 5 P/40)

Name of work: Brick pavement of various places of UC Nauabad

11952.0 Sft	@ Rs 3823.57	P%0 Sft	Rs 456993 .00
-------------	--------------	---------	---------------

Barrow pit excavation

Total Rs 540073 .00

33615.0 Cft			Rs 71180 .00
-------------	--	--	--------------

Terms & Conditions:

- 1 All works shall be carried out as per specification covered will be Public Health Engineering Local Government Department Hyderabad and other specification of other department as directed by Engineer Incharge.
- 2 No payment of cartage of material involved in the work will be made to the contractor separately.
- 3 All construction material will be brought by the contractor from the firm quarry and specified to the Estimate.
- 4 Any error or omission in the rates and schedule-B will be referred to the approval estimate of the works and schedule of rates decided separately.
- 5 No premium will be allowed on non-schedule items.

Contractor


Assistant Engineer
T.C Jam Nawaz Ali