



# **STANDARD BIDDING DOCUMENT**

**PROCUREMENT OF WORKS**

(For Contracts Costing up to Rs.2.5 Million)

**SPPRA**  
**(Website Tender)**

-: Name of Work :-

**REPAIR MAINTENANCE OF QUARTER NO.H-2 & H-2/A AT  
C.O.D STAFF COLONY FILTER PLANT.**

-: Name of Office:-


**PURIFICATION PLANT DIVISION, KW&SB**

C.O.D, Filter Plant, Gulshan-e-Iqbal Block-18, Karachi

Executive Engineer Contact # :- 0333-2393180

## BIDDING DATA

- (a) Name of Procuring Agency : Purification Plant Division KW&SB
- (b) Brief Description of Work : REPAIR MAINTENANCE OF QUARTER NO.H-2 & H-2/A AT C.O.D STAFF COLONY FILTER PLANT.
- (c) Procuring Agency Address : COD Filter Plant Gulshan-e-Iqbal Block 18 Karachi
- (d) Estimate Cost : (On Composite Schedule of Rates (CSR) offer rate basis)
- (e) Amount of Bid Security : 02% of bid amount
- (f) Period of Bid Validity : 90 Days
- (g) Security Deposit (Including Bid Security) : 10%
- (h) Venue Time and Date of Opening : The Tender sealed cover super scribed with the name of the work should be dropped in the Tender Box kept in office of the Chief Engineer (IP&D), Room No.5, Block "E" at 9th Mile Karsaz Karachi on 12-06-2015 at 02:30 by Procurement Committee-I, KW&SB.
- (i) Deadline of submission of bid along with time : 12-06-2015 at 2:00 PM
- (j) Time for completion from witten commence : 10 Days
- (k) Liquidity damage : 0.5% of Bid Cost per day of delay
- (l) Bid issued to Firm : M/S: \_\_\_\_\_
- Deposit Receipt No. & Date \_\_\_\_\_
- Amount : Rs. 500/-

  
Executive Engineer

Authority Issuing Bidding Document

**PARDEEP KUMAR**  
Executive Engineer  
P.P.Div. KW&SB

NAME OF WORK:- REPAIR MAINTENANCE OF QUARTER NO.H-2 & H-2/A AT C.O.D STAFF COLONY FILTER PLANT.

Description and rate of Items based on Marked (Offered rates)

Item No.	Qty	Description	Rate	Unit	Amount
1	220.5 Sft	First Class deodar wood wrought joinery in door & windows etc fixed in position i/c Chowkets hold fast hinges iron tower bolts lock, cleats handle & cords with hooks etc 2" thick deodar panitted or panetted nad glazed or fully glazed.		%Sft	-
2	288 Sft	Providing & laying 1" thick topping cement concrete (1:2:4) i/c surface finishing & dividing in to panels.		%Sft	-
3	695 Sft	Cement Plaster 1:6 upto 12'-0" heights 1/2".		%Sft	-
4	1 No	P/F onsa type white or colour glazed earthen ware w.c pan with cost of low level plastic flash tank of 3 gallons capacity of approved quality i/c making req. No. of hole in wall plainth & floor & making good in C.C 1:2:4. W.C. pan orisa type 23" with plastick tank of low down 3 glaaons C-I trape & C-I Thimble.		Each	-
5	225 Sft	White Glazed tiles 1/4" thick dado jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.		%Sft	-
6	253 Sft	Asbestor cement corrugaties sheet roofing i/c necessary over laps * G.I hooks bolts nuts screw washer & bitumen washer etc (excluding vallys & ridges etc).		%Sft	-
7	398 Sft	Making & fixing steel grated door with 1/16" thick sheeting i/c angle iron frame 2"X2" 3/8" & 3/4" bars 4" C/C with locking arrangement.		%Sft	-
8	18 Nos	Wiring for light or fan point whti 3.029PVC insulated wire 20mm (3/4) PVC conduit recessed in wall or columns as required,		Each	-
9	130 Rft	P/L R.C.C. pipe with rubber ring joing & fitting in treaches i/c cutting fitting & jointing with rubber ring i/c testing with walts to a head.		%Rft	-
10	1 No	S/F fiber glass tank of approved 12" dia qauality & design & wall thickness as specified i/c cost of nuts bolts & fixing in plate form of C.C 1:3:6 & making connction for in let & out let & over flow pipes etc complete 350 gallons		Each	-
11	55 Sft	S/F Position Aluminium channels framing for sladding windows & ventilation for ALCOP made with 5" mm thickk tinted glass glazing ( Bdg) & Aluminium gly screen i/c stoper & loking arrangement etc complete.		%Sft	-

12	2157	Sft	Distempering Two coats.		%Sft	-
					TOTAL AMOUNT	-

  
 Executive Engineer  
 P.P.Division  
 KW&SB

**PARDEEP KUMAR**  
 Executive Engineer  
 KW&SB

I/We hereby quoted Rs \_\_\_\_\_ (Rupees)

Execution of above work and I/We hereby undertaking accept all clauses of SPPRA 2010 and comply the Rules of KW&SB.

Signature of Contractor

**ANNEXTURE II**  
**PROCUREMENT PLAN (Non-Development)**

Serial No	Fund Head & Sub head	Name of work and break up	Allocated Funds and break up for different locations /sites	Items to be executed	Method of Procurement	Anticipated/Actual Date of Advertisement	Anticipated /Actual Date of Start	Anticipated /Actual Date of Completion	Remarks
a	b	c	d	e	f	g	h	i	j
	7403-79	Necessary Electric Wiring Fitting & Fixtures work of Qrt No. H-36 COD Filter Plant Staff Colony	23,00,000/- 98,773/- 22,01,227/-	Electric Work	16 (a)				
271	7403-79	R/M of Qrt No. G-11 at COD Staff Colony Filter Plant KW&SB	22,01,227/- 6,96,400/- 15,04,827/-		17 (1)				
	7403-79	R/M of Qrt No. H-2 & H-2/A at COD Staff Colony Filter Plant KW&SB	15,04,827/- 6,59,917/- 8,44,910/-		17 (1)				



**PARDEEP KUMAR**  
 Executive Engineer  
 P.P. Div. KINWASRA