

S.No. 01

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION UMERKOT STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	M&R of road from Umerkot Chhore road to Ahori Farm Syed Ali Mardan Shah road Mile 0/0-2/4 (In portions)
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	


EXECUTIVE ENGINEER
HIGHWAYS DIVISION
UMERKOT

Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 01

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works M&R of road from Umerkot Chhore road to Ahori Farm Syed Ali Mardan Shah road Mile 0/0-2/4 (In portions)
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 500000 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 10000 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit:-(including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 01

SCHEDULE "B"**PART - "A"**

NAME OF WORK: -

M&R of road from Umerkot Chhore road to Ahori Farm Syed Ali Mardan Shah road Mile 0/0-2/4 (In portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>BASE COURSE</u> Preparing base course including supplying and spreading stone metal of approved quality properly graded to maximum size of 1 1/2" in required thickness of (3") to proper camber and grade including supplying and spreading 15 Cft. Screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting the same so as to achieve 100% density as per modified AASHO specifications (Rate includes providing and using templates, camber plates, screens, forms etc. as directed). Rate includes all cost of materials, T&P, labours and carriage upto site of work.			
	Quantity 126 Cft.	@ Rs. 11538.43	P%Cft.	14538
2	<u>FIRST COAT SURFACE DRESSING</u> Providing 1st coat surface dressing on new or existing surface with 4.00 cft of crush bajri of 3/4" - 3/8" in guage in 30 lbs of Bitumen 80/100 penetration i/e cleaning the road surface rolling after coat etc. complete includes all cost of materials T&P carriage upto site of work.			
	Quantity 2023 Sft.	@ Rs. 1723.30	P%Sft.	34862
3	<u>1" THICK PREMIXED CARPET</u> Providing 1" thick capet in proper camber and grade i/c supplying of 10.00 cft crush bajri and 4.0 cft Hill snad of approved quarry quality and gauge and 67 lbs of bitumen of 80/100 penetration includes mixing in mechanical mixutre in required proportion i/e heating the materials and cleaning the road surface. Rate includes all cost of materials T&P and carriage upto site.			
	Quantity 10115 Sft.	@ Rs. 4783.68	P%Sft.	483869
			TOTAL	533269
4	<u>ADD DIFFERENT COST BITUMEN</u> Quantity 3.30 Ton @ Rs. 5427.00 P.Ton (-) 17890			
			GRAND TOTAL	515379

No. Premium will be allowed on Item No.**Note:** Item/Quantities/Rates and amount are estimated provisional and will be corrected to the Detail Working Estimate sanctioned by competent authority

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 02

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION UMERKOT STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	M&R Of Ahori Syed Ali Mardan Shah road to Morand Pattu i/c Culvert Mile 0/0-4/7 (In Portions)
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	

EXECUTIVE ENGINEER
HIGHWAYS DIVISION
UMERKOT

Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 02

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works M&R Of Ahoi Syed Ali Mardan Shah road to Morand Pattu i/c Culvert Mile 0/0-4/7 (In Portions)
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 1000000 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 20000 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit: (including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____
_____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

SCHEDULE "B"

NAME OF WORK: - M&R Of Ahori Syed Ali Mardan Shah road to Morand Pattu i/c Culvert Mile 0/0-4/7
(In Portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>BASE COURSE</u> Preparing base course including supplying and spreading stone metal of approved quality properly graded to maximum size of 1 1/2" in required thickness of (3") to proper camber and grade including supplying and spreading 15 Cft. Screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting the same so as to achieve 100% density as per modified AASHO specifications (Rate includes providing and using templates, camber plates, screens, forms etc. as directed). Rate includes all cost of materials, T&P, labours and carriage upto site of work.			
	Quantity	103	Cft.	@ Rs. 11625.04 P%Cft. 11974
2	<u>FIRST COAT SURFACE DRESSING</u> Providing 1st coat surface dressing on new or existing surface with 4.00 cft of crush bajri of 3/4" - 3/8" in guage in 30 lbs of Bitumen 80/100 penetration i/e cleaning the road surface rolling after coat etc. complete includes all cost of materials T&P carriage upto site of work.			
	Quantity	1655	Sft.	@ Rs. 1726.17 P%Sft. 28568
3	<u>1" THICK PREMIXED CARPET</u> Providing 1" thick capet in proper camber and grade i/c supplying of 10.00 cft crush bajri and 4.0 cft fill snad of approved quarry quality and gauge and 67 lbs of bitumen of 80/100 penetration includes mixing in mechanical mixutre in required proportion i/e heating the materials and cleaning the road surface. Rate includes all cost of materials T&P and carriage upto site.			
	Quantity	8275	Sft.	@ Rs. 4793.38 P%Sft. 396652
4	<u>EARTH WORK ON BERMS</u> Earth Work for embankment (Berms) from barrow pits including laying in 6" layers, clod breaking, ramming, dressing etc. complete. Lead upto 100 ft. and lift upto 5.0 ft. (in ordinary soil)			
	Quantity	0	Cft.	@ Rs. 2208.37 P0%Cft. 0
				TOTAL 437194
5	<u>ADD DIFFERENT COST BITUMEN</u> Quantity 2.70 Ton @ Rs. 5427.00 P.Ton (-) 14635			
				GRAND TOTAL 422559

No. Premium will be allowed on Item No.

Note: Item/Quantities/Rates and amount are estimated provisional and will be corrected to the Detail Working Estimate sanctioned by competent authority

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

SCHEDULE "B"

NAME OF WORK: - M&R Of Ahori Syed Ali Mardan Shah road to Morand Pattu i/c
Culvert Mile 0/0-4/7 (In Portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>EXCAVATION</u> Excavation in foundation of Building, Bridges and other structures including dag belling dressing, refilling around structure with excavated earth, watering and ramming lead upto 5.00 ft. (in ordinary soil) Quantity 1056 Cft. @ Rs. 3176.25 P%Cft. 3354	3176.25	P%Cft.	3354
2	<u>CEMENT CONCRETE RATIO (1:4:8)</u> Cement concrete bricks or stone ballast 1 ½ - 2" gauge Ration 1:4:8 Quantity 238 Cft. @ Rs. 9416.28 P%Cft. 22411	9416.28	P%Cft.	22411
3	<u>PUCCA BRICK WORK RATIO 1:4</u> Pucca brick work in foundation and plinth in cement sand mortar 1:4 Quantity 584 Cft. @ Rs. 12501.41 P%Cft. 73008	12501.41	P%Cft.	73008
4	<u>CEMENT CONCRETE</u> Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering (Ratio 1:2:4). Quantity 89 Cft. @ Rs. 14429.25 P%Cft. 12842	14429.25	P%Cft.	12842
5	<u>FABRICATION</u> Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) Quantity 5.04 CWT @ Rs. 4820.20 P.CWT 24294	4820.20	P.CWT	24294
6	<u>R.C.C. WORK. RATIO 1:2:4</u> Reinforced cement concrete work including all labour and materials except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). R.C. work in roof slab, berms, columns rafts, lintels and other structural members laid in situ or pre-cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft. sand 4 Cft. Shingle 1/8" to 1/4" gauge. Quantity 79 Cft. @ Rs. 337.00 PCft. 26623	337.00	PCft.	26623
7	<u>ERECTION AND REMOVAL</u> Erection and removal of centering for R.C.C. or plain cement concrete works of Partal wood (2nd class) (a) Vertical. Quantity 28 Sft @ Rs. 3127.41 P%Sft 876	3127.41	P%Sft	876
8	<u>CEMENT PLASTER 1:3</u> Cement Plaster 1:3 upto 20.0' height. 1/2" thick. Quantity 259 Sft @ Rs. 2344.59 P%Sft 6072	2344.59	P%Sft	6072
			TOTAL	169480

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

SCHEDULE "B"

NAME OF WORK: - M&R Of Ahori Syed Ali Mardan Shah road to Morand Pattu i/c
Culvert Mile 0/0-4/7 (In Portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>DISMENTALLING</u> RCC Ratio 1:2:4 Quantity 39 Cft. @ Rs. 5445.00		P0%Cft.	2124
2	<u>DISMENTALLING 1:2:4</u> CC Plain Ratio 1:2:4 Quantity 14 Cft. @ Rs. 3327.50		P0%Cft.	466
3	<u>DISMENTALLING (PUCCA BRICK WORK)</u> Pucca Brick work in Cement sand mortar ratio 1:4 Quantity 190 Cft. @ Rs. 1285.63		P0%Cft.	2443
4	<u>EXCAVATION</u> Excavation in foundation of Building, Bridges and other structures including dag belling dressing, refilling around structure with excavated earth, watering and ramming lead upto 5.00 ft. (in ordinary soil) Quantity 73 Cft. @ Rs. 3176.25		P0%Cft.	232
5	<u>CEMENT CONCRETE RATIO (1:4:8)</u> Cement concrete bricks or stone ballast 1 1/2 - 2" gauge Ratio 1:4:8 Quantity 65 Cft. @ Rs. 9416.28		P%Cft.	6121
6	<u>PUCCA BRICK WORK RATIO 1:4</u> Pucca brick work in foundation and plinth in cement sand mortar 1:4 Quantity 584 Cft. @ Rs. 12501.41		P%Cft.	73008
7	<u>CEMENT CONCRETE</u> Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering (Ratio 1:2:4). Quantity 89 Cft. @ Rs. 14429.25		P%Cft.	12842
8	<u>FABRICATION</u> Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) Quantity 5.05 CWT @ Rs. 4820.20		P.CWT	24342
9	<u>R.C.C. WORK. RATIO 1:2:4</u> Reinforced cement concrete work including all labour and materials except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). R.C. work in roof slab, berms, columns rafts, lintels and other structural members laid in situ or pre-cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft. sand 4 Cft. Shingle 1/8" to 1/4" gauge. Quantity 79 Cft. @ Rs. 337.00		PCft.	26623
10	<u>ERECTION AND REMOVAL</u> Erection and removal of centering for R.C.C. or plain cement concrete works of Partial wood (2nd class) (a) Vertical. Quantity 28 Sft @ Rs. 3127.41		P%Sft	881
11	<u>CEMENT PLASTER 1:3</u> Cement Plaster 1:3 upto 20.0' height. 1/2" thick. Quantity 259 Sft @ Rs. 2344.59		P%Sft	6072
			TOTAL	155154

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 03

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION UMERKOT STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	M&R Of Nanaksar Bodar Farm Road i/c Culverts Mile 0/0-9/2 (In Portions)
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	

ENGINEER IN CHARGE
HIGHWAYS DIVISION
UMERKOT

Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 03

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works M&R Of Nanaksar Bodar Farm Road i/c Culverts
Mile 0/0-9/2 (In Portions)
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways
Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 900000 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 18000 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit:-(including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways
Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____
_____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 03

SCHEDULE "B"**PART - "A"**

NAME OF WORK: -

M&R Of Nanaksar Bodar Farm Road i/c Culverts Mile 0/0-9/2 (In Portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT	
1	<u>BASE COURSE</u>				
	Preparing base course including supplying and spreading stone metal of approved quality properly graded to maximum size of 1 1/2" in required thickness of (3") to proper camber and grade including supplying and spreading 15 Cft. Screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting the same so as to achieve 100% density as per modified AASHO specifications (Rate includes providing and using templates, camber plates, screens, forms etc. as directed). Rate includes all cost of materials, T&P, labours and carriage upto site of work.				
	Quantity	19	Cft.	@ Rs. 10758.94	P%Cft. 2044
2	<u>FIRST COAT SURFACE DRESSING</u>				
	Providing 1st coat surface dressing on new or existing surface with 4.00 cft of crush bajri of 3/4" - 3/8" in guage in 30 lbs of Bitumen 80/100 penetration i/e cleaning the road surface rolling after coat etc. complete includes all cost of materials T&P carriage upto site of work.				
	Quantity	153	Sft.	@ Rs. 1696.20	P%Sft. 2595
3	<u>1" THICK PREMIXED CARPET</u>				
	Providing 1" thick capet in proper camber and grade i/c supplying of 10.00 cft crush bajri and 4.0 cft Hill snad of approved quarry quality and gauge and 67 lbs of bitumen of 80/100 penetration includes mixing in mechanical mixutre in required proportion i/e heating the materials and cleaning the road surface. Rate includes all cost of materials T&P and carriage upto site.				
	Quantity	1534	Sft.	@ Rs. 4693.12	P%Sft. 71992
					TOTAL 76631
4	<u>ADD DIFFERENT COST BITUMEN</u>				
	Quantity	0.48	Ton	@ Rs. 5427.00	P.Ton (-) 2601
					GRAND TOTAL 74030

No. Premium will be allowed on Item No.

Note: Item/Quantities/Rates and amount are estimated provisional and will be corrected to the Detail Working Estimate sanctioned by competent authority

CONTRACTOR



EXECUTIVE ENGINEER HIGHWAYS
DIVISION LUMERKOT

SCHEDULE "B"

NAME OF WORK: - M&R Of Nanaksar Bodar Farm Road i/c Culverts Mile 0/0-9/2 (In Portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>DISMENTALLING</u> RCC Ratio 1:2:4 Quantity 39 Cft. @ Rs. 5445.00	P0%	Cft.	2124
2	<u>DISMENTALLING 1:2:4</u> CC Plain Ratio 1:2:4 Quantity 14 Cft. @ Rs. 3327.50	P0%	Cft.	466
3	<u>DISMENTALLING (PUCCA BRICK WORK)</u> Pucca Brick work in Cement sand mortar ratio 1:4 Quantity 190 Cft. @ Rs. 1285.63	P0%	Cft.	2443
4	<u>CEMENT CONCRETE RATIO (1:4:8)</u> Cement concrete bricks or stone ballast 1 ½ - 2" gauge Ratio 1:4:8 Quantity 65 Cft. @ Rs. 9416.28	P%	Cft.	6121
5	<u>PUCCA BRICK WORK RATIO 1:4</u> Pucca brick work in foundation and plinth in cement sand mortar 1:4 Quantity 584 Cft. @ Rs. 12501.41	P%	Cft.	73008
6	<u>CEMENT CONCRETE</u> Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering (Ratio 1:2:4). Quantity 89 Cft. @ Rs. 14429.25	P%	Cft.	12842
7	<u>FABRICATION</u> Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) Quantity 5.05 CWT @ Rs. 4820.20	P.	CWT	24342
8	<u>R.C.C. WORK. RATIO 1:2:4</u> Reinforced cement concrete work including all labour and materials except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). R.C. work in roof slab, berms, columns rafts, lintels and other structural members laid in situ or pre-cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft. sand 4 Cft. Shingle 1/8" to 1/4" gauge. Quantity 79 Cft. @ Rs. 337.00	P	Cft.	26623
9	<u>ERECTION AND REMOVAL</u> Erection and removal of centering for R.C.C. or plain cement concrete works of Partial wood (2nd class) (a) Vertical. Quantity 28 Sft @ Rs. 3127.41	P%	Sft	881
10	<u>CEMENT PLASTER 1:3</u> Cement Plaster 1:3 upto 20.0' height. 1/2" thick. Quantity 259 Sft @ Rs. 2344.59	P%	Sft	6072
TOTAL				143970

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 04

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION UMERKOT STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	Repair Of Culvert Umerkot Diggu Via Bhanano Road Mile 4/0-6/0
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	

ENGINEER
HIGHWAYS DIVISION
UMERKOT

Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 04

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works Repair Of Culvert Umerkot Diggu Via Bhanano Road Mile 4/0-6/0
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 300000 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 6000 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit:-(including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways
Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____
_____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

SCHEDULE "B"

NAME OF WORK: - Repair Of Culvert Umerkot Diggua Via Bhanano Road Mile 4/0-6/0

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>DISMENTALLING</u> RCC Ratio 1:2:4 Quantity 39 Cft. @ Rs. 5445.00	P0%	Cft.	2124
2	<u>DISMENTALLING 1:2:4</u> CC Plain Ratio 1:2:4 Quantity 14 Cft. @ Rs. 3327.50	P0%	Cft.	466
3	<u>DISMENTALLING (PUCCA BRICK WORK)</u> Pucca Brick work in Cement sand mortar ratio 1:4 Quantity 190 Cft. @ Rs. 1285.63	P0%	Cft.	2443
4	<u>PUCCA BRICK WORK RATIO 1:4</u> Pucca brick work in foundation and plinth in cement sand mortar 1:4 Quantity 384 Cft. @ Rs. 12501.41	P%	Cft.	48005
5	<u>CEMENT CONCRETE</u> Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering (Ratio 1:2:4). Quantity 89 Cft. @ Rs. 14429.25	P%	Cft.	12842
6	<u>FABRICATION</u> Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) Quantity 5.05 CWT @ Rs. 4820.20	P.	CWT	24342
7	<u>R.C.C. WORK. RATIO 1:2:4</u> Reinforced cement concrete work including all labour and materials except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). R.C. work in roof slab, berms, columns rafts, lintels and other structural members laid in situ or pre-cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft. sand 4 Cft. Shingle 1/8" to 1/4" gauge. Quantity 79 Cft. @ Rs. 337.00	PCft.		26623
8	<u>ERECTION AND REMOVAL</u> Erection and removal of centering for R.C.C. or plain cement concrete works of Partal wood (2nd class) (a) Vertical. Quantity 28 Sft @ Rs. 3127.41	P%	Sft	881
9	<u>CEMENT PLASTER 1:3</u> Cement Plaster 1:3 upto 20.0' height. 1/2" thick. Quantity 259 Sft @ Rs. 2344.59	P%	Sft	6072
			TOTAL	123798

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 05

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION UMERKOT STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	M&R Of Road From Pithoro Ghulam Nabi Shah Road To Hondo Arisar Mile 0/0-1/0 (In Portions)
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	

EXC
VE
PRO
2015

Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 05

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works M&R Of Road From Pithoro Ghulam Nabi Shah Road To Hondo Arisar Mile 0/0-1/0 (In Portions)
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 900000 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 18000 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit:-(including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 05

SCHEDULE "B"**PART – "A"**NAME OF WORK: - M&R Of Road From Pithoro Ghulam Nabi Shah Road To Hondo Arisar Mile 0/0-1/0
(In Portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>BASE COURSE</u>			
	Preparing base course including supplying and spreading stone metal of approved quality properly graded to maximum size of 1 1/2" in required thickness of (3") to proper camber and grade including supplying and spreading 15 Cft. Screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting the same so as to achieve 100% density as per modified AASHO specifications (Rate includes providing and using templates, camber plates, screens, forms etc. as directed). Rate includes all cost of materials, T&P, labours and carriage upto site of work.			
	Quantity 512 Cft.	@ Rs. 11451.82	P%Cft.	58633
2	<u>FIRST COAT SURFACE DRESSING</u>			
	Providing 1st coat surface dressing on new or existing surface with 4.00 cft of crush bajri of 3/4" - 3/8" in guage in 30 lbs of Bitumen 80/100 penetration i/e cleaning the road surface rolling after coat etc. complete includes all cost of materials T&P carriage upto site of work.			
	Quantity 5123 Sft.	@ Rs. 1720.30	P%Sft.	88131
3	<u>1" THICK PREMIXED CARPET</u>			
	Providing 1" thick capet in proper camber and grade i/c supplying of 10.00 cft crush bajri and 4.0 cft Hill snad of approved quarry quality and gauge and 67 lbs of bitumen of 80/100 penetration includes mixing in mechanical mixutre in required proportion i/e heating the materials and cleaning the road surface. Rate includes all cost of materials T&P and carriage upto site.			
	Quantity 20492 Sft.	@ Rs. 4326.66	P%Sft.	886619
4	<u>EARTH WORK ON BERMS</u>			
	Earth Work for embankment (Berms) from barrow pits including laying in 6" layers, clod breaking, ramming, dressing etc. complete. Lead upto 100 ft. and lift upto 5.0 ft. (in ordinary soil)			
	Quantity 14014 Cft.	@ Rs. 2208.37	P0%Cft.	30948
			TOTAL	1064331
5	<u>ADD DIFFERENT COST BITUMEN</u>			
	Quantity 4.14 Ton	@ Rs. 5427.00	P.Ton (-)	22468
			GRAND TOTAL	1041863

No. Premium will be allowed on Item No.

Note: Item/Quantities/Rates and amount are estimated provisional and will be corrected to the Detail Working Estimate sanctioned by competent authority

CONTRACTOR



EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 06

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION UMERKOT STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	M&R Of Road From Kunri More Jhango Road Mile 2/4-3/4 (In Portions)
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	

EXCISE STAMP
M. S. SPPRA
UMERKOT

Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 06

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works M&R Of Road From Kunri More Jhango Road Mile 2/4-3/4 (In Portions)
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 500000 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 10000 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit:-(including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 06

SCHEDULE "B"**PART - "A"**

NAME OF WORK: -

M&R Of Road From Kunri More Jhango Road Mile 2/4-3/4 (In Portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>BASE COURSE</u>			
	Preparing base course including supplying and spreading stone metal of approved quality properly graded to maximum size of 1 1/2" in required thickness of (3") to proper camber and grade including supplying and spreading 15 Cft. Screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting the same so as to achieve 100% density as per modified AASHO specifications (Rate includes providing and using templates, camber plates, screens, forms etc. as directed). Rate includes all cost of materials, T&P, labours and carriage upto site of work.			
	Quantity 134 Cft.	@ Rs. 11408.51	P%Cft.	15287
2	<u>FIRST COAT SURFACE DRESSING</u>			
	Providing 1st coat surface dressing on new or existing surface with 4.00 cft of crush bajri of 3/4" - 3/8" in guage in 30 lbs of Bitumen 80/100 penetration i/e cleaning the road surface rolling after coat etc. complete includes all cost of materials T&P carriage upto site of work.			
	Quantity 3211 Sft.	@ Rs. 1718.87	P%Sft.	55193
3	<u>1" THICK PREMIXED CARPET</u>			
	Providing 1" thick capet in proper camber and grade i/c supplying of 10.00 cft crush bajri and 4.0 cft Hill snad of approved quarry quality and gauge and 67 lbs of bitumen of 80/100 penetration includes mixing in mechanical mixutre in required proportion i/e heating the materials and cleaning the road surface. Rate includes all cost of materials T&P and carriage upto site.			
	Quantity 10703 Sft.	@ Rs. 4325.11	P%Sft.	462916
			TOTAL	533396
4	<u>ADD DIFFERENT COST BITUMEN</u>			
	Quantity 2.22 Ton	@ Rs. 5427.00	P.Ton (-)	12048
			GRAND TOTAL	521348

No. Premium will be allowed on Item No.

Note: Item/Quantities/Rates and amount are estimated provisional and will be corrected to the Detail Working Estimate sanctioned by competent authority

CONTRACTOR



EXECUTIVE ENGINEER HIGHWAYS
DIVISION MERKOT

S.No. 07

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION UMERKOT STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	M&R Of Road From Kunri More Jhango Road Mile 3/4-4/4 (In Portions)
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	

EXC
HIGH
1838

Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 07

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works M&R Of Road From Kunri More Jhango Road Mile 3/4-4/4 (In Portions)
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 1000000 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 20000 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit:-(including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 07

SCHEDULE "B"**PART - "A"**

NAME OF WORK: -

M&R Of Road From Kunri More Jhango Road Mile 3/4-4/4 (In Portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>BASE COURSE</u>			
	Preparing base course including supplying and spreading stone metal of approved quality properly graded to maximum size of 1 1/2" in required thickness of (3") to proper camber and grade including supplying and spreading 15 Cft. Screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting the same so as to achieve 100% density as per modified AASHO specifications (Rate includes providing and using templates, camber plates, screens, forms etc. as directed). Rate includes all cost of materials, T&P, labours and carriage upto site of work.			
	Quantity 512 Cft.	@ Rs. 11451.82	P%Cft.	58633
2	<u>FIRST COAT SURFACE DRESSING</u>			
	Providing 1st coat surface dressing on new or existing surface with 4.00 cft of crush bajri of 3/4" - 3/8" in guage in 30 lbs of Bitumen 80/100 penetration i/e cleaning the road surface rolling after coat etc. complete includes all cost of materials T&P carriage upto site of work.			
	Quantity 5123 Sft.	@ Rs. 1720.30	P%Sft.	88131
3	<u>1" THICK PREMIXED CARPET</u>			
	Providing 1" thick capet in proper camber and grade i/c supplying of 10.00 cft crush bajri and 4.0 cft Hill snad of approved quarry quality and gauge and 67 lbs of bitumen of 80/100 penetration includes mixing in mechanical mixutre in required proportion i/e heating the materials and cleaning the road surface. Rate includes all cost of materials T&P and carriage upto site.			
	Quantity 20492 Sft.	@ Rs. 4326.66	P%Sft.	886619
4	<u>EARTH WORK ON BERMS</u>			
	Earth Work for embankment (Berms) from barrow pits including laying in 6" layers, clod breaking, ramming, dressing etc. complete. Lead upto 100 ft. and lift upto 5.0 ft. (in ordinary soil)			
	Quantity 14014 Cft.	@ Rs. 2208.37	P0%Cft.	30948
			TOTAL	1064331
5	<u>ADD DIFFERENT COST BITUMEN</u>			
	Quantity 4.14 Ton	@ Rs. 5427.00	P.Ton (-)	22468
			GRAND TOTAL	1041863

No. Premium will be allowed on Item No.

Note: Item/Quantities/Rates and amount are estimated provisional and will be corrected to the Detail Working Estimate sanctioned by competent authority

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 09

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION EMERKOT
STANDARD BIDDING DOCUMENT
FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	Repair Of 10 Rft Span Bridge Along Gulzar-e-Khalil To Jan Mohammad Siyal @ Mile 0/5
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	

EXCISE & TAX
DEPARTMENT
GULZAR-E-KHALIL


Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 09

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works Repair Of 10 Rft Span Bridge Along Gulzar-e-Khalil To Jan Mohammad Siyal @ Mile 0/5
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 269151 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 5383 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit.-(Including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

SCHEDULE "B"

NAME OF WORK: - Repair Of 10 Rft Span Bridge Along Gulzar-e-Khalil To Jan
Mohammad Siyal @ Mile 0/5

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>DISMENTALLING</u> RCC Ratio 1:2:4 Quantity 195 Cft. @ Rs. 5445.00	5445.00	P0%Cft.	10618
2	<u>DISMENTALLING 1:2:4</u> CC Plain Ratio 1:2:4 Quantity 36 Cft. @ Rs. 3327.50	3327.50	P0%Cft.	1198
3	<u>EXCAVATION</u> Excavation in foundation of Building, Bridges and other structures including dag belling dressing, refilling around structure with excavated earth, watering and ramming lead upto 5.00 ft. (in ordinary soil) Quantity 66 Cft. @ Rs. 3176.25	3176.25	P0%Cft.	211
4	<u>CEMENT CONCRETE RATIO (1:4:8)</u> Cement concrete bricks or stone ballast 1 ½ - 2" gauge Ration 1:4:8 Quantity 66 Cft. @ Rs. 9416.28	9416.28	P%Cft.	6250
5	<u>PUCCA BRICK WORK RATIO 1:4</u> Pucca brick work in foundation and plinth in cement sand mortar 1:4 Quantity 268 Cft. @ Rs. 12501.41	12501.41	P%Cft.	33535
6	<u>CEMENT CONCRETE</u> Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering (Ratio 1:2:4). Quantity 158 Cft. @ Rs. 14429.25	14429.25	P%Cft.	22726
7	<u>FABRICATION</u> Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) Quantity 12.81 CWT @ Rs. 4820.20	4820.20	P.CWT	61747
8	<u>R.C.C. WORK. RATIO 1:2:4</u> Reinforced cement concrete work including all labour and materials except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). R.C. work in roof slab, berms, columns rafts, lintels and other structural members laid in situ or pre-cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft. sand 4 Cft. Shingle 1/8" to 1/4" gauge. Quantity 223 Cft. @ Rs. 337.00	337.00	PCft.	75088
9	<u>ERECTION AND REMOVAL</u> Erection and removal of centering for R.C.C. or plain cement concrete works of Partal wood (2nd class) (a) Vertical. Quantity 14 Sft @ Rs. 3127.41	3127.41	P%Sft	438
10	<u>CEMENT PLASTER 1:3</u> Cement Plaster 1:3 upto 20.0' height. 1/2" thick. Quantity 268 Sft @ Rs. 2344.59	2344.59	P%Sft	6272
			TOTAL	218082

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 10

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION UMERKOT STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	Repair 3 Rft. Span Culvert Along Sirhari Shakh To Mehmood Mehar Road Mile 2/4
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	

2015
HIGHWAYS DIVISION
UMERKOT

Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 10

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works Repair 3 Rft. Span Culvert Along Sirhari Shakh To
Mehmood Mehar Road Mile 2/4
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways
Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 100000 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 2000 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit:-(including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways
Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____
_____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

SCHEDULE "B"

NAME OF WORK: - Repair 3 Rft. Span Culvert Along Sirhari Shakh To Mehmood Mehar Road Mile 2/4

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>DISMENTALLING</u> RCC Ratio 1:2:4 Quantity 42 Cft. @ Rs. 5445.00	5445.00	P0%Cft.	2287
2	<u>DISMENTALLING 1:2:4</u> CC Plain Ratio 1:2:4 Quantity 15 Cft. @ Rs. 3327.50	3327.50	P0%Cft.	499
3	<u>DISMENTALLING (PUCCA BRICK WORK)</u> Pucca Brick work in Cement sand mortar ratio 1:4 Quantity 58 Cft. @ Rs. 1285.63	1285.63	P0%Cft.	746
4	<u>EXCAVATION</u> Excavation in foundation of Building, Bridges and other structures including dag belling dressing, refilling around structure with excavated earth, watering and ramming lead upto 5.00 ft. (in ordinary soil) Quantity 73 Cft. @ Rs. 3176.25	3176.25	P0%Cft.	232
5	<u>CEMENT CONCRETE RATIO (1:4:8)</u> Cement concrete bricks or stone ballast 1 1/2 - 2" gauge Ration 1:4:8 Quantity 66 Cft. @ Rs. 9416.28	9416.28	P%Cft.	6215
6	<u>PUCCA BRICK WORK RATIO 1:4</u> Pucca brick work in foundation and plinth in cement sand mortar 1:4 Quantity 87 Cft. @ Rs. 12501.41	12501.41	P%Cft.	10876
7	<u>CEMENT CONCRETE</u> Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering (Ratio 1:2:4). Quantity 91 Cft. @ Rs. 14429.25	14429.25	P%Cft.	13131
8	<u>FABRICATION</u> Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.) Quantity 5.1 CWT @ Rs. 4820.20	4820.20	P.CWT	13390
9	<u>R.C.C. WORK. RATIO 1:2:4</u> Reinforced cement concrete work including all labour and materials except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds: lifting shuttering curing rendering and finishing the exposed surface (including screening and washing of shingle). R.C. work in roof slab, berms, columns rafts, lintels and other structural members laid in situ or pre-cast laid in position complete in all respects. Ratio (1:2:4) 90 lbs cement 2 Cft. sand 4 Cft. Shingle 1/8" to 1/4" gauge. Quantity 82 Cft. @ Rs. 337.00	337.00	PCft.	27634
10	<u>ERECTION AND REMOVAL</u> Erection and removal of centering for R.C.C. or plain cement concrete works of Partal wood (2nd class) (a) Vertical. Quantity 28 Sft @ Rs. 3127.41	3127.41	P%Sft	876
11	<u>CEMENT PLASTER 1:3</u> Cement Plaster 1:3 upto 20.0' height. 1/2" thick. Quantity 272 Sft @ Rs. 2344.59	2344.59	P%Sft	6377
			TOTAL	82263

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 08

SPPRA BIDDING DOCUMENT

HIGHWAYS DIVISION UMERKOT STANDARD BIDDING DOCUMENT FOR PROCUREMENT OF WORKS

(For Contracts Costing upto Rs. 2.500 Million)

Name of Work	M&R Of Road From Samaro Umerkot Road To Village Ghulam Hyder Kapri (Upto Ghulam Mohammad Kapri) Mile 0/0-2/0 (In Portions)
NIT No.	TC/G-55/1838 Dated: 25.05.2015
Tender issued Mr./M/s	
D/R No.	

EXECUTIVE ENGINEER
HIGHWAYS DIVISION
UMERKOT

Standard Bidding Documents is intended as a model for admeasurements (Percentage Rate/Unit price for unit rates in a Bill of Quantities types of Contract. The main text refers to admeasurements contract

S.No. 08

OFFICE OF THE EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

BIDDING DATA

- (a). Name of Procuring Agency Highways Division Umerkot
- (b). Brief Description of Works M&R Of Road From Samaro Umerkot Road To Village Ghulam Hyder Kapri (Upto Ghulam Mohammad Kapri) Mile 0/0-2/0 (In Portions)
- (c). Procuring Agency's address:- Office of the Executive Engineer Highways Division Umerkot
- (d). Estimated Cost:- Estimate Cost is Pak Rs. 1000000 /=
- (e). Amount of Bid Security:- Estimate Cost is Pak Rs. 20000 /=
- (f). Period of Bid Validity (days):- 60 Days
- (g). Security Deposit:-(including bid security):- 10% of contract price
- (h). Percentage, if any, to be deducted from bills :- 7.5% I.Tax & 8% S.Deposit
- (i). Deadline for Submission of Bids along with time :- 1:00 PM on 08.06.2015
- (j). Venue, Time, and Date of Bid Opening:- 2:00 PM on 09.06.2015
Office of the Executive Engineer Highways Division Umerkot
- (k). Time for Completion from written order of commence: - 01 Month
- (l). Liquidity damages:- 0.06% of Bid Cost (per day of delay)
- (m). Deposit Receipt No: _____ Date: _____
Amount: _____ (Rupees _____
_____)


EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT

S.No. 08

SCHEDULE "B"**PART - "A"**

NAME OF WORK: -

M&R Of Road From Samaro Umerkot Road To Village Ghulam Hyder Kapri (Upto Ghulam Mohammad Kapri) Mile 0/0-2/0 (In Portions)

QUANTITY	ITEM OF WORKS	RATE	UNIT	AMOUNT
1	<u>BASE COURSE</u> Preparing base course including supplying and spreading stone metal of approved quality properly graded to maximum size of 1 1/2" in required thickness of (3") to proper camber and grade including supplying and spreading 15 Cft. Screening and non plastic quarry fines, filling depressions with stone metal after initial rolling including watering and compacting the same so as to achieve 100% density as per modified AASHO specifications (Rate includes providing and using templates, camber plates, screens, forms etc. as directed). Rate includes all cost of materials, T&P, labours and carriage upto site of work.			
	Quantity 5025 Cft.	@ Rs. 10845.55	P%Cft.	544989
2	<u>FIRST COAT SURFACE DRESSING</u> Providing 1st coat surface dressing on new or existing surface with 4.00 cft of crush bajri of 3/4" - 3/8" in guage in 30 lbs of Bitumen 80/100 penetration 1/e cleaning the road surface rolling after coat etc. complete includes all cost of materials T&P carriage upto site of work.			
	Quantity 3655 Sft.	@ Rs. 1700.14	P%Sft.	62140
3	<u>TWO COAT SURFACE DRESSING</u> Providing Two coat surface dressing on new or existing surface with 39 lbs Bitumen and 5.00 Cft. of bajri of required size (1/2" - 3/4"), including cleaning the road surface, rolling etc. complete. (Rate includes all cost of materials, labours, T&P, and carriage upto site of work (3 Chains).			
	Quantity 18273 Sft.	@ Rs. 2113.34	P%Sft.	386171
4	<u>EARTH WORK ON BERMS</u> Earth Work for embankment (Berms) from barrow pits including laying in 6" layers, clod breaking, ramming, dressing etc. complete. Lead upto 100 ft. and lift upto 5.0 ft. (in ordinary soil)			
	Quantity 30202 Cft.	@ Rs. 2208.37	P0%Cft.	66697
			TOTAL	1059997
5	<u>ADD DIFFERENT COST BITUMEN</u>			
	Quantity 3.67 Ton	@ Rs. 5427.00	P.Ton (-)	19917
			GRAND TOTAL	1040080

No. Premium will be allowed on Item No.

Note: Item/Quantities/Rates and amount are estimated provisional and will be corrected to the Detail Working Estimate sanctioned by competent authority

CONTRACTOR

EXECUTIVE ENGINEER HIGHWAYS
DIVISION UMERKOT