



## **BIDDING DATA**

(This option should be filled in by the engineer / procuring agency before issuance of the bidding documents)

- a. Name of procuring Agency Town Committee (D) TMA Chambar Dist Tando Allahyar.
- b. Brief Description of work No. **01 Construction of cc block in village Abdul kareem Memon Hospital street /various House UC Chamber 1**
- c. Procuring Agency's address office of the Town Committee Chambar
- d. Estimated Cost . **1000000/=**
- e. Amount of bid security 20,000/= ( fill in lump sum amount in or %age of bid amount/ estimated cost , but not exceeding 2 % )
- f. Period of bid validity (days) 40 days (not more than sixty days)
- g. Security deposit⊕including security): **20,000/=**
- h. Percentage, if any to be deducted from bill: **7.5 % income tax.**
- i. Deadline for submission of bid along with time \_\_\_\_\_
- j. Venue time and date of bid opening TC meeting Hall,
- k. Time for completion from written order of commencement: Six Months
- l. Liquidity damages: 5000/= per day (0.05 of estimated cost or bid cost per day delay, out total not exceeding 10%)
- m. Deposit receipts No. Dated: Amount (in words and figures)  
(Executive Engineer / Authority issuing bidding document)

  
Engineer  
TC, Chambar

  
ADMINISTRATOR  
TC, Chambar

# OFFICE OF THE TOWN COMMITTEE CHAMBAR DISTRICT

## TANDO ALLAHYAR

### BILL OF QUANTITY

Name of work: (01 Construction of cc block in village Abdul kareem Memon  
Hospital street /various House UC Chamber 1

- |    |  |               |
|----|--|---------------|
| 1. | Barrow pit excavation undressed lead up to 100ft.(a)ordinary soil) (GSI No. 3 (a) p-1)   |               |
|    | 10450.00@ Rs. 2117.50 p%0 cft  | Rs. 22,128.00 |
| 2. | Earth work compaction (soft ordinary of hard soil) (a) lying earth in 6" layer leveling dressing complete (GSI No. 13(a)p-3 )  |               |
|    | 10450.00 @ Rs.263.00 p% 0C ft  | Rs. 2,748.00  |
| 3. | Carriage of 100 cft 5 tons of all material like stone aggregate, spawl, coal, lime, surkhi etc B.G ril fastening points and crossing bridge, girders, pipes sheets Tail Rail (R.A) |               |
|    | 10450.00 @Rs. 502.23 p% 0 Cft  | Rs. 52483.00  |
| 4. | Cement concrete bricks stone ballast 1 ½ " to 2" guage Ratio 1:4:8 (GSI No.4(b)P-14).  |               |
|    | 3300.00 @ Rs. 9416.28 P%0 Cft  | Rs. 310737.00 |
| 5. | Erection of removal of centering for RCC or plain cement concrete work for partial wood (vertical) (GSI No. 19 (B) (II) p-17)  |               |
|    |  | Rs. 15637.00  |
| 6. | Cement concrete plain i/c placing, compaction and for curing complete (1:2:4) (GSI No. 5(F)p-15)   |               |
|    | 2500.00 @ Rs. 14429.25% Cft  | Rs. 360731.00 |
|    | Total :  | Rs. 764465.00 |

  
**Engineer**

Town Committee  
TC, Chambar