


**OFFICE OF THE EXECUTIVE ENGINEER (B&R)  
SITE ZONE DMC WEST KARACHI**

**SUBJECT: - PROVIDING & FIXING OF SUBMERSIBLE 25 HP PUMP AND  
BORING & OTHER WORK IN GHAREEB NAWAZ COLONY  
UC-02SITE ZONE.**

**E/Cost: Open Rate E/Money 2%O/R T/Limit 30 Days Penalty 500/- PD.**

| S.No | Description of Work                                                                                                                                                                                                                                                                                          | Quantity | Rate Per Tons |
|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|---------------|
| 1.   | P/F and replacement of 25.H.P Pump and mortar existing borir g 200ft i/c overhauling of existing bore 8"dia i/c laying of casing 6" dia PVC Pipe with 4"dia 12 gauge M.S Pipes with flange nut and bolts i/c laying of 4 core 16mm cable i/c all arragement tripot (Chain Kuppy) comessioning in all respect | 01 Job   | Open Rate     |

  
**EXECUTIVE ENGINEER (B&R)  
SITE ZONE DMC (WEST)**

**Lum Sum Offer is Rupees** \_\_\_\_\_

**Signature** \_\_\_\_\_ **Address** \_\_\_\_\_

**OFFICE OF THE EXECUTIVE ENGINEER (B&R)**  
**SITE ZONE DMC WEST KARACHI**

**SUBJECT: - PROVIDING & FIXING OF 30 HP SUBMERSIBLE PUMP AND**  
**OTHER REPAIR WASH OF BORE AT WAJA WALI MUHAMMAD**  
**VILLAGE UC-02 SITE ZONE**

**E/Cost: Open Rate E/Money 2%O/R T/Limit 30 Days Penalty 500/- PD.**

| S.No | Description of Work                                                                                                                                                                                                                                                                                              | Quantity | Rate Per Tons |
|------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|---------------|
| 1.   | P/I and replacement of 30.H.P Pump and mortar existing boring 200ft i/c overhauling of existing bore 8" dia i/c laying of casing 6" dia PVC Pipe with 4" dia 12 gauge M. S Pipes with flange nut and bolts i/c laying of 4 core 16mm cable i/c all arrangement tripot (Chain Kuppy) commissioning in all respect | 01 Job   | Open Rate     |

  
**EXECUTIVE ENGINEER (B&R)**  
**SITE ZONE DMC (WEST)**

**Lum Sum Offer is Rupees** \_\_\_\_\_


**Signature** \_\_\_\_\_ **Address** \_\_\_\_\_

**OFFICE OF THE EXECUTIVE ENGINEER (B&R)**  
**SITE ZONE DMC WEST KARACHI**

**SUBJECT: - PROVIDING & FIXING OF PANNEL BOARDS AND REPLECMENT**  
**OF 4 CORE WIRE 16 MM GHAREEB NAWAZ COLONY AND WAJA**  
**WALI MUHAMMAD VILLAGE UC-02 SITE ZONE DMC (W)**

**E/Cost: Open Rate E/Money 2%O/R T/Limit 30 Days Penalty 500/- PD.**

| S.No | Description of Work                                                                                                                                                                                                                                                                                           | Quantity | Rate Per Tons |
|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|---------------|
| 1.   | P/F and replacement of 30.H.P Pump and mortar existing boring 200ft i/c overhauling of existing bore 8" dia i/c laying of casing 6" dia PVC Pipe with 4" dia 12 gauge M.S Pipes with flange nut and bolts i/c laying of 4 core 16mm cable i/c all arragement tripot (Chain Kuppy) comessioning in all respect | 01 Job   | Open Rate     |

  
**EXECUTIVE ENGINEER (B&R)**  
**SITE ZONE DMC (WEST)**

**Lum Sum Offer is Rupees** \_\_\_\_\_

**Signature** \_\_\_\_\_ **Address** \_\_\_\_\_

# OFFICE OF THE EXECUTIVE ENGINEER (B&R) SITE ZONE DMC WEST KARACHI

**SUBJECT: - OVERHALUING OF EXISTING BORE AND REPAIR OF DEEPWHEEL  
PUMP AND OTHER REPAIR WORK OF NOOR BAGH IN UC-02  
SITE ZONE DMC (WEST)**

**E/Cost: Open Rate E/Money 2%O/R T/Limit 30 Days Penalty 500/- PD.**

| S.No | Description of Work                                                                                                                                                                                                                                                                                             | Quantity | Rate Per Tons |
|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------|---------------|
| 1.   | P/F and replacement of 30.H.P Pump and mortar existing boring 200ft i/c overhauling of existing bore 8" dia i/c laying of casing 6" dia PVC Pipe with 4" dia 12 gauge M.S Pipes with flange nut and bolts i/c laying of 4 core 16mm cable i/c all arrangement tripot (Chain Kuppy) commissioning in all respect | 01 Job   | Open Rate     |

  
 EXECUTIVE ENGINEER (B&R)  
 SITE ZONE DMC (WEST)

**Lum Sum Offer is Rupees** \_\_\_\_\_

**Signature** \_\_\_\_\_ **Address** \_\_\_\_\_

# OFFICE OF THE EXECUTIVE ENGINEER (B&R) SITE ZONE DMC (WEST) KARACHI

**SUBJECT: - P/L 6" DIA P.E AND RCC PIPE FROM BIROHI ANJUMAN TO**  
**ABBASS HOTEL BIROHHI MOHALLAH AND SINDHI MOHALLAH**  
**UC-03 SITE ZONE DMC (WEST)**

**E/Cost: 9,53,873/-+O/R E/Money \_\_\_\_\_ /- T/Limit \_\_\_\_\_ Penalty 500/- PD.**

| S.No | Description of Work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                           | Quantity   | Rate Per%     |
|------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------|---------------|
| 1.   | Excavation of pipe line trenches pipe all kind of soil murum i/c trimming dressing leveling beds trenches correct level and graded cutting joints holes disposal of surplus earth with in 1 chains as directed by the Engg. Inch: P. fence guard lights flags temporary crossing non vehicler traffic where ever req: a lift up to 5 f. & lead up to 1 chain.                                                                                                                                                                                                                                 | 17094/Cft  | 4650 %0 Cft   |
| 2.   | P. Rec pipe ASTM class class 'C' 76-62 T/C 76-70 class II wall 'B' and fixing in trenches i/c cutting fitting jointing with rubber ring i/c testing with water to specified pressure 9" & 12" dia pipe.                                                                                                                                                                                                                                                                                                                                                                                       | 250/Rft    | 412 / P.Rft   |
| 3.   | Const of Main Holes 4 inside with Rec covers 21" dia 3x3/4 with flat iron frame 5ft depth 1:2:4 in laying CC cost in situ 9" thick wall and disposal of surplus stuff etc comp:                                                                                                                                                                                                                                                                                                                                                                                                               | 09/Nos.    | 13028 / Each  |
| 4.   | Add or deduct for depth of man holes above or beyond 5 ft (R/A).                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | 12.375/Rft | 2245.55/P.Rft |
| 5.   | Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc comp:                                                                                                                                                                                                                                                                                                                                                                                                                                                                                    | 15385/Cft  | 2760.0/%0Cft  |
| 6.   | P/L different dia P.E Pipe i/c cutting fitting & jointing and leveling i/c testing with water specified pressure etc comp etc 6" dia                                                                                                                                                                                                                                                                                                                                                                                                                                                          | 1100/Rft   | 530%Rft       |
| 7.   | Providing Chamber 21/2x21/2 (750mmx750mm) inside dimension 4 1/2 (1372mm) as per approved design for sluice valve 3" to 12" dia with 18" (475mm) dia inside cost iron cover and frame weight 1CWT 3qr fixed in Rec 1:2:4 (102mm) thick with 5 lbs steel per Cft 9" (299mm) thick brick masonry walls set 1:6 cement mortar 62(1552mm) thick cement concrete 1:2:4 flooring 1/2" (12.5mm) thick cement plaster 1:3 to all inside wall surface and to top i/c providing and fixing of m.s.f otrest every and foot beyond 2 1/2 ft depth curing excavation back filling and disposal of surplus. | 03Nos      | 18820 Each    |
| 8.   | P/F 6' dia Sluice valve                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | 03 No      | Open Rate     |

  
EXECUTIVE ENGINEER (B&R)  
SITE ZONE DMC (WEST)

I / we hereby quoted \_\_\_\_\_ Above / Below the SR.

Signature \_\_\_\_\_ Address \_\_\_\_\_


# OFFICE OF THE EXECUTIVE ENGINEER (B&R) SITE ZONE DMC (WEST) KARACHI

SUBJECT: - P/F FOR BORING IN DIFFERENT PLACES OF UC-01 AND UC-03

SITE ZONE

E/Cost: 6,66,551/- + O/R E/Money \_\_\_\_\_ /- T/Limit \_\_\_\_\_ Penalty 500/- PD.

| S.No | Description of Work                                                                                                                                                                                            | Quantity           | Rate Per%            |
|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------|----------------------|
| 1.   | Boring for tube well water boring from ground level up to 100' depth i/c sintary and with drawing of casing pipe                                                                                               | 700/Rft            | 414/P.Rft            |
| 2.   | P/L FVC Pressure pipe class "D" eq. Make fixing in trench i/c cutting fitting and jointing with 2" joint with one rubber i/c testing with water                                                                | 700/Rft            | 209.95/P.Rft         |
| 3.   | Carrage of PVC pipe of class by mechanical transport i/c loading unloading and stacking at site 1" dia<br>1 1/4" dia                                                                                           | 420/Rft<br>700/Rft | 28/P.Rft<br>34/P.Rft |
| 4.   | Shroinding with graded bajri 3/8 to 1/8 to between bore and blind pipe for the following diameters                                                                                                             | 700/Rft            | 102/P.Rft            |
| 5.   | Plugging of joint of casing and blind with cement concrete 1: 1 1/2 : 3                                                                                                                                        | 112/Cft            | 347/P.Rft            |
| 6.   | B/F deep well 3. HP Pump Single phase and making foudation 1: 2: 4                                                                                                                                             | 07 Nos             | Open Rate            |
| 7.   | Electrically main switch                                                                                                                                                                                       | 07 Nos             | Open Rate            |
| 8.   | M/S black steel M.S Pipe of M.S Sheet canforming to API-5L grade 42 specially welded and externally asphalt coated with fiber glass i/c laying jointing with filled welding in trenches and testing with water | 97/Rft             | 856.59/P/Rft         |

  
EXECUTIVE ENGINEER (B&R)  
SITE ZONE DMC (WEST)

I / we hereby quoted \_\_\_\_\_ Above / Below the SR.

Signature \_\_\_\_\_ Address \_\_\_\_\_


# OFFICE OF THE EXECUTIVE ENGINEER (B&R) SITE ZONE DMC (WEST) KARACHI

**SUBJECT: - IMP OF CC STREET AND SEWERAGE LINE IN WAJA WALI**

**MUHAMMAD VILLAGE IN DIFFERENT PLACES OF UC-02 SITE ZONE**

**E/Cost: 9,83,274/- E/Money \_\_\_\_\_ /- T/Limit \_\_\_\_\_ Penalty 500/- PD.**

| S.No | Description of Work                                                                                                                                                                                                                                                                                                                                           | Quantity  | Rate Per%     |
|------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------|---------------|
| 1.   | Excavation of pipe line trenches pipe all kind of soil murum i/c trimming dressing leveling beds trenches correct level and graded cutting joints holes disposal of surplus earth with in 1 chains as directed by the Engg: Inch: P. fence guard lights flags temporary crossing non vehicler traffic where ever req: a lift up to 5 ft & lead up to 1 chain. | 1750/Cft  | 4650 %0 Cft   |
| 2.   | P. Rec pipe ASTM class class 'C' 76-62 T/C 76-70 class II wall 'B' and fixing in trenches i/c cutting fitting jointing with rubber ring i/c testing with water to specified pressure 9" & 12" dia pipe.                                                                                                                                                       | 200/Rft   | 412 / P.Rft   |
| 3.   | Const of Main Holes 4 inside with Rcc covers 21" dia 3x3 with flat iron frame 5ft depth 1:2:4 in laying CC cost in situ 9" thick wall and disposal of surplus stuff etc comp:                                                                                                                                                                                 | 10/Nos.   | 13028 / Each  |
| 4.   | Adv or deduct for depth of man holes above or beyond 5 ft (RA).                                                                                                                                                                                                                                                                                               | 15/Rft    | 2245.55/P.Rft |
| 5.   | Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc comp:                                                                                                                                                                                                                                                    | 1575/Cft  | 2760.0/%0Cft  |
| 6.   | Earth work of Excavation undressed lead upto singe throw of Kassi Phwarah of shavel in ordinary soil.                                                                                                                                                                                                                                                         | 4565/Cft  | 1663.75%0Cft  |
| 7.   | Cartage of 100 Cft 5 tons all materials like stone aggregate spwals lime surkhi BG rail fasting points crossing bridge guders pipe sheet M/S Brass sheets 1000 trenches 10x5x3" 1000 tiles 12x6x2" 150 cft timber 100 mould fuel wood by trenches owned by the contractor withing 10 miles etc comp:                                                          | 3652/Cft  | 902.20%Cft    |
| 8.   | CC plain i/c placing compacting finishing and curing complete i/c screening and washing of stone aggregate withut shuttering ratio 1:4:8                                                                                                                                                                                                                      | 3630/Cft  | 9416.28%Cft   |
| 9.   | P/L 2" thick topping cement concrete 1:2:4 i/c surface finishing and dividing into panels eto completed.                                                                                                                                                                                                                                                      | 12500/Sft | 3275.50%Sft   |

  
**EXECUTIVE ENGINEER (B&R)  
SITE ZONE DMC (WEST)**

**I / we hereby quoted \_\_\_\_\_ Above / Below the SR.**

**Signature \_\_\_\_\_ Address \_\_\_\_\_**