

**OFFICE OF THE TOWN MUNICIPAL ADMINISTRATION BALDIA**

ESTIMATE COST	9,98,020/-	TIME LIMIT	15 Days
QUOTATION FEES	200/-		
PANELTY PER DAY			

**SUBJECT: - M/S R.C.C Main Hole cover & Ring Slab at Baldia Zone for Muharram-ul-Harram 2015**

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
08 01-	Manufacturing and supplying R.C.C main hole covers cast in situ 1:2:4 C.C. 3" inch deep in center reinforced with 3/8" dia M.S Bars welded on M.S. sheet i/c curing transportation. 21" dia. 24" dia.	675- Nos	913.63	Each	616700/-
09 02.	Manufacturing and supplying of R.C.C Ring Slab of 21" inside 36" dia out side 75 wide and to thick i/c 3/8" dia tor steel bar two concentric rings with 3/8" dia Nos. cross links bars welded and two sunk type hook, lasted in 1:1-1/2:3 concrete with embedded 15kg C.I frame in per feet position i/c terms partition charges for an average lead of 20 km per trip from casting yard to town office (A minimum of 25 slabs per trip will be transported.)	200- Nos	1906.60	Each	381320/-

  
A.E (B&R)

  
A.E.E (B&R)

I/We hereby quoted rate @ \_\_\_\_\_ % above/below the schedule of rates.

Contractor's Signature \_\_\_\_\_

Address \_\_\_\_\_  
\_\_\_\_\_

**OFFICE OF THE TOWN MUNICIPAL ADMINISTRATION BALDIA**

ESTIMATE COST	9,58,896/-	TIME LIMIT	15 Days
QUOTATION FEES	200/-		
PENALTY PER DAY			

**SUBJECT: - P/L 12" dia R.C.C Pipe line at different Street in UC-01 Baldia Zone DMC (West)  
Muharram-ul-Harram. 2015**

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches, and pits in all kind of soil of Murum Shape Leveling of beds of trenches to correct level & grade. surplus earth within a one chain as directed by Eng incharge.	14850	4650	%0Cft	69053/-
02	Excavation for pipe line in trenches, and pits in hard rock by hammering and chiseling i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within a one chain as directed by Engineers Incharge. Providing fence guards. Lights flags and temporary crossings for non-vehicular traffic where ever required lift up to 5ft. (1.52m) and lead upto one chain (30.5m)	1500	24150	%0Cft	36225/-
03	P/L reinforced cement concrete pipes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting, jointing with rubber rings etc complete KWSB Approved Rate, M/S Balochistan R.C.C Pipe Co. M/S Pakistan construction (Pvt.) Ltd. M/S Kamal R.C.C Pipe Co. 12" dia pipe	1100	367	P/Rft	403700/-
04	Construction of 4" dia manhole inside complete with 21" dia c c 1:2:4 pre cast C.I frame 15kg i/c the cost of M.S bars reinforcement and two handles 5" clear depth c c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KW&SB) approved rate.	45	9307	Each	418854/-
05	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 22.5	1609.15	P/ft	36206/-
06	Refilling the excavated stuff & surplus Earth etc. complete.	14715	2760	%Cft	40613/-
07	Carriage of 100 Cft Tons of all kind material like Cole, brick i/c loading unloading, 10 miles.	1635	595.80	%Cft	9741/-
08	Manufacturing and supplying R.C.C main hole covers cast in situ 1:2:4 C.C. 3" inch deep in center reinforced with 3/8" dia M.S Bars welded on M.S. sheet i/c curing transportation. 21" dia. 24" dia.	05	913.63	Each	9533/-
09	Manufacturing and supplying of R.C.C Ring Slab of 21" inside 36" dia out side 75 wide and to thick i/c 3/8" dia tor steel bar two concentric rings with 3/8" dia Nos. cross links bars welded and two sunk type hook, lasted in 1:1-1/2:3 concrete with embedded 15kg C.I frame in per feet position i/c terms partition charges for an average lead of 20 km per trip from casting yard to town office (A minimum of 25 slabs per trip will be transported.)	05	1906.60	Each	4568/-
10	Rate analysis for shifting to te site and fixing 26" dia Ring Slab in perfect position on damage manhole i/c cutting of damage portion of mentioned in past shape and lying of cement concrete mortar of 2" thickness and disport.	05	563.09	Each	2815/-

*M. Farid*

**A.E (B&R)**

*[Signature]*  
**A.E.E (B&R)**

I/We hereby quoted rate @ \_\_\_\_\_ % above/below the schedule of rates.

Contractor's Signature \_\_\_\_\_

Address \_\_\_\_\_

**OFFICE OF THE TOWN MUNICIPAL ADMINISTRATION BALDIA**

ESTIMATE COST	9,71,505/-	TIME LIMIT	15 Days
QUOTATION FEES	200/-		
PENALTY PER DAY			

**SUBJECT: - P/L Earth Filling around different Imam Bargh Street for Muharram-ul-Harram in Baldia Zone DMC (West) 2015**

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Earth work excavation of road side ditches including forming its banks or putting the same on embankment as directed and breaking dressing etc. complete (throw work) in ordinary soil.	14750 -Cft	1437.00	%0cft	21196/-
02	Filling watering and ramming earth under floor with new earth (Excavated from outside) lead up to one chain and lift upto 5 feet.	4688- Cft	3630	%0cft	17017/-
03	P/L aggregate base course material over prepared sub-grade in conformity with lines, graded, thickness and typical cross section as shown in drawing for new pavements at grade/widening existing pavements. Using well graded granular crushed stone with sand silt having smooth gradation curve within the limited for grading C or D as per AASHTO M-147-65 (1980) & compacting to 100% of the minimum dry density according to AASHTO 180 method D using approved mechanical means of i/c watering with all lead & lift complete as per specification as direct by the Engineer In charge.	14750 -Cft	5542.24	%0cft	817480/-
04	Cartage of 100cft. Tons all materials like stone aggregate, seals, time sulrkhi, BG rail fastening points, crossing bridge, guider pipe, sheet M/S Bars, sheets, 1000 trenches 10x5x3", 1000 tiles 12x6x2", 150 cft timber, 100 mould fuel wood by trenches owned by the contractor within 15 miles etc. complete.	19438 -Cft	595.80	%0cft	115812/-

*m. Farid*  
**A.E (B&R)**

*[Signature]*  
**A.E.E (B&R)**

I/We hereby quoted rate @ \_\_\_\_\_ % above/below the schedule of rates.

Contractor's Signature \_\_\_\_\_

Address \_\_\_\_\_


\_\_\_\_\_

**OFFICE OF THE TOWN MUNICIPAL ADMINISTRATION BALDIA**

ESTIMATE COST	9,67,400/-	TIME LIMIT	15 Days
QUOTATION FEES	200/-		
PANALTY PER DAY			

**SUBJECT: - P/L 12" dia R.C.C Pipe line at Block 'D' Street in UC-01 Gulshan-e-Ghazi Baldia Zone DMC (West) Muharram-ul-Harram. 2015**

S.NO	DISCREPTION	QTY	RATE	PER	AMOUNT
01	Excavation for pipe line in trenches, and pits in all kind of soil of Murum Shape Leveling of beds of trenches to correct level & grade, surplus earth within a one chain as directed by Eng incharge.	14850	4650	%0Cft	69053/-
02	Excavation for pipe line in trenches, and pits in hard rock by hammering and chiseling i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within a one chain as directed by Engineers Incharge. Providing fence guards. Lights flags and temporary crossings for non-vehicular traffic where ever required lift up to 5ft. (1.52m) and lead upto one chain (30.5m)	1500	24150	%0Cft	36225/-
03	P/L reinforced cement concrete pipes with rubber rings i/c cartage, loading unloading at site of work fixing in trenches cutting fitting, jointing with rubber rings etc complete KWSB Approved Rate, M/S Balochistan R.C.C Pipe Co. M/S Pakistan construction (Pvt.) Ltd. M/S Kamal R.C.C Pipe Co. 12" dia pipe	1100	367	P/Rft	403700/-
04	Construction of 4" dia manhole inside complete with 21" dia c c 1:2:4 pre cast C.I frame 15kg i/c the cost of M.S bars reinforcement and two handles 5" clear depth c c 1:2:4 cast in situ walls with 50% screened graded bajri of 9" thick i/c bending and channel i/c inside walls surface complete i/c cutting asphalt roads excavation in all kind of soil back filling and disposal of surplus stuff (KW&SB) approved rate.	46	9307.86	Each	428162/-
05	Extra depth beyond 5" ft or less then 5 deducted at the same rate (KWSB) approved rate.	(-) 23	1609.15	P/ft	37010/-
06	Refilling the excavated stuff & surplus Earth etc. complete.	14715	2760	%Cft	40613/-
07	Carriage of 100 Cft Tons of all kind material like Cole, brick i/c loading unloading, 10 miles.	1635	595.80	%Cft	9741/-
08	Manufacturing and supplying R.C.C main hole covers cast in situ 1:2:4 C.C. 3" inch deep in center reinforced with 3/8" dia M.S Bars welded on M.S. sheet i/c curing transportation. 21" dia. 24" dia.	05	913.63	Each	9533/-
09	Manufacturing and supplying of R.C.C Ring Slab of 21" inside 36" dia out side 75 wide and to thick i/c 3/8" dia tor steel bar two concentric rings with 3/8" dia Nos. cross links bars welded and two sunk type hook, lasted in 1:1-1/2:3 concrete with embedded 15kg C.I frame in per feet position i/c terms partition charges for an average lead of 20 km per trip from casting yard to town office (A minimum of 25 slabs per trip will be transported.)	05	1906.60	Each	4568/-
10	Rate analysis for shifting to te site and fixing 26" dia Ring Slab in perfect position on damage manhole i/c cutting of damage portion of mentioned in past shape and lying of cement concrete mortar of 2" thickness and disport.	05	563.09	Each	2815/-

  
**A.E (B&R)**

  
**A.E.E (B&R)**

I/We hereby quoted rate@\_\_\_\_\_ % above/below the schedule of rates.

Contractor's Signature \_\_\_\_\_

Address \_\_\_\_\_