

(BoQs) Schedule-B.
For
N.I.T.519, dated 14-9-2015
N.I.T.Sr. No.01 to 11.

(BoQs) SCHEDULE "B"

N.I.T. No: 01

NAME OF WORK: -

Constt. of one Class Room w Existing Shellless
Primary School w Tol: Digri & K.G. Mohammad Dist: M.Khas
e.G.P.S Faiz Mohammad Dal Deh-351 w Jawari Sar

S. No	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-------	-------------	-----	------	------	--------

Tol: K.G.M

- 1 Excavation in foundation of building, bridges and others structure i/c degbelling dressing refilling around structure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 5).

839.00 @ Rs. 3176.25 %OCft. Rs. 2665

- 2 Cement Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:5:10 (S.I.No 4 (c) Page No. 17).

367.00 @ Rs. 9416.28 %Cft. Rs. 34558

- 3 Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 25).

674.00 @ Rs. 11948.36 %Cft. Rs. 80532

- 4 RCC work i/c all labour & material except the cost of steel reinforcement and its labour for bending binding which will be paid separately. This rate also i.e all kinds of forms moulds lifting shuttering curing rendering the exposed surface including screening and washing of shingle (a) RCC work in roof slab, beams columns rafts lintels and other structural member laid in situ or precast laid in position complete in all respects ratio (1 : 2 : 4) 90 Lbs. Cement 2 Cft. Sand 4 Cft. Shingle 1/8" to 1/4" gauge (S.I.No. 6A Page 19).

427.00 @ Rs. 337.00 P.Cft. Rs. 143899

- 5 Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making and joints and fastening i/c cost of binding wire (also i/c removal of rust from bars. (S.I.No 7 Page 20).

19.06 @ Rs. 5001.70 P.Cwt. Rs. 95332

- 6 Filling and watering ramming earth under floor with surplus earth from foundation lead up to one chain and lift upto 5 feet | S.I.No.21/Page 4).

559.00 @ Rs. 1512.50 %OCft. Rs. 845

- 7 Filling and watering ramming earth under floor with surplus earth from out side lead up to one chain and lift upto 5 feet | S.I.No.22/Page 4).

139.00 @ Rs. 3630.00 %OCft. Rs. 505

- 8 Pucca brick in ground floor in cement sand mortar 1:6 (S.I.No 5 (e) Page No. 25).

723.00 @ Rs. 12674.36 %Cft. Rs. 91636

- 9 Providing & fixing G.I frames / chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing and jumbs. The cost also include all carriage tools and plants used in making and fixing (S.I.No. 28 Page No 98).

34.00 @ Rs. 228.90 P.Rft. Rs. 7783

(B) WINDOW CHOWKETS.

68.00 @ Rs. 240.50 P.Rft. Rs. 16354

- 10 Providing and fixing iron steel grill using solid square bars of size 1/2"x1/2" placed at 4" i/c and frame of flat iron patti of 3/4" x 3/4" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3-coats with 1st coat of red OXID paint etc (S.I.NO.30/P-93)

181.00 @ Rs. 194.16 P.Sft. Rs. 35143

- 11 Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 51).

1997.00 @ Rs. 2206.60 %Sft. Rs. 44066

- 12 Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 51).

1997.00 @ Rs. 2197.52 %Sft. Rs. 43884

- 13 Cement plaster 1:4 upto 20" height 3/4" thick (S.I.No 11 (c) Page No. 51).

88.00 @ Rs. 3015.76 %Sft. Rs. 2654

- 14 Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-52).

551 @ Rs. 1287.44 %Sft. Rs. 7094




Executive Engineer
Education Works Division
Mirpurkhas

Contd-P-No-02

15	First class deodar wood wrought joinery in doors and windows etc fixed in position i.e. chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks etc. Deodar paneled fully glazed 3/4" thick. (S.I.No. 7 (b) Page 57).(Shutter Only)	75.00	@ Rs. 902.93	P.Sft.	Rs. 67720
16	Extra labour rate for making cement plaster patts/band around straight or carved openings and around the edgers of roof slabs the width not less than 6" with fine finishing as directed by Engineer (S.I.No.35-P-54)	174.00	@ Rs. 19.36	P.Rft.	3369
17	Making Notice Board made with cement sand (S.I.No.1/P-94).	32.00	@ Rs. 58.11	P.Sft.	Rs. 1860
18	Providing & Laying C.C topping 1:2:4 i.c surface finishing and divided in to panels.(S.I.No.16 (d) Page No.47).				
	<u>2"THICK</u>	624.00	@ Rs. 3275.50	%Sft.	Rs. 20439
	3"THICK	383	@ Rs. 4411.82	%Sft.	Rs. 16897
19	Laying floor approved white glazed tile 1/4" thick in white cement 1:2 over 3/4 " thick cement mortar 1:2) complete (S.I.No. 24 / P-42	16.00	@ Rs. 27678.86	%Sft.	Rs. 4429
20	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick i/c finishing (S.I.No. 37 Page No.44).	41.00	@ Rs. 28253.61	%Sft.	11584
21	Colour washing on walls 03-coats. (S.I.No:25(c), P-54)	551.00	@ Rs. 1303.17	%Sft.	7180
22	White washing three coats (S.I.No. 26 (C) Page No. 53).	615.00	@ Rs. 829.95	%Sft.	Rs. 5104
23	Primary Coat of chalk under distemper (S.I.No. 23 Page No. 53).	2084.00	@ Rs. 442.75	%Sft.	Rs. 9227
24	Painting new surface (c) Preparing surface and painting doors & windows any type i/c edges (S.I.No.50/P-69).	187.00	@ Rs. 2116.41	%Sft.	Rs. 3958
25	Distemping 3 coats (S.I.No. 24 Page No. 53).	2084.00	@ Rs. 1079.65	%Sft.	Rs. 22500
26	Two coats of bitumen laid hot using 34 lbs for %sft over roof and blind with sand (S.I.No.13 / P-34)	624.00	@ Rs. 1887.40	%Sft.	Rs. 11777

G.TOTAL RS: 791687Contd-P-No:03


 Executive Engineer
 Education Works Division
 Mirpurkhas



PART - B

WATER SUPPLY & SANITARY FITTING

NIT No: 01



Name of Work:

GBPS FAIZ MOHAMMAD DAL Deh-351 4/c Jawarisar.

S.#	DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT
1	Providing and fixing squatting type white glazed earthen ware W.C. pan with front flush inlet and complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (B-II) W.C. of not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia earthen ware trap & plastic thumble.(S.I.No. 1(b)(ii)/page 1)	1 No.	@ 4802.60	Each	Rs. 4803
2	Providing RCC pipe with collars class-B and digging the trenches to required depth and fixing in position including cutting, fitting and jointing with maxphalt composition and cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of height pipe and refilling with excavated stuff.4" dia (S.I.No. 2/page 23) 6" dia	12 Rft	@ 199.25	P.Rft.	Rs. 2391
Total (Schedule Item)					Rs. 7194 /=

NON-SCHEDULE ITEMS

19	Providing & Fixing Hand Pump with all accessories with 1 1/2" dia G.I pipe i.c boaring, fitting and fixing in position and making on c.c platform 1:2:4 with 4" dia G.I casing pipe 4' high above the ground level complete (Market rate).				
(a)	Coir Strainer 1 1/2" Dia	6.0 Rft	@ 100.00	Rft	Rs. 600
(b)	Boaring 1 1-1/4" dia	30.0 Rft	@ 76.00	Rft	Rs. 2280
(c)	Hand Pump	1 No.	@ 6000.00	Each	Rs. 6000
Total (Non Schedule Item)					Rs. 8880 /=


 Executive Engineer
 Education Works Division
 Mirpurkhas


(BoQs) SCHEDULE "B"

NAME OF WORK: -

Constt: of one class room in Existing Shelterless Prj:
School in Tal: Digri & K. G. Mohammad Dist: M. Khas
e GBPS Otaque Ahmed Khan Bhurguri u/c Jawari Sar

S. No	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-------	-------------	-----	------	------	--------

Tal: K.G.M

1 Excavation in foundation of building, bridges and others structure i/c degbelling dressing refilling around structure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 5).

839.00 @ Rs. 3176.25 %OCft. Rs. 2665

2 Cement Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:5:10 (S.I.No 4 (c) Page No. 17).

367.00 @ Rs. 9416.28 %Cft. Rs. 34558

3 Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 25).

674.00 @ Rs. 11948.36 %Cft. Rs. 80532

4 RCC work i/c all labour & material except the cost of steel reinforcement and its labour for bending binding which will be paid separately. This rate also i.e all kinds of forms moulds lifting shuttering curing rendering the exposed surface including screening and washing of shingle (a) RCC work in roof slab, beams columns rafts lintels and other structural member laid in situ or precast laid in position complete in all respects ratio (1 : 2 : 4) 90 Lbs. Cement 2 Cft. Sand 4 Cft. Shingle 1/8" to 1/4" gauge (S.I.No. 6A Page 19).

427.00 @ Rs. 337.00 P.Cft. Rs. 143899

5 Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making and joints and fastening i/c cost of binding wire (also i/c removal of rust from bars. (S.I.No 7 Page 20).

19.06 @ Rs. 5001.70 P.Cwt. Rs. 95332

6 Filling and watering ramming earth under floor with surplus earth from foundation lead up to one chain and lift upto 5 feet | S.I.No.21/Page 4).

559.00 @ Rs. 1512.50 %OCft. Rs. 845

7 Filling and watering ramming earth under floor with surplus earth from out side lead up to one chain and lift upto 5 feet | S.I.No.22/Page 4).

139.00 @ Rs. 3630.00 %OCft. Rs. 505

8 Pucca brick in ground floor in cement sand mortar 1:6 (S.I.No 5 (e) Page No. 25).

723.00 @ Rs. 12674.36 %Cft. Rs. 91636

9 Providing & fixing G.I frames / chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing and jumbs. The cost also include all carriage tools and plants used in making and fixing (S.I.No. 28 Page No 98).

34.00 @ Rs. 228.90 P.Rft. Rs. 7783

(B) WINDOW CHOWKETS.

68.00 @ Rs. 240.50 P.Rft. Rs. 16354

10 Providing and fixing iron steel grill using solid square bars of size 1/2"x1/2" placed at 4" i/c and frame of flat iron patti of 3/4"x3/4" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3-coats with 1st coat of red CXID paint etc (S.I.NO.30/P-93)

181.00 @ Rs. 194.16 P.Sft. Rs. 35143

11 Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 51).

1997.00 @ Rs. 2206.60 %Sft. Rs. 44066

12 Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 51).

1997.00 @ Rs. 2197.52 %Sft. Rs. 43884

13 Cement plaster 1:4 upto 20" height 3/4" thick (S.I.No 11 (c) Page No. 51).

88.00 @ Rs. 3015.76 %Sft. Rs. 2654

14 Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-52).

551 @ Rs. 1287.44 %Sft. Rs. 7094




Executive Engineer
Education Works Division
Mirpurkhas

Contd-B-No-2

15	First class deodar wood wrought joinery in doors and windows etc fixed in position i.e. chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks etc. Deodar paneled fully glazed 3/4" thick. (S.I.No. 7 (b) Page 57).(Shutter Only)	75.00	@ Rs. 902.93	P.Sft.	Rs. 67720
16	Extra labour rate for making cement plaster patts/band around straight or carved openings and around the edgers of roof slabs the width not less than 6" with fine finishing as derected by Engineer (S.I.No.35-P-54)	174.00	@ Rs. 19.36	P.Rft.	3369
17	Making Notice Board made with cement sand (S.I.No.1/P-94).	32.00	@ Rs. 58.11	P.Sft.	Rs. 1860
18	Providing & Laying C.C topping 1:2:4 i.c surface finishing and divided in to panels. (S.I.No.16 (d) Page No.47).				
	<u>2"THICK</u>	624.00	@ Rs. 3275.50	%Sft.	Rs. 20439
	3"THICK	383	@ Rs. 4411.82	%Sft.	Rs. 16897
19	Laying floor approved white glazed tile 1/4" thick in white cement 1:2 over 3/4 " thick cement mortar 1:2) complete: (S.I.No. 24 / P-42	16.00	@ Rs. 27678.86	%Sft.	Rs. 4429
20	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick i/c finishing (S.I.No. 37 Page No.44).	41.00	@ Rs. 28253.61	%Sft.	11584
21	Colour washing on walls 03-coats. (S.I.No:25(c), P-54)	551.00	@ Rs. 1303.17	%Sft.	7180
22	White washing three coats (S.I.No. 26 (C) Page No. 53).	615.00	@ Rs. 829.95	%Sft.	Rs. 5104
23	Primary Coat of chalk under distemper (S.I.No. 23 Page No. 53).	2084.00	@ Rs. 442.75	%Sft.	Rs. 9227
24	Painting new surface (c) Preparing surface and painting doors & windows any type i/c edges (S.I.No.5©/P-69).	187.00	@ Rs. 2116.41	%Sft.	Rs. 3958
25	Distemping 3 coats (S.I.No. 24 Page No. 53).	2084.00	@ Rs. 1079.65	%Sft.	Rs. 22500
26	Two coats of bitumen laid hot using 34 lbs for %sft over roof and blind with sand (S.I.No.13 / P-34)	624.00	@ Rs. 1887.40	%Sft.	Rs. 11777

G.TOTAL RS: 791687

Contd - P.No-03


Executive Engineer
Education Works Division
Mirpurkhas



PART - B

WATER SUPPLY & SANITARY FITTING

NIT Sr-No: 02

Name of Work:


GBPS Orlaque Ahmed Khan Bhurguri Pol: K. G. m



S.#	DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT
1	Providing and fixing squatting type white glazed earthen ware W.C. pan with front flush inlet and complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (B-II) W.C. of not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia earthen ware trap & plastic thumble.(S.I.No. 1(b)(ii)/page 1)	1	No.	@ 4802.60 Each	Rs. 4803
2	Providing RCC pipe with collars class-B and digging the trenches to required depth and fixing in position including cutting, fitting and jointing with maxphalt composition and cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of height pipe and refilling with excavated stuff. 4" dia (S.I.No. 2/page 23) 6" dia	12	Rft	@ 199.25 P.Rft.	Rs. 2391
Total (Schedule Item)					Rs. 7194 /=-

NON-SCHEDULE ITEMS

19	Providing & Fixing Hand Pump with all accessories with 1 1/2" dia G.I pipe i.c boaring, fitting and fixing in position and making on c.c platform 1:2:4 with 4" dia G.I casing pipe 4' high above the ground level complete (Market rate).				
(a)	Coir Strainer 1 1/2" Dia	6.0	Rft	@ 100.00 Rft	Rs. 600
(b)	Boaring 1 1-1/4" dia	30.0	Rft	@ 76.00 Rft	Rs. 2280
(c)	Hand Pump	1	No.	@ 6000.00 Each	Rs. 6000
Total (Non Schedule Item)					Rs. 8880 /=-


 Executive Engineer
 Education Works Division
 Mirpurkhas

(BoQs) - SCHEDULE "B"

N.I.T Sr:No:03

NAME OF WORK:-

Const. of one clay room in Existing shelterless bry:
 School - Top Digri & K. G. Mohammad Distt: M. Khan & GBPS
 Rozdar Khan Delh-2574c Mir Imam Bux Tel: K.G.M.

S. No	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-------	-------------	-----	------	------	--------

- 1 Excavation in foundation of building, bridges and others structure i/c degbelling dressing refilling around structure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page I.No. 5).
 839.00 @ Rs. 3176.25 %OCft. Rs. 2665
 - 2 Cement (Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:5:10 (S.I.No 4 (c) Page No. 17).
 367.00 @ Rs. 9416.28 %Cft. Rs. 34558
 - 3 Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 25).
 674.00 @ Rs. 11948.36 %Cft. Rs. 80532
 - 4 RCC work i/c all labour & material except the cost of steel reinforcement and its labour for bending binding which will be paid separately. This rate also i.e all kinds of forms moulds lifting shuttering curing rer dering the exposed surface including screening and washing of shingle (a) RCC work in roof slab, beans columns rafts lintels and other structural member laid in situ or precast laid in position complete in all respects ratio (1: 2: 4) 90 Lbs. Cement 2 Cft. Sand 4 Cft. Shingle 1/8" to 1/4" gauge (S.I.No. 6A Page 19).
 427.00 @ Rs. 337.00 P.Cft. Rs. 143899
 - 5 Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making and joints and fastening i/c cost of binding wire (also i/c removal of rust from bars. (S.I.No 7 Pa. e 20).
 19.06 @ Rs. 5001.70 P.Cwt. Rs. 95332
 - 6 Filling and watering ramming earth under floor with surplus earth from foundation lead up to one chain and lift upto 5 feet | S.I.No.21/Page 4).
 559.00 @ Rs. 1512.50 %OCft. Rs. 845
 - 7 Filling and watering ramming earth under floor with surplus earth from out side lead up to one chain and lift upto 5 feet | S.I.No.22/Page 4).
 139.00 @ Rs. 3630.00 %OCft. Rs. 505
 - 8 Pucca brick in ground floor in cement sand mortar 1:6 (S.I.No 5 (e) Page No. 25).
 723.00 @ Rs. 12674.36 %Cft. Rs. 91636
 - 9 Providing & fixing G.I frames / chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 2" gauge G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing and jumbs. The cost also include all carriage tools and plants used in raking and fixing (S.I.No. 28 Page No 98).
 34.00 @ Rs. 228.90 P.Rft. Rs. 7783
- (B) WINDOW CHOWKETS.
- 68.00 @ Rs. 240.50 P.Rft. Rs. 16354
 - 10 Providing and fixing iron steel grill using solid square bars of size 1/2"x1/2" placed at 4" i/c and frame of flat iron patti of 3/4"x3/4" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3-coats with 1st coat of red OXID paint etc (S.I.NO.30/P-93)
 181.00 @ Rs. 194.16 P.Sft. Rs. 35143
 - 11 Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 51).
 1997.00 @ Rs. 2206.60 %Sft. Rs. 44066
 - 12 Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 51).
 1997.00 @ Rs. 2197.52 %Sft. Rs. 43884
 - 13 Cement plaster 1:4 upto 20" height 3/4" thick (S.I.No 11 (c) Page No. 51).
 88.00 @ Rs. 3015.76 %Sft. Rs. 2654
 - 14 Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-52).
 551 @ Rs. 1287.44 %Sft. Rs. 7094



Executive Engineer
 Education Works Division
 Mirpurkhas

Contd-P.No-02

15	First class deodar wood wrought joinery in doors and windows etc fixed in position i.e. chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks etc. Deodar paneled fully glazed 3/4" thick. (S.I.No. 7 (b) Page 57).(Shutter Only)	75.00	@ Rs. 902.93	P.Sft.	Rs. 67720
16	Extra labour rate for making cement plaster patts/band around straight or carved openings and around the edgers of roof slabs the width not less than 6" with fine finishing as derected by Engineer (S.I.No.35-P-54)	174.00	@ Rs. 19.36	P.Rft.	3369
17	Making Notice Board made with cement sand (S.I.No.1/P-94).	32.00	@ Rs. 58.11	P.Sft.	Rs. 1860
18	Provid ng & Laying C.C topping 1:2:4 i.c surface finishing and divided in to panels.(S.I.No.16 (d) Page No.47).				
	<u>2"THICK</u>	624.00	@ Rs. 3275.50	%Sft.	Rs. 20439
	3"THICK	383	@ Rs. 4411.82	%Sft.	Rs. 16897
19	Laying floor approved white glazed tile 1/4" thick in white cement 1:2 over 3/4 " thick cement mortar 1:2) complete (S.I.No. 24 / P-42	16.00	@ Rs. 27678.86	%Sft.	Rs. 4429
20	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick i/c finishing (S.I.No. 37 Page No.44).	41.00	@ Rs. 28253.61	%Sft.	11584
21	Colour washing on walls 03-coats. (S.I.No:25(c), P-54)	551.00	@ Rs. 1303.17	%Sft.	7180
22	White vashing three coats (S.I.No. 26 (C) Page No. 53).	615.00	@ Rs. 829.95	%Sft.	Rs. 5104
23	Primary Coat of chalk under distemper (S.I.No. 23 Page No. 53).	2084.00	@ Rs. 442.75	%Sft.	Rs. 9227
24	Painting new surface (c) Preparing surface and painting doors & windows any type i/c edges (S.I.No.50/P-69).	187.00	@ Rs. 2116.41	%Sft.	Rs. 3958
25	Distemping 3 coats (S.I.No. 24 Page No. 53).	2084.00	@ Rs. 1079.65	%Sft.	Rs. 22500
26	Two coats of bitumen laid hot using 34 lbs for %sft over roof and blind with sand (S.I.No.13 / P-34)	624.00	@ Rs. 1887.40	%Sft.	Rs. 11777

G.TOTAL RS: 791687Sul-d-P-No: 03

Executive Engineer
Education Works Division
Mirpurkhas



PART - B


NIT No: 03

WATER SUPPLY & SANITARY FITTING

Name of Work:

GBBS Rozdar Khan Deh-257 Tol. K.G.M.

S.#	DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT
1	Providing and fixing squatting type white glazed earthen ware W.C. pan with front flush inlet and complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (B-II) W.C. of not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia earthen ware trap & plastic thumble.(S.I.No. 1(b)(ii)/page 1)	1	No.	@ 4802.60 Each	Rs. 4803
2	Providing RCC pipe with collars class-B and digging the trenches to required depth and fixing in position including cutting, fitting and jointing with maxphalt composition and cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of height pipe and refilling with excavated stuff. 4" dia (S.I.No. 2/page 23) 6" dia	12	Rft	@ 199.25 P.Rft.	Rs. 2391
Total (Schedule Item)					Rs. 7194 /=-

NON-SCHEDULE ITEMS

19	Providing & Fixing Hand Pump with all accessories with 1 1/2" dia G.I pipe i.c boaring, fitting and fixing in position and making on c.c platform 1:2:4 with 4" dia G.I casing pipe 4' high above the ground level complete (Market rate).				
(a)	Coir Strainer 1 1/2" Dia	6.0	Rft	@ 100.00 Rft	Rs. 600
(b)	Boaring 1 1/4" dia	30.0	Rft	@ 76.00 Rft	Rs. 2280
(c)	Hand Pump	1	No.	@ 6000.00 Each	Rs. 6000
Total (Non Schedule Item)					Rs. 8880 /=-


 Executive Engineer
 Education Works Division
 Mirpurkhas

(BoQs) - SCHEDULE "B"

NAME OF WORK: CONSTRUCTION OF ONE CLASS ROOM PRIMARY SCHOOL @ GBPS
ALI BUX JARWAR U.C KHERAO TALUKA SINDHRI.

S. No	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
1	Excavation in foundation of building, bridges and others structure i/c degbelling dressing refilling around structure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 5).	839.00	@ Rs. 3176.25	%OCft.	Rs. 2665
2	Cement Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:5:10 (S.I.No 4 (c) Page No. 17).	367.00	@ Rs. 9416.28	%Cft.	Rs. 34558
3	Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 25).	674.00	@ Rs. 11948.36	%Cft.	Rs. 80532
4	RCC work i/c all labour & material except the cost of steel reinforcement and its labour for bending binding which will be paid separately. This rate also i.e all kinds of forms moulds lining shuttering curing rendering the exposed surface including screening and washing of shingle (a) F.CC work in roof slab, bears columns rafts lintels and other structural member laid in situ or precast laid in position complete in all respects ratio (1: 2: 4) 90 Lbs. Cement 2 Cft. Sand 4 Cft. Shingle 1/8" to 1/4" gauge (S.I.No. 6A Page 19)	427.00	@ Rs. 337.00	P.Cft.	Rs. 143899
5	Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making and joints and fastening i/c cost of binding wire (also i/c removal of rust from bars. (S.I.No 7 Page 20).	19.06	@ Rs. 5001.70	P.Cwt.	Rs. 95332
6	Filling and watering ramming earth under floor with surplus earth from foundation lead up to one chain and lift upto 5 feet S.I.No.21/Page 4).	559.00	@ Rs. 1512.50	%OCft.	Rs. 845
7	Filling and watering ramming earth under floor with surplus earth from out side lead up to on chain and lift upto 5 feet S.I.No.22/Page 4).	139.00	@ Rs. 3630.00	%OCft.	Rs. 505
8	Pucca brick in ground floor in cement sand mortar 1:6 (S.I.No 5 (e) Page No. 25).	723.00	@ Rs. 12674.36	%Cft.	Rs. 91636
9	Providing & fixing G.I frames / chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet including welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing and jumbs. The cost also include all carriage tools and plants used in making and fixing (S.I.No. 28 Page No 98).	34.00	@ Rs. 228.90	P.Rft.	Rs. 7783
(B) WINDOW CHOWKETS.					
		68.00	@ Rs. 240.50	P.Rft.	Rs. 16354
10	Providing and fixing iron steel grill using solid square bars of size 1/2"x1/2" placed at 4" i/c an d frame of flat iron patti of 3/4" x 3/4" i/c circle shape at 1-0 apart equivalent fitted with screws are pins i/c painting 3-coats with 1st coat of red OXID paint etc (S.I.NO.30/P-93)	181.00	@ Rs. 194.16	P.Sft.	Rs. 35143
11	Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 51).	1997.00	@ Rs. 2206.60	%Sft.	Rs. 44066
12	Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 51).	1997.00	@ Rs. 2197.52	%Sft.	Rs. 43884
13	Cement plaster 1:4 upto 20" height 3/4" thick (S.I.No 11 (c) Page No. 51).	88.00	@ Rs. 3015.76	%Sft.	Rs. 2654
14	Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-52).	551	@ Rs. 1287.44	%Sft.	Rs. 7094



Executive Engineer
Education Works Division

Contd - P-No. 02

15	First class deodar wood wrought joinery in doors and windows etc fixed in position i.e. chowkats hold fasts hinges, iron tower bolts, chocks cleats, handles and cords with hooks etc. Deodar paneled fully glazed 3/4" thick. (S.I.No. 7 (b) Page 57).(Shutter Only)	75.00	@ Rs. 902.93	P.Sft.	Rs. 67720
16	Extra labour rate for making cement plaster patts/band around straight or carved openings and around the edgers of roof slabs the width not less than 6" with fine finishing as derected by Engineer (S.I.No.35-P-54)	174.00	@ Rs. 19.36	P.Rft.	3369
17	Making Notice Board made with cement sand (S.I.No.1/P-94).	32.00	@ Rs. 58.11	P.Sft.	Rs. 1860
18	Providing & Laying C.C topping 1:2:4 i.c surface finishing and divided in to panels.(S.I.No.16 (d) Page No.47).				
	<u>2"THICK</u>	624.00	@ Rs. 3275.50	%Sft.	Rs. 20439
	3"THICK	383	@ Rs. 4411.82	%Sft.	Rs. 16897
19	Laying floor approved white glazed tile 1/4" thick in white cement 1:2 over 3/4 " thick cement mortar 1:2) complete (S.I.No. 24 / P-42	16.00	@ Rs. 27678.86	%Sft.	Rs. 4429
20	White glazed tiles 1/4" thick dado jointed in white cement and laid over 1:2 cement sand mortar 3/4" thick i/c finishing (S.I.No. 37 Page No.44).	41.00	@ Rs. 28253.61	%Sft.	11584
21	Colour washing on walls 03-coats. (S.I.No:25(c), P-54)	551.00	@ Rs. 1303.17	%Sft.	7180
22	White washing three coats (S.I.No. 26 (C) Page No. 53).	615.00	@ Rs. 829.95	%Sft.	Rs. 5104
23	Primary Coat of chalk under distemper (S.I.No. 23 Page No. 53).	2084.00	@ Rs. 442.75	%Sft.	Rs. 9227
24	Painting new surface (c) Preparing surface and painting doors & windows any type i/c edges (S.I.No.50/P-69).	187.00	@ Rs. 2116.41	%Sft.	Rs. 3958
25	Distemper ng 3 coats (S.I.No. 24 Page No. 53).	2084.00	@ Rs. 1079.65	%Sft.	Rs. 22500
26	Two coats of bitumen laid hot using 34 lbs for %sft over roof and blind with sand (S.I.No.13 / P-34)	624.00	@ Rs. 1887.40	%Sft.	Rs. 11777

G.TOTAL RS: 791687

Sul: P.No.03.

[Signature]
 Executive Engineer
 Education Works Division
 Mirpurkhas



PART - B

WATER SUPPLY & SANITARY FITTING

Name of Work: GBPS Ali Bux Jarwar 4c Kherao Tol: Sindhri

S.#	DESCRIPTION	QUANTITY	RATE	UNIT	AMOUNT	
1	Providing and fixing squatting type white glazed earthen ware W.C. pan with front flush inlet and complete with including the cost of flushing cistern with internal fitting and flush pipe with bend and making requisite number of holes in walls, plinth & floor for pipe connection & making good in cement concrete 1:2:4 (B-II) W.C. of not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" dia earthen ware tap & plastic thumble.(S.I.No. 1(b)(ii)/page 1)	1	No.	@ 4802.60	Each	Rs. 4803
2	Providing RCC pipe with collars class-B and digging the trenches to required depth and fixing in position including cutting, fitting and jointing with maxphalt composition and cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of height pipe and refilling with excavated stuff.4" dia (S.I.No. 2/page 23) 6" dia	12	Rft	@ 199.25	P.Rft.	Rs. 2391
Total (Schedule Item)					Rs.	7194 /=-

**NON-SCHEDULE ITEMS**

19	Providing & Fixing Hand Pump with all accessories with 1 1/2" dia G.I pipe i.c boaring, fitting and fixing in position and making on c.c platform 1:2:4 with 4" dia G.I casing pipe 4' high above the ground level complete (Market rate).					
(a)	Coir Strainer 1 1/2" Dia	6.0	Rft	@ 100.00	Rft	Rs. 600
(b)	Boaring 1 1-1/4" dia	30.0	Rft	@ 76.00	Rft	Rs. 2280
(c)	Hand Pump	1	No.	@ 6000.00	Each	Rs. 6000
Total (Non Schedule Item)					Rs.	8880 /=-

B.M.
Executive Engineer
Education Works Division
Mirpurkhas

(BoQs) SCHEDULE "B" NIT: Sr. No: 05

NAME OF WORK: Const. of Water Tank at village Asif Brohi
 Dch. Behro up. Araro. Bhingwari. Pals. Samaro.



S. No	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
1	Excavation for Tanks and reservoirs in soft soils i/c trimming and dressing des to true alignment/desingn section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain. (PHSI No. 01 Page - 67). 4884.00		@ Rs. 3000.00	%0Cft.	Rs. 14652
2	Excavation for Tanks and reservoirs in wet soil clay or mad i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where' ever required lift upto 5 leetand lead upto one chain. (PHSI No. 14 Page - 74). 1711.00		@ Rs. 4800.00	%0Cft.	Rs. 8213
3	Excavation for Tanks and reservoirs in sulshy or daldally soil i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain. (PHSI No. 15 Page - 74). 726.94		@ Rs. 7200.00	%0Cft.	Rs. 5234
4	Dressing slops of banks or ground surface. (S.I.No. 24 Page No.5). 1049.54		@ Rs. 1577.40	%Sft.	Rs. 16555
5	Excavation in foundation of building, bridges and others structure i/c degbelling dressing refilling around struc ure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 4). 579.00		@ Rs. 3176.25	%0Cft.	Rs. 1839
6	Cement Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:4:8 (S.I.No 4 (c) Page No. 14). 378.51		@ Rs. 9416.28	%Cft.	Rs. 35642
7	Cement Concret Plain including placing compcting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering Ratio 1:3:6 (S.I.No.5 (h) Page 15). Ratio 1:3:6 609.59		@ Rs. 12595.00	%Cft.	Rs. 76778
8	Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 20). 361.88		@ Rs. 11948.36	%Cft.	Rs. 43238
9	Brick lining (9" x 4 1/2" x 3") in 1:3 cement sand mortar. (S.I.No. 9 / P - 74). "A" Slop 376.32		@ Rs. 14204.44	%Cft.	Rs. 53454
	"B" Tank Bed 33.20		@ Rs. 13765.81	%Cft.	Rs. 4571

Cont: Page-02

Executive Engineer
 Education Works Division
 Mirpurkhas




10	Pacca brick work in other than building in ratio 1 : 6 (S.I.No.7/Page 25).	268.88	@ Rs. 12346.65	%Cft.	Rs. 33197
11	Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 58).	1294.82	@ Rs. 2206.60	%Sft.	Rs. 28571
12	Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 58).	1294.82	@ Rs. 2197.52	%Sft.	Rs. 28454
13	Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-58).	607.5	@ Rs. 1287.44	%Sft.	Rs. 7821
14	Damp proof pounce with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture 3"thick (S.I.No.23 (c) Page No.18).	123.38	@ Rs. 4982.18	%Sft.	Rs. 6147
15	Providing and fixing iron steel grill door with iron frame of 1-1/2"x1-1/2" x 1/4" and flate iron of 3/4"x1/4" with approved design and locking arrangement (S.I.No.31/ Page No.93).	16	@ Rs. 231.60	P.Sft.	Rs. 3706
16	Colour washing on walls 02-coats. (S.I.NO;25/p-54)	1572.55	@ Rs. 859.90	%Sft.	13522
17	Preparing surface and painting guard bars, gates of iron bars, gratings, railings (i/c standards braces, etc) and similar open work any type 02-coats. (S.I.No:05(d) P-70)	32.00	@ Rs. 1270.83	%Sft.	407
SCHEDULE ITEMS RS:					382001
18	Providing and cutting polypipe complete i/c cutting the trenches upto required depth, refilling remming etc complete 200psi 1" dia (F:A)	40.00	@ Rs. 20.00	P.Rft.	Rs. 800
19	Providing and fixing hand pump with all accessories 4" dia with fitting and fixing i/c labour etc complete (Market Rat	1.00	@ Rs. 6000.00	No.	Rs. 6000

NON-SCHEDULE ITEMS RS:	6800
-------------------------------	-------------

SCHEDULE ITEMS RS:	382001
---------------------------	---------------

G.TOTAL RS:	388801
--------------------	---------------


 Executive Engineer
 Education Works Division
 Mirpurkhas

(BoQs)

SCHEDULE "B"

NIT: Sr: No: 06

NAME OF WORK: Const. of Water Tonic Village Canal
Ali-leghari Deh-356 Ahori Palsghudh



S. No	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
1	Excavation for Tanks and reservoirs in soft soils i/c trimming and dressing des to true alignment/desingn section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain. (PHSI No. 01 Page - 67). 4884.00		@ Rs. 3000.00	%Cft.	Rs. 14652
2	Excavation for Tanks and reservoirs in wet soil clay or mad i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one-chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain. (PHSI No. 14 Page - 74). 1711.00		@ Rs. 4800.00	%Cft.	Rs. 8213
3	Excavation for Tanks and reservoirs in sulshy or daldally soil i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain. (PHSI No. 15 Page - 74). 726.94		@ Rs. 7200.00	%Cft.	Rs. 5234
4	Dressng slops of banks or ground surface. (S.I.No. 24 Page No.5). 1049.54		@ Rs. 1577.40	%Sft.	Rs. 16555
5	Excavation in foundation of building, bridges and others structure i/c degbelling dressing refilling around structu e with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 4). 579.00		@ Rs. 3176.25	%Cft.	Rs. 1839
6	Cement Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:4:8 (S.I.No 4 (c) Page No. 14). 378.51		@ Rs. 9416.28	%Cft.	Rs. 35642
7	Cement Concret Plain including placing compcting, finishing and curing, complete (including screening and wast ing of stone aggregate without shuttering Ratio 1:3:6 (S.I.No.5 (h) Page 15). Ratio 1:3:6 609.59		@ Rs. 12595.00	%Cft.	Rs. 76778
8	Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 20). 361.88		@ Rs. 11948.36	%Cft.	Rs. 43238
9	Brick lining (9" x 4 ^{1/2} " x 3") in 1:3 cement sand mortar. (S.I.No. 9 / P - 74). "A" Slop 376.32		@ Rs. 14204.44	%Cft.	Rs. 53454
	"B" Tank Bed 33.20		@ Rs. 13765.81	%Cft.	Rs. 4571

cont: P-2

Executive Engineer
Education Works Division
Mirpurkhas



10	Pacca brick work in other than building in ratio 1 : 6 (S.I.No.7/Page 25).	268.88	@ Rs. 12346.65	%Cft.	Rs. 33197
11	Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 58).	1294.82	@ Rs. 2206.60	%Sft.	Rs. 28571
12	Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 58).	1294.82	@ Rs. 2197.52	%Sft.	Rs. 28454
13	Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-58).	607.5	@ Rs. 1287.44	%Sft.	Rs. 7821
14	Damp proof pource with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture 3"thick (S.I.No.28 (c) Page No.18).	123.38	@ Rs. 4982.18	%Sft.	Rs. 6147
15	Providing and fixing iron steel grill door with iron frame of 1-1/2"x1-1/2" x 1/4" and flate iron of 3/4"x1/4" with approved design and locking arrangement (S.I.No.31/ Page No.93).	16	@ Rs. 231.60	P.Sft.	Rs. 3706
16	Colour wa shing on walls 02-coats. (S.I.NO;25/p-54)	1572.55	@ Rs. 859.90	%Sft.	13522
17	Preparing surface and painting guard bars, gates of iron bars, gratings, railings (i/c standards braces, etc) and similar open work any type 02-coats. (S.I.No:05(d) P-70)	32.00	@ Rs. 1270.83	%Sft.	407
18	Providing and cutting polypipe complete i/c cutting the trenches upto required depth, refilling remming etc complete 200psi 1" dia (RA)	40.00	@ Rs. 20.00	P.Rft.	Rs. 800
19	Providing and fixing hand pump with all accessories 4" dia with fitting and fixing i/c labour etc complete (Market Rat	1.00	@ Rs. 6000.00	No.	Rs. 6000

SCHEDUEL ITEMS RS: 382001.

NON-SCHEDULE ITEMS RS:	6800
SCHEDULE ITEMS RS:	382001
G.TOTAL RS:	388801

Executive Engineer
Education Works Division
Mumbai

(BoQs) SCHEDULE "B" NIT: Sr: No: 07

NAME OF WORK: Const. of Water Tanks at village Mohammad Khan Buledi, Deh - Juhar up F. Bhambra P. S. Jhuda



S. No	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
1	Excavation for Tanks and reservoirs in soft soils i/c trimming and dressing des to true alignment/desingn section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 01 Page - 67).	4884.00	@ Rs. 3000.00	%0Cft.	Rs. 14652
2	Excavation for Tanks and reservoirs in wet soil clay or mad i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 14 Page - 74).	1711.00	@ Rs. 4800.00	%0Cft.	Rs. 8213
3	Excavation for Tanks and reservoirs in sulshy or daldally soil i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 15 Page - 74).	726.94	@ Rs. 7200.00	%0Cft.	Rs. 5234
4	Dressing slops of banks or ground surface .(S.I.No. 24 Page No.5).	1049.54	@ Rs. 1577.40	%Sft.	Rs. 16555
5	Excava ion in foundation of building, bridges and others structure i/c degbellng dressing refilling around structure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 4).	579.00	@ Rs. 3176.25	%0Cft.	Rs. 1839
6	Cement Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:4:8 (S.I.No 4 (c) Page No. 14).	378.51	@ Rs. 9416.28	%Cft.	Rs. 35642
7	Cement Coñcret Plain including placing compcting, finishing and curing, complete (including screening and wash ng of ñtone aggregate without shuttering Ratio 1:3:6 (S.I.No.5 (h) Page 15).	609.59	@ Rs. 12595.00	%Cft.	Rs. 76778
8	Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 20).	361.88	@ Rs. 11948.36	%Cft.	Rs. 43238
9	Brick lining (9" x 4 1/2" x 3") in 1:3 cement sand mortar.(S.I.No. 9 / P - 74).				
"A"	<u>Slop</u>	376.32	@ Rs. 14204.44	%Cft.	Rs. 53454
"B"	<u>Tank Bed</u>	33.20	@ Rs. 13765.81	%Cft.	Rs. 4571

Contd - P - No. 02

Executive Engineer
 Education Works Division



10	Pacca brick work in other than building in ratio 1 : 6 (S.I.No.7/Page 25).	268.88	@ Rs. 12346.65	%Cft.	Rs. 33197
11	Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 58).	1294.82	@ Rs. 2206.60	%Sft.	Rs. 28571
12	Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 58).	1294.82	@ Rs. 2197.52	%Sft.	Rs. 28454
13	Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-58).	607.5	@ Rs. 1287.44	%Sft.	Rs. 7821
14	Damp proof pource with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture 3"thick (S.I.No.28 (c) Page No.18).	123.38	@ Rs. 4982.18	%Sft.	Rs. 6147
15	Providing and fixing iron steel grill door with iron frame of 1-1/2"x1-1/2" x 1/4" and flate iron of 3/4"x1/4" with approved design and locking arrangement (S.I.No.31/ Page No.93).	16	@ Rs. 231.60	P.Sft.	Rs. 3706
16	Colour washing on walls 02-coats. (S.I.NO;25/p-54)	1572.55	@ Rs. 859.90	%Sft.	13522
17	Preparing surface and painting guard bars, gates of iron bars, gratings, railings (i/c standards braces, etc) and similar open work any type 02-coats. (S.I.No:05(d) P-70)	32.00	@ Rs. 1270.83	%Sft.	407
SCHEDULE ITEMS RS: 382001.					
18	Providing and cutting polypipe complete i/c cutting the trenches upto required depth, refilling remming etc complete 200psi 1" dia (RA)	40.00	@ Rs. 20.00	P.Rft.	Rs. 800
19	Providing and fixing hand pump with all accessories 4" dia with fitting and fixing i/c labour etc complete (Market Rat	1.00	@ Rs. 6000.00	No.	Rs. 6000

NON-SCHEDULE ITEMS RS:	6800
SCHEDULE ITEMS RS:	382001
G.TOTAL RS:	388801


 Executive Engineer
 Education Works Division
 Mirpurkhas


(BoQs) SCHEDULE "B" NIT: Sr: No: 08

NAME OF WORK: Const: of Water Tank Village Allah
Bachayan Dars up Roshanabad P.O. Jhuda



S. No.	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
1	Excavation for Tanks and reservoirs in soft soils i/c trimming and dressing des to true alignment/desingn section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 01 Page - 67).	4884.00	@ Rs. 3000.00	%0Cft.	Rs. 14652
2	Excavation for Tanks and reservoirs in wet soil clay or mad i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 14 Page - 74).	1711.00	@ Rs. 4800.00	%0Cft.	Rs. 8213
3	Excavation for Tanks and reservoirs in sulshy or daldally soil i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 15 Page - 74).	726.94	@ Rs. 7200.00	%0Cft.	Rs. 5234
4	Dressing slops of banks or ground surface .(S.I.No. 24 Page No.5).	1049.54	@ Rs. 1577.40	%Sft.	Rs. 16555
5	Excavation in foundation of building, bridges and others structure i/c degbelling dressing refilling around structure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 4).	579.00	@ Rs. 3176.25	%0Cft.	Rs. 1839
6	Cement Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:4:8 (S.I.No 4 (c) Page No. 14).	378.51	@ Rs. 9416.28	%Cft.	Rs. 35642
7	Cement Concret Plain including placing compcting, finishing and curing, complete (including screening and wast ing of stone aggregate without shuttering Ratio 1:3:6 (S.I.No.5 (h) Page 15).	609.59	@ Rs. 12595.00	%Cft.	Rs. 76778
8	Pacca brck work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 20).	361.88	@ Rs. 11948.36	%Cft.	Rs. 43238
9	Brick lining (9" x 4 1/2" x 3") in 1:3 cement sand mortar.(S.I.No. 9 / P - 74).	"A" 376.32	@ Rs. 14204.44	%Cft.	Rs. 53454
	Tank Bed	"B" 33.20	@ Rs. 13765.81	%Cft.	Rs. 4571

cont: P-02



 Executive Engineer
 Education Works Division
 Mirpurkhas

10	Pacca brick work in other than building in ratio 1 : 6 (S.I.No.7/Page 25).	268.88	@ Rs. 12346.65	%Cft.	Rs. 33197
11	Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 58).	1294.82	@ Rs. 2206.60	%Sft.	Rs. 28571
12	Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 58).	1294.82	@ Rs. 2197.52	%Sft.	Rs. 28454
13	Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-58).	607.5	@ Rs. 1287.44	%Sft.	Rs. 7821
14	Damp proof pource with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture 3"thick (S.I.No.28 (c) Page No.18).	123.38	@ Rs. 4982.18	%Sft.	Rs. 6147
15	Providing and fixing iron steel grill door with iron frame of 1-1/2"x1-1/2" x 1/4" and flate iron of 3/4"x1/4" with approved design and locking arrangement (S.I.No.31/ Page No.93).	16	@ Rs. 231.60	P.Sft.	Rs. 3706
16	Colour washing on walls 02-coats. (S.I.NO;25/p-54)	1572.55	@ Rs. 859.90	%Sft.	13522
17	Preparing surface and painting guard bars, gates of iron bars, gratings, railings (i/c standards braces, etc) and similar open work any type 02-coats. (S.I.No:05(d) P-70)	32.00	@ Rs. 1270.83	%Sft.	407
SCHEDULE ITEMS RS:					382001
18	Providing and cutting polypipe complete i/c cutting the trenches upto required depth, refilling remming etc complete 200psi 1" dia (RA)	40.00	@ Rs. 20.00	P.Rft.	Rs. 800
19	Providing and fixing hand pump with all accessories 4" dia with fitting and fixing i/c labour etc complete (Market Rat	1.00	@ Rs. 6000.00	No.	Rs. 6000

NON-SCHEDULE ITEMS RS:	6800
------------------------	------

SCHEDULE ITEMS RS:	382001
--------------------	--------

G.TOTAL RS:	388801
-------------	--------


 Executive Engineer
 Education Works Division
 Mirpurkhas



(BoQs)

SCHEDULE "B"

NIT: Sr: No: 09

NAME OF WORK: SnsH: J. Water Fonic Village Malik
Khoshi-Mahammad Dew-168 P.P. Digr

S. No	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
-------	-------------	-----	------	------	--------

1 Excavation for Tanks and reservoirs in soft soils i/c trimming and dressing des to true alignment/desingn section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 01 Page - 67).
4884.00 @ Rs. 3000.00 %0Cft. Rs. 14652

2 Excavation for Tanks and reservoirs in wet soil clay or mad i/c trimming and dressing des to true alignment/ des gn section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one-chain as directed by engineer incharge i/c providing fence guards lights flags where' ever required lift upto 5 leetand lead upto one chain.(PHSI No. 14 Page - 74).
1711.00 @ Rs. 4800.00 %0Cft. Rs. 8213

3 Excavation for Tanks and reservoirs in sulshy or daldally soil i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 15 Page - 74).
726.94 @ Rs. 7200.00 %0Cft. Rs. 5234

4 Dressing slops of banks or ground surface .(S.I.No. 24 Page No.5).
1049.54 @ Rs. 1577.40 %Sft. Rs. 16555

5 Excavation in foundation of building, bridges and others structure i/c degbellling dressing refilling around structure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 4).
579.00 @ Rs. 3176.25 %0Cft. Rs. 1839

6 Cemen Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:4:8 (S.I.No 4 (c) Page No. 14).
378.51 @ Rs. 9416.28 %Cft. Rs. 35642

7 Cement Concret Plain including placing compcting, finishing and curing, complete (including screening and was ring of stone aggregate without shuttering Ratio 1:3:6 (S.I.No.5 (h) Page 15).
Ratio 1:3:6
609.59 @ Rs. 12595.00 %Cft. Rs. 76778

8 Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 20).
361.88 @ Rs. 11948.36 %Cft. Rs. 43238

9 Brick linir g (9" x 4^{1/2}" x 3") in 1:3 cement sand mortar.(S.I.No. 9 / P - 74).
"A" Slop
376.32 @ Rs. 14204.44 %Cft. Rs. 53454

"B" Tank Bed
33.20 @ Rs. 13765.81 %Cft. Rs. 4571

Cont: P-2


Executive Engineer
Education Works Division




10	Pacca brick work in other than building in ratio 1 : 6 (S.I.No.7/Page 25).	268.88	@ Rs. 12346.65	%Cft.	Rs. 33197
11	Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 58).	1294.82	@ Rs. 2206.60	%Sft.	Rs. 28571
12	Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 58).	1294.82	@ Rs. 2197.52	%Sft.	Rs. 28454
13	Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-58).	607.5	@ Rs. 1287.44	%Sft.	Rs. 7821
14	Damp proof pource with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture 3"thick (S.I.No.28 (c) Page No.18).	123.38	@ Rs. 4982.18	%Sft.	Rs. 6147
15	Providing and fixing iron steel grill door with iron frame of 1-1/2"x1-1/2" x 1/4" and flate iron of 3/4"x1/4" with approved design and locking arrangement (S.I.No.31/ Page No.93).	16	@ Rs. 231.60	P.Sft.	Rs. 3706
16	Colour washing on walls 02-coats. (S.I.NO;25/p-54)	1572.55	@ Rs. 859.90	%Sft.	13522
17	Preparing surface and painting guard bars, gates of iron bars, gratings, railings (i/c standards braces, etc) and similar open work any type 02-coats. (S.I.No:05(d) P-70)	32.00	@ Rs. 1270.83	%Sft.	407
SCHEDULE ITEMS RS:					<u>382001.</u>
18	Providing and cutting polypipe complete i/c cutting the trenches upto required depth, refilling remming etc complete 200psi 1" dia (R/A)	40.00	@ Rs. 20.00	P.Rft.	Rs. 800
19	Providing and fixing hand pump with all accessories 4" dia with fitting and fixing i/c labour etc complete (Market Rat	1.00	@ Rs. 6000.00	No.	Rs. 6000

NON-SCHEDULE ITEMS RS:	6800
-------------------------------	-------------

SCHEDULE ITEMS RS:	382001
---------------------------	---------------

G.TOTAL RS:	388801
--------------------	---------------


Executive Engineer
Education Works Division
Mirpurkhas

(BoQs) SCHEDULE "B" NIT: Sr: No: 10

NAME OF WORK: Inst. of Water Tanks Village, Karim
Tangri, Dist-359 up to Raskanabad P.O. Jhuda



S. No	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
1	Excavation for Tanks and reservoirs in soft soils i/c trimming and dressing des to true alignment/desingn section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand leac upto one chain.(PHSI No. 01 Page - 67).				
	4884.00		@ Rs. 3000.00	%0Cft.	Rs. 14652
2	Excavation for Tanks and reservoirs in wet soil clay or mad i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one-chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 14 Page - 74).				
	1711.00		@ Rs. 4800.00	%0Cft.	Rs. 8213
3	Excavation for Tanks and reservoirs in sulshy or daldally soil i/c trimming and dressing des to true alignment/ design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and dispesal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain.(PHSI No. 15 Page - 74).				
	726.94		@ Rs. 7200.00	%0Cft.	Rs. 5234
4	Dressing slops of banks or ground surface (S.I.No. 24 Page No.5).				
	1049.54		@ Rs. 1577.40	%Sft.	Rs. 16555
5	Excavation in foundation of building, bridges and others structure i/c degbelling dressing refilling around structure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 4).				
	579.00		@ Rs. 3176.25	%0Cft.	Rs. 1839
6	Cement Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:4:8 (S.I.No 4 (c) Page No. 14).				
	378.51		@ Rs. 9416.28	%Cft.	Rs. 35642
7	Cement Concret Plain including placing compcting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering Ratio 1:3:6 (S.I.No.5(h) Page 15).				
	609.59		@ Rs. 12595.00	%Cft.	Rs. 76778
8	Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 20).				
	361.88		@ Rs. 11948.36	%Cft.	Rs. 43238
9	Brick lining (9" x 4 ^{1/2} " x 3") in 1:3 cement sand mortar.(S.I.No. 9 / P - 74).				
"A"	<u>Slop</u>				
	376.32		@ Rs. 14204.44	%Cft.	Rs. 53454
"B"	<u>Tank Bed</u>				
	33.20		@ Rs. 13765.81	%Cft.	Rs. 4571

Cont: P-02

[Signature]
 Executive Engineer
 Education Works Division
 Mirpurkhas



10	Pacca brick work in other than building in ratio 1 : 6 (S.I.No.7/Page 25).	268.88	@ Rs. 12346.65	%Cft.	Rs. 33197
11	Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 58).	1294.82	@ Rs. 2206.60	%Sft.	Rs. 28571
12	Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 58).	1294.82	@ Rs. 2197.52	%Sft.	Rs. 28454
13	Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-58).	607.5	@ Rs. 1287.44	%Sft.	Rs. 7821
14	Damp prc of pource with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture 3"thick (S.I.No.28 (c) Page No.18).	123.38	@ Rs. 4982.18	%Sft.	Rs. 6147
15	Providing and fixing iron steel grill door with iron frame of 1-1/2"x1-1/2" x 1/4" and flate iron of 3/4"x1/4" with apprved design and locking arrangement (S.I.No.31/ Page No.93).	16	@ Rs. 231.60	P.Sft.	Rs. 3706
16	Colour washing on walls 02-coats. (S.I.NO;25/p-54)	1572.55	@ Rs. 859.90	%Sft.	13522
17	Preparing surface and painting guard bars, gates of iron bars, gratings, railings (i/c standards braces, etc) and similar open work any type 02-coats. (S.I.No:05(d) P-70)	32.00	@ Rs. 1270.83	%Sft.	407
SCHEDULE ITEMS RS:					382001.
18	Providing and cutting polypipe complete i/c cutting the trenches upto required depth, refilling remming etc complete 200psi 1" d a (RA)	40.00	@ Rs. 20.00	P.Rft.	Rs. 800
19	Providing and fixing hand pump with all accessories 4" dia with fitting and fixing i/c labour etc complete (Market Rat	1.00	@ Rs. 6000.00	No.	Rs. 6000

NON-SCHEDULE ITEMS RS: 6800

SCHEDULE ITEMS RS: 382001

G.TOTAL RS: 388801

Executive Engineer
Education Works Division
Mirpurkhas

(BoQs) SCHEDULE "B" NIT: Sr: No: 11

NAME OF WORK: Smith of Water Tanks - Village - Jattan
Wala Deu - 19.5 up to Tando J. Mohomed Pal - Digori.

S. No.	DESCRIPTION	QTY	RATE	UNIT	AMOUNT
1	Excavation for Tanks and reservoirs in soft soils i/c trimming and dressing des to true alignment/design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and disposal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain. (PHSI No. 01 Page - 67).				
	4884.00		@ Rs. 3000.00 %0Cft.		Rs. 14652
2	Excavation for Tanks and reservoirs in wet soil clay or mad i/c trimming and dressing des to true alignment/design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and disposal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain. (PHSI No. 14 Page - 74).				
	1711.00		@ Rs. 4800.00 %0Cft.		Rs. 8213
3	Excavation for Tanks and reservoirs in sulshy or daldally soil i/c trimming and dressing des to true alignment/design section/profiles and shape leveling of beds of trenches to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and disposal of surplus excavation earth with in one chain as directed by engineer incharge i/c providing fence guards lights flags where ever required lift upto 5 leetand lead upto one chain. (PHSI No. 15 Page - 74).				
	726.94		@ Rs. 7200.00 %0Cft.		Rs. 5234
4	Dressing slops of banks or ground surface. (S.I.No. 24 Page No.5).				
	1049.54		@ Rs. 1577.40 %Sft.		Rs. 16555
5	Excavation in foundation of building, bridges and others structure i/c degbelling dressing refilling around structure with excavated earth watering and remaining up to lead 5 feet (b) in ordinary soil. (S.I.No. 18 b Page No. 4).				
	579.00		@ Rs. 3176.25 %0Cft.		Rs. 1839
6	Cement Concrere brick or stone ballast 1 1/2 to 2" gauge ratio 1:4:8 (S.I.No 4 (c) Page No. 14).				
	378.51		@ Rs. 9416.28 %Cft.		Rs. 35642
7	Cement Concret Plain including placing compcting, finishing and curing, complete (including screening and wasing of stone aggregate without shuttering Ratio 1:3:6 (S.I.No.5.(h) Page 15).				
	609.59		@ Rs. 12595.00 %Cft.		Rs. 76778
8	Pacca brick work in foundation & plinth in cement sand mortar ratio 1:6 (S.I.No. 4 (e) Page 20).				
	361.88		@ Rs. 11948.36 %Cft.		Rs. 43238
9	Brick linir g (9" x 4 ^{1/2} " x 3") in 1:3 cement sand mortar. (S.I.No. 9 / P - 74).				
"A"	<u>Slop</u>				
	376.32		@ Rs. 14204.44 %Cft.		Rs. 53454
"B"	<u>Tank Bed</u>				
	33.20		@ Rs. 13765.81 %Cft.		Rs. 4571

Snit - B - No: 02

Executive Engineer
 Education Works Division
 Mirpurkhas





10	Pacca brick work in other than building in ratio 1 : 6 (S.I.No.7/Page 25). 268.88	@ Rs. 12346.65 %Cft.	Rs. 33197
11	Cement Plaster 1/2" (1:6) upto 20 feet height (b) 1/2" thick (S.I.No 13 (b) Page No 58). 1294.82	@ Rs. 2206.60 %Sft.	Rs. 28571
12	Cement plaster 3/8" thick (1:4) upto 20 feet height (S.I.No 11 (c) Page No. 58). 1294.82	@ Rs. 2197.52 %Sft.	Rs. 28454
13	Cement pointing struck of joints on wall (a) (1:3) Ratio (S.I.No. 19 (a) Page-58). 607.5	@ Rs. 1287.44 %Sft.	Rs. 7821
14	Damp proof pource with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture 3"thick (S.I.No.28 (c) Page No.18). 123.38	@ Rs. 4982.18 %Sft.	Rs. 6147
15	Providing and fixing iron steel grill door with iron frame of 1-1/2"x1-1/2" x 1/4" and flate iron of 3/4"x1/4" with approved design and locking arrangement (S.I.No.31/ Page No.93). 16	@ Rs. 231.60 P.Sft.	Rs. 3706
16	Colour washing on walls 02-coats. (S.I.NO;25/p-54) 1572.55	@ Rs. 859.90 %Sft.	13522
17	Preparing surface and painting guard bars, gates of iron bars, gratings, railings (i/c standards braces, etc) and similar open work any type 02-coats. (S.I.No:05(d) P-70) 32.00	@ Rs. 1270.83 %Sft.	407
18	Providing and cutting polypipe complete i/c cutting the trenches upto required depth, refilling remming etc complete 200psi 1" d a (RA) 40.00	@ Rs. 20.00 P.Rft.	Rs. 800
19	Providing and fixing hand pump with all accessories 4" dia with fitting and fixing i/c labour etc complete (Market Rat 1.00	@ Rs. 6000.00 No.	Rs. 6000

SCHEDULED ITEMS RS:

382001

NON-SCHEDULED ITEMS RS:

6800

SCHEDULED ITEMS RS:

382001

G.TOTAL RS:

388801

Executive Engineer
Education Works Division
WALLMURKHAS

WORK - PLAN.

For N.I.T.No.519, dated 14-9-2015
NIT Sr.No. 01 to 11.

**WORK PALN FOR (ANNUAL DEVELOPMENT PROGRAMME) FOR
THE YEAR 2015-16 IN RESPECT OF EDUCATIN WORKS
DIVISION, MIRPURKHAS 0233-9290215.**

Cost Centre MS9397 Allocation 2015-16 Rs.7.200 (M).



S.#.	Name/Nature of work/Sub-Head.	Taluka.	Estimated Cost
01	02	03	04

**PAK-MILLENNIUM DEVELOPEMNT GORALS COMMUNITY
DEVELOPMENT PROGRAMME.**

Construction of One Class Room Exisitng Shelterless Primary
Schools in Taluka Digri & Kot Ghulam Mohammad District
Mirpurkhas-

1	GBPS Faiz Mohammad Dal Deh-351 u.c.Jawarisar.	K.G.M	925,000
2	GBPS Otaque Ahmed Khan Bhurgari u.c.Jawarisar.	K.G.M	925,000
3	GBPS Rozdar Khan Deh-257 u.c.Mir Imam Bux.	K.G.M	925,000



**Construction of One Class Room in Existing Shelterless
Primary Schools.**

4	at Village Ali Bux Jarwar u.c. Kherao.	Sindhri.	925,000
---	--	----------	---------

Construction of Water Tank @ Village:-

5	Asif Brohi Deh Senhro u.c.Araro Bhurghari.	Samaro	500,000
6	Liaquat Ali Laghari Deh-356 Ahori	Jhudo.	500,000
7	Mohammad Khan Buledi deh-Jinhar u.c.Faz'bro.	Jhudo.	500,000
8	Allah Bachayo Dars u.c.Roshanabad.	Jhudo.	500,000
9	Malik Khoshi Mohamad Deh-168 u.c.Puban.	Digri.	500,000
10	Karim Tangri Deh-359 u.c.Roshanabad.	Jhudo.	500,000
11	Jattan Wala Deh-195 u.c.Tando Jan Mohammad.	Digri.	500,000

Total:- **7,200,000**


 Executive Engineer
 Education Works Division
 Mirpurkhas


PROCUREMENT COMMITTEE



**GOVERNMENT OF SINDH
WORKS & SERVICES DEPARTMENT**

Karachi, dated the 30th July, 2013.

NOTIFICATION

No. E&A(W&S)3-9/91/2013: With the approval of competent authority, a Procurement Committee with the following composition, in terms of Rule-7 of Sindh Public Procurement Rules-2010, is hereby constituted for procurement of "Goods & Works" in the office of Executive Engineer, Education Works Division, Mirpurkhas, excluding procurement involving foreign exchange with the following composition:-

- | | | |
|------|---|------------|
| i) | Executive Engineer,
Education Works Division,
Mirpurkhas. | Chairman ✓ |
| ii) | District Officer,
Elementary Education,
Education & Literacy Department,
Mirpurkhas. | Member |
| iii) | Divisional Accounts Officer,
Education Works,
Mirpurkhas. | Member |

2. The Functions & Responsibilities of the Committee, in term of Rule-7 & 8 of SPPRA-2010, shall be as under:

- Preparing of bidding documents.
- Carrying out Technical as well as Financial Evaluation of the bids.
- Preparing Evaluation report as provided in Rule-45;
- Making recommendation for the award of contract to the competent authority; and
- Perform any other function ancillary and incidental to the above.

**QAZI SHAHID PERVEZ
SECRETARY TO GOVT. OF SINDH**

No. E&A(W&S)3-9/91-2013

Karachi dated the 30th July, 2013.

A copy is forwarded for information to:-

- The Accountant General, Sindh, Karachi.
- The Secretary to Govt. of Sindh, Education & Literacy Department, Karachi.
- The Managing Director, SPPRA, Karachi.
- The Chief Engineer (Buildings), Hyderabad.
- The Superintending Engineer, Works & Services, District Mirpurkhas.
- The Deputy Secretary (Tech) Works & Services Department.
- The Deputy Secretary (Admin) Works & Services Department.
- The Deputy Director, PM&E Cell, W&SD.
- PS to Secretary Works & Services Department.
- PA to Additional Secretary (Tech), Works & Services Department.
- ✓ 11. The Chairman / members of the Committee.
12. Notification file.

Muhammad Zakir

(MUHAMMAD ZAKIR)
SECTION OFFICER (GENERAL)
FOR SECRETARY TO GOVT. OF SINDH

12/4/13

T/c