

**SCHEDULE "B"**

NAME OF WORK

Construction of road from Dehi Tando Jan Mohammad at Point 57  
More to Jhudo with link to Village Haji Ibrahim Jat & Ghulam Mustifa  
Brohi Mile 8/0-9/0

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 1 Earth work for road embankment by Bulldozers, ploughing, mixing clod Breaking, dressing, compacting, with Optimum moisture content lead upto 100'ft & lift upto 5'ft in all types of soil except rock upto 85% density.

**"B" 85% Density**                      **184800 Cft @ RS 3656.23 P.% 0 Cft      RS: 675,671**  
(Rate Rs. Three thousand Six Hundred Fifty Six)  
(Paiza Twenty Three) only Per Thousand Cft)

- 2 Earth work for road embankment by Bulldozers including ploughing, mixing clod breaking, dressing, ramming etc complete. Lead upto 95-100% Modified AASHO specifications.

**"A" 95-100% Density**                      **500120 Cft @ RS 6190.17 P.% 0 Cft      RS: 3,095,828**  
(Rate Rs. Six Thousand One Hundred Ninety)  
(Paiza Seventy) only Per Thousand Cft)

- 3 Providing Sand cushion i.e supplying and spreading pit/canal sand of approved quality source of supply to site of work i/c watering & rolling etc complete, rate i/c all cost of materials T&P labour & carriage 3miles.

**38069 Cft @ RS 1479.41 P.% Cft      RS: 563,197**  
Rate Rs. One Thousand Four Hundred Seventy Nine  
(Paiza Forty One) only per hundred Cft )

- 4 Preparing Sub-Base Course by supplying & spreading the stone metal 1-1/2" to 2" guage of approved quality from Onger quarry required thickness of 6" in 2 layers to proper camber & graded i/c hand packing fitting voids with 20 Cft Pit/Canal Sand having plasticity index of not more than 6% of suitable quality watering and compacting to achieve 98- 00% density as per Modified AASHO specifications. Rate includes all costs of materials, labour, T&P and cartriage to site of work.

**65261 Cft @ RS 9773.63 P.% Cft      RS: 6,378,369**  
(Rate Rs. Nine Thousand Seven Hundred Seventy Three)  
(Paiza Sixty Three) only Per Hundred Cft)

- 5 Laying Brick on end edging including supply of 9"x4 1/2"x3" 1st class bricks excavation for laying edging with small side parallel to the road. Rate includes all costs of materials, labour & carriage the site of work.

**10877 Rft @ RS 2813.32 P.% Rft      RS: 306,005**  
(Rate Rs: Two Thousand Eight Hundred Thirteen)  
(Paiza Thirty Two) only per hundred RFT )

- 6 Preparing Base Course by supplying and spreading stone metal of approved quarry properly grade to maximum size of 1-1/2" in required thickness of 3" to proper camber & grade i/c supplying & spreading 15 Cft screening and non-plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering & compacting the same so as to achieve 100% density as per modified AASHO Specifications. This rate i/c providing & using templates, camber plates screen forms as directed Rate includes all costs of materials, T&P labour, carriage to site of work.

**43725 Cft @ RS 11123.44 P.% Cft      RS: 4,863,724**  
(Rate Rs. Eleven Thousand One Hundred Twenty Three)  
(Paiza Forty Four) only per hundred Cft)

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 7 Providing surface dressing (3rd Coat) on new or existing surface with 79Lbs of Bitumen of 80/100 penetration & 9.75Cft bajri of 1/2" to 3/4" guage i/c cleaning the road surface rolling after each coat separately rate i/c all cost of material & T&P & carriage to site of work.

65261 Sft @ RS 4287.36 P.% Sft RS: 2,797,974  
(Rate Rs: Four Thousand Two Hundred Eighty Seven)  
(Paisa Thirty Six) only.Per Hundred Sft)

- 8 Add Different cost of Bitumen 23.02 Ton @ RS 14242.00 P.Ton. (-) RS: 327,851

**Total RS: 18,352,917**

**Note**

- 01 Contractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Ter der.

**CONTRACTOR**

EXECUTIVE ENGINEER  
PROVINCIAL HIGHWAY DIVISION  
BADIN

**SCHEDULE "B" PART "B"****NAME OF WORK**

**Construction of 3' Span Culverts on Dehi Tando Jan Mohammad  
at Point 57 More to Jhudo with link to Village Haji Ibrahim Jat  
& Ghulam Mustifa Brohi Mile 8/0-9/0**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   |        |

- 1 Excavation in foundation of Building, Bridges & other structure i/c dag belling dressing refilling around the structure with excavated watering & ramming lead upto 1 chain & left upto 5ft (in ordinary

2407 Cft @ RS 3176.25 P.% 0 Cft RS: 7,645

- 2 Cement concrete Brick or stone ballast 1-<sup>1</sup>/<sub>2</sub>" to 2" guage Rastio 1:4:8.

250 Cft @ RS 9416.28 P.% Cft RS: 23,541

- 3 Pacca brick work in foundation and plinth in cement sand mortor Ratio 1:4.

537 Cft @ RS 12501.41 P.% Cft RS: 67,133

- 4 Cement concrete plain including Placing, compacting, Finishing & Curr ng complete including screening & washing stone aggregate without shuttring ration 1:2:4.

98 Cft @ RS 14429.25 P.% Cft RS: 14,141

- 5 Fabr cation of mild steel reinforcement for cement ckloncrete i/c cutting bending laying in position, making joints and fasdtening including cost binding wire (also inkluded removal of rust from

7.10 Cwt @ RS 4820.2 P. Cwt RS: 34,223

- 6 RCC work including all labour & materials sesxcept the cost of steel reinforcement & its labour for bending & binding which will be paid separately. This rate also includes all kinds of forms moulds, lifting, shuttering, curring & finishing the exposed surface including, screening & washing of shingle RCC work in roof slab, beams, coulms, rafts, lintles & other structural members laid in posit on complete in all respect, Ratio 1:2:4..

92 Cft @ RS 337.00 P. Cft RS: 31,004

- 7 Errection & removal of centering for RCC or CC plain (b) vertical partial wood .

100 Sft @ RS 3127.41 P.% Sft RS: 3,127

- 8 Ceme it Plaster 1:3 upto 20' height 1/2" thick.

306 Sft @ RS 2344.59 P.% Sft RS: 7,174

**Total RS: 187,988**

Note

|   |      |         |
|---|------|---------|
| 4 | Nos: | 751,954 |
|---|------|---------|

- 01 Contractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

CONTRACTOR

EXECUTIVE ENGINEER  
PROVINCIAL HIGHWAY DIVISION  
BADIN

**SCHEDULE "B"**

**NAME OF WORK: Improvement of road from Dhadhar road from Bhaddo Kolhi to Village Dr. Ashraf Bhugri road mile 0/0-2/0.**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 1 Making diagonal grooves of 1 1/2 x 1 1/2 @ 2 ft in road surface.

63360 Sft @ RS 146.41 P.% Sft RS: 92,765  
(Rate Rs. One Hundred Forty Six)  
(Paissa Forty One) only Per Hundred Sft)

- 2 Laying Brick on end edging includidng suspply of 9"x4 1/2"x3"1st class bricks excavation for laying edging with small side parallel to the road. Rate includesall costs of materials, labour & carriage the site of work

21754 Rft @ RS 2761.22 P.% Rft RS: 600,676  
(Rate Rs: Two Thousand Seven Hundred Sixty One)  
(Paissa Twenty Two) only per hundred Rft)

- 3 Preparing Base Course by supplying and spreading stone metal of approved quarry properly grade to maximum size of 1-1/2" in required thickness of 3" to proper camber & grade i/c supplying & spreading 15 Cft screening and non-plastic quarry fines, filling depressions with store metal after initial rolling i/c watering & compacting the same so as to achieve 100% density as per modified AASHO Specifications. This ratre i/cs providing & using templates, camber plates screen forms as directed Rate includes all costs of materials, T&P labour, carriage to site of work.

65261 Cft @ RS 9677.77 P.% Cft RS: 6,315,809  
(Rate Rs: Nine Thosand Seven Hundred Seventy Seven)  
(Paissa Seventy Seven) only per hundred Cft)

- 4 Providing surface dressing (1st Coat) on new or existing surfasce with 30Lbs of Eitumen of 80/100 penetration & 4Cft bajri of 1/2" to 3/4" guage i/c clearing the road surface rolling after each coat separatelly rate i/c all cost of material & T&P & carriage to site of work.

130522 Sft @ RS 1649.94 P.% Sft RS: 2,153,535  
(Rate Rs: One Thousand Six Hundred Forty Nine)  
(Paissa Ninety Four) only. Per Hundred Sft)

- 5 Providing 1-1/2" thick (Consolideted) premix carpet in proper camber & grade i/c supply of 15 Cft Bajri & 5 Cft Hill Sand of approved qual ty & guage 93 Lbs Bitumen of 80/100 penetration i/c mixing in machinical mixer in required propotion including heating the matterial & cleaning the road surface. (Rate includes cost of materials T&P & carriage up to site of work.

130522 Sft @ RS 6388.39 P.% Sft RS: 8,338,254  
(Rate Rs: Six Thousand Three Hundred Eighty Eight)  
(Paissa Thirty Nine) only Per Hundred Sft)

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 6 Earth work for road embankment by Buildozers, ploughing, mixing clod Breaking, dressing, compacting, with Optimum moisture content lead upto 100'ft & lift upto 5'ft in all types of soil except rock upto 85% density.

672642 Cft @ RS 3656.23 P.% 0 Cft RS: 2,459,334  
 (Rate Rs: Three Thousand Six Hundred Fifty Six)  
 (Paisa Twenty Three) only Per Thousand Cft)

- 7 Add Different cost of Bitumen 71.67 Ton @ RS 14242.00 P.Ton. (-) RS: 1,020,724

**Total RS: 18,939,649**

**Note**

- 01 Contractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

CONTRACTOR

EXECUTIVE ENGINEER  
 PROVINCIAL HIGHWAY DIVISION  
 BADIN

**SCHEDULE "B" PART "B"**

**NAME OF WORK: Improvement of road from Dhadhar road from Bhaddo Kolhi to Village  
Dr. Ashraf Bhugri road mile 0/0-2/0.**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   |        |

- 1 Dismantling cement concrete reinforcement separating reinforcement from concrete cleaning & straightening the same RCC work.

116 Cft @ RS 5445.00 P.% Cft RS: 6,316

- 2 Cement concrete plain including Placing, compacting, Finishing & Curring complete including screening & washing stone aggregate without shuttering ration 1:2:4.

83 Cft @ RS 14429.25 P.% Cft RS: 11,976

- 3 Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position, making joints and fastening including cost binding wire (also included removal of rust from bars)

5.80 Cwt @ RS 4820.2 P. Cwt RS: 27,957

- 4 RCC work including all labour & materials except the cost of steel reinforcement & its labour for bending & binding which will be paid separately. This rate also includes all kinds of forms moulds, lifting, shuttering, curring & finishing the exposed surface including screening & washing of shingle RCC work in roof slab, beams, coulmns,rafts,lintles & other structural members laid in position complete in all respect, Ratio 1:2:4..

92 Cft @ RS 337.00 P. Cft RS: 31,004

- 5 Brick on Edging flooring laid in 1:6 cement mortar over a bed of 3/4" thick cement mortar.

77 Sft @ RS 5256.63 P.% Sft RS: 4,048

- 6 Errection & removal of centering for RCC or CC plain (b) vertical partial wood.

149 Sft @ RS 3127.41 P.% Sft RS: 4,660

- 7 Cement Plaster 1:3 upto 20' height 1/2" thick.


307 Sft @ RS 2344.29 P.% Sft RS: 7,197

**Total RS: 93,158**

**Note**

- 01 Contractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

**CONTRACTOR**

  
**EXECUTIVE ENGINEER  
PROVINCIAL HIGHWAY DIVISION  
BADIN**

**SCHEDULE "B"****NAME OF WORK: Reconditioning of road from Talhar-Rajo Khanani mile 0/0-2/4.**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 1 Preparing Base Course by supplying and spreading stone metal of approved quarry properly grade to maximum size of 1-1/2" in required thickness of 3" to proper camber & grade i/c supplying & spreading 15 Cft screening and non-plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering & compacting the same so as to achieve 100% density as per modified AASHO Specifications. This rate i/c providing & using templates, camber plates, screen forms as directed. Rate includes all costs of materials, T&P labour, carriage to site of work.

**8910 Cft @ RS 9774.15 P.% Cft RS: 870,877**  
 (Rate Rs: Nine Thousand Seven Hundred Seventy Four)  
 (Paiza Fifteen) only per hundred Cft )

- 2 Providing Two Coats surface dressing on new or existing surface with 30+25=55Lbs of Bitumen of 80/100 penetration & 4+2.75=6.75 Cft bajri of 3/8" to 1/2" gauge i/c cleaning the road surface rolling after each coat separately rate i/c all cost of material & T&P & carriage to site of work.

**118800 Sft @ RS 2957.24 P.% Sft RS: 3,513,201**  
 (Rate Rs: Two Thousand Nine Hundred Fifty Seven)  
 (Paiza Twenty Four) only. Per Thousand Cft)

- 3 Laying to proper line and grade mixed Asphalt concrete paver finished hydrolic/electric control prepared to specified formula according approved by Engineer incharge i/c rolling and finishing to proper line grade level camber etc complete. Rate i/c take

**244728 Sft @ RS 9101.33 P.% Sft RS: 22,273,503**  
 (Rate Rs: Nine Thousand One Hundred Zero One)  
 (Paiza Thirty Three) only. Per Hundred Sft)

- 4 Earth work for road embankment by Bulldozers, ploughing, mixing, clod Breaking, dressing, compacting, with Optimum moisture content lead upto 100'ft & lift upto 5'ft in all types of soil except rock upto 85% density.

**813934 Cft @ RS 3656.23 P.% 0 Cft RS: 2,975,930**  
 (Rate Rs: Three Thousand Six Hundred Fifty Six)  
 (Paiza Twenty Three) only. Per Thousand Cft)

- 5 Add Different cost of Bitumen **157.31 Ton @ RS 14242.00 P.Ton. (-) RS: 2,240,409**

**Total RS: 27,393,102**

**Note**

- 02 Contractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

CONTRACTOR

EXECUTIVE ENGINEER  
 PROVINCIAL HIGHWAY DIVISION  
 BADIN



**SCHEDULE "B" PART "B"**


**NAME OF WORK: Reconditioning of road from Talhar-Rajo Khanani mile 0/0-2/4.  
(03 Nos: Culverts)**

| S. #  | Item of Work  | Quantity | Rate          | Unit    | Amount     |
|-------|---|----------|---------------|---------|------------|
| 01    | 02  | 03       | 04            | 05      |            |
| 1     | Dismantling cement concrete reinforcement separating reinforcement from concrete cleaning & straightening the same RCC work.  | 96 Cft   | @ RS 5445.00  | P.% Cft | RS: 5,227  |
| 2     | Cement concrete plain including Placing, compacting, Finishing & Curring complete including screening & washing stone aggregate without shuttering ration 1:2:4.  | 83 Cft   | @ RS 14429.25 | P.% Cft | RS: 11,976 |
| 3     | Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position, making joints and fastening including cost binding wire (also included removal of rust from   | 5.80 Cwt | @ RS 4820.2   | P. Cwt  | RS: 27,957 |
| 4     | RCC work including all labour & materials except the cost of steel reinforcement & its labour for bending & binding which will be paid separately. This rate also includes all kinds of forms moulds, lifting, shuttering, curring & finishing the exposed surface including screening & washing of shingle RCC work in roof slab, beams, columns, rafts, lintels & other structural members laid in position complete in all respect, Ratio 1:2:4. | 92 Cft   | @ RS 337.00   | P. Cft  | RS: 31,004 |
| 5     | Brick on Edging flooring laid in 1:6 cement mortar over a bed of 3/4" thick cement mortar.  | 77 Sft   | @ RS 5256.63  | P.% Sft | RS: 4,048  |
| 6     | Erection & removal of centering for RCC or CC plain (b) vertical partial wood.  | 149 Sft  | @ RS 3127.41  | P.% Sft | RS: 4,660  |
| 7     | Cement Plaster 1:3 upto 20ft Height 1/2" thick.   | 307 Sft  | @ RS 2344.29  | P.% Sft | RS: 7,197  |
| TOTAL |   |          |               |         | 92,069     |

**Note**

- 01 Contractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

**CONTRACTOR**

  
**EXECUTIVE ENGINEER  
PROVINCIAL HIGHWAY DIVISION  
BADIN**



**SCHEDULE "B" PART "B"**

**NAME OF WORK: Const: of road from Army Farm Otaq of Kazi Aijaz road to Village  
Ali Nawaz Dars UC Dei Jarkas mile 3/0-4/0.**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   |        |

- 1 Excavation in foundation of Building, Bridges & other structure i/c  
dag belling dressing refilling around the structure with excavated  
watering & ramming lead upto 1 chain & left upto 5ft (in ordinary

1900 Cft @ RS 3176.25 P.% 0 Cft RS: 6,035

- 2 Cement concrete Brick or stone ballast 1-<sup>1</sup>/<sub>2</sub>" to 2" guage Rastio 1:4:8.

254 Cft @ RS 9416.28 P.% Cft RS: 23,917

- 3 Pacca brick work in foundation and plinth in cement sand mortor  
Ratio 1:4.

537 Cft @ RS 12501.41 P.% Cft RS: 67,133

- 4 Cement concrete plain including Placing, compacting, Finishing &  
Cu ring complete including screening & washing stone aggregate  
without shuttring ration 1:2:4.

97 Cft @ RS 14429.25 P.% Cft RS: 13,996

- 5 Fabrication of mild steel reinforcement for cement ckloncrete i/c  
cutting bending laying in position, making joints and fasdtening  
including cost binding wire (also inkluded removal of rust from bars)

6.79 Cwt @ RS 4820.20 P. Cwt RS: 32,729

- 6 RCC work including all labour & materials sesxcept the cost of steel  
reinforcement & its labour for bending & binding which will be paid  
separately. This rate also inclludes all kinds of forms moulds, lifting,  
shuttering, curring & finishing the exposed surface  
including, screening & washing of shingle RCC work in roof  
slab, beams, coulms, rafts, lintles & other structural members laid in  
position complete in all respect, Ratio 1:2:4..

92 Cft @ RS 337.00 P. Cft RS: 31,004

- 7 Errection & removal of centering for RCC or CC plain (b) vertical partal  
wood.

101 Sft @ RS 3127.41 P.% Sft RS: 3,159

- 8 Cement Plaster 1:3 upto 20' height 1/2" thick.

306 Sft @ RS 2344.59 P.% Sft RS: 7,174

**Total RS: 185,147**

|                                      |
|--------------------------------------|
| <b>3 Nos: Culverts = RS: 555,442</b> |
|--------------------------------------|

**Note**

- 01 Contractor & Department are abide by the condition of sanction estimate,  
Items of work, Quantity, Rate & Premium as per Technical Sanctioned  
accorded by the competent authority in case of any variation in Schedule "B" of  
Tender.

**CONTRACTOR**

  
**EXECUTIVE ENGINEER**  
**PROVINCIAL HIGHWAY DIVISION**  
**BADIN**

**SCHEDULE "B"**

**NAME OF WORK: Renovation / Reconditioning of road from Village Rasheed Arain, Taluka Tando Bago Jhudo mile 0/0-1/7.**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 1 Laying Brick on end edging including supply of 9"x4 1/2"x3" Ist class bricks excavation for laying edging with small side parallel to the road. Rate includes all costs of materials, labour & carriage to the site of work

**20394 Rft @ RS 2813.32 P.% Rft RS: 573,748**

(Rate Rs: Two Thousand Eight Hundred Thirteen)  
(Paissa Thirty Two) only per hundred Rft)

- 3 Preparing Base Course by supplying and spreading stone metal of approved quarry properly grade to maximum size of 1-1/2" in required thickness of 3" to proper camber & grade i/c supplying & spreading 15 Cft screening and non-plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering & compacting the same so as to achieve 100% density as per modified AASHO Specifications. This rate i/c providing & using templates, camber plates, screen forms as directed. Rate includes all costs of materials, T&P labour, carriage to site of work.

**70686 Cft @ RS 11123.44 P.% Cft RS: 7,862,715**

(Rate Rs: Eleven Thousand One Hundred Twenty Three)  
(Paissa Forty Four) only per hundred Cft)

- 4 Providing surface dressing (1st Coat) on new or existing surface with 30Lbs of Bitumen of 80/100 penetration & 4Cft bajri of 1/2" to 3/4" gauge i/c cleaning the road surface rolling after each coat separately rate i/c all cost of material & T&P & carriage to site of work.

**122364 Sft @ RS 1689.67 P.% Sft RS: 2,067,548**

(Rate Rs: One Thousand Six Hundred Eighty Nine)  
(Paissa Sixty Seven) only Per Hundred Sft)

- 5 Providing 1" thick (Consolidated) premix carpet in proper camber & grade i/c supply of 10 Cft Bajri & 4 Cft Hill Sand of approved quality & gauge 67 Lbs Bitumen of 80/100 penetration i/c mixing in mechanical mixer in required proportion including heating the material & cleaning the road surface. (Rate includes cost of materials T&P & carriage up to site of work.

**122364 Sft @ RS 4666.50 P.% Sft RS: 5,710,116**

(Rate Rs: Four Thousand Six Hundred Sixty Six)  
(Paissa Fifty ) only Per Hundred Sft)

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 6 Earth work for road embankment by Buildozers, ploughing, mixing clod Breaking, dressing, compacting, with Optimum moisture content lead upto 100'ft & lift upto 5'ft in all types of soil except rock upto 85% density.

640341 Cft @ RS 3656.23 P.% 0 Cft RS: 2,341,234  
 (Rate Rs: Three Thousand Six Hundred Fifty Six)  
 (Paiza Twenty Three) only Per Thousand Cft)

- 7 Add Different cost of Bitumen 52.99 Ton @ RS 14242.00 P.Ton. (-) RS: 754,684

**Total RS: 17,800,678**

**Note**

- 01 Contractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

**CONTRACTOR**

**EXECUTIVE ENGINEER  
 PROVINCIAL HIGHWAY DIVISION  
 BADIN**

**SCHEDULE "B" PART "B"**

**NAME OF WORK: Renovation / Reconditioning of road from Village Rasheed Arain, Taluka Tando Bago Jhudo mile 0/0-1/7.**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   |        |

- 1 Dismantling cement concrete reinforcement separating reinforcement from concrete cleaning & straightening the same RCC work.

102 Cft @ RS 5445.00 P.% Cft RS: 5,554

- 2 Cement concrete plain including Placing, compacting, Finishing & Curring complete including screening & washing stone aggregate without shuttring ration 1:2:4.

75 Cft @ RS 14429.25 P.% Cft RS: 10,822

- 3 Fabrication of mild steel reinforcement for cement ckloncrete i/c cutting bending laying in position, making joints and fasdtening including cost binding wire (also inkluded removal of rust from bars)

5.12 Cwt @ RS 4820.2 P. Cwt RS: 24,679

- 4 RCC work including all labour & materials sesxcept the cost of steel reinforcement & its labour for bending & binding which will be paid separately. This rate also includes all kinds of forms moulds, lifting, shuttering, curring & finishing the exposed surface including screening & washing of shingle RCC work in roof slab, beams, coulmns, rafts, lintles & other structural members laid in position complete in all respect, Ratio 1:2:4..

81 Cft @ RS 337.00 P. Cft RS: 27,297

- 5 Brick on Edging flooring laid in 1:6 cement mortor over a bed of 3/4" thick cement mortor.

68 Sft @ RS 5256.63 P.% Sft RS: 3,575

- 6 Errrection & removal of centering for RCC or CC plain (b) vertical partal wood .

110 Sft @ RS 3127.41 P.% Sft RS: 3,440

- 7 Cement Plaster 1:3 upto 20' height 1/2" thick.

282 Sft @ RS 2344.59 P.% Sft RS: 6,612


**Total RS: 81,979**

**Note**

|                          |                |
|--------------------------|----------------|
| <b>3 Nos: of Culvert</b> | <b>245,936</b> |
|--------------------------|----------------|

- 01 Con ractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

**CONTRACTOR**

  
**EXECUTIVE ENGINEER**  
**PROVINCIAL HIGHWAY DIVISION**  
**BADIN**

**SCHEDULE "B"**

**NAME OF WORK: Construction of road from Tando Bago-Pangrio road at mile Khalifo Qasim to Pangrio Wango road via AC Chack Yaqoob Shah mile 2/0-3/0**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 1 Earth work for road embankment by Buildozers, ploughing, mixing clod Breaking, dressing, compacting, with Optimum moisture content lead upto 100'ft & lift upto 5'ft in all types of soil except rock upto 85% density.

**"B" 85% Density**                      **162812 Cft @ RS 3656.23 P.% 0 Cft      RS: 595,278**  
(Rate Rs. Three thousand Six Hundred Fifty Six)  
(Paiza Twenty Three) only Per Thousand Cft)

- 2 Earth work for road embankment by Buildozers including ploughing, mixing clod breaking, dressing, ramming etc complete. Lead upto 95-100% Modified AASHO specifications.

**"A" 95-100% Density**                      **583224 Cft @ RS 6190.17 P.% 0 Cft      RS: 3,610,256**  
(Rate Rs. Six Thousand One Hundred Ninety)  
(Paiza Seventeen) only. Per Thousand Cft)

- 3 Providing Sand cushion i.e supplying and spreading pit/canal sand of approved quality source of supply to site of work i/c watering & rolling etc complete, rate i/c all cost of materials T&P labour & carriage 3miles.

**38068 Cft @ RS 1479.41 P.% Cft      RS: 563,182**  
Rate Rs. One Thousand Four Hundred Seventy Nine  
(Paiza Forty One) only per hundred Cft )

- 4 Preparing Sub-Base Course by supplying & spreading lthe stone metal 1-1/2" to 2" guage of approved quality from Onger quarry required thickness of 6" in 2 layers to proper camber & graded i/c hand packing fitting voids with 20 Cft Pit/Canal Sand having plasticity index of not more than 6% of suitable quality watering and compacting to achieve 98-100% density as per Modified AASHO specifications. Rate includes all costs of materials, labour, T&P and cartriage to site of work.

**54166 Cft @ RS 9860.24 P.% Cft      RS: 5,340,898**  
(Rate Rs. Nine Thousand Eight Hundred Sixty)  
(Paiza Twenty Four) only. Per Hundred Cft )

- 5 Laying Brick on end edging includidng suspply of 9"x4 1/2"x3" Ist class bricks excavation for laying edging with small side parallel to the road. Rate includes all costs of materials, labour & carriage the site of work.

**10877 Rft @ RS 2834.16 P.% Rft      RS: 308,272**  
(Rate Rs: Two Thousand Eight Hundred Thirty Four)  
(Paiza Sixteen) only per hundred RFT )

- 6 Preparing Base Course by supplying and spreading stone metal of approved quarry properly grade to maximum size of 1-1/2" in required thickness of 3" to proper camber & grade i/c supplying & spreading 15 Cft screening and non-plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering & compacting the same so as to achieve 100% density as per modified AASHO Specifications. This rate i/c providing & using templates, camber plates screen forms as directed Rate includes all costs of materials, T&P labour, carriage to site of work.

**43725 Cft @ RS 11219.81 P.% Cft      RS: 4,905,862**  
(Rate Rs. Eleven Thousand Two Hundred Nineteen)  
(Paiza Eighty One) only per hundred Cft )

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 7 Providing Three Coats surface dressing on new or existing surfasce with 40+25+14=79Lbs of Bitumen of 80/100 penetration & 5.5+2.75+1.5=9.75 ft bajri of 1/4" to 1/2" guage i/c cleaning the road surface rolling after each coat separately rate i/c all cost of material & T&P & carriage to site of work.

65261 Sft @ RS 4282.87 P.% Sft RS: 2,795,044  
(Rate Rs: Four Thousand Two Hundred Eighty Two)  
(Paissa Eighty Seven) only.Per Hundred Sft )

- 8 Add Different cost of Bitumen 23.02 Ton @ RS 14242.0 P.Ton. (-) RS: 327,851

**Total RS: 17,790,940**

#### Note

- 01 Premium will be allowed on above item (Difference cost of Bitumen)
- 02 Contractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

CONTRACTOR

EXECUTIVE ENGINEER  
PROVINCIAL HIGHWAY DIVISION  
ABADIN

## SCHEDULE "B" PART "B"

**NAME OF WORK: Construction of road from Tando Bago-Pangrio road at mile Khalifo Qasim to Pangrio Wango road via AC Chack Yaqoob Shah mile 2/0-3/0**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   |        |

- 1 Excavation in foundation of Building, Bridges & other structure i/c dig belling dressing refilling around the structure with excavated watering & ramming lead upto 1 chain & left upto 5ft (in ordinary)
 

2118 Cft @ RS 3176.25 P.% 0 Cft RS: 6,727
- 2 Cement concrete Brick or stone ballast 1-<sup>1/2</sup>" to 2" guage Rastio 1:4:8.
 

223 Cft @ RS 9416.28 P.% Cft RS: 20,998
- 3 Pacca brick work in foundation and plinth in cement sand mortor Ratio 1:4.
 

486 Cft @ RS 12501.41 P.% Cft RS: 60,757
- 4 Cement concrete plain including Placing, compacting, Finishing & Curring complete including screening & washing stone aggregate wi hout shuttring ration 1:2:4.
 

87 Cft @ RS 14429.25 P.% Cft RS: 12,553
- 5 Fabrication of mild steel reinforcement for cement ckloncrete i/c cutting bending laying in position, making joints and fasdtening including cost binding wire (also inkluded removal of rust from bars)
 

6.00 Cwt @ RS 4820.20 P. Cwt RS: 28,921
- 6 RCC work including all labour & materials sesxcept the cost of steel reinforcement & its labour for bending & binding which will be paid separately. This rate also inclludes all kinds of forms moulds, lifting, shuttering, curring & finishing the exposed surface including, screening & washing of shingle RCC work in roof slab, beams, coulmsns, rafts, lintles & other structural members laid in position complete in all respect, Ratio 1:2:4..
 

80 Cft @ RS 337.00 P. Cft RS: 26,960
- 7 Errection & removal of centering for RCC or CC plain (b) vertical partial wood.
 

92 Sft @ RS 3127.41 P.% Sft RS: 2,877
- 8 Cement Plaster 1:3 upto 20' height 1/2" thick.
 

281 Sft @ RS 2344.59 P.% Sft RS: 6,588

**Total RS: 166,383**

|                                      |
|--------------------------------------|
| <b>5 Nos: Culverts = RS: 831,913</b> |
|--------------------------------------|

**Note**

- 01 Cont actor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

**CONTRACTOR**

**EXECUTIVE ENGINEER  
PROVINCIAL HIGHWAY DIVISION  
BADIN**



**SCHEDULE "B" PART "C"**

**NAME OF WORK: Construction of road from Tando Bago-Pangrio road at mile Khalifo Qasim to Pangrio Wango road via AC Chack Yaqoob Shah mile 2/0-3/0**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   |        |

- 1 Pacca brick work in foundation and plinth in cement sand mortor  
Ratio 1:4.

2410 Cft @ RS 12501.41 P.% Cft RS: 301,284

- 2 Cement concrete plain including Placing, compacting, Finishing &  
Curring complete including screening & washing stone aggregate  
without shuttring ration 1:2:4.

557 Cft @ RS 14429.25 P.% Cft RS: 80,371

- 3 Fabrication of mild steel reinforcement for cement ckloncrete i/c  
cutting bending laying in position, making joints and fasdtening  
including cost binding wire (also inkluded removal of rust from bars)

86.44 Cwt @ RS 4820.20 P. Cwt RS: 416,658

- 4 RCC work including all labour & materials sesxcept the cost of steel  
reinforcement & its labour for bending & binding which will be paid  
separately. This rate also inclludes all kinds of forms moulds, lifting,  
shuttering, curring & finishing the exposed surface  
including,screening & washing of shingle RCC work in roof  
slab, beams, coulmns,rafts,lintles & other structural members laid in  
position complete in all respect, Ratio 1:2:4..

1658 Cft @ RS 337.00 P. Cft RS: 558,746

- 5 Erection & removal of centering for RCC or CC plain (b) vertical partal  
wood .

32 Sft @ RS 3127.41 P.% Sft RS: 1,001

- 6 Cernent Plaster 1:3 upto 20' height 1/2" thick.


1104 Sft @ RS 2344.59 P.% Sft RS: 25,884

**Total RS: 1,383,944**

**Note**

- 01 Contractor & Department are abide by the condition of sanction estimate,  
Items of work, Quantity, Rate & Premium as per Technical Sanctioned  
accorded by the competent authority in case of any variation in Schedule "B" of  
Tender.

**CONTRACTOR**

  
**EXECUTIVE ENGINEER**  
**PROVINCIAL HIGHWAY DIVISION**  
**BADIN**

**SCHEDULE "B"**

**NAME OF WORK: Const: of road from Army Farm Otaq of Kazi Aijaz road to Village Ali Nawaz Dars UC Dei Jarkas mile 3/0-4/0.**

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 1 Earth work for road embankment by Bulldozers, ploughing, mixing clod Breaking, dressing, compacting, with Optimum moisture content lead upto 100'ft & lift upto 5'ft in all types of soil except rock upto 85% density.

**"B" 85% Density** **162812 Cft @ RS 3656.23 P.% 0 Cft RS: 595,278**  
(Rate Rs. Three thousand Six Hundred Fifty Six)  
(Paiza Twenty Three) only Per Thousand Cft)

- 2 Earth work for road embankment by Bulldozers including ploughing, mixing clod breaking, dressing, ramming etc complete. Lead upto 95-100% Modified AASHO specifications.

**"A" 95-100% Density** **547081 Cft @ RS 6190.17 P.% 0 Cft RS: 3,386,524**  
(Rate Rs. Six Thousand One Hundred Ninety)  
(Paiza Seventy) only Per Thousand Cft)

- 3 Providing Sand cushion i.e supplying and spreading pit/canal sand of approved quality source of supply to site of work i/c watering & rolling etc complete, rate i/c all cost of materials T&P labour & carriage 3m les.

**38069 Cft @ RS 1479.41 P.% Cft RS: 563,197**  
Rate Rs. One Thousand Four Hundred Seventy Nine  
(Paiza Forty One) only per hundred Cft )

- 4 Preparing Sub-Base Course by supplying & spreading lthe stone metal 1-1/2" to 2" guage of approved quality from Onger quarry required thickness of 6" in 2 layers to proper camber & graded i/c hand packing fitting voids with 20 Cft Pit/Canal Sand having plasticity index of not more than 6% of suitable quality watering and compacting to achieve 98- 00% density as per Modified AASHO specifications. Rate includes all costs of materials, labour , T&P and cartriage to site of work.

**54166 Cft @ RS 9773.63 P.% Cft RS: 5,293,984**  
(Rate Rs. Nine Thousand Seven Hundred Seventy Three)  
(Paiza Sixty Three) only Per Hundred Cft)

- 5 Laying Brick on end edging includidng suspply of 9"x4 1/2"x3" Ist class bricks excavation for laying edging with small side parallel to the road. Rate includes all costs of materials, labour & carriage the site of work

**10877 Rft @ RS 2823.74 P.% Rft RS: 307,138**  
(Rate Rs: Two Thousand Eight Hundred Twenty Three)  
(Paiza Seventy Four) only per hundred RFT)

- 6 Preparing Base Course by supplying and spreading stone metal of approved quarry properly grade to maximum size of 1-1/2" in required thickness of 3" to proper camber & grade i/c supplying & spreading 15 Cft screening and non-plastic quarry fines, filling depressions with stone metal after initial rolling i/c watering & compacting the same so as to achieve 100% density as per modified AASHO Specifications. This ratre i/c providing & using templates, camber plates screen forms as directed Rate includes all costs of materials, T&P labour, carriage to site of work.

**43725 Cft @ RS 11123.44 P.% Cft RS: 4,863,724**  
(Rate Rs. Eleven Thousand One Hundred Twenty Three)  
(Paiza Forty Four) only per hundred Cft)

| S. # | Item of Work | Quantity | Rate | Unit | Amount |
|------|--------------|----------|------|------|--------|
| 01   | 02           | 03       | 04   | 05   | 06     |

- 7 Providing surface dressing (3 Coat) on new or existing surface with 79Lbs of Bitumen of 80/100 penetration & 9.75Cft bajri of 1/2" to 3/4" guage i/c cleaning the road surface rolling after each coat separately rate i/c all cost of material & T&P & carriage to site of work.

65261 Sft @ RS 4275.84 P.% Sft RS: 2,790,456  
(Rate Rs: Four Thousand Two Hundred Seventy Five)  
(Paisa Eighty Four) only.Per Hundred Sft)

- 8 Add Different cost of Bitumen 23.02 Ton @ RS 14242.00 P.Ton. (-) RS: 327,851

**Total RS: 17,472,451**

**Note**

- 01 Contractor & Department are abide by the condition of sanction estimate, Items of work, Quantity, Rate & Premium as per Technical Sanctioned accorded by the competent authority in case of any variation in Schedule "B" of Tender.

CONTRACTOR

EXECUTIVE ENGINEER  
PROVINCIAL HIGHWAY DIVISION  
BADIN