

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
District ADP Schemes											
128	Providing building to existing shelterless Primary Schools Taluka Larkano (2010-11 Programme) (05 Units)	-	11,682	0,500	A.D.P	National Open Competitive Bidding	-	0,250	0,250	-	-
129	Construction / Reconstruction of building for existing Primary Schools Taluka Larkano (2010-11 Programme)	-	20,000	4,000	A.D.P	National Open Competitive Bidding	-	1,500	2,000	0,000	-
130	Construction / Reconstruction of building for existing Primary Taluka Ratodero (2010-11 Programme)	-	20,000	2,800	A.D.P	National Open Competitive Bidding	-	-	0,000	1,500	-
131	Construction / Reconstruction of building for existing Primary Schools Taluka Dokri & Bakrani (2010-11 Programme)	-	20,000	2,500	A.D.P	National Open Competitive Bidding	-	-	1,000	0,000	-
132	Integrated rehabilitation of Primary Schools in Taluka Larkano (2010-11 Programme)	-	20,000	4,000	A.D.P	National Open Competitive Bidding	-	1,500	0,500	0,000	-
133	Integrated rehabilitation of Primary Schools in Taluka Ratodero (2010-11 Programme)	-	20,000	4,000	A.D.P	National Open Competitive Bidding	-	1,000	1,000	0,000	-
134	Integrated rehabilitation of Primary Schools in Taluka Bakrani (2010-11 Programme)	-	15,000	2,000	A.D.P	National Open Competitive Bidding	-	-	2,500	2,000	Additional funds amounting to Rs. 2,500 (M) are demanded

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
135	Integrated rehabilitation of Primary Schools in Taluka Dokri (2010-11 Programme)	-	20,000	4,000	A.D.P	National Open Competitive Bidding	-	-	0,000	1,000	-
139	Construction of building for existing Shelterless Primary Schools in Taluka Ratodero (5 Units) (2011-12 Programme) (Revised)	-	16,374	3,600	A.D.P	National Open Competitive Bidding	-	-	0,000	1,000	-
140	Construction of building for existing Shelterless Primary Schools in Taluka Larkano (5 Units) (2011-12 Programme) (Revised)	-	15,000	3,200	A.D.P	National Open Competitive Bidding	-	-	0,000	1,000	-
141	Construction of building for existing Shelterless Primary Schools in Taluka Dokri (5 Units) (2011-12 Programme) (Revised)	-	15,000	3,600	A.D.P	National Open Competitive Bidding	-	-	0,000	1,000	-
142	Construction of building for existing Shelterless Primary Schools in Taluka Bakrani (5 Units) (2011-12 Programme) (Revised)	-	15,000	3,600	A.D.P	National Open Competitive Bidding	-	3,000	0,600	0,000	-
143	Rehabilitation of building for existing Primary Schools in Taluka Larkano (14 Units) (2011-12 Programme)	-	19,800	3,600	A.D.P	National Open Competitive Bidding	-	-	3,000	1,500	Additional funds amounting to Rs. 0.900 (M) are demanded

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
144	Rehabilitation of building for existing Primary / Middle Schools in Taluka Ratodero (10 Units) (2011-12 Programme)	-	19,900	3,600	A.D.P	National Open Competitive Bidding	-	-	0,000	1,000	-
145	Rehabilitation of building for existing Primary Schools in Taluka Bakrani & Dokri (24 Units) (2011-12 Programme)	-	20,000	3,000	A.D.P	National Open Competitive Bidding	-	3,500	3,500	1,000	Additional funds amounting to Rs. 5,000 (M) are demanded
146	Construction of additional class rooms in existing Primary Schools in Taluka Ratodero (16 Class Rooms) (2011-12 Programme)	-	15,840	4,000	A.D.P	National Open Competitive Bidding	-	-	3,000	0,000	-
147	Construction of additional class rooms in existing Primary Schools in Taluka Larkano (16 Class Rooms) (2011-12 Programme)	-	15,840	3,600	A.D.P	National Open Competitive Bidding	-	1,000	2,000	0,500	-
148	Construction of additional class rooms in existing Primary Schools in Taluka Bakrani / Dokri (16 Class Rooms) (2011-12 Programme)	-	15,840	3,600	A.D.P	National Open Competitive Bidding	-	3,000	1,000	0,700	Additional funds amounting to Rs. 1,100 (M) are demanded
149	Reconstruction of dangerous Primary / Middle School Buildings in Taluka Larkano (6 Units) (2011-12 Programme)	-	19,500	3,600	A.D.P	National Open Competitive Bidding	-	4,500	1,500	0,500	Additional funds amounting to Rs. 2,900 (M) are demanded

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
150	Reconstruction of dangerous Primary School Buildings in Taluka Ratodero (9 units) (2011-12 Programme)	-	17.700	3.600	A.D.P	National Open Competitive Bidding	-	2.000	0.800	0.800	-
151	Reconstruction of dangerous Primary / Middle School Buildings in Taluka Bakrani / Dokri (12 Units) (2011-12 Programme)	-	19.900	2.500	A.D.P	National Open Competitive Bidding	-	-	2.500	2.000	Additional funds amounting to Rs. 2.000 (M) are demanded
152	Construction of building for existing Shelterless Primary Schools in Taluka Larkano	-	16.530	4.000	A.D.P	National Open Competitive Bidding	-	3.000	5.000	2.000	Additional funds amounting to Rs. 6.000 (M) are demanded
153	Construction of building for existing Shelterless Primary Schools in Taluka Bakrani / Dokri.	-	18.768	4.000	A.D.P	National Open Competitive Bidding	-	-	6.000	6.000	Additional funds amounting to Rs. 8.000 (M) are demanded
154	Construction of additional class rooms in existing Primary Schools in Taluka Ratodero	-	16.920	4.000	A.D.P	National Open Competitive Bidding	-	-	5.000	5.000	Additional funds amounting to Rs. 6.000 (M) are demanded
155	Construction of additional class rooms in existing Primary Schools in Taluka Ratodero	-	19.176	4.000	A.D.P	National Open Competitive Bidding	-	-	6.000	7.000	Additional funds amounting to Rs. 9.000 (M) are demanded
156	Construction of additional class rooms in existing Primary Schools in Taluka Bakrani & Dokri	-	14.664	4.000	A.D.P	National Open Competitive Bidding	-	3.000	2.000	1.000	Additional funds amounting to Rs. 2.000 (M) are demanded

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
157	Integrated Rehabilitation of Elementary Schools in Taluka Ratodero	-	19,900	4,000	A.D.P	National Open Competitive Bidding	-	4,000	4,500	3,500	Additional funds amounting to Rs. 8,000 (M) are demanded
158	Integrated Rehabilitation of Elementary Schools in Taluka Larkano	-	20,000	5,000	A.D.P	National Open Competitive Bidding	-	2,000	5,000	4,000	Additional funds amounting to Rs. 6,000 (M) are demanded
159	Integrated rehabilitation of Elementary Schools in Taluka Dokri & Bakrani	-	20,000	5,000	A.D.P	National Open Competitive Bidding	-	3,000	5,000	3,000	Additional funds amounting to Rs. 6,000 (M) are demanded
160	Reconstruction of dangerous Primary Schools Buildings of Taluka & District Larkano	-	18,800	4,000	A.D.P	National Open Competitive Bidding	-	-	11,000	4,000	Additional funds amounting to Rs. 11,000 (M) are demanded
161	Integrated rehabilitation of building for Govt. Pilot Higher Secondary School Larkano (2010-11 Programme)	-	20,000	2,900	A.D.P	National Open Competitive Bidding	-	-	1,000	0,000	-
162	Integrated rehabilitation / provision of approach road including drainage to GBHS, Saint Joseph Larkano (2010-11 Programme)	-	15,000	2,500	A.D.P	National Open Competitive Bidding	-	-	1,000	1,500	-
163	Integrated rehabilitation of building for Govt. Boys High School Ratodero (2010-11 Programme)	-	18,000	3,600	A.D.P	National Open Competitive Bidding	-	-	2,000	1,500	-

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
164	Rehabilitation and provision of missing facilities of building for existing Secondary / Higher Secondary Schools Taluka Larkano (2010-11 Programme)	-	20,000	2,400	A.D.P	National Open Competitive Bidding	-	2,000	0,400	0,000	-
165	Rehabilitation and provision of missing facilities of building for existing Secondary / Higher Secondary Schools Taluka Ratodero (2010-11 Programme)	-	20,000	3,000	A.D.P	National Open Competitive Bidding	-	-	3,000	0,000	-
166	Rehabilitation and provision of missing facilities of building for existing Secondary / Higher Secondary Schools Taluka Bakrani / Dokri (2010-11 Programme)	-	20,000	4,000	A.D.P	National Open Competitive Bidding	-	-	2,000	0,000	-
167	Construction of additional class rooms in existing Secondary / Higher Secondary Schools Taluka & District Larkano (16 class rooms) (2010-11 Programme)	-	18,003	0,600	A.D.P	National Open Competitive Bidding	-	-	0,500	0,500	-
168	Construction of additional class rooms in existing Secondary / Higher Secondary Schools Taluka Ratodero District Larkano (16 class rooms) (2010-11 Programme)	-	18,003	2,000	A.D.P	National Open Competitive Bidding	-	-	1,000	1,000	-

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
169	Construction of additional class rooms in existing Secondary / Higher Secondary Schools Taluka Dokri District Larkano (8 Class Rooms) (2010-11 Programme)	-	8,979	1,040	A.D.P	National Open Competitive Bidding	-	-	1,000	0,000	-
170	Provision of missing facilities in existing Secondary / Higher Secondary Schools Taluka Ratodero (2010-11 Programme) (5 Units)	-	18,089	2,400	A.D.P	National Open Competitive Bidding	-	-	2,000	0,000	-
171	Provision of missing facilities in existing Secondary / Higher Secondary Schools Taluka Bakrani (2010-11 Programme)	-	13,089	3,000	A.D.P	National Open Competitive Bidding	-	-	2,000	0,000	-
172	Provision of missing facilities in existing Secondary / Higher Secondary Schools Taluka Dokri (2010-11 Programme)	-	14,363	3,000	A.D.P	National Open Competitive Bidding	-	-	1,500	0,000	-
173	Construction of Auditorium Hall at Govt. Girls High School Dokri (2010-11 Programme)	-	9,362	3,600	A.D.P	National Open Competitive Bidding	-	-	1,000	0,000	-
174	Rehabilitation of Govt. Boys Higher Secondary School Naudero (2010-11 Programme)	-	15,000	2,500	A.D.P	National Open Competitive Bidding	-	-	1,000	0,000	-

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
177	Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Larkano (7 Units) (2011-12 Programme)	-	19,500	3,000	A.D.P	National Open Competitive Bidding	-	2,000	4,000	4,000	Additional funds amounting to Rs. 7,000 (M) are demanded
178	Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Ratodero (6 Units) (2011-12 Programme)	-	20,000	5,000	A.D.P	National Open Competitive Bidding	-	-	5,000	5,000	Additional funds amounting to Rs. 5,000 (M) are demanded
179	Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Bakrani (07 Units) (2011-12 Programme)	-	20,000	4,000	A.D.P	National Open Competitive Bidding	-	1,000	3,000	-	-
180	Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Dokri (4 Units) 92011-12 Programme)	-	19,800	4,000	A.D.P	National Open Competitive Bidding	-	-	5,000	-	Additional funds amounting to Rs. 1,000 (M) are demanded
181	Provision of essential facilities in existing High / Higher Secondary Schools in Taluka Larkano (5 Units) (2011-12 Programme)	-	18,250	3,000	A.D.P	National Open Competitive Bidding	-	-	5,000	3,000	Additional funds amounting to Rs. 5,000 (M) are demanded
182	Provision of essential facilities in existing High / Higher Secondary Schools in Taluka Ratodero (3 Units) (2011-12 Programme)	-	18,650	5,000	A.D.P	National Open Competitive Bidding	-	-	12,000	0,000	Additional funds amounting to Rs. 7,000 (M) are demanded

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO

ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
169	Construction of additional class rooms in existing Higher Secondary Schools Taluka Dokri District Larkano (8 Class Rooms) (2010-11 Programme)	-	8.979	1.040	A.D.P	National Open Competitive Bidding	-	-	1.000	0.000	-
170	Provision of missing facilities in existing Secondary / Higher Secondary Schools Taluka Ratodero (2010-11 Programme) (5 Units)	-	18.089	2.400	A.D.P	National Open Competitive Bidding	-	-	2.000	0.000	-
171	Provision of missing facilities in existing Secondary / Higher Secondary Schools Taluka Bakrani (2010-11 Programme)	-	13.089	3.000	A.D.P	National Open Competitive Bidding	-	-	2.000	0.000	-
172	Provision of missing facilities in existing Secondary / Higher Secondary Schools Taluka Dokri (2010-11 Programme)	-	14.363	3.000	A.D.P	National Open Competitive Bidding	-	-	1.500	0.000	-
173	Construction of Auditorium Hall at Govt. Girls High School Dokri (2010-11 Programme)	-	9.362	3.600	A.D.P	National Open Competitive Bidding	-	-	1.000	0.000	-
174	Rehabilitation of Govt. Boys Higher Secondary School Naudero (2010-11 Programme)	-	15.000	2.500	A.D.P	National Open Competitive Bidding	-	-	1.000	0.000	-

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO

ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
177	Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Larkano (7 Units) (2011-12 Programme)	-	19,500	3,000	A.D.P	National Open Competitive Bidding	-	2,000	4,000	4,000	Additional funds amounting to Rs. 7,000 (M) are demanded
178	Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Ratodero (6 Units) (2011-12 Programme)	-	20,000	5,000	A.D.P	National Open Competitive Bidding	-	-	5,000	5,000	Additional funds amounting to Rs. 5,000 (M) are demanded
179	Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Bakrani (07 Units) (2011-12 Programme)	-	20,000	4,000	A.D.P	National Open Competitive Bidding	-	1,000	-	3,000	-
180	Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Dokri (4 Units) 92011-12 Programme)	-	19,800	4,000	A.D.P	National Open Competitive Bidding	-	-	-	5,000	Additional funds amounting to Rs. 1,000 (M) are demanded
181	Provision of essential facilities in existing High / Higher Secondary Schools in Taluka Larkano (5 Units) (2011-12 Programme)	-	18,250	3,000	A.D.P	National Open Competitive Bidding	-	-	-	5,000	Additional funds amounting to Rs. 5,000 (M) are demanded
182	Provision of essential facilities in existing High / Higher Secondary Schools in Taluka Ratodero (3 Units) (2011-12 Programme)	-	18,650	5,000	A.D.P	National Open Competitive Bidding	-	-	12,000	0,000	Additional funds amounting to Rs. 7,000 (M) are demanded

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO

ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks	
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr		
183	Provision of essential facilities in existing High / Higher Secondary Schools in Taluka Bakrami / Dokri (7 Units) (2011-12 Programme)	-	17,900	3,000	A.D.P	National Open Competitive Bidding	-	-	6,000	3,000	3,000	Additional funds amounting to Rs. 6,000 (M) are demanded
184	Rehabilitation / Improvement of Historical Educational Buildings in District Larkano (3 Units) (2011-12 Programme)	-	20,000	4,500	A.D.P	National Open Competitive Bidding	-	-	5,000	3,000	3,000	Additional funds amounting to Rs. 3,500 (M) are demanded
185	Integrated rehabilitation of Govt. Boys High School Badah (1 Unit) (2011-12 Programme)	-	18,000	4,000	A.D.P	National Open Competitive Bidding	-	-	8,000	0,000	0,000	Additional funds amounting to Rs. 4,000 (M) are demanded
186	Construction of Auditorium Hall at GBHS, Bangulidero (1 Unit) (2011-12 Programme)	-	13,000	4,000	A.D.P	National Open Competitive Bidding	-	-	3,000	0,000	0,000	-
187	Construction of Computer Block at Govt. Boys Higher Secondary School Pilot Larkano (1 Unit) (2011-12 Programme)	-	15,000	4,000	A.D.P	National Open Competitive Bidding	-	-	4,000	0,000	0,000	-
188	Construction of Computer Block at Govt. Boys Higher Secondary School Ratodero (1 Unit) (2011-12 Programme)	-	15,000	3,000	A.D.P	National Open Competitive Bidding	-	-	3,000	0,000	0,000	-
189	Construction of Computer Block at Govt. Boys Higher Secondary School Naudero (1 Unit) (2011-12 Programme)	-	15,000	1,500	A.D.P	National Open Competitive Bidding	-	1,000	0,500	0,000	0,000	-

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No.	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
190	Development of Park in existing High / Higher Secondary Schools in District Larkano (9 Units) (2011-12)	-	20,000	3,000	A.D.P	National Open Competitive Bidding	-	2,000	6,000	5,000	Additional funds amounting to Rs.10,000 (M) are demanded
191	Construction of Scout Head Quarter in existing High / Higher Secondary Schools District Larkano (2 Units) (2011-12 Programme)	-	20,000	5,000	A.D.P	National Open Competitive Bidding	-	-	5,000	0,000	-
192	Construction/Reconstruction of Workshop (for Dress Making & Designing) in existing Secondary / Higher Secondary Schools District Larkano (3 Units) (2011-12 Programme)	-	16,200	0,800	A.D.P	National Open Competitive Bidding	-	-	10,000	0,000	Additional funds amounting to Rs.9,200 (M) are demanded
193	Construction of Residential Quarters / Bungalows for District Education Officers (3 Units) (2011-12 Programme)	-	18,003	4,000	A.D.P	National Open Competitive Bidding	-	-	10,000	0,000	Additional funds amounting to Rs.6,000 (M) are demanded
194	Rehabilitation / Improvement of Education Office Buildings District Larkano (7 Units) (2011-12 Programme)	-	19,900	3,000	A.D.P	National Open Competitive Bidding	-	-	5,000	2,000	Additional funds amounting to Rs.4,000 (M) are demanded

Provincial Schemes

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO
ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks	
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr		
126	Rehabilitation / Reconstruction of existing Primary & Elementary Schools in Sindh (damaged due to rain /flood or any other conditions) in District Larkano (37-Units)	-	55.579	51.134	A.D.P	National Open Competitive Bidding	30.000	20.000	5.134	-	-	-
127	Up-gradation of Primary Schools to Middle Schools in Sindh (2007-08 Programme) (460-Units) (16 Units for District Larkano)	-	41.024	4.696	A.D.P	National Open Competitive Bidding	-	7.000	1.600	-	-	Additional funds amounting to Rs. 3.904(M) are demanded
159	Up-gradation of Middle Schools to High Schools in Sindh (2008-09 Programme) (115 Units) (8 Units for District Larkano)	-	108.688	8.696	A.D.P	National Open Competitive Bidding	15.000	35.000	34.164	-	-	Additional funds amounting to Rs. 75.468 (M) are demanded
161	Establishment of Single Section High Schools in Sindh (2008-09 Programme) (53 Units)(3 Units for District Larkano)	-	61.131	5.000	A.D.P	National Open Competitive Bidding	13.000	7.000	3.434	-	-	Additional funds amounting to Rs. 18.434 (M) are demanded
162	Up-gradation of Middle Schools to High Schools & High Schools to Higher Secondary Schools in Sindh (2007-08 Programme) (17 Units for District Larkano)	-	152.923	30.000	A.D.P	National Open Competitive Bidding	-	50.000	48.050	-	-	Additional funds amounting to Rs. 68.050 (M) are demanded
164	Rehabilitation of existing High/ Higher Secondary Schools in Sindh (2008-09 Programme) (12 Units for District Larkano)	-	64.392	7.000	A.D.P	National Open Competitive Bidding	1.000	5.300	0.000	-	-	-

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO

ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
196	Rehabilitation of existing High Schools & Higher Secondary Schools in District Larkano (08 Units)	-	56.419	14.000	A.D.P	National Open Competitive Bidding	-	-	10.000	10.000	Additional funds amounting to Rs. 6.000 (M) are demanded
208	Improvement of existing Public School in Larkana Division	-	0.000	15.000	A.D.P	National Open Competitive Bidding	-	-	5.000	10.000	-
231	Establishment of Shaheed Benzair Bhutto Cadet College @ Garhi Khuda Bux Larkana (2010-11 Programme) (1 Unit)	-	364.720	30.000	A.D.P	National Open Competitive Bidding	-	-	30.000	30.000	Additional funds amounting to Rs. 30.000 (M) are demanded
232	Establishment of Govt. Boys / Girls Degree Colleges in Sindh (2010-11 Programme) (23 Units) (1 Unit for District Larkano)	-	96.587	4.490	A.D.P	National Open Competitive Bidding	-	-	10.000	10.000	Additional funds amounting to Rs. 15.510 (M) are demanded
233	Establishment of Shaheed Mohtarma Benzair Bhutto Govt. College of Education at Larkana (2011-12 Programme)(revised)	-	151.183	25.997	A.D.P	National Open Competitive Bidding	-	-	20.000	0.000	-
250	Rehabilitation & Provision of missing facilities in existing Colleges in Sindh	-	0.000	50.000	A.D.P	National Open Competitive Bidding	-	-	10.000	0.000	-
264	Construction / Reconstruction of building in existing Degree Colleges(GBDC Ratodero & GBDC Larkano)(B.Sc Block) (2014-15 Programme)	-	57.928	15.000	A.D.P	National Open Competitive Bidding	-	-	54.000	0.000	Additional funds amounting to Rs. 39.000 (M) are demanded

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO

ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr	
276	Construction / Repair/Raising of Compound Wall of Colleges in Sindh (Security Threatened Colleges) (2015-16 Programme)	-	0.000	10.000	A.D.P	National Open Competitive Bidding	-	-	7.500	2.500	-
293	Construction / Reconstruction of existing Offices for Field Officers of Education & Literacy Department in Larkano Division (03-Units) (2014-15 Programme)	-	26.470	20.000	A.D.P	National Open Competitive Bidding	-	-	10.000	10.000	-
1223	Construction of 2-roomed building & additional class rooms to existing Primary Schools Taluka Ratodero District Larkano (16 Units)	-	69.468	25.599	A.D.P	National Open Competitive Bidding	-	-	5.000	5.000	-
1233	Integrated rehabilitation and provision of missing facilities to existing Elementary Schools Taluka Ratodero District Larkano (79 Units)	-	191.429	56.032	A.D.P	National Open Competitive Bidding	-	-	2.500	1.500	-
1234	Integrated rehabilitation and provision of missing facilities to existing Elementary Schools District Larkano (123 Units) (Revised)	-	291.498	97.458	A.D.P	National Open Competitive Bidding	-	-	3.000	2.000	-

Larkana Dev Package

OFFICE OF THE EXECUTIVE ENGINEER, EDUCATION WORKS DIVISION, LARKANO
ONGOING DEVELOPMENT SCHEMES OF EDUCATION SECTOR PERTAINING TO DISTRICT LARKANO

ANNUAL PROCUREMENT PLAN

ADP No. 2015-16	Description of Procurement	Quantity (Where applicable)	Estimated Cost	Funds Allocated	Source of funds (ADPs Non-ADPs)	Proposed Procurement Method	Timing of Procurements				Remarks	
							1st Qtr	2nd Qtr	3rd Qtr	4th Qtr		
1236	Establishment of Begum Nusrat Bhutto Girls Degree College Larkano	-	131.979	60.190	A.D.P	National Open Competitive Bidding	-	-	12.500	5.000	-	-
1237	Construction of additional Lecture Halls (10 Nos.) at Govt. Girls Degree College Larkano	-	38.208	20.295	A.D.P	National Open Competitive Bidding	-	-	5.000	5.000	-	-
1238	Integrated rehabilitation of existing Elementary Schools in District Larkano (15 Units)	-	50.104	26.802	A.D.P	National Open Competitive Bidding	-	1.000	3.000	0.500	-	-
1287	Construction of Biliawal Bhutto Zardari Peoples Parks at Larkano (modified)	-	99.450	10.000	A.D.P	National Open Competitive Bidding	-	-	10.000	0.000	-	-


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO



NOTIFICATION

NO SO(G) HDVE&A/PRO-EW/14-15: In pursuance of Rule - 7 of the Sindh Public Procurement Rules, 2010, a Departmental Procurement Committee comprising of following Officers for procurement of Services Educational Institutes / Offices / Line Departments working under Administrative Department Education & Literacy Department to be procured under ADP / Regular Budget / SNE of Government of Sindh as per the following order:

- | | |
|--|----------|
| Executive Engineer (Education Works)
Concerned Education Works Division
Education & Literacy Department | Chairman |
| Assistant Engineer
Local Government Public Health Engineering Department | Member |
| Assistant Engineer (Education Works) of Headquarter
Concerned Education Works sub Division
Education & Literacy Department | Member |

Tasks

- Preparing bidding documents;
- Carrying out technical as well as financial evaluation of the bids;
- Preparing evaluation report as provided in Rule 45 of SPPRA 2010;
- Making recommendations for the award of contract to the competent authority; and
- Performing any other function ancillary and incidental to the above.

- DR. FAZLULLAH PECHUHO -
 SECRETARY TO GOVT. OF SINDH

NO SO(G) HDVE&A/PRO-EW/14-15:

Karachi, date the 28th May, 2015

(A copy is forwarded for information & necessary action to:-

1. All Members of the Committee.
2. The P.S. to Senior Minister, Education & Literacy Department, Govt. of Sindh, Karachi.
3. The P.S. to Secretary, Education & Literacy Department.
4. The P.S. to Secretary, Local Government Public Health Engineering Department.
5. Office Order File

DEPUTY SECRETARY (GA) 28/05/15



SINDH EDUCATION &
 LITERACY DEPARTMENT





NOTIFICATION

NO.S.O(G. EDU&A/PRO-EW(CRC)/14-15: In pursuance of Rule - 31 of the Sindh Public Procurement Rules, 2010 a Departmental Complaint Redressal Committee comprising of following Officers is constituted as under to resolve complaints of aggrieved bidders:-

- | | |
|--|----------|
| 1. Superintendent Engineer (Education Works) of concerned Education Works Circle Education & Literacy Department | Chairman |
| 2. Representative of District Account Officer / Accountant General, Sindh | Member |
| 3. Representative of Head of procuring Agency (Professional from relevant field concerning) | Member |

Tasks:


- To perform according to Rule - 31 of SPPRA, 2010;
- Perform any other function ancillary and incidental to the above.

SECRETARY EDUCATION
TO GOVT. OF SINDH
Karachi, date the 28th May, 2015

NO.S.O(G. EDU&A/PRO-EW(CRC)/14-15:

A copy is forwarded for information & necessary action to:-

- All Members of the Committee.
- The P.S to Secretary, Education & Literacy Department.
- Office Order File




28/04/15
DEPUTY SECRETARY (GA)

BIDDING DOCUMENT**1**Issued toAnd charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- Providing building to existing shelterless Primary Schools Taluka Larkano (2010-11 Programme) (05 Units) at GBPS. Mumtaz Colony (balance work) (ADP No. 128 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 250,000
- e) Amount of Bid Security (2%) (fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 5,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 12,500
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano, As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No. dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR



EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

SCHEDULE " B "**S.No: 1**

NAME OF WORK:- **PROVIDING BUILDING TO EXISTING SHELTERLESS
PRIMARY SCHOOL TALUKA LARKANA (2010-11
PROGRAMME) (5-UNITS) AT GBPS MUMTAZ COLONY
(BALANCE WORK).**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Supplying and filling sand under floor and plugging in walls. (S.I.No: 29 P/25).				
		917.00	@ Rs: 1141/25	% Cft	Rs: 10,465.00
					(Rs: one thous: one hund: forty one & twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:6:12. (S.I.No: 4 (d) P.17).				
		299.00	@ Rs: 8122/95	% Cft	Rs: 24,288.00
					(Rs: eight thous: one hund: twenty two & ninty five only)
3	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		180.00	@ Rs:12346/65	% Cft	Rs: 22,224.00
					(Rs: tweleve thous: three forty six & sixty five only)
4	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		360.00	@ Rs:2206/60	% Sft	Rs: 7,944.00
					(Rs: two thous: two hund: six & sixty only)
5	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		360.00	@ Rs:2197/52	% Sft	Rs: 7,911.00
					(Rs: two thous: one hund: ninty seven & twenty two only)
6	Supplying and fixing broden glasses on courtyard walls including 1:3:6 cement concrete coping (S.I.No: 61 P/104).				
		160.00	@ Rs:70/44	P Lft	Rs: 11,270.00
					(Rs: seventy & forty four only)
7	S/F in position approved grill of 3/4" x 1/4" size flat iron of approved design including painting tt coats etc complete (weight not to be less than 3.7 Lbs/ sq. foot of finished grill). (S.I.No: 26 P.9				
		338.00	@ Rs: 194/16	P.Sft	Rs: 65,626.00
					(Rs: one hund: ninty four & sixteen only)



S.No:	Description	Qty:	Rate	Unit	Amount
8	Cement pointing struck joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	240.00	@ Rs:1287/44	% Sft	<u>Rs: 3,090.00</u> (Rs: one thous: two hund: eighty seven & fourty four only)
9	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing andndividing into panels. (a) 2" Thick. (S.I.No: 16 (a) P. 41).	909.00	@ Rs: 4411/82	% Sft	<u>Rs: 29,774.00</u> (Rs: four thous: four hund: eleven & eighty two only)
10	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	1281.00	@ Rs:1887/40	% Sft	<u>Rs: 24,178.00</u> (Rs: one thous: eight hund; eighty seven & fourteen only)
11	Distempering three coats. (S.I.No.24 (c) P/53).	360.00	@ Rs:1079/65	% Sft	<u>Rs: 3,887.00</u> (Rs: one thos: seventy nine & sixty five only)
12	Prepareing the surface and painting with weather coat of approved make to old weather coat surface. (S.I.No:39 P/55).	240.00	@ Rs:1498/48	% Sft	<u>Rs: 3,596.00</u> (Rs: one thous: four hund; ninty eight & forty eight only)
G.Total:					<u>Rs: 214,253.0</u>




BIDDING DOCUMENT**2****Issued to**And charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Integrated rehabilitation of Primary Schools in Taluka Larkano (2010-11 Programme) (16 Units) at GBPS, Faizal Colony (balance work) (ADP No. 132 of 2015-16)**
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 1,000,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 20,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 50,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along with time:- As per NIT.
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano. As per NIT
- k) Time for Completion from written order of commence:- 15 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR



EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

SCHEDULE " B "

S.No: 2

NAME OF WORK:- INTEGRATED REHABILITATION OF PRIMARY SCHOOLS IN
TALUKA LARKANO (2010-11 PROGRAMME) (16-UNITS) AT GBPS
FAISAL COLONY (BALANCE WORK)

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling brick work in lime or cement mortar. (S.I.No.13 P/10).	248.00	@ Rs: 1285/63	% Cft	Rs: 3,188.00 (Rs: one two hund: eighty five & sixty three only)
2	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).	36.00	Rs 5445/-	% Cft	Rs: 1,960.00 (Rs: five thous: four hund: forty five only)
3	Removing cement or lime plaster (S.I.No: 53 P/13).	554.00	@ Rs: 121/-	% Sft	Rs: 670.00 (Rs: one hund: twenty one only)
4	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	525.00	@ Rs: 3176/25	% 0 Cft	Rs: 1,667.00 (Rs: three thous: one hund: seventy hund: twenty five only)
5	Cement concerte brick or stone ballast 1 1/2" to 2" gauge (c) Ratio. 1:5:10. (s.i.No: 4 (c) P/14).	159.00	@ Rs: 8694/95	% 0 Cft	Rs: 14,143.00 (Rs: eight thous: six hund: ninty four & ninty five only)
6	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	8788.00	@ Rs: 1141/25	% Cft	Rs: 100,293.00 (Rs: one thous: one hund: forty one & twenty five only)
7	Extra Lead 3.0 Miles	8788.00	@ Rs: 579/41	% 0 Cft	Rs: 50,918.00 (Rs: five hund: sevnty nine & fourty one only)
8	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:6:12. (S.I.No: 4 (d) P.17).	496.00	@ Rs: 8122/95	% Cft	Rs: 40,290.00 (Rs: eight thous: one hund: twenty two & ninty five only)



S.No:	Description	Qty:	Rate	Unit	Amount
9	S/F in position approved grill of 3/4" x 1/4" size flat iron of approved design including painting 11 coats etc complete (weight not to be less than 3.7 Lbs/ sq. foot of finished grill). (S.I.No: 26 P.9)	158.00	@ Rs: 194/16	P.Sft	Rs: 30,677.00
					(Rs: one hund: ninty four & sixteen only)
10	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	864.00	@ Rs:11948/36	%Cft	Rs: 103,233.00
					(Rs: eleven thous: nine hund: eighty five & thirty six only)
11	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	276.00	@ Rs:337/-	P.Cft	Rs: 93,012.00
					(Rs: three hund: thirty seven only)
12	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	15.00	@ Rs:5001/70	P.Cwt	Rs: 75,025.00
					(Rs: five thous: one & seventy only)
13	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (a) 3" Thick. (S.I.No: 16 (a) P. 41).	1760.00	@ Rs: 4411/82	%Sft	Rs: 77,648.00
					(Rs: four thous: four hund: eleven & eighty two only)
14	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment. (S.I.No.24P/91).	60.00	@ Rs:726/72	P. Sft	Rs: 43,603.00
					(Rs: seven hund: twenty six & seventy two only)
15	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).	34.00	@ Rs:12674/36	%Cft	Rs: 4,309.00
					(Rs: tweleve thous: six hund: seventy four & thirty six only)
16	Pacca brick work other than building including striking of joints upto 20' ft. height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).	627.00	@ Rs:12346/65	%Cft	Rs: 77,413.00
					(Rs: tweleve thous: three forty six & sixty five only)



S.No:	Description	Qty:	Rate	Unit	Amount
17	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).				
		554.00	@ Rs:660/- (Rs: six hund: sixty only)	% Sft	<u>Rs: 3,656.00</u>
18	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		2763.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	<u>Rs: 60,968.00</u>
19	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		2763.00	@ Rs:2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% Sft	<u>Rs: 60,717.00</u>
20	Cement pointing struck joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).				
		545.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	<u>Rs: 7,016.00</u>
21	Extra labour rate for making cemet plaster patta/band around straight are couyard opening and around the edges of roof slabs the wight not less tham 6' with fine finishing as directed by Engineer Incharge. (S.I.NO.35 P/54)				
		99.00	@ Rs: 19/36 (Rs: ninteen & thirty six only)	% S.ft	<u>Rs: 1,917.00</u>
22	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).				
		98.00	@ Rs:27747/06 (Rs: twenty seven thous: seven hund fourty seven & six only)	% Sft	<u>Rs: 27,192.00</u>
23	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).				
		842.00	@ Rs: 1948/10 (Rs: one thous: nine hund: fourty eight & ten only)	% Sft	<u>Rs: 16,403.00</u>
24	Distempering three coats. (S.I.No.24 (c) P/53).				
		1981.00	@ Rs:1079/65 (Rs: one thos: seventy nine & sixty five only)	% Sft	<u>Rs: 21,388.00</u>



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

25 Painting guard bars , gates iron bars gratings railings i/c standard barsees etc:
smiler open works.

96.00 @ Rs:1270/83 % S.ft Rs: 1,220.00
(Rs: one thous: two hund: seventy & eighty three only)

26 Providing and laying HALLA or pettern tiles glazed 8"x8"x1/4" on floor or wall facing in required
pattern of STILE specification jointed in white cement and pigment over a base of 1:2 grey ceme
3/4" thick including washing and filling of joints with slurry of white cement and pigment in desire
shape with finishing ,cleaning and cost of wax polish etc. complete including cutting tiles to prop
(S.I.No: 62 P.47).

84.00 @ Rs: 34520/31 % Sft Rs: 28,997.00
(Rs: thirty four thous: five hund: twenty & thirty one only)

G.Total: Rs: 947,523.0



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

1	P/f squating type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern wit internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less th clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble	2.00	@ Rs: 4802/60	Each	Rs: 9,605.00 (Rs: four thous: eight hund; two & sxity only)
2	S/F conceled stop cock of superior quality with C.P head 1/2" dia.	2.00	@ Rs: 889/46	P.No	Rs: 1,778.00 (Rs: eight hund; eighty nine fourty six only)
3	S/F long bib-cock of superior quality with C.P head 1/2" dia	2.00	@ Rs: 1384/24	P.No	Rs: 2,768.00 (Rs: one thous: three hund; eighty four & twenty four only)
4	providing chambers (15"X19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3 set-on 1:6 cement mortar 6" thick C.C. 1:4:8 in foundation 1/2" thick cement plaster 1:3. to all ins wall surface and to top 1" thick C.C 1:2:4. flooring complete with hinged clear opening (Wt: Qr) i fixed in cement conceate 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc (S.I.No: 2 P/20).	1.00	@ Rs: 5913/22	Each	Rs: 5,913.00 (Rs: five thous: nine hund; thirteen & twenty two only)
5	P/f water pumping set 3 HP unonablock single phase 220 volls with 1 1/2"x11/4" suntire delivery (60 ft head i/c making c.c 1:3:6 plater form of requred size fixing with units + hoolis E. S.I.No: 23P/33).	1.00	@ Rs:15254/48	P.No:	Rs: 15,254.00 (Rs: fifteen thous: two hund: fifty four & fouty eight only)
6	S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost c nute and bolts and fixing in plate iron of cement conceate 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (250 gallons).	1.00	@ Rs: 21989/61	P.Gallan	Rs: 21,990.00 (Rs: twnty one thous:nine hund; eighty nine & sixty one only)
G.Total:					Rs: 57,308.0



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

<u>(a) 1/2" Dia</u>	10.00	@ Rs: 66/81	P.Rft	Rs: 668.00
		(Rs: sixty six & eighty one only)		

<u>(b) 3/4" Dia</u>	50.00	@ Rs: 78/01	P.Rft	Rs: 5,850.00
		(Rs: sevnty eight & One only)		

<u>(C) 1" Dia</u>	10.00	@ Rs: 97/91	P.Rft	Rs: 979.00
		(Rs: ninety seven & ninty one only)		

<u>(d) 4" Dia</u>	16.00	@ Rs: 397/77	P.Rft	Rs: 6,364.00
		(Rs: three hund: ninty seven & seventy seven only)		

<u>(e) 6" Dia</u>	5.00	@ Rs: 757/59	P.Rft	Rs: 3,787.00
		(Rs: seven hund: fifty seven & fifty nine only)		

- 2 P/F Bend/ Elbow (90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in U.SA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<u>(a) 1/2" Dia</u>	3.00	@ Rs: 101/39	P.Rft	Rs: 304.00
		(Rs: one hund; one & thirty nine only)		

<u>(b) 3/4" Dia</u>	22.00	@ Rs: 103/05	P.No	Rs: 2,267.00
		(Rs: one hund; three & five only)		

<u>(C) 1" Dia</u>	3.00	@ Rs: 125/90	P.No	Rs: 377.00
		(Rs: one hund; twenty five & ninty only)		

<u>(d) 4" Dia</u>	2.00	@ Rs: 425/45	P.No	Rs: 850.00
		(Rs: four hund: twenty five & fourty five only)		



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>(a) 3/4" Dia</u>	9.00	@ Rs: 110/40	P.No	Rs:	993.00
		(Rs: one hundred; ten & fourteen only)			

<u>(b) 1" Dia</u>	2.00	@ Rs: 132/43	P.No	Rs:	264.00
		(Rs: one hundred: thirty two & forty three only)			

<u>(c) 4" Dia</u>	2.00	@ Rs: 712/75	P.No	Rs:	1,425.00
		(Rs: seven hundred: twelve & seventy five only)			

- 4 P/F COUPLING / SOCKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

<u>(b) 3/4" Dia</u>	17.00	@ Rs: 98/15	P.No	Rs:	1,668.00
		(Rs: ninety eight & fifteen only)			

- 5 P/F UNION of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>(a) 3/4" Dia</u>	2.00	@ Rs: 312/81	P.Rft	Rs:	625.00
		(Rs: three hundred; twelve & eighty one only)			

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 6 P/F UPVC P-Trap W/Elbow (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

4" Dia 4.00 @ Rs:818/04 P.No Rs: 3,272.00
(Rs: eight hund: eighteen & four only)

- 7 P/F UPVC PLUG ELBOW (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 2.00 @ Rs:677/65 P.No Rs: 1,355.00
(Rs: six hund; seventy seven & sixty five only)

- 8 P/F UPVC PLUG TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 2.00 @ Rs:847/42 P.No Rs: 1,695.00
(Rs: eight hund; forty seven & forty two only)

- 9 P/F UPVC VENT COWEL (LOCAL) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 2.00 @ Rs:187/93 P.No Rs: 375.00
(Rs: one hund: eighty seven & ninty three only)

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

10 Hand pump all accessories i/c fitting and fixing with local made container with wooden shoe i/c the complete.

(a) Filter	10.00	@ Rs: 76/05	P.Rft	Rs: 760.00
		(Rs: seventy six & five only)		

(b) G.I Pipe	70.00	@ Rs: 38/95	P.Rft	Rs: 2,726.00
		(Rs: thirty eight & ninty five only)		

(C) Machine	1.00	@ Rs: 1441/65	Each	Rs: 1,442.00
		(Rs: one thous: four hund: forty one & sixty five only)		

Total:	Rs: 38,046.00
---------------	----------------------

S.I	Rs: 57,308.00
------------	----------------------

Total:	Rs: 95,354.00
---------------	----------------------

BIDDING DOCUMENT**3**


Issued to

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- Integrated rehabilitation of Primary Schools in Taluka Larkano (2010-11 Programme) (16 Unlts) at GGPS. Model Backer (balance work) (ADP No. 132 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 400,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 8,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 20,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano. As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No. dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR



EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

SCHEDULE " B "

S.No: 3

NAME OF WORK:- INTEGRATED REHABILITATION OF PRIMARY SCHOOLS IN
TALUKA LARKANO (2010-11 PROGRAMME) (16-UNITS)
AT GGPS MODEL BACKER (BALANCE WORK)

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dimantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		22.00	@ Rs: 3327/50	% Cft	Rs: 732.00
					(Rs: three thous: two hund: twenty seven & fifty only)
2	Remoning cement or lime plaster. (S.i.No.53 P/13).				
		212.00	@ Rs:121/-	% Sft	Rs: 256.00
					(Rs: one hund: twenty one only)
3	Dismantling brick work in lime or cement mortor. (S.I.No.13 P/10).				
		11.00	@ Rs: 1285/63	% Cft	Rs: 141.00
					(Rs: one two hund: eighty five & sixty three only)
4	Dismantling glazed or encaustic tile etc (S.I.No: 55 P/13).				
		234.00	@ Rs: 786/50	% Sft	Rs: 1,840.00
					(Rs: seven hund: eighty six & fifty only)
5	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		15.00	@ Rs:11948/36	% Cft	Rs: 1,792.00
					(Rs: eleven thous: nine hund: eighty five & thirty six only)
6	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		10.00	@ Rs:12674/36	% Cft	Rs: 1,267.00
					(Rs: tweleve thous: six hund: seventy four & thirty six only)
7	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		12.00	@ Rs:337/-	P.Cft	Rs: 4,044.00
					(Rs: three hund: thirty seven only)



S.No:	Description	Qty:	Rate	Unit	Amount
8	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	1.00	@ Rs:5001/70	P.Cwt	Rs: 5,001.00
			(Rs: five thous: one & seventy only)		
9	Applying floating coat of cement 1/32" thick. (S.I.No.14 P/59).	212.00	@ Rs: 660/-	% Sft	Rs: 1,399.00
			(Rs: six hund: sixty only)		
10	Cement plaster (1:6) upto 20' ft: height 1/2" thick. (S.I.No: 13 (b) P.58).	253.00	@ Rs: 2206/60	% Sft	Rs: 5,582.00
			(Rs: two thous: two hund: six & sixty only)		
11	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I.No: 11 (a) P.58).	253.00	@ Rs: 2197/52	% S.ft	Rs: 5,560.00
			(Rs: two thous: one hund: ninty seven & twenty two only)		
12	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowka hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutter).	24.00	@ Rs: 902/93	P.Sft	Rs: 21,670.00
			(Rs: nine hund: two & ninty three only)		
13	Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).	18.00	@ Rs: 14429/25	%Cft	Rs: 2,597.00
			(Rs: fourteen thous: four hund: twenty nine & twenty five only)		
14	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).	292.00	@ Rs:27747/06	% Sft	Rs: 81,021.0
			(Rs: twenty seven thous: seven hund fourty seven & six only)		
15	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	1857.00	@ Rs:1887/40	% Sft	Rs: 35,049.00
			(Rs: one thous: eight hund; eighty seven & fourteen only)		



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 16 Providing and laying single per layer of polythene sheet 0.13 mm thick for water proffing as per specification and instruction of Engineer incharge. (S.I.No: 38 P/37).

727.00 @ Rs:10/70 P.Sft Rs: 7,778.00
(Rs: ten & seventy only)

- 17 Single layer of tiles 9" x4" 1/2" x2" laid over 4" earth 1" mud plaster without Bhoosa grouted with cement sand 1:3 on top of R: C:C slab provide with 34 Lbs. Bituman coating sand blined. (S.I.No: 5 P/33).

727.00 @ Rs: 5310/35 % S.ft Rs: 38,606.00
(Rs: five thous: three hund: ten & thrity five only)

- 18 Cement concreate brick or stone ballast 1/2" to 2" guage. (S.I.No: 4 (d) P/ 14).

12.00 @ Rs: 8122/95 % Cft Rs: 975.00
(Rs: eight thous: one hund: twenty two & ninty five only)

- 19 Providing and laying 1" thick topping cement concreate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).

126.000 @ Rs: 4411/82 % Sft Rs: 5,558.00
(Rs: four thous: four hund: eleven & eighty two only)

(B) 2"Thick

686.00 @ Rs: 3275/50 % S.ft Rs: 22,470.00
(Rs: three thous: two hund; seventy five & fifty only)

- 20 S/F in position approved grill of 3/4" x 1/4" size flat iron of approved design inluding painting three coats etc complete (weight not to be less than 3.7 Lbs/ sq. foot of finished grill). (S.I.No: 26 P.97).

36.00 @ Rs: 194/16 P.Sft Rs: 6,990.00
(Rs: one hund: ninty four & sixteen only)

- 21 Distempering two coats. (S.I.No.24 (b) P/53).

2006.00 @ Rs:1043/90 % Sft Rs: 20,940.00
(Rs: ten hund; forty three & ninty only)

S.No.	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 22 Preparing surface and painting of doors and windows any type (including edges)
(ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).

48.00 @ Rs:2116/41 % Sft Rs: 1,015.0
(Rs: two thous: one hund: sixteen & fourty one only)

- 23 Painting guard bars , gates iron bars gratings railings i/c standard barsees etc:
smiler open works.

96.00 @ Rs:1270/83 % S.ft Rs: 1,219.00
(Rs: one thous: two hund: seventy & eighty three only)

G.Total: Rs: 273,502.0



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less th clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble

3.00	@ Rs: 4802/60	P.No:	Rs: 14,407.00
(Rs: four thous: eight hund; two & sxity only)			

- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome brass waster of approved pattern 1-1/4" dia malleable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and flc for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P. 3)

1.00	@ Rs: 4928/-	P.Each	Rs: 4,928.00
(Rs: four thous: nine hund; twenty eight only)			

- 3 Add: Extra for labour for providing and fixing of erthern wire pedestal white or coloured glazed

1.00	@ Rs: 2533/47	P.No:	Rs: 2,533.00
(Rs: four thous: five hund; thirty three & fourty seven only)			

- 4 P/F 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden pleat (a) Standard pattern. (S.I.No.3 (a) P/7).

1.00	@ Rs:2376/-	P.Each	Rs: 2,376.00
(Rs: two thous: three hund; seventy six only)			

- 5 S/F conceled stop cock of superior quality with C.P head 1/2" dia.

4.00	@ Rs: 889/46	P.No	Rs: 3,557.00
(Rs: eight hund; eighty nine fourty six only)			

- 6 S/F long bib-cock of superior quality with C.P head 1/2" dia

4.00	@ Rs:1109/46	P.No	Rs: 4,437.00
(Rs: one thous: one hund; nine & forty six only)			

- 7 S/F Swan type piller cock of superior quality etc:

1.00	@ Rs: 877/80	P.Gallan	Rs: 877.00
(Rs: eight hund; seventy seven & eighty only)			

S.No:	Description	Qty:	Rate	Unit	Amount
8	providing chambers (15"X19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3:6 block set-on 1:6 cement mortor 6" thick C.C.1:4:8 in foundation 1/2" thick cement plaster 1:3. to all inside wall surface and to top 1" thick C.C 1:2:4. flooring complete with hinged clear opening (Wt: Qr) etc fixed in cement concrete 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc. (S.I.No: 2 P/20).	2.00	@ Rs: 5913/22	Each	Rs: 5,913.00
					(Rs: five thous: nine hund; thirteen & twenty two only)
9	P/f water pumping set 3 HP unonablock single phase 220 volls with 1 1/2"x1 1/4" suntire delivery (60 ft head i/c making c.c 1:3:6 plater form of required size fixing with units + hoolls E.S.I.No: 23P/33).	1.00	@ Rs:15254/48	P.No:	Rs: 15,254.00
					(Rs: fifteen thous: two hund: fifty four & fouty eight only)
10	Providing & fixing steel sinks stainless local make complete with cast iron or wrought iron brackets 6 inches built in wall, 1-1/2" c.p bubber plug chrome plated brass chain, 1-1/2" c.p brass waste, with 1-1/2" P.V.C waste pipe & making requisite number of holes in wall & plinth & floor for pipe connection & making good in cement concrete 1:2:4.(S.I.No: 19 P/6)	1.00	@ Rs: 5162/30	P.No	Rs: 5,162.00
					(Rs: five thous: one hund: sixty two & thirty only)
11	Supplying & fixing sink mixture cock of surperior quality with head of approved qaulity. (S.I.No:17 P/19).	1.00	@ Rs: 2745/60	P.No	Rs: 2,746.00
					(Rs: two thous: seven hund: forty five & sixty only)
			G.Total:		Rs: 62,189.00

BIDDING DOCUMENT**4**


Issued to _____

And charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Integrated rehabilitation of Primary Schools in Taluka Ratodero (2010-11 Programme) (13 Units) at GBPS, Khairodero (balance work) (ADP No. 133 of 2015-16)**
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 1,000,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 20,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 50,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 12 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR



EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

Schedule-B

4.

INTEGRATED REHABILITATION OF PRIMARY SCHOOLS IN TALUKA
Name of Work:- **RATODERO (2011-12 PROGRAME) (16 UNITS) @ GBPS KHAIRODERO**
TALUKA RATODERO DISTRICT LARKANO (BALANCE WORK).

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 22 P/10)	417.00	@ Rs: 3,327.50	% Cft	Rs: 13,876
	(Thirty three hundred twenty seven rup:& fifty paise only)				
2	Removing cement or lime plaster. (S.I No. 53 P/13)	2812.00	@ Rs: 121.00	% Cft	Rs: 3,403
	(One hundred & twenty rup: only)				
3	Dismantling brick work in lime or cement mortar. (S.I No.13 P/10)	80.00	@ Rs: 1,285.63	% Cft	Rs: 1,029
	(Twelve hundred eighty five rup & sixty three paise only)				
4	Applying Floating Coat of Cement 1/32" thick (S.I No. 14 P/52)	2812.00	@ Rs. 660.00	% Sft	Rs. 18,559
	(Six hundred Sixty Rup: Only)				
5	Cement Plaster 1:4 upto 12" height. 3/4" thick (S.I No. 11 (c) P/51)	2812.00	@ Rs: 3,015.76	% Sft	Rs: 84,803
	(Three thousand fifteen rup: & seventy six paise only)				
6	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	630.00	@ Rs: 3,176.25	% 0Cft	Rs: 2,001
	(Thirty one hundred seventy six rup: & twenty five paise only)				
7	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10. (S.I. No. 4 © P/14)	355.00	@ Rs: 8,694.95	% Cft	Rs: 30,867
	(Eighty six hund: ninty four rup: & ninty five paise only)				
8	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	516.00	@ Rs: 11,948.36	% Cft	Rs: 61,654
	(Eleven thousand nine hund: forty eight rup: & thirty six paise only)				



S #	Description	Qty	Rate	Unit	Amount
9	Pacca brick work in Ground i/c striking of joints in cement sand mortar ratio 1:6.	152.00 (Twelve thousand	Rs. 12,674.36	% Cft	Rs. 19,265
10	Supply and fixing sand under floor including plugging in to walls	855.00 (Eleven hundred	Rs: 1,141.25	% Cft	Rs: 9,758
11	Providing and Laying 3" thick top cement concrete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	1729.00 (Four	Rs: 4,411.82	% Sft	Rs: 76,280
12	Cement concrete plain i/c plastering, washing of stone aggregate with compacting, finishing & curing complete i/c screening & shuttering. Ratio 1:3:6.	123.00 (Fourteen thousand	Rs. 14,429.25	% Cft	Rs. 17,748
13	Providing & Laying HALF A or part required floor & pattern of S.H.L. over a base of 1:2 grey cement concrete glazed 6"x6"x1/4" on floor or wall facing in location jointed in white cement & pigment 1/4" thick etc i/c the cost of polish & cutting	876.00 (Thirty thousand	Rs. 30,509.77	% Sft	Rs. 267,266
14	Supply & Fixing in Position iron/3 coats etc. complete (weight not less than 3.7 Lbs./Sq. Foot of finished grill). (S.I No. 26 P/92)	58.00 (One hundred	Rs. 180.50	P. Sft	Rs. 10,469
15	P/F G.I frame Chowkats of size 7" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c heavy hold fasts filling with cement sand slurry of ratio 1:6 and repairing the jambs. The	72.00 (Two hundred	Rs: 228.90	P. Rft	Rs: 16,481
16	P/F G.I frame Chowkats of size 7" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c heavy hold fasts filling with cement sand slurry of ratio 1:6 and repairing the jambs. The	59.00 (Two hundred	Rs: 240.50	P. Rft	Rs: 14,190

S #	Description	Rate	Unit	Amount
17	1 st class deodar wood wrought iron cleats with hooks etc deodar pl	121.00 (Twelve hundred)	1,273.76 P. Sft	Rs: 154,125 Three rup: & Seventy Six paisa only)
(B)	<u>Shutter Only.</u>	18.00 (Nine hundred)	902.93 P. Sft	Rs: 16,253 Twenty three paisa only)
18	P/F of Portland Cement (4000) Without steel	144.00 (Four hundred)	226.02 P. Sft	Rs: 32,547 Twenty six rupees & two paisa only)
19	P & S of 3mm per layer of polythene	1895.00	10.70 P.Sft	Rs. 20,277 Ten rupees & seventy paisa only)
20	Providing & laying H.M.S.A on floor in form of STILE with grey cement mortar (3/1)	81.00 (Thirty four hundred)	34,520.31 % Sft	Rs: 27,961 Two hundred twenty rupees & thirty one paisa only)
21	Primary coat of chalk diste.	2812.00 (Four hundred)	442.75 % Sft	Rs: 12,450 Two rupees & seventy five paisa only)
22	Diste. (two coats) (1/1)	3319.00 (One thousand)	1,043.90 % Sft	Rs: 50,306 Fifty three rup: & ninty paisa only)
23	Painting Doors & Windows on (surface). (S.I No. 4 (c) P/67)	211.00 (Twelve hundred)	1,212.21 % Sft	Rs: 2,558 Two rup: & twenty one paisa only)
(b)	<u>Old Surface.</u>	320.00 (Three hundred)	1,498.48 % Sft	Rs: 4,840 Eight rup: & Forty Eight paisa only)
24	Painting of Cement	2403.00 (Two thousand)	1,984.10 % Sft	Rs: 47,678 Sixty rupees & six paisa only)

Total Rs:

1,016,641

S.#	Description	Rate	Unit	Qty	Amount
-----	-------------	------	------	-----	--------

PART - B

- 1 P/F squatting type white glazed earthen ware W.C pan of with i/c cost of flushing cistern with internal fitting & flush pipe with bend making good in cement concrete 1:2:4.(i) W.C not less than 19" clear opening b/w flushing & 6 gallons flushing tank with

2.00 @ Rs: 4,846.80 P. No. Rs. 9,694
(Forty eight hundred forty six rup: & eighty paisa only)

- 2 P/F 6"x6" C.I Floor Trap of the approved self cleaning & C.I secured down grating holes in walls plinth & floor for pipe connection & making good in C.C 1:2:4.

2.00 @ Rs: 2,024.46 P. No. Rs. 4,049
(Two thousand twenty four rup: only)

- 3 Providing G.I pipe specials & clamps etc i/c fixing, cutting & fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of the 6/4" dia

100.00 @ Rs: 95.79 P. Rft Rs. 9,579
(Ninty five rupees seventy nine paisa only)

1" dia

50.00 @ Rs: 128.55 P. Rft Rs. 6,428
(One Hunderd Twenty Eight rupees Fifty Five paisa only)

- 4 S/F C.P brass bib cock 1/2" dia standard pattern.

6.00 @ Rs: 1,109.46 P. No. Rs. 6,657
(Eleven hundred Nine rupees & Forty Six paisa only)

- 5 P/F approved quality A.C motor pumping set (Javed Engineering) made 1-1/4" 1" section & delivery with base & complying 1 H.Power single phase motor (Siemens make) 60" ft; head of 2800 KPM i/c the cost of C.I fitting nuts, bolts & the cost of 1:2:4 plate f

1.00 @ Rs: 5,115.00 P. No. Rs. 5,115
(Fifty one hundred fifteen rupees only)

- 6 S/F Fibre Glass Tank of approved quality & design & wall thickness as specified i/c the cost of nuts, bolts & fixing in plate form of cement concrete 1:2:6 & making connection for inlet-outlet & over flow pipe etc complete. (150 Gallons).

1.00 @ Rs: 21,989.61 P. Gallon Rs. 21,990
(Twenty One Thousand Nine Hund: Eight Nine Rup: & Sixty One paisan only)

- 7 Hand pump with all accessories i/c fitting & fixing with local made coir strainer with wooden shoe etc complete.

(a) Filter

10.00 @ Rs: 76.05 P. No. Rs. 761
(Seventy six rupees & five paisa only)

(b) G.I Pipe

90.00 @ Rs: 38.95 P. Rft Rs. 3,506
(Thirty eight rupees & ninty five paisa only)

(c) Machine

1.00 @ Rs: 1,441.60 P. No. Rs. 1,442
(Fourteen hundred forty one rup: & sixty paisa only)

S.I Rs. 69,218

N.S.I Rs. 10,824


Grand Total	Rs.	58,394
--------------------	------------	---------------

BIDDING DOCUMENT**5**Issued toAnd charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation of building for existing Primary Schools in Taluka Bakrani & Dokri (24 Units) (2011-12 Programme) at GBPS, Gul Muhammad Hisbani Tal: Bakrani**
(ADP No. 145 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 700,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 14,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 35,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commencement:- 15 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE-B 5

Name of work: Rehabilitation of Building for existing primary schools
 AT: GBPS Gul Muhammad Hisbani ADP:145

SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
1	Dismantling Pacca brick work in cement mortar	75.00	@Rs: 1285.63	%Cft	Rs:	964.00 (Rs: Twolve thousand Eighty Five & P.S Sixty Three only)
2	Dismantling C.C plain 1:2:4. (S.I.No 19 (c) P/11).	159.00	@Rs: 3327.50	%Cft	Rs:	5291.00 (Rs: Three thousand Three Hundred Twenty Seven & P.S Fifty
3	Removing Cement or Lime Plaster	1290.00	@Rs: 121.0	%Cft	Rs:	1561.00 (Rs: One Hunared Twenty One only)
4	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	35.00	@ Rs: 3176.25	%0 Cft	Rs:	317.00 (Three Thousand One Hund:Seventy Six & P.S Twenty Five or
5	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	190.00	@Rs: 8694.95	% Cft	Rs:	16520.00 (Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
6	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I No 4 (C) 23.	137.00	@ Rs: 11948.36	% S ft	Rs:	16369.00 (Eleven Thousand Nine Hund: Forty Eight & P.S Thirty Six
7	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	122.00	@Rs: 337.0	P.Cft	Rs:	41114.00 (Three Hundred Thirty Seven only)
8	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No 07 (b) P/20)	5.45	@ Rs: 5001.70	P.CWt	Rs:	27239.00 (Five Thousand One &P.S Seventy).
9	S/F sand floor and plugging into walls (S.I.No 29 P/31).	525.00	@Rs: 1141.25	%Cft	Rs:	5992.00 (Rs:One Thousand One Hund: Forty One & P.S Twenty Five
10	Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/24)	82.00	@Rs: 12674.36	% Cft	Rs:	10393.00 (Twlove thousand Six Hundred Seventy Four & Thirty Six only
11	Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/24)	180.00	@Rs: 12346.65	% Cft	Rs:	22224.00 (Tolive Thousand Three Hundred Forty Six & P.S Sixty Five c


SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
12	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I.No.13 P/57)	1855.00	@Rs: 2206.60	% Sft	Rs:	40932.00 (Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
13	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	1855.00	@ Rs: 2197.52	%S.ft	Rs:	40764.00 (Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)
14	Cement pointing and stricking of joints on walls ratio. 1: 2 (S.I No.19 (a) P/53)	240.00	@ Rs: 1287.44	%Cft	Rs:	3090.00 (Twolive Thousand Eighty Seven & P.S Fourty Four only)
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)	94.00	@ Rs: 1273.86	P.Sft	Rs:	119733.00 (Nine Hundraed Two P.S Ninty Three only)
16	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3 " thick. (S.I.No c	1396.00	@ Rs: 4411.82	% S.ft	Rs:	61589.00 (Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two or
(B)	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2 " thick. (S.i.No c	607.00	@ Rs: 3275.50	% S.ft	Rs:	19882.00 (Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two o
17	White wash three coats (S.I.No 26 (c) 59).	820.00	@Rs: 425.84	% Sft	Rs:	4150.00 (Rs: Four Hundred Twenty Five & P.S Eighty Four only)
18	Primary coat of chalk under distempring (S.I No: 23 P 59)	1869.00	@ Rs: 442.75	% Sft	Rs:	7959.00 (Four Hundred Fourty Two & P.S Seventy Five only)
19	Distempring three coats, (S.I.No 24 (b) P/59)	1869.00	@ Rs: 1043.90	% Sft	Rs:	20179.00 (Rs: One Thousand Seventy Nine & P.S Sixty Five only)
20	Painting doors & Window any type.	152.00	@ Rs: 2116.41	%Cft	Rs:	3217.00 (Rs: One Two Thousand one Hund: Sixteen & P.S Fourty One
21	Preparing surface painting guards bars gates iron grating railing i/c standards brass etc similar open work. (S.I.No 4 d P/76 ii)	96.00	@Rs: 1270.83	%Cft	Rs:	1220.00 (Rs: Five Hundred Eighty Five & Fifty Four only)

RS: 470699.00



Part B

1	P/F and 22"x16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a Primary Cost of red land painth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia	1.0	@Rs: 4253.90	Each	Rs:	4254.0
2	P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the building(S.I.No:1p8).	8	@Rs: 333.21	Each	Rs:	2666.0
3	Providing and fixing 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/4" thick and built and nuts and extra painting to match the colour of the building.	2.0	@Rs: 270.60	Each	Rs:	567.0
4	Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to macth the colour of the building and testing presure head of 200' and handing.					
(a)	<u>1/2" dia</u>	25.0	@ Rs: 7321	PRft	Rs:	1830.0
(b)	<u>3/4" dia</u>	50.0	@ Rs: 95.79	Rs:	Rs:	4790.0
5	P/F 4" dia C.I terminal guard i/c extra painting to match the colour of the building.(S.I.No:11p9).	2.0	@Rs: 389.70	Each	Rs:	779.0
6	S/F C.P brass bib cock 1/2"dia standard patter.	2.0	@Rs: 337.92	Each	Rs:	676.0
7	Providing RCC pipe with colors class "B" and dying trenches to required depth and fixing in position and cement mortar 1:1 and test <u>staff (a) 4" dia</u> refilling with excavted staff Lav:	10.0	@ Rs: 146.57	Each	Rs:	3758.0
(B)	<u>6" dia</u>	11.0	@ Rs: 199.25	Each	Rs:	2192.0
8	S/F conceled stop cock of superior quality with C.P head 1/2" dia.	2.0	@ Rs: 478.28	Rs:	Rs:	957.0
9	S/F long bib-cock of superior quality with C.P head 1/2" dia	1.0	@ Rs: 1109.46	Rs:	Rs:	1409.0
10	P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.	1.0	@ Rs: 5115	Rs:	Rs:	5115.0
11	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i.c the complete.					
(a)	<u>Filter</u>	10.0	@ Rs: 76/05	P.Rft	Rs:	761.0
(b)	<u>G.I Pipe</u>	40.0	@ Rs: 38/95	P.Rft	Rs:	3506.0
(c)	<u>Machine</u>	1.0	@ Rs: 1441.65	P.No	Rs:	1442.0

TOTAL: Rs: 34,702.00

BIDDING DOCUMENT**6**


Issued to

And charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation of building for existing Primary Schools in Taluka Bakrani & Dokri (24 Units) (2011-12 Programme) at GBPS. Bakrani**
(ADP No. 145 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 800,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 16,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 40,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 15 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE-B 6

Name of work: Rehabilitation Reconstruction of Existing Primary Schools in sindh
AT: GBPS Bakrani Taluka Bakrani

SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
1	Dismenlin Pacca brick work in cement mortar	103.60	@Rs: 1285.63	%Cft	Rs:	1332.00 (Rs: Twolve thousand Eighty Five & P.S Sixty Three only)
2	Dismenlin C.C plain 1:2:4. (S.I.No 19 (c) P/11).	217.60	@Rs: 3327.50	%Cft	Rs:	7220.00 (Rs: Three thousand Three Hundred Twenty Seven & P.S Fifty only)
3	Removing Cement or Lime Plaster	1247.65	@Rs: 121.0	%Cft	Rs:	1510.00 (Rs: One Hunared Twenty One only)
8	S/F sand floor and plugging into walls (S.I.No 29 P/31).	3628.00	@Rs: 1141.25	%Cft	Rs:	41404.00 (Rs:One Thousand One Hund: Fourty One & P.S Twenty Five only)
4	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I No 4 (C) 23.	771.25	@ Rs: 11948.36	% S.ft	Rs:	92152.00 (Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six only)
5	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	124.0	@Rs: 337.0	P.Cft	Rs:	41788.00 (Three Hundred Thirty Seven only)
6	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	4.982	@ Rs: 5001.70	P.CWt	Rs:	24918.00 (Five Thousand One &P.S Seventy).
7	Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/24)	73.12	@Rs: 12674.36	% Cft	Rs:	9268.00 (Twlove thousand Six Hundred Seventy Four & Thirty Six only)
8	Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/24)	337.00	@Rs: 12346.65	% Cft	Rs:	41670.00 (Tolive Thousand Three Hundred Fourty Six & P.S Sixty Five only)
9	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	264.00	@Rs: 8694.95	% Cft	Rs:	22955.00 (Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
10	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3 " thick. (S.I.No c P/46)	1509.0	@ Rs: 4411.82	% S.ft	Rs:	66575.00 (Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)
11	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I.No.13 P/57)	1877.65	@Rs: 2206.60	% Sft	Rs:	41432.00 (Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
12	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	1877.65	@ Rs: 2197.52	%S.ft	Rs:	41263.00 (Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)



SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
13	Cement pointing and striking of joints on walls ratio. 1: 2 (S.I No.19 (a) P/53)	450.00	@ Rs: 1287.44	%Cft	Rs:	5793.00 (Twelve Thousand Eighty Seven & P.S Forty Four only)
14	M/F Steel grated doors with 1/16" thick sheeting i/c agnle iron frame 2"x2"x1/3" square bars 4" centre to centers.	24.00	@ Rs: 726.72	%Sft	Rs:	17441.00 (Rs: Seven Hundred Twenty Six & P.S Seventy Two only)
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)	17.50	@ Rs: 1273.86	P.Sft	Rs:	15801.00 (Nine Hundraed Two P.S Ninty Three only)
16	P/F G.I frame of size 7x2 or 4-1/2"x3" for Window 20" guage G.I sheet i/c weldedhings & fixing etc i/c all carriagew tools and plants used in making and fixing (S.I.No:29 P/98)	16.50	@Rs: 228.90	P.Rft	Rs:	3777.00 (Rs: Two Hundrad Twenty Einght & P.S Ninty only)
17	P/F G.I frame of size 7x2 or 4-1/2"x3" for Door 20" guage G.I sheet i/c weldedhings & fixing etc i/c all carriagew tools and plants used in making and fixing (S.I.No:29 P/98)	26.98	@Rs: 240.50	P.Rft	Rs:	6489.00 (Rs: Two hundred Fourty & P>S Fifty only)
18	White wash three coats (S.I.No 26 (c) 59).	1397.50	@Rs: 425.84	% Sft	Rs:	11599.00 (Rs: Four Hundred Twenty Five & P.S Eighty Four only)
19	Distempring three coats, (S.I.No 24 (b) P/59)	4,428.0	@ Rs: 1079.65	% Sft	Rs:	47809.00 (Rs: One Thousand Seventy Nine & P.S Sixty Five only)
20	Painting doors & Window any type.	424.0	@ Rs: 2116.41	%Cft	Rs:	8974.00 (Rs: One Two Thousand one Hund: Sixteen & P.S Forty One onl)
21	S/Fin position iron steel grill of 3/4" X 1/4"flate iron of approved design i/c painting three coats etc complete with weigh not to beless than 3.7 Lbs sq: ft: of finished grill.	48.0	@Rs: 194.16	P.Sft	Rs:	9320.00 (Rs: One hundred Ninty Four & P.S Sixteen only)
22	Preparing surface painting guards bars gates iron grating railing i/c standards brass etc similar open work. (S.I.No 4 d P/76 ii)	160.00	@Rs: 1270.83	%Cft	Rs:	2033.00 (Rs: Five Hundred Eighty Five & Fifty Four only)
23	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approved make old surface.	522.00	@Rs: 1948.10	%Sft	Rs:	2122.00 (One Thousand Nine Hundred Forty Eight & P.S Ten only)
13	P/L Hala pattered tiles glazed 8"x8 1/4" of floor of wall cacing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile. (S.I No: 62 P/53)	187.00	@ Rs: 34520.31	%Sft	Rs:	64552.00 (Rs: Thity Four Thousand Five Hundred Twenty & P.S Thirty One)

RS: 629197.00




BIDDING DOCUMENT**7**Issued toAnd charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Construction of additional class rooms in existing Primary Schools in Taluka Larkano (2011-12 Programme) (16 class rooms) at GBPS. Doulat Chandio (1 C.Room)**
(ADP No. 147 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 950,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 19,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 47,500
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 15 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE " B "**S.No:****NAME OF WORK:-****CONSTRUCTION OF ADDITIONAL CLASS ROOMS
IN EXISTING PRIMARY SCHOOLS IN TALUKA
LARKANO (2011-12 PROGRAMME) (16-CLASS ROOMS)
AT GBPS DOULAT CHANDIO (1 C/ROOM).**

S.No. 7

S.No	Description	Qty:	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil	979.00	@ Rs:3176/25	%OCft	Rs: 3,102.00 (Rs: three thous: one hund: seventy hund: twenty five or
2	Cement concrete brick or stone ballaste 11/2" to 2" guage ratio 1:5:10.	163.00	@ Rs:8694/95	% Cft	Rs: 14,172.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6	742.00	@ Rs:11948/36	% Cft	Rs: 88,656.00 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	Filling, watering and ramming earth in floor with surplus earth from foundation lead upto one chain and lift upto 5' ft.	653.00	@ Rs:1512/50	% Cft	Rs: 988.00 (Rs: one thous: five hund: tweleve & fifty only)
5	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4	508.00	@ Rs: 337/-	P.Cft	Rs: 171,196.00 (Rs: three hund: thirty seven only)
6	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars	22.678	@ Rs: 5001/70	P.Cwt	Rs: 113,428.00 (Rs: five thosu: one & seventy only)
7	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	2080.00	@ Rs: 1141/25	% Cft	Rs: 23,738.00 (Rs: one thous: one hund: forty one & twenty five only)

S.No:	Description	Qty:	Rate	Unit	Amount
8	Pacca brick work in Ground floor i/c striking of joints cement sand mortor Ratio 1:6				
		1082.00	@ Rs:12674/36	% Cft	<u>Rs: 137,137.00</u>
					(Rs: twelve thous: six hund: seventy four & thirty six only)
9	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:6:12. (S.I.No: 4 (d) P.17).				
		137.00	@ Rs: 8122/95	% Cft	<u>Rs: 11,128.00</u>
					(Rs: eight thous: one hund: twenty two & ninty five only)
10	P/F G.I frame chokats of size 7" x2" or 4" x 3" for doors using 20 gauge G.I sheet i/c solded hignes and fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and planst used in making and fixing.				
		18.00	@ Rs:228/90	P.Rft	<u>Rs: 4,120.00</u>
					(Rs: two hund: twenty eight & ninty only)
11	P/F G.I frame chowkhats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c sold fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and used in making and fixing .(S.I.No.28 P/98).				
		83.00	@ Rs: 240/50	P.Rft	<u>Rs: 19,962.00</u>
					(Rs: two hund: forty & fifty only)
12	Cement plaster (1:6) upto 12' ft: height 1/2" thick.				
		2034.00	@ Rs:2206/60	% S.ft	<u>Rs: 44,882.00</u>
					(Rs: two thous: two hund: six & sixty only)
13	Cement plaster 1:4 upto 12' ft; height 3/8" thick.				
		2034.00	@ Rs: 2197/52	% S.ft	<u>Rs: 44,698.00</u>
					(Rs: two thous: one hund: ninty seven & twenty two only)
14	Notice board made with cement.				
		32.00	@ Rs: 58/11	P.Sft	<u>Rs: 1,860.00</u>
					(Rs: fifty eight & eleven only)
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. (Only Shutters).				
		61.00	@ Rs:902/93	P.Sft	<u>Rs: 55,079.00</u>
					(Rs: nine hund: two & ninty three only)

S.No:	Description	Qty:	Rate	Unit	Amount
16	Cement pointing and stricking of joints on walls ratid. 1: 2	616.00	@ Rs: 1287/44	% S.ft	Rs: 7,931.00 (Rs: one thous: two hund: eighty seven & fourty four only)
17	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3" thick.	460.00	@ Rs: 3275/50	% S.ft	Rs: 15,067.00 (Rs: three thous: two hund; seventy five & fifty only)
	<u>(B) 1-1/2" thick</u>				
		716.00	@ Rs:2935/10	% S.ft	Rs: 21,015.00 (Rs: two thous: nine hund; thirty five & ten only)
18	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	616.00	@ Rs: 1948/10	% Sft	Rs: 12,000.0 (Rs: one thous: nine hund: fourty eight & ten only)
19	White wash three coats.	639.00	@ Rs:829/95	% S.ft	Rs: 5,303.00 (Rs: eight hund: twenty nine & ninty five only)
20	Primary coat of chalk under distempring.	1993.00	@ Rs: 442/75	% Sft	Rs: 7,938.00 (Rs: four hund; fourty tow & seventy five only)
21	Distempring three coats	1993.00	@ Rs:1079/65	% Sft	Rs: 19,358.00 (Rs: one thos: seventy nine & sixty five only)
22	Painting doors and windows anytype	121.00	@ Rs:2116/41	% S.ft	Rs: 2,561.00 (Rs: two thous: one hund: sixteen & fourty one only)
G.Total:					Rs: 825,319.0




BIDDING DOCUMENT**8**Issued toAnd charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Construction of additional class rooms in existing Primary Schools in Taluka Bakrani/ Dokri (16 C.Rooms) (2011-12 Programme) at GBPS. Shadan Jatoi (1 C.Room)**
(ADP No. 148 of 2015-16)
- c) Procuring Agency's address:- Near Hgih Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 1,000,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 20,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (Including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 50,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 15 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE-B 8**Name of work:**Construction of Additional Class Rooms in Existing Primary Schools in T:
At:GBPS Shadan Jatoi (1.C/R) ADP:148

SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
1	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	834.00	@ Rs: 3176.25	%0 Cft	Rs:	2649.00 (Three Thousand One Hund:Sevnty Six & P.S Twenty Five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5: 10 (S.I.No 4 (C) P/16).	419.00	@Rs: 9416.28	% Cft	Rs:	36508.00 (Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
3	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) 23.	890.00	@ Rs: 11948.36	% S.ft	Rs:	106441.00 (Eleven Thousand Nine Hund: Forty Eight & P.S Thirty Six only)
4	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	209.11	@Rs: 337 0	P.Cft	Rs:	70470.00 (Three Hundred Thirty Seven only)
5	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	10.27	@ Rs: 5001.70	P.CWt	Rs:	51361.00 (Five Thousand One &P.S Sevnty).
6	Filling watering and remaing earth under floor with Surplus lead up to one chain and lift up to f5'ft	4756.00	@Rs: 1512.25	% C.ft	Rs:	17264.00 (One thousand four hundred eighty eight & p.s thiry only)
7	Pacca brick work in Ground floor i/c striking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P/14)	1210.00	@Rs: 12674.36	% Cft	Rs:	153360.00 (Twlove thousand Six Hundred Sevnty Four & Thirty Six only)
8	Supplying Girders at site of work(Sch: of Material)	10.00	@ Rs: 3850.0	P.Cwt	Rs:	38500.00 (Three Thousand Eight Hundred Fifty only)
9	Supplying T-iron at site of work (Sch: of Material).	9.63	@ Rs: 3375.0	P.Cwt	Rs:	34437.00 (Three Thousand Three Hundred Sevnty Five only)
10	Errection of rolled steel beams or old rails in roof etc crrection and fixing in position.	19.63	@ Rs: 186.44	P.Cwt	Rs:	3658.00 (One Hundred Eighty Six & P.S Thirty Four only)
11	Providing and laying single per layer of polythen sheet 0.13 mm thick for water proffing as per specification and instruments of Engineer Incharge.	677.48	@Rs: 10.70	P.Sft	Rs:	7249.00



SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
12	First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leaping over 1/4" thick cement plaster 1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in 1:3 cement mortar with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)	677.48	@ Rs: 11443.10	%Sft	Rs:	77525.00 (Rs:Eleven thousand Four Hundred Forty Three & P.S Ten)
13	Preparing surface painting guards bars gates iron grating railing i/c standards brass etc similar open work. (S.I.No 4 d P/76 ii)	488.75	@Rs: 1270.83	%Cft	Rs:	6211.00 (Rs: Five Hundred Eighty Five & Fifty Four only)
14	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	2093.66	@Rs: 2206.60	% Sft	Rs:	46199.00 (Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
15	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	2093.66	@ Rs: 2197.52	%S.ft	Rs:	46009.00 (Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)
16	Notice board made with cement.	32.00	@Rs: 58.11	% Sft	Rs:	2988.00 (Eighty Eight & P.S Eleven only)
17	P/F G.I frame of size 7x2 or 4-1/2"x3" for Window 20" guage G.I sheet i/c weldedhings & fixing etc i/c all carriagew tools and plants used in making and fixing (S.I.No:29 P/98)	18.00	@Rs: 228.90	P.Rft	Rs:	4120.00 (Rs: Two Hundrad Twenty Einght & P.S Ninty only)
18	P/F G.I frame of size 7x2 or 4-1/2"x3" for Door 20" guage G.I sheet i/c weldedhings & fixing etc i/c all carriagew tools and plants used in making and fixing (S.I.No:29 P/98)	84.00	@Rs: 240.50	P.Rft	Rs:	20202.00 (Rs: Two hundred Fourty & P>S Fifty only)
19	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)	60.57	@ Rs: 902.93	P.Sft	Rs:	54694.00 (Nine Hundraed Two P.S Ninty Three only)
20	Cement pointing and stricking of joints on walls ratio. 1: 2 (S.I No.19 (a) P/53)	876.00	@ Rs: 1287.44	%Cft	Rs:	11278.00 (Twolve Thousand Eighty Seven & P.S Fourty Four only)
21	S/Fin position iron steel grill of 3/4" X 1/4"flate iron of approved design i/c painting three coats etc complete with weigh not to beless than 3.7 Lbs sq: ft: of finished grill.	150.78	@Rs: 194.16	P.Sft	Rs:	6772.00 (Rs: One hundred Ninty Four & P.S Sixteen only)
22	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3 " thick. (S.I.No c P/46)	440.00	@ Rs: 4411.82	% S.ft	Rs:	19412.00 (Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)
23	Primary coat of chalk under distempring (S.I No: 23 P 59)	2093.66	@ Rs: 442.75	% Sft	Rs:	9270.00 (Four Hundred Fourty Two & P.S Seventy Five only)
24	Distempring three coats, (S.I.No 24 (b) P/59)	2093.66	@ Rs: 1043.90	% Sft	Rs:	21856.00 (Rs: One Thousand Seventy Nine & P.S Sixty Five only)

SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
25	White wash three coats (S.I.No 26 (c) 59).					
		440.00	@Rs: 425.84	% Sft	Rs:	3652.00
						(Rs: Four Hundred Twenty Five & P.S Eighty Four only)
26	Painting doors & Window any type.					
		152.00	@ Rs: 2116.41	%Cft	Rs:	1763.00
						(Rs: One Two Thousand one Hund: Sixteen & P.S: Forty One onl
27	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approved make old surface.					
		876.00	@Rs: 1948.10	%Sft	Rs:	17065.00
						(One Thousand Nine Hundred Fourty Eight & P.S Ten only)
28	P/L Hala patternen tiles glazed 8"*8 1/4" of floor of wall cacing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile. (S.I No: 62 P/53)					
		30.82	@ Rs: 34520.31	%Sft	Rs:	10639.00
						(Rs: Thity Four Thousand Five Hundred Twenty & P.S Thirty One)

RS: 801552.00




BIDDING DOCUMENT**9**Issued toAnd charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Integrated rehabilitation of Elementary Schools in Taluka Ratodero (12 Units) (2013-14 Programme) at GGPS. Usman Unar (ADP No. 157 of 2015-16)**
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 600,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 12,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 30,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

9

Schedule-B

INTEGRATED REHABILITATION OF ELEMENTARY SCHOOLS IN TALUKA

Name of Work:- **RATODERO (12 UNITS) (2013-14 PROGRAMME) @GGPS USMAN UNAR**
TALUKA RATODERO DISTRICT LARKANO

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	450	@ Rs: 3,176.25	% OCft	Rs: 1,429
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	150	@ Rs: 8,694.95	% Cft	Rs: 13,042
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	678.00	@ Rs: 11,948.36	% Cft	Rs: 81,010
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Supply and fixing sand under floor including plugging in to walls	2125	@ Rs: 1,141.25	% Cft	Rs: 24,252
	(Eleven hundred forty one rupees & twenty five paisa only)				
5	Providing and Laying 2" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	800.00	@ Rs: 4,411.82	% Sft	Rs: 35,295
	(Forry four hundred eleven rup: & eighty two paisa only)				
6	Pacca brick work other than building $\frac{1}{c}$ striking of joints in cement sand mortar ratio 1:6.	300.00	@ Rs: 12,346.65	% Cft	Rs: #RFFI
	(Twelve thousand three hund: forty six rup: & sixty five paisa only)				
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	400	@ Rs: 2,206.60	% Cft	Rs: 8,826
	(Twenty tow hund: six rup: & sixty paisa only)				
8	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	400	@ Rs: 2,197.52	% Sft	Rs: 8,790
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	400.00	@ Rs: 1,287.44	% Sft	Rs: 5,150
	(Twelve hundred eighty seven rupees & forty for paisa only)				
10	White wash two coats. (S.I. No. 26 P No. 54)				

S #	Description	Qty	Rate	Unit	Amount
		168.00	@ Rs. 425.00	% Sft (Four hundred twenty five rup: & paisa only)	Rs. 3,598
11	Primary coat of chalk distemper(S.I No. 23 P/53)	627	@ Rs: 442.75	% Sft (Four hundred forty two rupees & seventy five paisa only)	Rs: 2,776
12	Distemping two coats.(S.I No. 24(b) P/54)	567	@ Rs: 1,043.90	% Sft (One thousand forty three rup: & ninty paisa only)	Rs: 5,919
13	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick	80	@ Rs. 27,678.86	% Cft (Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)	Rs. 22,143
14	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)	252	@ Rs. 28,253.61	% P.Cwt (Twenty seven thousand seven hund: forty seve rupp: & six paisa only)	Rs. 71,199
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)	203	@ Rs. 30,509.77	% Sft (Thirty thousand five hund: nine rupees & seventy seven paisa only)	Rs. 61,935
16	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	23.00	@ Rs: 337.00	P.Cft (Three hundred Thirty seven rup: only)	Rs: 7,751
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	1.129	@ Rs: 5,001.70	P.Cwt (Five thousand one rup: & seventy paisa only)	Rs: 5,647
18	Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. ... P/92)	68.00	@ Rs. 180.50	P. Sft (One hundred eighty Five rupees & fifty Paisa only)	Rs. 12,274

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel
 44 @ Rs: 226.00 P. Sft Rs: 9,944
 (Two hundred twenty six rupees only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c
 20 Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio 1:6
 and repairing the jambs. The cost also i/c all carriage, tools and pla
 7 @ Rs: 228.90 P. Rft Rs: 1,602
 (Two hundred twenty eight rupees & ninty paisa only)

1st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts
 21 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25
 P/60)
 6.00 @ Rs: 902.93 P. Sft Rs: 5,418
 (Nine hund: two rup: & ninty three paisa only)


Total Rs: 421,893

BIDDING DOCUMENT**10**Issued toAnd charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: _____/_____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation & Provision of missing facilities of building for existing Secondary / Higher Secondary Schools Taluka Larkano (09 Units) (2010-11 Prog:)at GGHS(EM) Larkano (balance work)**
(ADP No. 164 of 2015-16)
- c) Procuring Agency's address:- Near Hgih Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 600,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 12,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 30,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 15 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE " B "

S.No: 10

NAME OF WORK:- REHABILITATION & PROVISION OF MISSING FACILITIES OF BUILDING FOR EXISTING SECONDARY / HIGHER SECONDARY SCHOOLS IN TALUKA LARKANO (09-UNITS) (2010-11 PROGRAMME) AT GGHS (E M) LARKANO (BALANCE WORK).

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dimantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		175.00	@ Rs: 3327/50	% Cft	Rs: 5,823.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
2	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		0.482	@ Rs:5001/70	P.Cwt	Rs: 2,410.0
			(Rs: five thous: one & seventy only)		
3	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		5.000	@ Rs:337/-	P.Cft	Rs: 1,685.00
			(Rs: three hund: thirty seven only)		
4	Providing and fixing ornamental cement jalli 2" thick. (1:2:4) with out steel. (S.I.No.11 P/17).				
		647.000	@ Rs:226/02	P.Sft	Rs: 146,234.00
			(Rs: two hund; twenty six & two only)		
5	Single layer of tiles 9" x4" 1/2" x2" laid over 4" earth 1" mud plaster without Bhoosa grouted with cement sand 1:3 on top of R: C:C slab provide with 34 Lbs. Bituman coating sand blined. (S.I.No: 5 P/33).				
		2235.000	@ Rs: 5310/35	% S.ft	Rs: 118,686.00
			(Rs: five thous: three hund: ten & thrity five only)		
6	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).				
		511.00	@ Rs:27747/06	% Sft	Rs: 141,787.00
			(Rs: twenty seven thous: seven hund forty seven & six only)		
7	Cement Pointing 1:2 flash on floor. (S.I.No: 18 P/52).				
		2235.00	@ Rs: 939/57	% S.ft	Rs: 20,999.00
			(Rs: nine hund: thirty nine & fifty seven only)		



S.No:	Description	Qty:	Rate	Unit	Amount
15	Distempering two coats.	1110.00	@ Rs:1043/90	% Sft	<u>Rs: 11,587.00</u>
					(Rs: ten hund; forty three & ninty only)
16	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	547.00	@ Rs. 1948/10	% Sft	<u>Rs 10,656.00</u>
					(Rs: one thous: nine hund: forty eight & ten only)
17	Painting guard bars , gates iron bars gratings railings i/c standard barsees etc: smiler open works.	213.00	@ Rs:2116/41	% S.ft	<u>Rs: 4,507.00</u>
					(Rs: two thous: one hund: sixteen & forty one only)
18	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowka hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Surface).	22.00	@ Rs: 902/93	P.Sft	<u>Rs: 19,864.00</u>
					(Rs: nine hund: two & ninty three only)
G.Total:					<u>Rs: 552,848.00</u>




S.No:	Description	Qty:	Rate	Unit	Amount
8	Pacca brick work in First floor in cement sand mortar Ratio 1:6.	16.00	@ Rs:13112/99	P.Cwt	Rs: 2,098.00 (Rs: thirteen thous: one hund; tweleve & ninty nine only)
9	Cement plaster 1:6 upto 12' height (b) 1/2" thick.	44.00	@ Rs:2346/60	% Sft	Rs: 1,032.00 (Rs: two thous: three hund: forty six & sixty only)
10	Cement plaster 1:4 upto 12' height (a) 3/8" thick.	44.00	@ Rs:2337/52	% Sft	Rs: 1,028.00 (Rs: two thous: three hund: thirty seven & fifty two only)
11	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete (weight not to be less than 3.7 lbs/Sq.foot of finished grill).(S.I.No.26 P/92).	44.00	@ Rs:180/50	P. Sft	Rs: 7,942.00 (Rs: one hund: eighty & fifty only)
12	Galvanized wire gauze fixed to chowkats wikth 3/4" deodar stips and screws. (S.I.No.14 (d) P/59).	88.00	@ Rs:190/72	P. Sft	Rs: 16,783.00 (Rs: one hund; ninty & seventy two only)
13	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	700.00	@ Rs: 4411/82	% Sft	Rs: 30,882.00 (Rs: four thous: four hund: eleven & eighty two only)
(B) <u>2"Thick</u>					
		12.00	@ Rs: 3275/50	% S.ft	Rs: 3,930.00 (Rs: three thous: two hund; seventy five & fifty only)
14	Primary coat of chalk distempering. (S.I.No.23 P/57).	1110.00	@ Rs:442/75	% Sft	Rs: 4,915.00 (Rs: four hund; fourty two & seventy five only)

BIDDING DOCUMENT**11**Issued toAnd charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation of building for existing High / Higher Secondary Schools in Taluka Bakrani (07 Units) (2011-12 Programme) at GBHS, Arija (balance work)**
(ADP No. 179 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 1,000,000
- e) Amount of Bid Security (2%) (fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 20,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 50,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commencement:- 15 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No. dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE-B 11

Name of work: Rehabilitation of building for existing High/Higher Secondary School
At: GBHS Arija Taluka Bakrani.

SNo	Description	Qty:	Rate	Unit	Rs:	Amount.
1	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	1056.00	@ Rs: 3176.25	%0 Cft	Rs:	3354.00 (Three Thousand One Hund:Seventy Six & P.S Twenty Five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	1185.00	@Rs: 8694.95	% Cft	Rs:	103035.00 (Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
3	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I No 4 (C) 23.	617.00	@ Rs: 11948.36	% S.ft	Rs:	73721.00 (Eleven Thousand Nine Hund: Forty Eight & P.S Thirty Six only)
4	S/F sand floor and plugging into walls (S.I.No 29 P/31).	3926.00	@Rs: 1141.25	%Cft	Rs:	44805.00 (Rs:One Thousand One Hund: Forty One & P.S Twenty Five only)
5	Pacca brick work in Ground floor i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/24)	88.00	@Rs: 12674.36	% Cft	Rs:	11153.00 (Twlove thousand Six Hundred Seventy Four & Thirty Six only)
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	104.33	@Rs: 337.0	P.Cft	Rs:	35159.00 (Three Hundred Thirty Seven only)
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No 07 (b) P/20)	4.65	@ Rs: 5001.70	P.CWt	Rs:	23258.00 (Five Thousand One &P.S Seventy).
8	Pacca brick work in other than building i/c striking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/24)	54.00	@Rs: 12346.65	% Cft	Rs:	6667.00 (Tolive Thousand Three Hundred Forty Six & P.S Sixty Five only)
9	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3 " thick. (S.I.No c P/46)	2042.00	@ Rs: 4411.82	% S.ft	Rs:	66886.00 (Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)
10	S/Fin position iron steel grill of 3/4" X 1/4"flate iron of approved design i/c painting three coats etc complete with weigh not to beless than 3.7 Lbs sq: ft: of finished grill.	540.00	@Rs: 194.16	P.Sft	Rs:	104846.00 (Rs: One hundred Ninty Four & P.S Sixteen only)
11	P/L Hala pattered tiles glazed 8"*8 1/4" of floor of wall cacing in required pattern of cement over a base of 1:2 grey cement mortar 3/4" thick i/c washing and filling joints with slury of white cement and pigment in desired shape with finishing cleaning and cost of wax polish etc complete i/c cutting tile to proper profile. (S.I No: 62 P/53)	289.00	@ Rs: 34520.31	%Sft	Rs:	99764.00 (Rs: Thity Four Thousand Five Hundred Twenty & P.S Thirty One)

SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
12	C.C plain i/c compacting and curring etc complete i/c screening and washaning of stone aggregate without shuttering Ratio. 1:2:4 (S.I.No 5 P/18)	56.30	@Rs: 14429.25	%Cft	Rs:	8124.00 (Rs: Fourteen thousand Four Hundred Twenty Nine & P.S Twenty F
13	White glaze tiles 1/4" thick dado jointed white cement and laid over 1:2 cement sand mortar 3/4"thick i/c finishing.	215.00	@ Rs: 28253.61	P.Sft	Rs:	60745.00 (Rs: Twenty Thousand Two Hund:Fifty Three & P.S Sixty One only)
14	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2 (S.I No. 24 P/48).	181.00	@Rs: 21000.00	P.Sft	Rs:	38010.00 (Rs: Ten thousand four hundred sixteen & p.s thirty four only)
15	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	320.00	@Rs: 2206.60	% Sft	Rs:	7061.00 (Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
16	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	320.00	@ Rs: 2197.52	%S.ft	Rs:	7032.00 (Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)
17	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approved make old surface.	320.00	@Rs: 1948.10	%Sft	Rs:	6234.00 (One Thousand Nine Hundred Fourty Eight & P.S Ten only)
18	Distemping three coats, (S.I.No 24 (b) P/59)	800.00	@ Rs: 1079.65	% Sft	Rs:	8637.00 (Rs: One Thousand Seventy Nine & P.S Sixty Five only)

RS: 708491.00



S.No	Description	Qty:	Rate	Unit		Amount
------	-------------	------	------	------	--	--------

Part B

1	P/F Squating type white glass W.C pan of i/c coat of finishing cistring with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	3.0 @ Rs: 4846.60	P.No:	Rs:	14539.0
2	P/F and 22"x16" lavatory basion in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a Primary Cost of red land painth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia	2.0 @Rs: 4253.90	Each	Rs:	4254.0
2	P/F 6"x2" or 6"x3" C.I floor trap.	1.0 @Rs: 2024.43	Rft	Rs:	2024.0
3	P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon coonections (S.I.No: 9p3).	1.0 @Rs: 77.85	Each	Rs:	78.0
4	P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the buildding(S.I.No:1p8).	12.0 @Rs: 333.21	Each	Rs:	3999.0
5	Providing and fixing 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/4" thick and built and nuts and extra painting to match the colour of the building.	2.0 @Rs: 270.60	Each	Rs:	541.0
6	Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to macth the colour of the building and testing presure head of 200' and handing.				
(a)	<u>1/2" dia</u>	25.0 @ Rs: 7321	PRft	Rs:	1830.0
(b)	<u>3/4" dia</u>	25.0 @ Rs: 95.79	Rs:	Rs:	2394.0
7	P/F 4" dia C.I terminal guard i/c extra painting to match the colour of the building.(S.I.No:11p9).	2.0 @Rs: 389.70	Each	Rs:	779.0
8	Providing and fixing full way gun metal vallues with whelds threaded of flained ends with rubber washing (ii) 3/4" (Light pattern).	1.0 @Rs: 197.12	Each	Rs:	197.0
9	S/F C.P brass bib cock 1/2"dia standard patter.	2.0 @Rs: 337.92	Each	Rs:	676.0
10	S/F conceled stop cock of superior quality with C.P head 1/2" dia.	1.0 @ Rs: 478.28	Rs:	Rs:	478.0
11	S/F long bib-cock of superior quality with C.P head 1/2" dia	1.0 @ Rs: 1109.46	Rs:	Rs:	1109.0
12	P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.	1.0 @ Rs: 5115	Rs:	Rs:	5115.0
13	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete.(250 Gallons).	250.0 @ Rs: 87.95	Rs:	Rs:	21987.0
14	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i.c the complete.				
(a)	<u>Filter</u>	10.0 @ Rs: 76/05	P.Rft	Rs:	761.0
(b)	<u>G.I Pipe</u>	80.0 @ Rs: 38/95	P.Rft	Rs:	3116.0
(c)	<u>Machine</u>	1.0 @ Rs: 1441.65	P.No	Rs:	1442.0



TOTAL: Rs: 65,319.00

BIDDING DOCUMENT**12**


Issued to _____

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: _____/_____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation / Improvement of Historical Educational Buildings in District Larkano (2011-12 Programme) (03 Units) at GGHSS, Larkano (Elect.)**
(ADP No. 184 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 250,000
- e) Amount of Bid Security (2%) (fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 5,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 12,500
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commencement:- 6 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

Schedule B 12

Name of Work:- Rehabilitation/ Improvement of Historical Education buildings in District Larkano
(2010-11 Progg:) at: GGHSS Larkano (Electric Taluka Larkano ADP No: 184

SNo:	ITEM OF WORK	Qty:	Rate	Amount.
1	Wiring for light or fan (point with 1/1.13(3/029)PVC insulated wire in 20mm(3/4") channel patti on surface as required (S.I.No: 129 P 15).	35.00	@ Rs: 910.0 P.Point	Rs: 31,850.00
2	Wiring for Plug point with (3/029) PVC insulated wire in 20mm(3/4") Channel patti on surface as required (S.I.No: 130 P 15)	10.00	@ Rs: 742.0 P.Point	Rs: 7,420.00
3	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/029) Copper conductor in 3/4" dia PVC conduit on surface (S.I.No: 3 P 1)	300.00	@ Rs: 171.0 P.Meter	Rs: 51,300.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/044)(6 MM2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 5 P 1).	110.00	@ Rs: 305.0 P.Meter	Rs: 33,550.00
4	Providing and laying (Main or sub-Main) PVC insulated wirh size 2-7/052)(10mm2) Copper conductor in 1" dia PVC conduit on surface (S.I.No: 6 P 1).	100.00	@ Rs: 428.0 P.Meter	Rs: 42,800.00
5	Providing & Fixing A.C one way S.P 5ampsswitch flush type (S.I.No: 219 P 33)	40.00	@ Rs: 54.0 P.Each	Rs: 2,160.00
6	Providing & Fixing 2 pin 5 amps plug & socket flush type. (S.I.No: 225 P 33)	8.00	@ Rs: 83.0 P.Each	Rs: 664.00
7	Providing & Fixing Brass Battern holder. (S.I.No: 232 P 33)	40.00	@ Rs: 70.0 P.Each	Rs: 2,800.00
8	P/Fixing A.C Baklite Ceiling rose with two terminals (S.I.No: 228 P 33)	12.00	@ Rs: 72.0 P.Each	Rs: 864.00
9	Providing and fixing brass ceiling fan 56" (good quality).	14.00	@ Rs: 3185.0 P.Each	Rs: 44,590.00
10	Providing & Fixing flush type S.P plug socket switch and shoe unit on given board recessed in the walls or columns & covered with plastic sheet (S.I.No: 18 P 11)	2.00	@ Rs: 156.97 P.Each	Rs: 313.00
11	Fixing A.C ceiling fan regulator on S.W board.(S.I.No: 1 (b) P 14)	14.00	@ Rs: 91.30 P.Each	Rs: 1,278.00
12	P/F mild steel bar fan clam 15.8 mm (5/8") dia suitable for RCC roof.(S.I.No: 1 P 14)	14.00	@ Rs: 141.01 P.Each	Rs: 1,974.00
13	P/F Earthing set with 2'x2'x1/2" copper plate buried in ground at a depth of 12" or less if water comes out from the ground level with salt and charcoal,etc,i/c making the pit 12" deep by excavation of all type of soil. Earth Plate to be connected with No:8 S.W.G bare copper wire run in 1/2"dia C.I pipe straight from the earth upto metallie electrical assaray i/c providing necessary tee,(S.I.No: 22 P26).	1.00	@ Rs: 2570.37 P.Each	Rs: 2,570.37
14	P/F Cirecuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board necessary connection. (S.I.No: 2 P 20)	4.00	@ Rs: 948.0 P.Each	Rs: 3,792.00
15	P/F Energy saver superior quality i/c fixing on extg: holder etc complete (S.I.No: 6 P 33)	45.00	@ Rs: 497.0 P.Each	Rs: 22,365.00

TOTAL: Rs: 250,290.4



IN

BIDDING DOCUMENT**13**


Issued to

And charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Construction of Computer Block at Govt. Boys Higher Secondary School Naudero (2011-12 Programme)**
GBHSS. Naudero (balance work)
(ADP No. 189 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 1,000,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 20,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 50,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

Schedule-B 13Name of Work:- **CONSTRUCTION OF COMPUTER BLOCK @GBHSS NAUDERO (2011-12 PROGRAMME) TALUKA RATODERO DISTRICT LARKANO.**

S #	Description	Qty	Rate	Unit	Amount
1	P/F 3/8" thick marble tiles of approved quality & colour shade size 8"x4/6"x4" in dado skirting & facing removal / tucking of existing plaster surface etc over 1/2" thick base of cement mortar 1:3 setting mortar base i/c filling the joints & washing the	1000.00	@ Rs. 567.48	P. Sft	Rs. 567,480 (Five hundred sixty seven rupees forty eight paisa only)
2	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)	810.00	@ Rs. 30,509.77	% Sft	Rs. 247,129 (Thirty thousand five hund: nine rupees & seventy seven paisa only)
3	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	300.00	@ Rs: 3,176.25	% 0Cft	Rs: 953 (Thirty one Hundred seventy six rup: & twenty five paisa only)
4	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	37.50	@ Rs: 8,694.95	% Cft	Rs: 3,261 (Eighty six hund: ninty four rup: & ninty five paisa only)
5	Pacea brick work in foundation and plinth in cement sand mortar ratio 1:6.	168.00	@ Rs: 11,948.36	% Cft	Rs: 20,073 (Eleven thousand nine hund: forty eight rup: & thirty six paisa only)
6	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	343.00	@ Rs. 2,206.60	% Cft	Rs. 7,569 (Twenty tow hund: six rup: & sixty paisa only)
7	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	343.00	@ Rs: 2,197.52	% Sft	Rs: 7,537 (Twenty one hund: ninty seven rup: & fifty two paisa only)
8	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	19.80	@ Rs: 337.00	P.Cft	Rs: 6,673 (Three hundred Thirty seven rup: only)



S #	Description	Qty	Rate	Unit	Amount
9	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	0.884	@ Rs: 5,001.70	P.Cwt	Rs: 4,422
	(Five thousand one rup: & seventy paisa only)				
10	French Polish Complete (a) on New Work.	408.00	@ Rs. 3,841.75	% Cft	Rs. 15,674
	(Tharty Eight hund: Forty One rup: & Seventy Five paisa only)				
11	Providing Fixing Approved quality Mortice Lock.	6.00	@ Rs. 1,786.13	Each	Rs. 10,717
	(Tharty Eight hund: Forty One rup: & Seventy Five paisa only)				
	Preparing the surface & painting with matt finish i/c rubbing the surface with bothy				
12	(Silon Carbide rubbing brick) filling the voids with zik.	672.00	@ Rs. 2,717.00	% Cft	Rs. 18,258
	(Twenty Seven hund: Seventeen rup: & only)				
13	Distampering three coats.(S.I No. 24(b) P/54)	192.00	@ Rs: 1,079.65	% Sft	Rs: 2,073
	(One thousand Seventy nine rup: & sixty five paisa only)				
	Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper				
14	filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).(S.I No. 38 (a) P/55)	363.00	@ Rs: 2,567.95	% Sft	Rs: 9,322
	(Twenty five hundred sixty seven rupees & ninty five paisa only)				

Total Rs: 921,140

Sr. #	Description	Rate	Unit	Amount
-------	-------------	------	------	--------

PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 19" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.

2.00 @ Rs: 4802/60 P.No: Rs: 9,605
(Forty Eight hundred Two rup: & Sixty paisa only)

- 2 P/F & fixing 22" x 16" lavatory basin in white glazed earthen ware complete with and i/c the cost of W.I or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary cost of red lead paint & pair of 1/2" dia chrome brass waster of approved pattern 1-1/4" dia malleable iron of cp bars traps. Malleable iron or brass unions & making requisite number of holes in walls plinth and for piep connection and making good in c.c 1:2:4 (foreign equivalent). (S.I.No: 13 P. 3)

2.0 @ Rs: 4928/- P.Each Rs: 9,856
(Forty Nine hundred Twenty Eight rup: & paisa only)

- 3 Add: Extra for labour for providing and fixing of erthern wire pedestal white or coloured glazed

2.0 @ Rs: 2533/47 P.No: Rs: 5,067
(Twenty Five hundred Thirty Three rup: & Forty Seven paisa only)

- 4 P/F in position nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to nyloon connections.

4.0 @ Rs: 447/15 P.No: Rs: 1,789
(Four hundred Forty Seven rup: & Fifteen paisa only)

- 5 P/F 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden pleat (a) Standard pattern. (S.I.No.3 (a) P/7).

2.0 @ Rs:2376/- P.Each Rs: 4,752
(Twenty Three hundred Seventy Six rup: & paisa only)

- 6 S/F conceled stop cock of superior quality with C.P head 1/2" dia.

6.0 @ Rs: 889/46 P.No Rs: 5,336
(Eight hundred Eighty Nine rup: & Forty Six paisa only)

- 7 S/F long bib-cock of superior quality with C.P head 1/2" dia

4.0 @ Rs: 1384/24 P.No Rs: 5,536
(Thirteen hundred Eighty Four rup: & Twenty Four paisa only)

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

8 S/F Swan type pillar cock of superior quality etc:

2.0 @ Rs: 877/80 P.Gallan Rs: 1,756
 (Seven hundred Seventy Seven rup: & Eighty paisa only)

9 providing chambers (15"X19"(inside dimension)24" deep for house meters with 6" thick C.C 1:3:6 block on 1:6 cement mortar 6" thick C.C.1:4:8 in foundation 1/2" thick cement plaster 1:3. to all inside wall surface and to top 1" thick C.C 1:2:4. flooring complete with hinged clear opening (Wt: Qr) etc fixed in cement concrete 1:2:4. i/c curing excavation back filling & disposal of surplus earth etc. (S.I.No: 2 P/20).

4.0 @ Rs: 5913/22 Each Rs: 23,653
 (Fifty Nine hundred Thirteen rup: & Twenty Two Pessa only)

10 P/f water pumping set 3 HP unonablock single phase 220 volls with 1 1/2"x11/4" suntime delivery (60 ft head i/c making c.c 1:3:6 plater form of required size fixing with units + hoolls E.S.I.No: 23P/33).

1.0 @ Rs:15254/48 P.No: Rs: 15,254
 (FifteenThousand Twohundred Fifty Four rup: & Forty Two Pessa only)

11 Providing and fixing handle valves (china). (S.I.No: 5 P/ 17).

3.0 @ Rs: 365/42 Each Rs: 1,096
 (Three hundred Sixty Five rup: & Forty Two Pessa only)

12 S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concrete 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (350 gallons).

1.0 @ Rs: 30773/42 P.Gallan Rs: 30,773
 (ThartyThousand Seven hundred Seventy Three rup: & Forty Two Pessa only)

G.Total: Rs: 114,473

(B)N.S.I

1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

50.0 @ Rs: 66/81 P.Rft Rs: 3,340
 (Sixty Six rup: & Eithy One Pessa only)



Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

250.0 @ Rs: 78/01 P.No Rs: 19,503
(Seventy Eight rup: & One Pessa only)

400.0 @ Rs: 97/91 P.No Rs: 7,833
(Ninety Seven rup: & Ninety One Pessa only)

100.0 @ Rs: 397/77 P.No Rs: 39,777
(Three Hund: Ninety Seven rup: & Seventy Seven Pessa only)

- 2 P/F Bend/ Elbow (90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

8.0 @ Rs: 101/39 P.Rft Rs: 811
(One Hund: One rup: & Tharty Nine Pessa only)

35.0 @ Rs: 103/05 P.No Rs: 3,606
(One Hund: Three rup: & Five Pessa only)

30.0 @ Rs: 125/90 P.No Rs: 3,777
(One Hund: Twenty Five rup: & Ninety Pessa only)

8.0 @ Rs: 425/45 P.No Rs: 3,404
(Four Hund: Twenty Five rup: & Forty Five Pessa only)

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

10.0 @ Rs: 103/05 P.Rft Rs: 1,031
(One Hund: Three rup: & Five Pessa only)

14.0 @ Rs: 110/40 P.No Rs: 1,545
(One Hund: Ten rup: & Forty Pessa only)

8.0 @ Rs: 132/43 P.No Rs: 1,059
(One Hund: Tharty Two rup: & Forty Three Pessa only)

4.0 @ Rs:712/75 P.No Rs: 2,851
(seven Hund: Twelve rup: & seventy Five Pessa only)

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

(a) 1/2" Dia

4.0 @ Rs: 94/89 P.Rft Rs: 380
(Ninty Four rup: & seventy Eighty Nine Pessa only)

(b) 3/4" Dia

16.0 @ Rs:98/15 P.No Rs: 1,570
(Ninty Eight rup: & Fifteen Pessa only)

(C) 1" Dia

8.0 @ Rs:110/40 P.No Rs: 883
(One Hund: Ten rup: & Forty Pessa only)

(d) 4" Dia

4.0 @ Rs:343/83 P.No Rs: 1,375
(Three Hund: Forty Three rup: & Eighty Three Pessa only)

- 5 P/F UNION of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious size fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in U in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material s meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

(a) 3/4" Dia

4.0 @ Rs: 312/81 P.Rft Rs: 1,251
(Three Hund: Twelve rup: & Eighty One Pessa only)

(b) 1" Dia

5.0 @ Rs:381/37 P.No Rs: 1,907
(Three Hund: Eighty One rup: & Tharty Seven Pessa only)

- 6 P/F clips / saddle / clamps of approved material & design upto 60 ft. height as per instructions of the Engineer Incharge. Rate includes all costs of labour, material, (N.S.I).

(a) 1" Dia

20.0 @ Rs: 26/61 P.Rft Rs: 532
(Twenty Six rup: & Sixty One Pessa only)

Sr.#	Description	Rate	Unit	Amount
------	-------------	------	------	--------

- 7 P/F UPVC P-Trap W/Elbow (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 5.0 @ Rs:818/04 P.No _____ Rs: 4,090
(Eight Hund: Eighty Eight rup: & Four Pessa only)

- 8 P/F UPVC WYE (Y) (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

7.0 @ Rs:933/13 P.No _____ Rs: 6,531
(Nine Hund: Tharty Three rup: & Thirteen Pessa only)

- 9 P/F UPVC PLUG ELBOW (45 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4.0 @ Rs:677/65 P.No _____ Rs: 2,710
(Six Hund: Seventy Seven rup: & Sixty Five Pessa only)

- 10 P/F UPVC PLUG TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDC made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. R includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

4" Dia 4.0 @ Rs:847/42 P.No _____ Rs: 3,389
(Eight Hund: Forty Seven rup: & Forty Two Pessa only)

Sr.#	Description	Rate	Unit	Amount
11	P/F UPVC VENT COWEL (LOCAL) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe / fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).			
	4" Dia	3.0 @ Rs:187/93	P.No	Rs: 563
	(One Hund: Eighty Seven rup: & Ninety Three Pessa only)			
12	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.			
	(a) Filter	10.0 @ Rs: 76/05	P.Rft	Rs: 760
	(Seventy Six rup: & Five Pessa only)			
	(b) G.I Pipe	80.0 @ Rs: 38/95	P.Rft	Rs: 3,116
	(Tharty Eight Six rup: & Ninety Five Pessa only)			
	(C) Machine	1.0 @ Rs: 1441/65	Each	Rs: 1,442
	(Fourteen Hund: Forty One rup: & Sixty Five Pessa only)			
	G.Total:			Rs: 119,036



BIDDING DOCUMENT**14**


Issued to

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation / Reconstruction of existing Primary & Elementary Schools in Sindh (damaged due to rain / flood or any other conditions) in District Larkano (37 Units) (2014-15 Programme) at GBPS, Bhoonbhatpur Tal: Ratodero**
(ADP No. 126 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 500,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 10,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 25,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 12 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR



EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

14
Schedule-B

**REHABILITATION/RECONSTRUCTION OF EXISTING PRIMARY /
ELEMENTARY SCHOOLS IN SINDH (DAMAGED DUE TO RAIN FLOOD OR ANY
OTHER CONDITION) IN DISTRICT LARKANA (37 UNITS) (2014-15
PROGRAMME) @GBPS BHOOBHT PUR TALUKA RATODERO.**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	450	@ Rs: 3,176.25	% 0Cft	Rs: 1,429
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	150	@ Rs: 8,694.95	% Cft	Rs: 13,042
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	678.00	@ Rs: 11,948.36	% Cft	Rs: 81,010
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Supply and fixing sand under floor including plugging in to walls	2125	@ Rs: 1,141.25	% Cft	Rs: 24,252
	(Eleven hundred forty one rupees & twenty five paisa only)				
5	Providing and Laying 2" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	800.00	@ Rs: 4,411.82	% Sft	Rs: 35,295
	(Four y four hundred eleven rup: & eighty two paisa only)				
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	300.00	@ Rs: 12,346.65	% Cft	Rs. #REF!
	(Tweliv : thousand three hund: forty six rup: & sixty five paisa only)				
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	400	@ Rs: 2,206.60	% Cft	Rs. 8,826
	(Twenty tow hund: six rup: & sixty paisa only)				
8	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	400	@ Rs: 2,197.52	% Sft	Rs: 8,790
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	400.00	@ Rs: 1,287.44	% Sft	Rs: 5,150
	(Twelve hundred eighty seven rupees & forty for paisa only)				

S #	Description	Qty	Rate	Unit	Amount
10	White wash two coats. (S.I. No. 26 P No. 54)	168.00	@ Rs. 425.00	% Sft (Four hundred twenty five rup: & paisa only)	Rs. 3,598
11	Primary coat of chalk distemper(S.I No. 23 P/53)	627	@ Rs: 442.75	% Sft (Four hundred forty two rupees & seventy five paisa only)	Rs: 2,776
12	Distemping two coats.(S.I No. 24(b) P/54)	567	@ Rs: 1,043.90	% Sft (One thousand forty three rup: & ninty paisa only)	Rs: 5,919
13	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick	80	@ Rs. 27,678.86	% Cft (Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)	Rs. 22,143
14	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 1/4" thick i/c finishing (S.I No 24 P/45)	252	@ Rs. 28,253.61	% P.Cwt (Twenty seven thousand seven hund: forty seve rup: & six paisa only)	Rs. 71,199
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)	203	@ Rs. 30,509.77	% Sft (Thirty thousand five hund: nine rupees & seventy seven paisa only)	Rs. 61,935
16	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	23.00	@ Rs: 337.00	P.Cft (Three hundred Thirty seven rup: only)	Rs: 7,751
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	1.129	@ Rs: 5,001.70	P.Cwt (Five thousand one rup: & seventy paisa only)	Rs: 5,647
18	Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. ... P/92)	68.00	@ Rs. 180.50	P. Sft	Rs. 12,274

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(One hundred eighty Five rupees & fifty Paise only)

19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel
 44 @ Rs: 226.00 P. Sft Rs: 9,944
 (Two hundred twenty six rupees only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c
 20 Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio 1:6
 and repairing the jambs. The cost also i/c all carriage, tools and pla
 7 @ Rs: 228.90 P. Rft Rs: 1,602
 (Two hundred twenty eight rupees & ninty paisa only)

1st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts
 21 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25
 P/60)
 6.00 @ Rs: 902.93 P. Sft Rs: 5,418
 (Nine hund: two rup: & ninty three paisa only)

Total Rs: 421,893




S.#	Description	Rate	Unit	Qty	Amount
-----	-------------	------	------	-----	--------

PART - B

- 1 P/F squatting type white glazed earthen ware W.C pan of with i/c cost of flushing cistern with internal fitting & flush pipe with bend making good in cement concrete 1:2:4.(i) W.C not less than 19" clear opening b/w flushing & 6 gallons flushing tank with

2.00
 @ Rs: 4,846.80 P. No. Rs. 9,697
 (Forty eight hundred forty six rup: & eighty paisa only)

- 2 P/F 22"x16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I & C.I cantilever brackets 6 inches built into walls painted white in two coats after a primary cost of red lead painted & pair

1.00
 @ Rs: 4,694.80 P. No. Rs. 4,695
 (Forty six hundred ninety four rupees & eighty paisa only)

- 6 P/F 6"x6" C.I Floor Trap of the approved self cleaning & C.I secured down grating holes in walls plinth & floor for pipe connection & making

6.00
 @ Rs: 2,024.46 P. No. Rs. 6,076
 (Two thousand twenty four rup: only)

- 4 P/F in position Nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to Nyloon connections.

2.00
 @ Rs: 447.15 P. No. Rs. 895
 (Four hundred forty seven rup: & fifteen paisa only)

- 5 P/F 4" dia C.I soil vent pipe i/c cutting, fitting & extra painting to match the colour of the building.

12.00
 @ Rs: 666.19 P. Rft Rs. 7,995
 (Three hundred thirty three rup: & nineteen paisa only)

- 6 P/F 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/4" thick & bolts & nuts & extra painting to match the

2.00
 @ Rs: 270.60 P. No. Rs. 541
 (Two hundred seventy rupees & sixty paisa only)

S.#	Description	Rate	Unit	Qty	Amount
-----	-------------	------	------	-----	--------

Providing G.I pipe specials & clamps etc i/c fixing, cutting & fitting
 7 complete two coats of after cleaning the pipe etc with white zinc paint
 with pigment to match the colour of the building & testing the pressure

(A) 1/2" dia

				25.00	
@ Rs:	76.21	P. Rft		Rs.	1,905

(Seventy three rupees & twenty one paisa only)

(B) 6/4" dia

				50.00	
@ Rs:	95.79	P. Rft		Rs.	4,790

(Ninty five rupees seventy nine paisa only)

8 P/F 4" dia C.I terminal guard i/c extra painting to match the colour of the building.

				2.00	
@ Rs:	689.70	P. No.		Rs.	1,379

(Three hundred eighty nine rupees & seventy paisa only)

9 P/F full way gun metal valves with whelds threaded of

				1.00	
@ Rs:	197.12	P. No.		Rs.	197

10 S/F C.P brass bib cock 1/2" dia standard pattern.

				2.00	
@ Rs:	667.92	P. No.		Rs.	1,336

(Three hundred thirty seven rupees & ninty two paisa only)

11 Providing RCC pipe with collars class "B" & digging the benches to

(A) 4" Dia

				24.00	
@ Rs:	146.57	P. Rft		Rs.	3,518

(One hundred forty six rupees & fifty seven paisa only)

(B) 6" Dia

				12.00	
@ Rs:	199.25	P. Rft		Rs.	2,391

(One hundred & Ninty nine paisa only)

12 S/F concealed stop cock of superior quality with C.P head 1/2" dia.

				2.00	
@ Rs:	478.28	P. No.		Rs.	957

(Four hundred Seventy eight rupees & twenty eight paisa only)

S.#	Description	Rate	Unit	Qty	Amount
-----	-------------	------	------	-----	--------

16 S/F long bib cock of superior quality with C.P head 1/2" dia.
 = 1.00
 @ Rs: 1,109.46 P. No. Rs. 1,109
 (Eleven hundred nine rupees & forty six paisa only)

14 P/F approved quality A.C motor pumping set (Javed Engineering) made
 = 1.00
 @ Rs: 5,115.00 P. No. Rs. 5,115
 (Fifty one hundred fifteen rupees only)

15 S/F Fibre Glass Tank of approved quality & design & wall thickness as
 = 1.00
 @ Rs: 21,989.61 P. Gallon Rs. 21,990
 (Twenty one thousand nine hundred eighty nine rup: & sixty one paisa only)

16 Hand pump with all accessories i/c fitting & fixing with local made coir

(a) Filter
 = 10.00
 @ Rs: 76.05 P. No. Rs. 761
 (Seventy six rupees & five paisa only)

(b) G.I Pipe
 = 90.00
 @ Rs: 68.95 P. Rft Rs. 6,206
 (Thirty eight rupees & ninty five paisa only)

(c) Machine
 = 1.00
 @ Rs: 1,441.60 P. No. Rs. 1,442
 (Fourteen hundred forty one rup: & sixty paisa only)

Total Rs. 82,986

N.S.I Rs. 10,824

Grand Total	Rs. (S.I)	72,162
--------------------	------------------	---------------

BIDDING DOCUMENT**15**


Issued to

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation / Reconstruction of existing Primary & Elementary Schools in Sindh (damaged due to rain / flood or any other conditions) in District Larkano (37 Units) (2014-15 Programme) at GGVC. Garhi Khuda Bux Tal: Ratodero**
(ADP No. 126 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 400,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 8,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 20,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 12 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

Schedule-B 15

**REHABILITATION/RECONSTRUCTION OF EXISTING
PRIMARY/ELEMENTARY SCHOOLS IN SINDH (DAMAGED DUE TO
RAIN/FLOOD OR ANY OTHER CONDITION) IN DISTRICT LARKANO
(37 UNITS) (2014-15 PROGRAMME) @GGVS GARHI KHUDA BUX BHUTTO**

S #	Description	Qty	Rate	Unit	Amount
1	Dismantling cement concrete reinforced separating reinforcement from concrete cleaning & straightening the same. (S.I No. 22 P/10)	470.20	@ Rs: 3,327.50	% Cft	Rs: 15,646
					(Thirty three hundred twenty seven rup:& fifty paisa only)
2	Removing cement or lime plaster. (S.I No. 53 P/13)	1420.98	@ Rs: 121.00	% Cft	Rs: 1,719
					(One hundred & twenty rup: only)
3	Cement Plaster 1:4 upto 12" height. 3/4" thick (S.I No. 11 (c) P/51)	1420.98	@ Rs: 3,015.76	% Sft	Rs: 42,853
					(Thre thousand fifteen rup: & seventy six paisa only)
4	Providing and Laying 3" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	1880.81	@ Rs: 4,411.82	% Sft	Rs: 82,978
					(Forry four hundred eleven rup: & eighty two paisa only)
5	Primary coat of chalk distemper(S.I No. 23 P/53)	1420.98	@ Rs: 442.75	% Sft	Rs: 6,291
					(Four hundred forty two rupces & seventy five paisa only)
6	Distemping two coats.(S.I No. 24(b) P/54)	5447.09	@ Rs: 1,043.90	% Sft	Rs: 56,862
					(One thousand forty three rup: & ninty paisa only)
7	Preparing surface & painting with weather coat i/c rubbing the surface with rubbing brick / sand paper filling the voids with chalk / plaster then painting with weather coat of approved make (New surface).(S.I No. 38 (a) P/55)	2278.84	@ Rs: 2,567.95	% Sft	Rs: 58,519
					(Twenty five hundred sixty seven rupees & ninty five paisa only)
8	Painting doors & Windows any type (Old surface).(S.I No. 4 (c) P/67)	608	@ Rs: 1,212.21	% Sft	Rs: 7,370
					(Twelve hundred twelve rup: & twenty one paisa only)



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

9 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13

2129.33 @ Rs. 1,887.40 % Sft Rs. 40,189
 (Eighteen hundred eighty seven rupces & forty paisa only)

10 1st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

32.00 @ Rs: 902.93 P. Sft Rs: 28.894
 (Nine hund: two rup: & ninty three paisa only)


Total Rs. 341,323

BIDDING DOCUMENT**16**Issued toAnd charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation / Reconstruction of existing Primary & Elementary Schools in Sindh (damaged due to rain / flood or any other conditions) in District Larkano (37 Units) (2014-15 Programme) at GGPS, Agani Tal: Larkano**
(ADP No. 126 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 400,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 8,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 20,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 12 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE " B "

S.No: 16

NAME OF WORK:- REHABILITATION / RECONSTRUCTION OF EXISTING
PRIMARY & ELEMENTARY SCHOOLS IN SINDH DAMGED
OTHER CONDITION DISTRICT LARKANA (37-UNITS)
AT GGPS AGANI TALUKA LARKANO.

S.No:	Description	Qty:	Rate	Unit	Amount
1	Removing cement or lime plaster (S.I.No: 53 P/13).				
		270.00	@ Rs:121/-	% Sft	Rs: 327.00
			(Rs: one hund: twenty one only)		
2	Supplying of T-Iron at the site of work				
		845.00	@ Rs: 3575/-	P.Cwt	Rs: 3,021.00
			(Rs: three thous: five hund: seventy five only)		
3	Errection and rolled steel beams or old rails in roof etc errection and fixing in positlon. (S.I.No. P/).				
		37.691	@ Rs: 186/34	P.Cwt	Rs: 7,210.00
			(Rs: one hund: eighty six & thirty four only)		
4	First class tile roofing consisting of 4" earth and 1" mud plaster with Gobri leeping over 1/2" thick cement plaster 1"6 with 34 Lbs. Of hot bituman coating sand blinded provided over 2 layers of tiles 12" x 6" x 1 1/4" laid in 1:6 cement mortar with 1/2" thick sand wiced layer of 1:6 cement mortar including 1:2 cement pointing underside of tiles complete including curing etc. (S.I.No: 1 P/32).				
		998.000	@ Rs: 11443/10	% Sft	Rs: 114,202.00
			(Rs: eleven thous: four hund: fourty three & ten only)		
5	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		114.00	@ Rs:12674/36	% Cft	Rs: 14,449.00
			(Rs: tweleve thous: six hund: seventy four & thirty six only)		
6	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		24.00	@ Rs:12346/65	% Cft	Rs: 2,963.00
			(Rs: tweleve thous: three forty six & sixty five only)		
7	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).				
		785.00	@ Rs:660/-	% Sft	Rs: 5,181.00
			(Rs: six hund: sixty only)		



S.No:	Description	Qty:	Rate	Unit	Amount
8	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).				
		1255.00	@ Rs:2206/60	% Sft	<u>Rs: 27,693.0</u>
			(Rs: two thous: two hund: six & sixty only)		
9	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).				
		1255.00	@ Rs:2197/52	% Sft	<u>Rs: 27,579.0</u>
			(Rs: two thous: one hund: ninty seven & twenty two only)		
10	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkat hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutters).				
		83.00	@ Rs: 902/93	P.Sft	<u>Rs: 74,943.00</u>
			(Rs: nine hund: two & ninty three only)		
11	Providing and laying 1" thick topping cement concreate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).				
		54.000	@ Rs: 4411/82	% Sft	<u>Rs: 2,603.00</u>
			(Rs: four thous: four hund: eleven & eighty two only)		
12	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangment. (S.I.No.24P/91).				
		24.00	@ Rs:726/72	P. Sft	<u>Rs: 17,441.0</u>
			(Rs: seven hund: twenty six & seventy two only)		
13	Primary coat of chalk distempering. (S.I.No.23 P/57).				
		2952.00	@ Rs:442/75	% Sft	<u>Rs: 13,070.00</u>
			(Rs: four hund; fourty two & seventy five only)		
14	Distempering two coats.				
		4957.00	@ Rs:1043/90	% Sft	<u>Rs: 51,746.00</u>
			(Rs: ten hund; forty three & ninty only)		
15	White washing three coats. (S.I.No.26 (c) P/53).				
		1125.00	@ Rs:829/95	% Sft	<u>Rs: 9,337.00</u>
			(Rs: eight hund: twenty nine & ninty five only)		

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 16 Preparing surface and painting of doors and windows any type (including edges)
(ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).

488.00 @ Rs:2116/41 % Sft Rs: 10,328.0
(Rs: two thous: one hund: sixteen & fourty one only)

- 17 Painting guard bars , gates iron bars gratings railings i/c standard baises etc:
smiler open works.

785.00 @ Rs:1270/83 % S.ft Rs: 9,976.00
(Rs: one thous: two hund: seventy & eighty three only)

G.Total: Rs: 392,069.0



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less th clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble

2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00

(Rs: four thous: eight hund; two & sxity only)

- 2 S/F fibre glass tenk of approved qulity and design and wall thickness as apccoified i/c the cost c nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (150 gallons).

1.00 @ Rs: 87/95 P.No Rs: 13,192.00

(Rs: eighty seven & ninty five only)

- 3 Providing RCC pipe with collars class"B" and digging the tenches to required depth and fixing in position including cutting fitting and jointing with mexphalt composition and cement mortar 1:1 and testing with water pressure jto a head of 4" feet a bove the top of the highest pipe and refilling with excavated staff. (S.I.No: 2 P/ 23). with excavated staff.

4" dia 18.00 @ Rs: 146/57 P.Rft Rs: 2,638.00

(Rs: one hund: forty six & fifty seven only)

- 4 Providing G.I Pipe & special including fixing cutting & fitting complete with & i/c the cost of cutting trench upto 2-1/2" feet deep refilling watering ramming and disposel of surplus earth winthin one chain and painting 2 cost of bituman pain to pipes & secals after cleaning & bassian cloth soaked in maxphalt composition wrapped tightly round pipes and testing to a pressure head of 200 feet and handing. (S.I.No: 1(ii) P/14).

(a) 3/4" dia 55.00 @ Rs: 86/36 Rft Rs: 4,750.00

(Rs: eighty six & thirty six only)

(b) 1" dia 14.00 @ Rs: 116/20 Rft Rs: 1,627.00

(Rs: one hund; sixteen & twenty only)

- 5 S/F long bib-cock of superior quality with C.P head 1/2" dia

14.00 @ Rs: 1384/24 P.No Rs: 2,768.00

(Rs: one thous: three hund; eighty four & twenty four only)



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 6 P/F approved quality A.C motor pumping set(Javed Engineering)made 1-1/4" 1" section and delivery with base and compling 1 H.Powor single phase motor (Siemens make)60' ft:head of 2800 KPM i/c the cost of C.I fitting nuts bolts and the cost of 1;2:4 Plate from.

1.00	@ Rs: 5115/-	P.No	Rs:	5,115.00
	(Rs: five thous: one hund: fifteen only)			

- 7 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

(a) Filter	10.00	@ Rs: 76/05	P.Rft	Rs:	760.00
		(Rs: seventy six & five only)			

(b) G.I Pipe	85.00	@ Rs: 38/95	P.Rft	Rs:	3,311.00
		(Rs: thrity eight & ninty five only)			

(C) Machine	1.00	@ Rs: 1441/65	Each	Rs:	1,442.00
		(Rs: one thous: four hund: fourty one & sixty five only)			

G.Total:				Rs:	45,208.00
-----------------	--	--	--	-----	------------------



BIDDING DOCUMENT**17**


Issued to

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation / Reconstruction of existing Primary & Elementary Schools in Sindh (damaged due to rain / flood or any other conditions) in District Larkano (37 Units) (2014-15 Programme) at GBPS. Mian Lal Tal: Larkano**
(ADP No. 126 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 300,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 6,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 15,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 12 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE " B "**S.No: 17**

NAME OF WORK:- **REHABILITATION / RECONSTRUCTION OF EXISTING PRIMARY & ELEMENTARY SCHOOLS IN SINDH (DAMAGED DUE TO RAIN / FLOOD OR ANY OTHER CONDITIONS) IN DISTRICT LARKANO (37 UNITS) (2014-15 PROGRAMME) AT GBPS MIAN LAL TALUKA LARKANO.**

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dimantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		128.00	@ Rs: 3327/50	% Cft	Rs: 4,131.00
					(Rs: three thous: two hund: twenty seven & fifty only)
2	Removing cement or lime plaster (S.I.No: 53 P/13).				
		457.00	@ Rs: 121/-	% Sft	Rs: 553.00
					(Rs: one hund: twenty one only)
3	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).				
		176.00	@ Rs: 3176/25	% 0 Cft	Rs: 559.00
					(Rs: three thous: one hund: seventy hund: twenty five only)
4	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14)				
		27.00	@ Rs: 8694/95	% Cft	Rs: 2,347.00
					(Rs: eight thous: six hund: ninty four & ninty five only)
5	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		76.00	@ Rs:11948/36	% Cft	Rs: 9,080.00
					(Rs: eleven thous: nine hund: eighty five & thirty six only)
6	Pacca brick work in Ground floor in cement sand mortar. (S.I.No.1(e) P/20).				
		13.00	@ Rs:12674/36	% Cft	Rs: 1,647.00
					(Rs: tweleve thous: six hund: seventy four & thirty six only)
7	Pacca brick work other than building including striking of joints upto 20' ft: height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).				
		157.00	@ Rs:12346/65	% Cft	Rs: 19,384.00
					(Rs: tweleve thous: three forty six & sixty five only)



S.No:	Description	Qty:	Rate	Unit	Amount
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).	17.00	@ Rs:337/- (Rs: three hund: thirty seven only)	P.Cft	Rs: 5,729.00
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)	0.75	@ Rs:5001/70 (Rs: five thous: one & seventy only)	P.Cwt	Rs: 3,751.00
10	Cement pointing struck joints on walls (a) Ratio 1:2. (S.I.No.19 (a) P/52).	210.00	@ Rs:1287/44 (Rs: one thous: two hund: eighty seven & fourty four only)	% Sft	Rs: 2,703.00
11	Applying floating of cement 1/32" thick.. (S.I.No.14 P/53).	457.00	@ Rs:660/- (Rs: six hund: sixty only)	% Sft	Rs: 3,016.00
12	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	734.00	@ Rs:2206/60 (Rs: two thous: two hund: six & sixty only)	% Sft	Rs: 16,194.00
13	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	734.00	@ Rs:2197/52 (Rs: two thous: one hund: ninty seven & twenty two only)	% Sft	Rs: 16,130.00
14	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	20.00	@ Rs: 1141/25 (Rs: one thous: one hund: forty one & twenty five only)	% Cft	Rs: 228.00
15	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	40.00	@ Rs: 4411/82 (Rs: four thous: four hund; eleven & eighty two only)	% Sft	Rs: 1,765.00
(B)	<u>2"Thick</u>	742.00	@ Rs: 3275/50 (Rs: three thous: two hund; seventy five & fifty only)	% S.ft	Rs: 24,304.00

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

16 Notice board made with cement. (S.I.No: 1 P/94).

64.00 @ Rs: 58/11 P.Sft Rs: 3,719.00
(Rs: fifty eight & eleven only)

17 S/F in position iron steel grill of 3/4" X flate iron of approved design i/c painting three coats etc complete with weight not to be less than 3.7 Lbs sq: ft: of finished grill. (S.I.No: P/).

6.00 @ Rs:194/16 P.Sft Rs: 1,165.00
(Rs: one hund: ninty four & sixteen only)

18 P/F G.I Frame / Chowkhats of size 7" x 2" or 4 1/2" x 3" for door using 20 gauge G.I sheet i/c we and fixing at site with necessary hold fasts. Filling with cement sand slurry of ration 1:6 and repa jams. The cost aslo i/c all carriage. Tools and plants used in making and fixing. (S.I.No: 28 P.)

16.00 @ Rs:228/90 P.Rft Rs: 3,662.00
(Rs: two hund: twenty eight & ninty only)

19 P/F G.I frame chokats of size 7" x2" or 4" x 3" for Windows using 20 gauge G.I sheet i/c solded fixing at site with necessary hold fosts filling with cement sand repairing i/c all carriage tools and used in making and fixing .(S.I.No: P/).

20.00 @ Rs: 240/50 P.Rft Rs: 7,215.00
(Rs: two hund: forty & fifty only)

20 Supplying M-S bars 5/8" dia (Schedule of Material).

0.28 @ Rs: 3700/- % S.ft Rs: 1,054.00
(Rs: three thous: seven hund: only)

21 Cutting and fixing iron bars for barred windows. (S.I.No: P/).

6.00 @ Rs: 28/25 P.Cwt Rs: 170.00
(Rs: twenty eight & twenty five only)

22 First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4" thick. (Only Shutters).

17.00 @ Rs: 902/93 P.Sft Rs: 15,350.00
(Rs: nine hund: two & ninty three only)

S.No:	Description	Qty:	Rate	Unit	Amount
23	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangement. (S.I.No.24P/91).	24.00	@ Rs:726/72	P. Sft	<u>Rs: 17,441.00</u> (Rs: seven hund: twenty six & seventy two only)
24	White washing three coats. (S.I.No.26 (c) P/53).	900.00	@ Rs:829/95	% Sft	<u>Rs: 7,470.00</u> (Rs: eight hund: twenty nine & ninty five only)
25	Distempering three coats. (S.I.No.24 (c) P/53).	5915.00	@ Rs:1079/65	% Sft	<u>Rs: 63,861.00</u> (Rs: one thos: seventy nine & sixty five only)
26	Preparing surface and painting of doors and windows any type (including edges) (ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).	304.00	@ Rs:2116/41	% Sft	<u>Rs: 6,433.00</u> (Rs: two thous: one hund: sixteen & forty one only)
27	Painting guard bars , gates iron bars gratings railings i/c standard barse etc: smiler open works.	96.00	@ Rs:1270/83	% S.ft	<u>Rs: 1,220.00</u> (Rs: one thous: two hund: seventy & eighty three only)
G.Total:					<u>Rs: 240,281.00</u>

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

- 1 P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less th clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble

2.00 @ Rs: 4802/60 P.No: Rs: 9,605.00
(Rs: four thous: eight hund; two & sxity only)

- 2 S/F long bib-cock of superior quality with C.P head 1/2" dia

2.00 @ Rs: 1384/24 P.No Rs: 2,768.00
(Rs: one thous: three hund; eighty four & twenty four only)

- 3 P/F approved quality A.C motor pumping set(Javed Engineering)made 1-1/4" 1" section and delivery with base and compling 1 H.Powor single phase motor (Siemens make)60' ft:head of 2800 KPM i/c the cost of C.I fitting nuts bolts and the cost of 1;2:4 Plate from.

1.00 @ Rs: 5115/- P.No Rs: 5,115.00
(Rs: five thous: one hund: fifteen only)

- 4 S/F fibre glass tenk of approved quilty and design and wall thickness as apecoified i/c the cost c nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (150 gallons).

1.00 @ Rs: 13198/- P.Gallan Rs: 13,198.00
(Rs: thriteen thous: one hund: ninty eight only)

G.Total:

Rs: 30,686.00

N.S.I

- 5 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

3/4" Dia 20.00 @ Rs: 78/01 P.No Rs: 1,560.00
(Rs: sevnty eight & One only)



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 7 P/F Bend/ Elbow (90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<u>3/4" Dia</u>	4.00	@ Rs: 103/05	P.No	Rs:	412.00
(Rs: one hund; three & five only)					

- 8 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

<u>(a) Filter</u>	10.00	@ Rs: 76/05	P.Rft	Rs:	760.00
(Rs: seventy six & five only)					

<u>(b) G.I Pipe</u>	70.00	@ Rs: 38/95	P.Rft	Rs:	3,116.00
(Rs: thrity eight & ninty five only)					

<u>(C) Machine</u>	1.00	@ Rs: 1441/65	Each	Rs:	1,442.00
(Rs: one thous: four hund: fourty one & sixty five only)					

G.Total:				Rs:	7,290.00
-----------------	--	--	--	-----	-----------------




BIDDING DOCUMENT**18**Issued toAnd charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation / Reconstruction of existing Primary & Elementary Schools in Sindh (damaged due to rain / flood or any other conditions) in District Larkano (37 Units) (2014-15 Programme) at GBMS. Ratokot Tal: Larkano**
(ADP No. 126 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 400,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 8,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 20,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commencement:- 12 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.,dt:
- n) Rate quoted by Contractor: PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE " B "

S.No: 18

NAME OF WORK:- REHABILITATION / RECONSTRUCTION OF EXISTING PRIMARY & ELEMENTARY SCHOOLS IN SINDH (DAMAGED DUE TO RAIN / FLOOD OR ANY OTHER CONDITIONS) IN DISTRICT LARKANO (37 UNITS) (2014-15 PROGRAMME) AT GBMS RATOKOT TALUKA LARKANO.

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dimantling cement concrete plain 1:2:4. (S.I.No.19 © P/10).				
		38.00	@ Rs: 3327/50	% Cft	Rs: 1,264.00
					(Rs: three thous: two hund: twenty seven & fifty only)
2	Remoning cement or lime plaster. (S.i.No.53 P/13).				
		267.00	@ Rs:121/-	% Sft	Rs: 323.00
					(Rs: one hund: twenty one only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		98.00	@ Rs:11948/36	% Cft	Rs: 11,709.0
					(Rs: eleven thous: nine hund: eighty five & thirty six only)
4	Cement concreate brick or stone ballast 1/2" to 2" guage. (S.I.No: 4 (d) P/ 14).				
		32.00	@ Rs: 8122/95	% Cft	Rs: 2,599.00
					(Rs: eight thous: one hund: twenty two & ninty five only)
5	Applying floating coat of cement 1/32" thick. (S.I.No. 14 P/59).				
		267.00	@ Rs: 660/-	% Sft	Rs: 1,762.00
					(Rs: six hund: sixty only)
6	Cement plaster (1 G) upto 20' ft height 1/2" thick (S I No: 13 (b) P 58).				
		267.00	@ Rs: 2206/60	% Sft	Rs: 5,891.00
					(Rs: two thous: two hund: six & sixty only)
7	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I.No: 11 (a) P.58).				
		267.00	@ Rs: 2197/52	% S.ft	Rs: 5,867.00
					(Rs: two thous: one hund: ninty seven & twenty two only)



S.No:	Description	Qty:	Rate	Unit	Amount
8	Supplying and filling sand under floor and plugging in walls. (S.I.No: 29 P/25).	1329.00	@ Rs: 1141/25	% Cft	<u>Rs: 15,167.0</u> (Rs: one thous: one hund: forty one & twenty five only)
9	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).	350.00	@ Rs:27747/06	% Sft	<u>Rs: 97,115.0</u> (Rs: twenty seven thous: seven hund fourty seven & six only)
10	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing and dividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	402.00	@ Rs: 4411/82	% Sft	<u>Rs: 17,956.00</u> (Rs: four thous: four hund: eleven & eighty two only)
11	White washing three coats. (S.I.No.26 (c) P/53).	1935.00	@ Rs:829/95	% Sft	<u>Rs: 16,060.00</u> (Rs: eight hund: twenty nine & ninty five only)
12	Primary coat of chalk under distemping.	6027.00	@ Rs: 442/75	% S.ft	<u>Rs: 26,685.00</u> (Rs: four hund; fourty tow & seventy five only)
13	Distemping three coats	6027.00	@ Rs:1079/65	% Sft	<u>Rs: 65,070.00</u> (Rs: one thous: seventy nine & sixty five only)
14	Cement pointing strucking joints on walls (a) Ratio 1:2. (S.I.No. 19 (a) P/52).	260.000	@ Rs:1287/44	% Sft	<u>Rs: 3,347.0</u> (Rs: one thous: two hund: eighty seven & fourty four only)
15	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	2264.00	@ Rs: 1498/48	% Sft	<u>Rs: 33,925.00</u> (Rs: one thous: nine hund: fourty eight & ten only)

S.No.	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 16 Preparing surface and painting of doors and windows any type (including edges)
(ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).

721.00 @ Rs:2116/41 % Sft Rs. 15,250.0
(Rs: two thous: one hund: sixteen & fourty one only)

- 17 Painting guard bars , gates iron bars gratings railings i/c standard barse etc:
smiler open works.

102.00 @ Rs:1270/83 % S.ft Rs: 1,296.00
(Rs: one thous: two hund: seventy & eighty three only)

G.Total: Rs: 321,295.0

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

1	P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern wit internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less th clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble	2.00	@ Rs: 4802/60	Each	Rs: 9,605.00
					(Rs: four thous: eight hund; two & sxy only)
2	S/F conceled stop cock of superior quality with C.P head 1/2" dia.	2.00	@ Rs: 889/46	P.No	Rs: 1,778.00
					(Rs: eight hund; eighty nine fourty six only)
3	S/F long bib-cock of superior quality with C.P head 1/2" dia	2.00	@ Rs: 1384/24	P.No	Rs: 2,768.00
					(Rs: one thous: three hund; eighty four & twenty four only)
4	P/f water pumping set 3 HP unonablock single phase 220 volts with 1 1/2"x1 1/4" suntire delivery (60 ft head i/c making c.c 1:3:6 plater form of required size fixing with units + hoolis E.S.I.No: 23P/33).	1.00	@ Rs:15254/48	P.No:	Rs: 15,254.00
					(Rs: fifteen thous: two hund: fifty four & fouty eight only)
5	S/F fibre glass tenk of approved qulity and design and wall thickness as apecoified i/c the cost c nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (100 gallons).	100.00	@ Rs: 87/95	P.Gallan	Rs: 8,795.00
					(Rs: twnty one thous:nine hund; eighty nine & sixty one only)
G.Total:					Rs: 38,200.0

S.No.	Description	Qty.	Rate	Unit	Amount
-------	-------------	------	------	------	--------

N.S.I

- 1 P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).

<u>(a) 3/4" Dia</u>	50.00	@ Rs: 78/01	P.Rft	Rs: 5,850.00
		(Rs: sevnty eight & One only)		

<u>(b) 4" Dia</u>	10.00	@ Rs: 397/77	P.Rft	Rs: 3,978.00
		(Rs: three hund: ninty seven & seventy seven only)		

- 2 P/F Bend/ Elbow (90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of verious sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<u>(a) 3/4" Dia</u>	22.00	@ Rs: 103/05	P.No	Rs: 2,267.00
		(Rs: one hund; three & five only)		

<u>(b) 4" Dia</u>	2.00	@ Rs: 425/45	P.No	Rs: 850.00
		(Rs: four hund: twenty five & fourty five only)		

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separatly,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>(a) 3/4" Dia</u>	9.00	@ Rs: 110/40	P.No	Rs: 993.00
		(Rs: one hund; ten & fourteen only)		

S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 4 P/F COUPLING / SCOKET of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I)

<u>(b) 3/4" Dia</u>	17.00	@ Rs:98/15	P.No	Rs:	1,668.00
(Rs: ninty eight & fifteen only)					

- 5 P/F UNION of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of verious sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D-1784 type 1 grade 1. Rate includes all costs of labour, material cartage, scaffolding / ladders etc complete (N.S.I).

<u>(a) 3/4" Dia</u>	2.00	@ Rs: 312/81	P.Rft	Rs:	625.00
(Rs: three hund; tweleve & eighty one only)					


Total:	Rs:	16,231.00
S.I	Rs:	38,200.00
Total:	Rs:	54,431.00

BIDDING DOCUMENT**19**Issued toAnd charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation / Reconstruction of existing Primary & Elementary Schools in Sindh (damaged due to rain / flood or any other conditions) in District Larkano (37 Units) (2014-15 Programme) at GBPS. Rewachand Tal: Dokri**
(ADP No. 126 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 700,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 14,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 35,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 12 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

SCHEDULE-B 19**Name of work:**

Rehabilitation Re-Construction of existing Primary & Elementary School
in sindh (due to rain/flood or any other condition)
At: GBPS Rewachand Taluka Dokri AD:126

SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
1	Dismenlin Pacca brick work in cement mortor	138.0	@Rs: 1285.63	%Cft	Rs:	1774.00 (Rs: Twolve thousand Eighty Five & P.S Sixty Three only)
3	Removing Cement or Lime Plaster	1750.0	@Rs: 121.0	%Cft	Rs:	2117.00 (Rs: One Hunared Twenty One only)
4	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	194.0	@ Rs: 3176.25	%0 Cft	Rs:	616.00 (Three Thousand One Hund: Seventy Six & P.S Twenty Five only)
5	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	90.00	@Rs: 8694.95	% Cft	Rs:	7825.00 (Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
9	S/F sand floor and plugging into walls (S.I.No 29 P/31).	390.0	@Rs: 1141.25	%Cft	Rs:	4450.00 (Rs:One Thousand One Hund: Forty One & P.S Twenty Five only)
6	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) 23.	148.00	@ Rs: 11948.36	% S.ft	Rs:	17683.00 (Eleven Thousand Nine Hund: Forty Eight & P S Thirty Six only)
7	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I No. 6 (a) P/18)	8.0	@Rs: 337.0	P.Cft	Rs:	2696.00 (Three Hundred Thirty Seven only)
8	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars, (S.I.No 07 (b) P/20)	0.357	@ Rs: 5001.70	P.CWt	Rs:	1785.00 (Five Thousand One &P.S Seventy).
10	Pacca brick work in Ground floor i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P/24)	45.0	@Rs: 12674.36	% Cft	Rs:	5703.00 (Twlove thousand Six Hundred Seventy Four & Thirty Six only)
11	Pacca brick work in other than building i/c stricking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P/24)	138.00	@Rs: 12346.65	% Cft	Rs:	17038.00 (Tolive Thousand Three Hundred Fourty Six & P.S Sixty Five only)
12	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No. 13 P/57)	1750.00	@Rs: 2206.60	% Sft	Rs:	38615.00 (Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)



SNo:	Discription	Qty:	Rate	Unit	Rs:	Amount.
13	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	1750.00	@ Rs: 2197.52	%S.ft	Rs:	38456.00 (Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)
17	Cement pointing and stricking of joints on walls ratio. 1: 2 (S.I No.19 (a) P/53)	375.00	@ Rs: 1287.44	%Cft	Rs:	4828.00 (Twolve Thousand Eighty Seven & P.S Fourty Four only)
17	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 3 " thick. (S.I.No c P/46	886.0	@ Rs: 4411.82	% S.ft	Rs:	39088.00 (Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)
(B)	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2 " thick. (S.I.No c P/46	240.0	@ Rs: 3275.50	% S.ft	Rs:	7861.00 (Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)
15	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)	88.0	@ Rs: 1273.86	P.Sft	Rs:	112090.00 (Nine Hundraed Two P.S Ninty Three only)
19	Notice board made with cement.	64.00	@Rs: 58.11	% Sft	Rs:	3719.00 (Eighty Eight & P.S Eleven only)
20	S/Fin position iron steel grill of 3/4" X 1/4"flate iron of approved design i/c painting three coats etc complete with weigh not to beless than 3.7 Lbs sq: ft: of finished grill.	162.0	@Rs: 194.16	P.Sft	Rs:	31453.00 (Rs: One hundred Ninty Four & P.S Sixteen only)
21	White wash three coats (S.I.No 26 (c) 59).	2332.00	@Rs: 425.84	% Sft	Rs:	99354.00 (Rs: Four Hundred Twenty Five & P.S Eighty Four only)
16	Preparing the surface and painting with weather coat i/c rubbing the surface coat i/c rubbing the surface with brick /sen paper filling the voids with chalk plaster of paris and then painting with weather coat of approved make old surface.	3980.00	@Rs: 1948.10	%Sft	Rs:	77534.00 (One Thousand Nine Hundred Fourty Eight & P.S Ten only)
22	Primary coat of chalk under distempring (S.I No: 23 P 59)	5236.00	@ Rs: 442.75	% Sft	Rs:	23182.00 (Four Hundred Fourty Two & P.S Seventy Five only)
23	Distempring three coats. (S.I.No 24 (b) P/59)	5108.00	@ Rs: 1043.90	% Sft	Rs:	55148.00 (Rs: One Thousand Seventy Nine & P.S Sixty Five only)
24	M/F Steel grated doors with 1/16" thick sheeting i/c agnle iron frame 2"x2"x1/3" square bars 4" centre to centers.	24.0	@ Rs: 726.72	%Sft	Rs:	17441.00 (Rs: Seven Hundred Twenty Six & P.S Seventy Two only)
25	Painting doors & Window any type.	416.00	@ Rs: 2116.41	%Cft	Rs:	8804.00 (Rs: One Two Thousand one Hund: Sixteen & P.S Fourty One onl

RS: 539260.00

Part B

- 1 P/F Squating type white glass W.C pan of i/c coat of finishing cistring with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.
2.0 @ Rs: 4846.60 Rs: 9,694.00
- 2 Providing and fixing 22"x16" lavatory basin in white glazed earthen ware complete with and i/c the cost of V or C.I cantilever brackets 6 inches built into walls painted white in 2 coats after a primary coat of red lead paint and pair of 1/2" dia d c
1.0 @ Rs: 4694.80 Rs: 4,695.00
- 3 P/F 6x6 C.I Floor Trap of the approved self cleaning & C.I secured down grating holes in nuts lining joints to Nyloon connection.
3.0 @ Rs: 2024.46 Rs: 6,073.00
- 4 P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon connections
2.0 @ Rs: 447.15 Rs: 894.30
- 5 P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the building
12.0 @Rs: 333.21 PRft Rs 3999.00
- 6 P/F 4"x4" dia C.I branch of the required degree with access doors rubber washer 3/8" thick and bolts and unts and extra painting to match the colour of the building.
2.0 @ Rs: 270.60 P/No Rs: 541.20
- 7 Providing G.I pipe specials and clamps etc i/c fixing cutting fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to mach the colour of lthe building and testing pressure head of 200' and handling.
- (A) 1/2" dia
25.00 @ Rs: 76.21 PRft Rs: 1905.00
- (B) 6/4" dia
50.00 @ Rs: 95.79 PRft Rs: 4790.00
- 8 Providing and fixing 4" dia C.I terminal guard i/c extra painting to match the colour of the colour of the building.
2.0 @ Rs: 689.70 PRft Rs: 1379.00
- 9 Providing and fixing full way gun metal vallues with whelds threaded of flanged ends with rubber washing. (ii)3/4" (Light pattern)
1.0 @ Rs: 197.12 P.No Rs: 197.00
- 10 P/F C.I.Bross bib cock 1/2 " Dia.
2.00 @ Rs: 667.92 P.No Rs: 1336.00
- 11 Providing RCC pipe with colors class "B" and dying trenches to required depth and fixing in position and cement mortar 1:1 and testing with water presure to ahead with of 4" ft above of the highest pipe and refilling with excavted staff
- (a) 4"Dia
24.0 @ Rs: 146.57 PR ft Rs: 3518.0
- (b) 6"Dia
@ Rs: 199.25 PR ft Rs: 2391.0
- 12 S/F conceled stop cock of superior quality with C.P head 1/2" dia.
2.0 @ Rs: 478.28 P.No Rs: 957.00



13	S/F Long bib cock. (a) 1/2 "Dia				
	1.00	@ Rs: 1109.46	P.No	<u>Rs: 1109.00</u>	
14	P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.				
	1 No.	@ Rs: 5115	P.No:	<u>Rs: 5115.00</u>	
15	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete. (250 Gallons).				
	1.0	@Rs: 21989.61	P.Gallans	<u>Rs 21990.00</u>	
16	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.				
A	Filter.				
	10.0	@ Rs: 76.05	P.Rft	<u>Rs: 761.00</u>	
B	G.I pipe				
	90.0	@ Rs: 68.95	P.Rft	<u>Rs: 6206.00</u>	
C	Machine				
	1 No.	@Rs: 1441.60	P.No:	<u>Rs: 1442.00</u>	
				<hr/>	
TOTAL:B				Rs: 78992.50	
				<hr/>	
N.S.I				Rs: 10824.00	
				<hr/>	
G.Total				Rs: 68166.00	




BIDDING DOCUMENT**20**Issued toAnd charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation / Reconstruction of existing Primary & Elementary Schools in Sindh (damaged due to rain / flood or any other conditions) in District Larkano (37 Units) (2014-15 Programme) at GBMS. Saindad Junejo Tal: Dokri**
(ADP No. 126 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 700,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 14,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 35,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 12 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE-B 20

Name of work: Rehabilitation Reconstruction of Existing Primary & Elementary Schools
(Damaged due to rain/flood or any other conditions)
At: GBMS Sain Dad Junejo

SNo	Discription	Qty:	Rate	Unit	Rs:	Amount.
1	Dismantlin R.C.C Work 1:2:4	436.0	@Rs: 5445.0	%Cft	Rs:	23740.00 (Rs: Five thousand Forty Five only)
2	Dismantlin Pacca brick work in cement mortor	166.0	@Rs: 1285.63	%Cft	Rs:	2134.00 (Rs: Twolve thousand Eighty Five & P.S Sixty Three only)
3	Dismantlin C.C plain 1:2:4. (S.I.No 19 (c) P/11).	97.0	@Rs: 3327.50	%Cft	Rs:	3228.00 (Rs: Three thousand Three Hundred Twenty Seven & P.S Fifty only)
4	Removing Cement or Lime Plaster	2626.0	@Rs: 121.0	%Cft	Rs:	3177.00 (Rs: One Hunared Twenty One only)
5	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	35.0	@ Rs: 3176.25	%0 Cft	Rs:	111.00 (Three Thousand One Hund:Seventy Six & P.S Twenty Five only)
6	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	12.00	@Rs: 8694.95	% Cft	Rs:	1043.00 (Eight Thousand Six Hund:Ninty Four & P. S Ninty five only)
7	Pacca brick work in foundation and plinth in cement sand mortor ration 1:6 (S.I No 4 (C) 23.	49.00	@ Rs: 11948.36	% S.ft	Rs:	5855.00 (Eleven Thousand Nine Hund: Forty Eight & P. S Thirty Six only)
8	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No. 6 (a) P/18)	16.0	@Rs: 337.0	P.Cft	Rs:	5392.00 (Three Hundred Thirty Seven only)
9	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars. (S.I.No 07 (b) P/20)	0.714	@ Rs: 5001.70	P.CWt	Rs:	3571.00 (Five Thousand One & P. S Seventy).
10	S/F sand floor and plugging into walls (S.I.No 29 P/31).	1300.0	@Rs: 1141.25	%Cft	Rs:	14836.00 (Rs:One Thousand One Hund: Forty One & P. S Twenty Five only)
11	Pacca brick work in Ground floor i/c striking of joints cement sand mortor Ratio 1:6 (S.I No 5 (C) P/24)	166.0	@Rs: 12674.36	% Cft	Rs:	21039.00 (Twlove thousand Six Hundred Seventy Four & Thirty Six only)
12	Supplying Girders at site of work(Sch: of Material)	5.500	@ Rs: 3850.0	P.Cwt	Rs:	21175.000 (Three Thousand Eight Hundred Fifty only)

SNo	Discription	Qnty:	Rate	Unit	Rs:	Amount.
13	Supplying T-iron at site of work (Sch: of Material).	12.017	@ Rs: 3375.0	P.Cwt	Rs:	42961.000 (Three Thousand Three Hundred Seventy Five only)
14	First class tiles roofing consisting of 4" earth and 1" plaster with Gobri leeping over 1/4" thick cement plaster 1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in 1:6 cement mortor with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)	746.0	@ Rs: 11443.00	%Sft	Rs:	85366.0 (Rs:Eleven thousand Four Hundred Forty Three & P.S Ten)
15	Errection of rolled steel beams or old rails in roof etc crrection and fixing in position.	17.517	@ Rs: 186.34	P.Cwt	Rs:	3264.00
16	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)	41.0	@ Rs: 902.93	P.Sft	Rs:	37020.00 (Nine Hundraed Two P.S Ninty Three only)
17	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No:13 P/57)	2626.00	@Rs: 2206.60	% Sft	Rs:	57945.00 (Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
18	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	2626.00	@ Rs: 2197.52	%S.ft	Rs:	57707.00 (Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)
19	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2 " thick. (S.I.No c P/46)	606.0	@ Rs: 3275.50	% S.ft	Rs:	18850.00 (Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)
20	White wash three coats (S.I.No 26 (c) 59).	607.00	@Rs: 829.95	% Sft	Rs:	5038.00 (Rs: Four Hundred Twenty Five & P.S Eighty Four only)
21	Primary coat of chalk under distemping (S.I No: 23 P 59)	2316.00	@ Rs: 425.84	% Sft	Rs:	9862.00 (Four Hundred Forty Two & P.S Seventy Five only)
22	Distemping three coats. (S.I.No 24 (b) P/59)	2316.00	@ Rs: 1079.65	% Sft	Rs:	25005.00 (Rs: One Thousand Seventy Nine & P.S Sixty Five only)
23	Painting doors & Window any type.	176.00	@ Rs: 2116.41	%Cft	Rs:	3725.00 (Rs: One Two Thousand one Hund: Sixteen & P.S Forty One onl)

RS: 452044.00




BIDDING DOCUMENT**21**Issued toAnd charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Rehabilitation of existing High / Higher Secondary Schools in Sindh (2008-09 Programme) at GGHSS. Naudero (balance work)**
(ADP No. 164 of 2015-16)
- c) Procuring Agency's address:- Near Hgih Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 600,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 12,000
- f) Period of Bid Validity (days):- 28_Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 30,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 12 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

Schedule-B 2.1

**Rehabilitation of existing High/Higher Secondary School in Sindh (2008-09
Name of Work:- Programme) @ GGHSS Naudero Taluka Ratodero District Larkana (Balance
Work).**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	450	@ Rs: 3,176.25	% OCft	Rs: 1,420
					(Thirty one Hundred seventy six rup: & twenty five paisa only)
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	150	@ Rs: 8,694.95	% Cft	Rs: 13,042
					(Eighty six hund: ninty four rup: & ninty five paisa only)
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	678.00	@ Rs: 11,948.36	% Cft	Rs: 81,010
					(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)
4	Supply and fixing sand under floor including plugging in to walls	2125	@ Rs: 1,141.25	% Cft	Rs: 24,252
					(Eleven hundred forty one rupees & twenty five paisa only)
5	Providing and Laying 2" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	800.00	@ Rs: 4,411.82	% Sft	Rs: 35,295
					(Forry four hundred eleven rup: & eighty two paisa only)
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	300.00	@ Rs. 12,346.65	% Cft	Rs. #REF!
					(Twelve thousand three hund: forty six rup: & sixty five paisa only)
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	400	@ Rs. 2,206.60	% Cft	Rs. 8,826
					(Twenty tow hund: six rup: & sixty paisa only)
8	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	400	@ Rs: 2,197.52	% Sft	Rs: 8,790
					(Twenty one hund: ninty seven rup: & fifty two paisa only)
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	400.00	@ Rs: 1,287.44	% Sft	Rs: 5,150
					(Twelve hundred eighty seven rupees & forty for paisa only)

S #	Description	Qty	Rate	Unit	Amount
10	White wash two coats. (S.I. No. 26 P No. 54)	168.00	@ Rs. 425.00 % Sft (Four hundred twenty five rup: & paisa only)	Rs.	3,598
11	Primary coat of chalk distemper(S.I No. 23 P/53)	627	@ Rs: 442.75 % Sft (Four hundred forty two rupees & seventy five paisa only)	Rs:	2,776
12	Distemping two coats.(S.I No. 24(b) P/54)	567	@ Rs: 1,043.90 % Sft (One thousand forty three rup: & ninty paisa only)	Rs:	5,919
13	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick	80	@ Rs. 27,678.86 % Cft (Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)	Rs.	22,143
14	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)	252	@ Rs. 28,253.61 % P.Cwt (Twenty seven thousand seven hund: forty seve rupp: & six paisa only)	Rs.	71,199
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)	203	@ Rs. 30,509.77 % Sft (Thirty thousand five hund: nine rupees & seventy seven paisa only)	Rs.	61,935
16	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	23.00	@ Rs: 337.00 P.Cft (Threc hundred Thirty seven rup: only)	Rs:	7,751
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	1.129	@ Rs: 5,001.70 P.Cwt (Five thousand one rup: & seventy paisa only)	Rs:	5,647
18	Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. ... P/92)	68.00	@ Rs. 180.50 P. Sft (One hundred eighty Five rupees & fifty Paisa only)	Rs.	12,274

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel
44 @ Rs: 226.00 P. Sft Rs: 9,944
(Two hundred twenty six rupees only)

P/F G.I frame Chowkats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c
20 Welded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio 1:6
and repairing the jambs. The cost also i/c all carriage, tools and pla
7 @ Rs 228.90 P. Rft Rs: 1,602
(Two hundred twenty eight rupees & ninety paisa only)

1st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts
21 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25
P/60)
6.00 @ Rs: 902.93 P. Sft Rs: 5,418
(Nine hund: two rup: & ninty three paisa only)

Total Rs: 421,893

S.#	Description	Rate	Unit	Qty	Amount
-----	-------------	------	------	-----	--------

PART - B

- 1 P/F squatting type white glazed earthen ware W.C pan of with i/c cost of flushing cistern with internal fitting & flush pipe with bend making good in cement concrete 1:2:4. (i) W.C not less than 19" clear opening b/w flushing & 6 gallons flushing tank with

2.00 @ Rs: 4,846.80 P. No. Rs. 9,694
(Forty eight hundred forty six rup: & eighty paisa only)

- 2 P/F 22"x16" lavatory basin in white glazed earthen ware complete with & i/c the cost of W.I & C.I cantilever brackets 6 inches built into walls painted white in two coats after a primary cost of red lead painted & pair of 1/2" dia etc & making requisite n

1.00 @ Rs: 4,694.80 P. No. Rs. 4,695
(Forty six hundred ninty four rupees & eighty paisa only)

- 3 P/F 6"x6" C.I Floor Trap of the approved self cleaning & C.I secured down grating holes in walls plinth & floor for pipe connection & making good in C.C 1:2:4.

3.00 @ Rs: 2,024.46 P. No. Rs. 6,073
(Two thousand twenty four rup: only)

- 4 P/F in position Nyloon connections complete with 1/2" dia brass stop cock with pair of brass nuts lining joints to Nyloon connections.

2.00 @ Rs: 447.15 P. No. Rs. 894
(Four hundred forty seven rup: & fifteen paisa only)

- 5 P/F 4" dia C.I soil vent pipe i/c cutting, fitting & extra painting to match the colour of the building.

12.00 @ Rs: 666.21 P. Rft Rs. 7,995
(Six hundred Sixty Six rup: & Twenty One paisa only)

- 6 P/F 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/4" thick & bolts & nuts & extra painting to match the colour of the building.

2.00 @ Rs: 270.60 P. No. Rs. 541
(Two hundred seventy rupees & sixty paisa only)

- 7 Providing G.I pipe specials & clamps etc i/c fixing, cutting & fitting complete two coats of after cleaning the pipe etc with white zink paint with pigment to match the colour of the

(A) 1/2" dia

25.00 @ Rs: 76.21 P. Rft Rs. 1,905
(Seventy six rupees & twenty paisa only)

(B) 3/4" dia

50.00 @ Rs: 95.79 P. Rft Rs. 4,790
(Ninty five rupees & seventy nine paisa only)

S.#	Description	Rate	Unit	Qty	Amount
-----	-------------	------	------	-----	--------

- 8 P/F 4" dia C.I terminal guard i/c extra painting to match the colour of the building.
2.00 @ Rs: 689.70 P. No. Rs. 1,379
(Three hundred eighty nine rupees & seventy paisa only)
- 9 P/F full way gun metal valves with whelds threaded of flanged endswith rubber washing 6/4"
1.00 @ Rs: 197.12 P. No. Rs. 197
(one hundred ninty seven rupees & twelive paisa only)
- 10 S/F C.P brass bib cock 1/2" dia standard pattern.
2.00 @ Rs: 667.92 P. No. Rs. 1,336
(Three hundred thirty seven rupees & ninty two paisa only)
- 11 Providing RCC pipe with collars class "B" & digging the benches to required depth & fixing in
(A) 4" Dia
24.00 @ Rs: 146.57 P. Rft Rs. 3,518
(One hundred forty six rupees & fifty seven paisa only)
- (B) 6" Dia
12.00 @ Rs: 199.25 P. Rft Rs. 2,391
(One hundred Ninety nine rupees & twenty five paisa only)
- 12 S/F concealed stop cock of superior quality with C.P head 1/2" dia.
2.00 @ Rs: 478.28 P. No. Rs. 957
(Four hundred Seventy eight rupees & twenty eight paisa only)
- 13 S/F long bib cock of superior quality with C.P head 1/2" dia.
1.00 @ Rs: 1,109.46 P. No. Rs. 1,109
(Eleven hundred nine rupees & forty six paisa only)
- 14 P/F approved quality A.C motor pumping set (Javed Engineering) made 1-1/4" 1" section &
1.00 @ Rs: 5,115.00 P. No. Rs. 5,115
(Fifty one hundred fifteen rupees only)
- 15 S/F Fibre Glass Tank of approved quality & design & wall thickness as specified i/c the cost
1.00 @ Rs: 21,989.61 P. Gallon Rs. 21,990
(Twenty one thousand nine hundred eighty nine rup: & sixty one paisa only)
- 16 Hand pump with all accessories i/c fitting & fixing with local made coir strainer with wooden shoe etc complete.
(a) Filter
10.00 @ Rs: 76.05 P. No. Rs. 761
(Seventy six rupees & five paisa only)

S.#	Description	Rate	Unit	Qnty	Amount
-----	-------------	------	------	------	--------

(b) G.I Pipe

90.00 @ Rs: 68.95 P. Rft Rs. 6,206
 (Thirty eight rupees & ninty five paisa only)

(c) Machine

1.00 @ Rs: 1,441.60 P. No. Rs. 1,442
 (Fourteen hundred forty one rup: & sixty paisa only)

Total Rs. 82,986

N.S.I Rs. 10,824

Grand Total	Rs. (S.I)	72,162
--------------------	------------------	---------------




BIDDING DOCUMENT**22**Issued toAnd charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Integrated rehabilitation of existing Elementary Schools in District Larkano (15 Units) at GBPS. Panjoo Ghanghro (balance work)**
(ADP No. 1238 of 2015-16)
- c) Procuring Agency's address:- Near Hgih Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 500,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 10,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 25,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

Schedule-B 22

INTEGRATED REHABILITATION OF EXISTING ELEMENTARY SCHOOLS IN
Name of Work:- DISTRICT LARKANO (15 UNITS) @GBPS PANJOO GHANGHRO TALUKA
RATODERO DISTRICT LARKANO (BALANCE WORK).

S No: 22

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

- 1 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:3:6.

43.84 @ Rs. 14,429.25 % Cft Rs. 6,326

(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)

- 2 Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar 1:2 complete.(S.I No. 23 P/45)

274.02 @ Rs. 27,678.86 % Cft Rs. 75,846

(Twenty seven thousand six hund seventy eighty rup: & eighty six paisa only)

- 3 Providing and Laying 1" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)

2092.53 @ Rs: 4,411.82 % Sft Rs: 92,319

(Forry four hundred eleven rup: & eighty two paisa only)

(B) 2" Thick

1566.02 @ Rs: 3,275.50 % Sft Rs: 51,295

(Thirty two hundred seventy five rup: & fifty paisa only)

- 4 Two coats of Bitumen laid hot using 34lbs, for % over with sand of one 3/4" thick. (S.I No. 13 P/34)

1566.02 @ Rs. 1,887.40 % Sft Rs. 29,557

(Eighteen hundred eighty seven rupccs & forty paisa only)

- 5 White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)

56.15 @ Rs. 28,253.61 % P.Cwt Rs. 15,864

(Twenty seven thousand seven hund: forty seve rupp: & six paisa only)



S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

6 1st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)

221.55 @ Rs: 902.93 P. Sft Rs: 200,044

(Nine hund: two rup: & ninty three paisa only)

7 Painting doors & Windows any type (Old surface).(S.I No. 4 (c) P/67)

443.10 @ Rs: 1,212.21 % Sft Rs: 5,371

(Twelve hundred,twelve rup :& twenty one paisa only)

8 Primary coat of chalk distemper(S.I No. 23 P/53)

128.00 @ Rs: 442.75 % Sft Rs: 567

(Four hundred forty two rupees & seventy five paisa only)

9 Distampering three coats.(S.I No. 24(b) P/54)

128.00 @ Rs: 1,079.65 % Sft Rs: 1,382

(One thousand Seventy nine rup: & sixty five paisa only)

Total Rs: 478,571



BIDDING DOCUMENT**23**Issued toAnd charged Rs. 1500/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- Intograted rehabilitation and provision of missing facilities to existing Elementary Schools District Larkano (123 Units) at GBPS. Mahota (balance work)
(ADP No. 1234 of 2015-16)
- c) Procuring Agency's address:- Near Hqih Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 1,000,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but no exceeding 5%) Rs. 20,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 50,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE " B "**S.No: 23**

NAME OF WORK:- INTEGRATED REHABILITATION AND PROVISION OF MISSING FACILITIES TO EXISTING ELEMENTARY SCHOOL DISTRICT LARKANO (123-UNITS) UNDER LARKANO EDUCATION PACKAGE) AT GBPS MAHOTA (REHAB: C/WALL, LAV:) (BALANCE WORK) TALUKA LARKANO.

S.No:	Description	Qty:	Rate	Unit	Amount
1	Dismantling brick work in lime or cement mortar. (S.I.No.13 P/10).				
		296.00	@ Rs: 1285/63	% Cft	Rs: 3,805.00
			(Rs: one two hund: eighty five & sixty three only)		
2	Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and straightening the same. (S.I.No.20 P/10).				
		92.00	Rs 5445/-	% Cft	Rs: 5,009.00
			(Rs: five thous: four hund: forty five only)		
3	Dimantling cement concrete plain 1:2:4. (S.I.No.19 (c) P/10).				
		581.00	@ Rs: 3327/50	% Cft	Rs: 19,333.00
			(Rs: three thous: two hund: twenty seven & fifty only)		
4	Cement concreate brick or stone ballast 1/2" to 2" guage. (S.I.No: 4 (d) P/ 14).				
		89.00	@ Rs: 8122/95	% Cft	Rs: 7,229.00
			(Rs: eight thous: one hund: twenty two & ninty five only)		
5	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)				
		251.00	@ Rs:11948/36	% Cft	Rs: 29,990.00
			(Rs: eleven thous: nine hund: eighty five & thirty six only)		
6	RCC work in roof slab beam columns rafts lintel and other structure member laid in situ or precast laid in position complete in all respect ratio 1:2:4 (S.I.No.6 P/16).				
		225.00	@ Rs:337/-	P.Cft	Rs: 75,825.00
			(Rs: three hund: thirty seven only)		
7	Fabrication of Tor steel reinforcement for cement concrete i/c cutting bending and laying in position i/c the cost of binding wire also removal of rust from bars.(S.I.No.8 (b) P/16)				
		12.05	@ Rs:5001/70	P.Cwt	Rs: 60,270.00
			(Rs: five thous: one & seventy only)		

S.No:	Description	Qty:	Rate	Unit	Amount
8	Pacca brick work other than building including striking of joints upto 20' ft. height in (e) cement sand mortar 1:6 (S.I.No.7 (e) P/21).	671.00	@ Rs:12346/65	% Cft	Rs: 82,846.00 (Rs: twelve thous: three forty six & sixty five only)
9	Cement plaster 1:6 upto 12' height (b) 1/2" thick. (S.I.No.13 (b) P/51).	2664.00	@ Rs:2206/60	% Sft	Rs: 58,783.00 (Rs: two thous: two hund: six & sixty only)
10	Cement plaster 1:4 upto 12' height (a) 3/8" thick. (S.I.No.11 (a) P/51).	2664.00	@ Rs:2197/52	% Sft	Rs: 58,541.00 (Rs: two thous: one hund: ninty seven & twenty two only)
11	Extra labour rate making grooves of 1"x1/4" or 3/4"x1/2" plastered surface with true edges both vertically and horizontally with uniform depth and with groove base smothly finished etc complete as per instruction horizontally with uniform depth and with groove base smothly finished etc complete as per instruction	888.00	@ Rs: 7/71	P.Rft	Rs: 6,846.00 (Rs: seven & seventy one only)
12	Making and fixing steel grated door with 1/16" thick sheeting including angle iron frame 2"x2" 3/8" and 3/4" square bars 4" centre to centre with locking arrangement. (S.I.No.24P/91).	63.00	@ Rs:726/72	P. Sft	Rs: 45,783.00 (Rs: seven hund: twenty six & seventy two only)
13	Cement Concerate plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without Ratio. 1:2:4.(S.I.No: 5 (f) P/ 15).	111.00	@ Rs:14429/25	%Cft	Rs: 16,016.00 (Rs: fourteen thous: four hund: twenty nine & twenty five only)
14	Laying floors of approved coloured glazed tiles 1/4" thick laid in white cement and pigment on a bed of 3/4" thick cement mortar 1:2. (S.I. No: 25 P/42).	791.00	@ Rs:27747/06	% Sft	Rs: 219,479.00 (Rs: twenty seven thous: seven hund fourty seven & six only)
15	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	1903.00	@ Rs: 4411/82	% Sft	Rs: 83,957.00 (Rs: four thous: four hund: eleven & eighty two only)



2018

S.No:	Description	Qty:	Rate	Unit	Amount
16	Two Coats of bituman laid hot using 34 Lbs for % Sft. Ober roof and blinded with sand at one Cft. Per % Sft. (S.I.No: 13 P/34).	3484.00	@ Rs:1887/40	% Sft	Rs: 65,759.00 (Rs: one thous: eight hund; eighty seven & fourteen only)
17	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutter).	42.00	@ Rs: 902/93	P.Sft	Rs: 37,923.00 (Rs: nine hund: two & ninty three only)
18	White wash two coats.	2511.00	@ Rs:425/84	% Sft	Rs: 10,693.00 (Rs: four hund: twenty five & eighty four only)
19	Distempering two coats. (S.I.No.24 (b) P/53).	8841.00	@ Rs:1043/90	% Sft	Rs: 92,291.00 (Rs: ten hund; forty three & ninty only)
20	Painting doors and windows any type. (ii) Each subsequent coat. (S.I.No.4 (c) (ii) P/76).	784.00	@ Rs:1160/06	% Sft	Rs: 9,095.00 (Rs: one thous: one hund; sixty & six only)
21	Prepareing the surface and painting with weather coat of approved make to old weather coat surface. (S.I.No:39 P/55).	1332.00	@ Rs:1498/48	% Sft	Rs: 19,960.00 (Rs: one thous: four hund; ninty eight & forty eight only)
22	Painting guard bars , gates iron bars gratings railings i/c standard barsed etc: smiler open works.	126.00	@ Rs:1270/83	% S.ft	Rs: 1,601.00 (Rs: one thous: two hund: seventy & eighty three only)
G.Total:					Rs: 1,011,032.0

BIDDING DOCUMENT**24**

Issued to

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- Integrated rehabilitation and provision of missing facilities to existing Elementary Schools District Larkano (123 Units) at GBPS, Main Dokri (balance work)
(ADP No. 1234 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 500,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 10,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 25,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE-B

Name of work:- Integrated Rehabilitation of Missing Facilities to Existing Elementary School
(Under Larkana Education Package) At: GBPS Main Dokri (Reh:C/W) Taluka Dokri.

S.no	Description	Qty:	Rate	Unit	Amount.
1	Excavation in foundation of building bridges and other structure member with excavated lead upto one chain and lift upto 5" ft in ordingay soil (S.I.No: 18p4).	676.00	@ Rs: 3176.25	%0 Cft	Rs: 508.00 (Three Thousand One Hund:Seventy Six & P.S Twenty Five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage Ration 1:5:10 (S.I.No 4 (C) P/16).	449.00	@Rs: 8694.95	% Cft	Rs: 39040.00 (Eight Thousand Six Hund:Ninty Four & P.S Ninty five only)
3	Pacca brick work in foundation and plinth in cement sand mortar ration 1:6 (S.I No 4 (C) 23.	105.00	@ Rs: 11948.36	% S.ft	Rs: 12546.00 (Eleven Thousand Nine Hund: Fourty Eight & P.S Thirty Six only)
4	S/F sand floor and plugging into walls (S.I.No 29 P/31).	2480.00	@Rs: 1141.25	%Cft	Rs: 28303.00 (Rs:One Thousand One Hund: Fourty One & P.S Twenty Five only)
5	Pacca brick work in Ground floor i/c stricking of joints cement sand mortar Ratio 1:6 (S.I No 5 (C) P/24)	144.00	@Rs: 12674.36	% Cft	Rs: 18251.00 (Twlove thousand Six Hundred Seventy Four & Thirty Six only)
6	2nd class tiles roofing consisting of 4" earth and 1" plaster with Gobri leeping over 1/4" thick cement plaster 1:6 with 34lbs: if bituumen coating sand blinded provided over 2 layers of tiles 12"x6" 1 1/4" laid in 1:6 cement mortar with 1/4" thick sand of tiles complete i/c currin etc complete (S.I.No 1 P/38)	190.48	@ Rs: 7607.25	%Sft	Rs: 14453.00
7	Cement plaster 1:6 upto 20' ft; height 1/2" thick. (S.I No.13 P/57)	727.00	@Rs: 2206.60	% Sft	Rs: 16042.00 (Two hundred Three Hund: Fifty Six & P.S Seventy Eight only)
8	Cement plaster 1:4 upto 20' ft; height 3/8" thick. (S.I No: 11(a) P 57)	727.00	@ Rs: 2197.52	%S.ft	Rs: 15976.00 (Two Twousand One Hund: Ninty Seven & P.S Fifty Two only)
9	First Class deodar wood wrought joinery in doors and windows etc: fixed in position i/c deodar panelled and glazed (b) 1-3/4thicks.(Only Shutters)	35.00	@ Rs: 902.93	P.Sft	Rs: 44582.00 (Nine Hundraed Two P.S Ninty Three only)
10	P/L 1" thick cement concrete topping 1:2:4 i/c surface finishing and dividing into paenlls Ration 2 " thick. (S.I.No c P/46	1090.00	@ Rs: 3275.50	% S.ft	Rs: 35703.00 (Rs: Four Thousand Four Hundred Eleven & P.S Eighty Two only)
11	White wash three coats (S.I.No 26 (c) 59).	544.00	@Rs: 829.95	% Sft	Rs: 5415.00 (Rs: Four Hundred Twenty Five & P.S Eighty Four only)
12	Primary coat of chalk under distempring (S.I No: 23 P 59)	2403.00	@ Rs: 442.75	% Sft	Rs: 10639.00 (Four Hundred Fourty Two & P.S Seventy Five only)
13	Distempring three coats. (S.I.No 24 (b) P/59)	2403.00	@ Rs: 1079.65	% Sft	Rs: 25944.00 (Rs: One Thousand Seventy Nine & P.S Sixty Five only)
14	Painting doors & Window any type.	257.00	@ Rs: 2116.41	%Cft	Rs: 5439.00 (Rs: One Two Thousand one Hund: Sixteen & P.S Fourty One only)

TOTAL: Rs: 272,341.00

Part-B

1	P/F Squating type white glass W.C pan of i/c coat of finishing cistring with internal fitting and flush pipe between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	5.0 @Rs: 4846.80	P.No:	Rs:	24234.00
2	P/F and 22"x16" lavatory basion in white glazed earthen ware complete with & i/c the cost of W.I conntilever brackets 6 inch built into walls painted white in two cost after a Primary Cost of red land painth a pair of 1/4" dia chrome plate pillar trape 1-1/2" dia	1.0 @Rs: 4694.80	Each	Rs:	4695.00
3	P/F 6"x2" or 6"x3" C.I floor trap.	5.0 @Rs: 2024.43	Rft	Rs:	10212.00 (Two Hundred Fourty Four & P.S Thirty Five only)
4	P/F in position nyloon connection complete with 1/2" dia brass stop cock with pair brass nuts lining joints to nyloon coonections (S.I.No: 9p3).	5.0 @Rs: 447.15	Each	Rs:	2236.00
5	P/F 4" dia C.I soil and vent pipe i/c cutting fitting and extra painting to match the colour of the building(S.I.No:1p8).	30.0 @Rs: 666.21	Each	Rs:	19986.00
6	P/F 4"x4" dia C.I branch of the required dgree with accesss doors rubber washer 3/8"thick and builts and extra painting to matakch the colour of the building.	5.0 @Rs: 270.60	Each	Rs:	1353.00
7	Providing and G.I pipes special & clamps etc i.c fixing cutting and fitting complete with and i.c the cost of breaking through walls and roof making good etc painting two coats after cleaning the pipe etc,with zink paid with pigment to match the colour of the buildings.and testing with water to a preasure head of 200 ft.and handling.(S.I.No: 1p11).				
(A)	1/2" dia	50.0 @Rs: 76.21	Each	Rs:	3811.00
(B)	3/4" dia	75.0 @Rs: 95.79	Each	Rs:	7184.00
8	P/F 4" dia C.I terminal guard i/c extra painting to match the colour of the building.(S.I.No:11p9).	1.0 @Rs: 689.70	Each	Rs:	690.00
9	Providing and fixing full way gun metal vallues with whelds threabed of flaigned ends with rubber washing (ii) 3/4" (Light pattern).	1.0 @Rs: 197.12	Each	Rs:	197.00
10	S/F C.P brass bib cock 1/2"dia standard patter.	5.0 @Rs: 337.92	Each	Rs:	1690.00
11	Providing RCC pipe with colors class "B" and dying trenches to required depth and fixing in position and cement mortar 1:1 and test <u>staff (a) 4" dia</u> . refilling with excavted staff				
	<u>4" dia</u> .	24.0 @Rs: 146.57	Each	Rs:	3518.00
	<u>6" dia</u> .	12.0 @Rs: 199.25	Each	Rs:	2391.00
12	S/F conceled stop cock of superior quality with C.P head 1/2" dia.	5.0 @Rs: 478.28	P.No	Rs:	2391.00



13	S/F long bib-cock of superior quality with C.P head 1/2" dia	5.0	@ Rs: 1109.46	P.No	Rs:	5547.00
14	P/F approved quality AC Motor pumping set(Javed Engineering) Made etc.	1.0	@ Rs: 5115.00	Each	Rs:	5115.00
15	S/F Fibre glass tank of approved quality and design and wall thickness as specified i/c the cost of nuts and bolts and fixing in plate form of cement concrete 1:2:6 and making connection for inlet-outlet and over flow pipe etc complete. (150 Gallans)	150.0	@Rs: 87.95	Each	Rs:	13193.00
22	Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i.c the complete					
(A)	<u>Filter</u>	10.0	@ Rs: 76.05	Each	Rs:	761.00
(B)	<u>G.I Pipe</u>	70.0	@ Rs: 68.95	Each	Rs:	4827.00
©	<u>Machine</u>	1.0	@ Rs: 1441.60	P.No	Rs:	1442.00

TOTAL: Rs: 115,471.00

N.S.I. Rs: 10,824.00

TOTAL: Rs: 104,647.00




BIDDING DOCUMENT**25**Issued toAnd charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- Integrated rehabilitation and provision of missing facilities to existing Elementary Schools District Larkano (123 Units) at GBPS, Gokalpur (balance work)
(ADP No. 1234 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 400,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 8,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 20,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR



 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

SCHEDULE " B "

S.No: 25

NAME OF WORK:- INTEGRATED REHABILITATION AND PROVISION OF MISSING FACILITIES TO EXISTING ELEMENTARY SCHOOLS DISTRICT LARKANO (123-UNITS) UNDER LARKANO EDUCATION PACKAGE) AT GBPS GOKAL PUR (REHAB:) (BALANCE WORK) TALUKA LARKANO.

S.No:	Description	Qty:	Rate	Unit	Amount
1	Excavation in foundation of building bridges and other structures including dag belling dressing refilling around structure with excavated earth watering and remming lead upto 5ft. (b) in ordinary soil (S.I.No: 18 (b) P/4).	138.00	@ Rs: 3176/25	% 0 Cft	Rs: 437.00 (Rs: three thous: one hund: seventy hund: twenty five only)
2	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).	45.00	@ Rs: 8694/95	%.Cft	Rs: 3,913.00 (Rs: eight thous: six hund: ninty four & ninty five only)
3	Pacca brick work in foundation and plinth in (e) cement sand mortar 1:6. (S.I.No.4 (e) P/20)	220.00	@ Rs:11948/36	%.Cft	Rs: 26,252.00 (Rs: eleven thous: nine hund: eighty five & thirty six only)
4	Supplying and filling sand under floor and plugging in walls.(S.I.No: 29 P/25).	334.00	@ Rs: 1141/25	%. Cft	Rs: 3,813.00 (Rs: one thous: one hund: forty one & twenty five only)
5	Extra lead 3 miles	334.00	@ Rs: 579/41	%.Cft	Rs: 1,936.00 (Rs: five hund: sevnty nine & fourty one only)
3	Cement concrete brick or stone ballast 1-1/2 " to 2" guage (c) Ratio 1:5:10. (S.I.No: 4 (c) P/ 14).	434.00	@ Rs: 8694/95	%.Cft	Rs: 37,740.00 (Rs: eight thous: six hund: ninty four & ninty five only)
4	Providing and laying 1" thick topping cement concerate (1:2:4) including surface finishing anddividing into panels. (d) 3" Thick. (S.I.No: 16 (d) P. 41).	1376.00	@ Rs: 4411/82	%. Sft	Rs: 60,686.00 (Rs: four thous: four hund: eleven & eighty two only)


JEN

S.No:	Description	Qty:	Rate	Unit	Amount
5	Cement Pointing 1:2 flash on floor. (S.I.No: 18 P/52).	1335.00	@ Rs: 939/57	% S.ft	Rs: 12,539.00 (Rs: nine hund: thirty nine & fifty seven only)
6	Supplying and fixing in position iron/steel grill of 3/4"x1/4" size flate iron of approved design i/c painting three coats etc complete (weight not to be less than 3.7 lbs/Sq. foot of finished grill).(S.I.No.26 P/92).	6.00	@ Rs:180/50	P. Sft	Rs: 1,083.0 (Rs: one hund: eighty & fifty only)
7	First Class deodar wood wrought, joinery in doors and windows etc, fixed in position i/c chowkats hold fasts hinges, iron tower bolts. Chocks cleats, handles and cords with hooks, etc 1 3/4" thick (S.I.No: 7 (b) P. 57) (Only Shutter).	263.00	@ Rs: 902/93	P.Sft	Rs: 237,470.00 (Rs: nine hund: two & ninty three only)
8	Extra labour rate for making cemet plaster patta/band around straight are couyard opening and around the edges of roof slabs the wight not less tham 6' with fine finishing as directed by Engineer Incharge. (S.I.NO.35 P/54)	480.00	@ Rs: 19/36	% Sft	Rs: 9,298.0 (Rs: ninteen & thirty six only)
9	White washing three coats. (S.I.No.26 (c) P/53).	1191.00	@ Rs:829/95	%.Sft	Rs: 9,893.00 (Rs: eight hund: twenty nine & ninty five only)
10	Primary coat of chalk under distemping.	3688.00	@ Rs: 442/75	% S.ft	Rs: 16,325.00 (Rs: four hund; fourty two & seventy five only)
11	Distemping three coats. (S.I.No.24 (c) P/53).	4860.000	@ Rs:1079/65	%.Sft	Rs: 52,465.00 (Rs: one thos: seventy nine & sixty five only)
12	Preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick/sand paper, filling the voids with chalk/plaster of pairs and then painting with weather coat of approved make. 2nd & subsequent coat. (S.I.No.38 (b) P/55).	3770.00	@ Rs: 1948/10	%.Sft	Rs: 73,444.00 (Rs: one thous: nine hund: fourty eight & ten only)



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 13 Preparing surface and painting of doors and windows any type (including edges)
(ii) Each subsequent coat of paint. (S.I.No.5 (c) P/69).

500.00 @ Rs:2116/41 % Sft Rs: 10,582.0
(Rs: two thous: one hund: sixteen & fourty one only)

- 14 Painting guard bars , gates iron bars gratings railings i/c standard barsees etc:
smiler open works.

1266.00 @ Rs:1270/83 % S.ft Rs: 16,100.00
(Rs: one thous: two hund: seventy & eighty three only)

G.Total: Rs: 573,976.00



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

PART-B

1	P/f squatting type white glazed earthen ware W.C pan of with i/c the cost of flushing cistern with internal fitting and flush pipe with bend making good in cement concrete 1:2:4(i) W.C not less than 16" clear opening between flushing and 3 gallons flushing tank with 4" dia C.P trap and C.I thumble.	2.00	@ Rs: 4802/60	P.No:	Rs: 9,605.00
					(Rs: four thous: eight hund; two & sixty only)
2	P/f water pumping set 3 HP unonablock single phase 220 volls with 1 1/2"x1 1/4" suntire delivery (60 ft head i/c making c.c 1:3:6 plater form of required size fixing with units + hools E.S.I.No: 23P/33).	1.00	@ Rs:15254/48	P.No:	Rs: 15,254.00
					(Rs: fifteen thous: two hund: fifty four & fouty eight only)
3	S/F long bib-cock of superior quality with C.P head 1/2" dia	2.00	@ Rs: 1384/24	P.No	Rs: 2,768.00
					(Rs: one thous: three hund: eighty four & twenty four only)
4	S/F fibre glass tenk of approved quilty and design and wall thickness as apecoified i/c the cost of nute and bolts and fixing in plate iron of cement concerte 1:2:7 and making and commoction for inlet- outlet and over flow pipe etc complete (200.gallons).	1.00	@ Rs:87/95	P.Gallan	Rs: 17,590.00
					(Rs: Twenty One thous: nine hund: eighty nine & Sixty only)
G.Total:					Rs: 45,217.0

N.S. I

1	P/F UPVC Pipe (AGM) SCH: 40 (E) on surface using Clips/ Saddle of approved quality and Material etc paid separatly recessed in Masonry, C.C or R-C-C upto 60' height and making good with C.C I/C cutting, finishing etc complete as per instruction of the Engineer Incharge. Specification of material Should meet the requirement of class 12 & 5 B in accordance with AS + MD 1784 type grade 1 rate I/C all cost of labour, material charges Scaffolding Ladders etc complete (N.S.I).				
	(a) 3/4" Dia	45.00	@ Rs: 78/01	P.No	Rs: 3,510.00
					(Rs: sevnty eight & One only)
	(b) 1-1/4" Dia	6.00	@ Rs: 114/59	P.No	Rs: 587.00
					(Rs: one hund:: fourteen & fifty nine only)
	(c) 4" Dia	10.00	@ Rs: 397/77	P.No	Rs: 3,977.00
					(Rs: three hund: ninty seven & seventy seven only)



S.No:	Description	Qty:	Rate	Unit	Amount
-------	-------------	------	------	------	--------

- 2 P/F Bend/ Elbow (90 degree) of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quality and design of various sizes fixed to UPVC pipe/fittings paid separately, using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per class 12454-B In accordance Incharge. Specifications of the material should meet the requirements of material, cartage, scaffolding / ladders etc. complete. (N.S.I)

<u>3/4" Dia</u>	5.00	@ Rs: 103/05	P.No	Rs:	515.00
(Rs: one hund; three & five only)					

<u>(b) 4" Dia</u>	2.00	@ Rs: 425/45	P.No	Rs:	850.00
(Rs: four hund: twenty five & fourty five only)					

- 3 P/F TEE of SCH- 40 PVC of NAMAT OR EQUIVALENT make of approved quilty and design of various sizes fixed to UPVC pipe / fittings paid separately,using approved adhesive compound (AGM or WELDON, made in USA, in ORANGE colour) upto 60 ft height as per instruction of the Engineer Incharge. Specifications of the material should meet the requirements of class 12454-B in accordance with the ASTM-D_ 1784 type 1 grade TEE 1. Rate includes all costs of labour, material cartage.

<u>3/4" Dia</u>	3.00	@ Rs: 110/40	P.No	Rs:	331.00
(Rs: one hund; ten & fourteen only)					

- 4 Hand pump all accessoried i/c fitting and fixing with local made coir strainer with wooden shoe i/c the complete.

<u>(a) Filter</u>	10.00	@ Rs: 76/05	P.Rft	Rs:	760.00
(Rs: seventy six & five only)					

<u>(b) G.I Pipe</u>	80.00	@ Rs: 38/95	P.Rft	Rs:	3,116.00
(Rs: thrity eight & ninty five only)					

<u>(C) Machine</u>	1.00	@ Rs: 1441/65	Each	Rs:	1,442.00
(Rs: one thous: four hund: fourty one & sixty five only)					

Total:	Rs:	15,088.0
---------------	------------	-----------------

S.I	Rs:	45,217.0
------------	------------	-----------------


G.Total:	Rs:	60,305.0
-----------------	------------	-----------------

BIDDING DOCUMENT**26**Issued toAnd charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____ / ____ /2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Integrated rehabilitation and provision of missing facilities to existing Elementary Schools Taluka Ratodero District Larkano (79 Units) at GBPS. Ratodero-II (balance work)**
(ADP No. 1233 of 2015-16)
- c) Procuring Agency's address:- Near Hgih Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 500,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but no exceeding 5%) Rs. 10,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 25,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

Schedule-B 26

INTEGRATED REHABILITATION AND PROVISION OF MISSING FACILITIES

TO EXISTING ELEMENTARY SCHOOLS TALUKA RATODERO DISTRICT

Name of Work:-

LARKANO (79 UNITS) UNDER LARKANA EDUCATION PACKAGE (REVISED)

@GBPS RATODERO-II (BOUNDARY WALL).

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	450	@ Rs: 3,176.25	% 0Cft	Rs: 1,429
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	150	@ Rs: 8,694.95	% Cft	Rs: 13,042
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	678.00	@ Rs: 11,948.30	% Cft	Rs: 81,010
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Supply and fixing sand under floor including plugging in to walls	2125	@ Rs: 1,141.25	% Cft	Rs: 24,252
	(Eleven hundred forty one rupees & twenty five paisa only)				
5	Providing and Laying 2" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	800.00	@ Rs: 4,411.82	% Sft	Rs: 35,295
	(Forry four hundred eleven rup: & eighty two paisa only)				
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	300.00	@ Rs. 12,346.65	% Cft	Rs. 37,040
	(Twelve thousand three hund: forty six rup: & sixty five paisa only)				
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	400	@ Rs. 2,206.60	% Cft	Rs. 8,826
	(Twenty tow hund: six rup: & sixty paisa only)				
8	Cement plaster 1:4 up to 12" height 3/8" thick. (S.I No. 11(a) P/51)	400	@ Rs: 2,197.52	% Sft	Rs: 8,790
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	400.00	@ Rs: 1,287.44	% Sft	Rs: 5,150
	(Twelve hundred eighty seven rupees & forty for paisa only)				



S #	Description	Qty	Rate	Unit	Amount
10	White wash two coats. (S.I. No. 26 P No. 54)	168.00	@ Rs. 425.00	% Sft	Rs. 3,598
			(Four hundred twenty five rup: & paisa only)		
11	Primary coat of chalk distemper (S.I. No. 23 P/53)	627	@ Rs. 442.75	% Sft	Rs. 2,776
			(Four hundred forty two rupees & seventy five paisa only)		
12	Distemping two coats (S.I. No. 24(b) P/54)	567	@ Rs. 1,043.90	% Sft	Rs. 5,919
			(One thousand forty three rup: & ninty paisa only)		
13	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick	80	@ Rs. 27,678.86	% Cft	Rs. 22,143
			(Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)		
14	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I. No.24 P/ 45)	252	@ Rs. 28,253.61	% P.Cwt	Rs. 71,199
			(Twenty seven thousand seven hund: forty seve rupp: & six paisa only)		
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)	203	@ Rs. 30,509.77	% Sft	Rs. 61,935
			(Thirty thousand five hund: nine rupees & seventy seven paisa only)		
16	RCC work in roof slab beam columns rafts lintel & other structure member and in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	23.00	@ Rs. 337.00	P.Cft	Rs. 7,751
			(Three hundred Thirty seven rup: only)		
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding with also removal of rust from bars. (S.I.No. 8 (b) P/16)	1.129	@ Rs. 5,001.70	P.Cwt	Rs. 5,647
			(Five thousand one rup: & seventy paisa only)		
18	Supply & Fixing in Position iron/steel grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complete (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I. No. ... P/92)	68.00	@ Rs. 180.50	P. Sft	Rs. 12,274

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------


(One hundred eighty Five rupees & fifty Paise only)

19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel
 1-1 @ Rs. 226.00 P. Sft Rs. 9,944
 (Two hundred twenty six rupees only)

P/F G.I frame ChowKats of size 7'x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c
 20 Welded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio 1:6
 and repairing the jambs. The cost also i/c all carriage, tools and pla
 7 @ Rs. 228.90 P. Rft Rs. 1,602
 (Two hundred twenty eight rupees & ninty paisa only)

1st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts
 21 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25
 P/60)
 6.00 @ Rs. 902.93 P. Sft Rs. 5,418
 (Nine hund: two rup. & ninty three paisa only)

Total Rs: 421,893



BIDDING DOCUMENT**27**


Issued to _____

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: _____ / _____ /2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Integrated rehabilitation and provision of missing facilities to existing Elementary Schools Taluka Ratodero District Larkano (79 Units) at GBPS. Ratodero-II (1st floor electrification)**
(ADP No. 1233 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 300,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 6,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 15,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR



EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

SCHEDULE "B"

S No: 27

Repair and maintenance of Rehabilitation and Provision of missing facilities to existing Elementary Schools in the District of Dharwad under Larkana Education Package (Revised) at CHPN Ratanwadi, K. B. Dist. Tal. K. B. Tal. Ratanwadi (Finance) ADP No. 1233

Sl. No.	ITEM OF WORK	Qty.	Rate	Unit	Amount
1	Wiring - 1 point on wall with 1/1-13(3/029)PVC insulated wire in 20mm(3/4") channel pipe on surface (S.I.No. 129 P.15)	@ Rs: 910.0	P Point	Rs.	910.00
2	Wiring - 1 point on wall with (3/029) PVC insulated wire in 20mm(3/4") Channel pipe on surface (S.I.No. 130 P.15)	@ Rs: 742.0	P Point	Rs.	742.00
3	Wiring on CH unit with 1/1-13 (3/029)PVC insulated wire in 20mm(3/4")PVC conduit (S.I.No. 131 P.15)	@ Rs: 1590.0	P Point	Rs.	1590.00
4	Providing and laying (Main or sub Main) PVC insulated with size 2 / 029} Copper wire in 20mm(3/4") PVC conduit on surface (S.I.No. 3 P.1)	@ Rs: 171.0	P Meter	Rs.	171.00
5	Providing and laying (Main or sub Main) PVC insulated with size 2 / 044}(6 MM ²) Copper wire in 20mm(3/4") PVC conduit on surface (S.I.No. 5 P.1)	@ Rs: 305.0	P Meter	Rs.	305.00
6	Providing and laying (Main or sub Main) PVC insulated with size 2 / 052}(10mm ²) Copper wire in 20mm(3/4") PVC conduit on surface (S.I.No. 6 P.1)	@ Rs: 428.0	P Meter	Rs.	428.00
7	Providing and laying PVC one way S.P 5amp switch flush type (S.I.No. 216 P.30)	@ Rs: 54.0	P Each	Rs.	54.00
8	Providing and laying 2 pin 5 amps plug & socket flush type (S.I.No. 225 P.33)	@ Rs: 83.0	P Each	Rs.	83.00
9	Providing and laying waxlite ceiling rose with two terminal (S.I.No. 232 P.36)	@ Rs: 70.0	P Each	Rs.	70.00
10	Providing and laying waxlite ceiling rose with two terminals (S.I.No. 228 P.33)	@ Rs: 72.0	P Each	Rs.	72.00
11	Providing and laying brass ceiling fan 56" (good quality)	@ Rs: 3186.0	P Each	Rs.	3186.00
12	Providing and laying main type S.P. plug socket switch and shoe unit on given board (S.I.No. 18 P.11)	@ Rs: 156.97	P Each	Rs.	156.97
13	Providing and laying fan regulator on S.W board (S.I.No. 1 (b) P.14)	@ Rs: 91.30	P Each	Rs.	91.30


20/11/2019

- | | | | | | | |
|----|--|---------------|---------|----|----|--|
| 14 | 1/2" mild steel gal. iron clamp 15.8 mm (5/8") dia suitable for RCC roof. (S.I No. 1 P 14) | @ Rs. 141.01 | P Each | Rs | Rs | |
| 15 | 3/4" mm plywood board double shutter to accommodate heavy duty circuit breakers
(S.I No. 8 P 13) | @ Rs. 1426.34 | P Sq ft | Rs | Rs | |
| 16 | 1/2" copper wire gal. 2x2x12" copper plate buried in ground at a depth of 12" in form of wire mesh from etc. above level with salt and charcoal for making test pit 12" dia by excavation of all type of soil. Earth Plate to be connected with No. 6 25/20 gauge wire run in 1/2" dia C.I pipe straight from the earth upto metallic electrical assembly i/c providing necessary tee. (S.I No. 22 P 26) | @ Rs. 2570.37 | P Each | Rs | Rs | |
| 17 | D.P. Circuit breakers 6 Amps to 63 Amps D.P i/c fixing on a prepared board
mechanical connection (S.I No. 2 P 20) | @ Rs. 948.0 | P Each | Rs | Rs | |
| 18 | P/0 Energy saver superior quality i/c fixing on extg. holder etc complete. (S.I No. 6 P 3) | @ Rs. 497.0 | P Each | Rs | Rs | |

TOTAL :



BIDDING DOCUMENT**28**


Issued by

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Integrated rehabilitation and provision of missing facilities to existing Elementary Schools Taluka Ratodero District Larkano (79 Units) at GBPS, Masudero (balance work)**
(ADP No. 1233 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 500,000
- e) Amount of Bid Security (2%) (Paid in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 10,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 25,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor: PART-A= above/ below schedule items.
PART-B =..... above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

Schedule-B**INTEGRATED REHABILITATION AND PROVISION OF MISSING FACILITIES****TO EXISTING ELEMENTARY SCHOOLS TALUKA RATODERO DISTRICT**

Name of Work:-

LARKANO (79 UNITS) UNDER LARKANA EDUCATION PACKAGE (REVISED)**@GBPS MASOODERO (BOUNDARY WALL).**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	450	@ Rs: 3,176.25	% 0Cft	Rs: 1,429
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	150	@ Rs: 8,694.95	% Cft	Rs: 13,042
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	678.00	@ Rs: 11,948.36	% Cft	Rs: 81,010
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Supply and fixing sand under floor including plugging in to walls	2125	@ Rs: 1,141.25	% Cft	Rs: 24,252
	(Eleven hundred forty one rupees & twenty five paisa only)				
5	Providing and Laying 2" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	800.00	@ Rs: 4,411.82	% Sft	Rs: 35,295
	(Forry four hundred eleven rup: & eighty two paisa only)				
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	300.00	@ Rs. 12,346.65	% Cft	Rs. 37,040
	(Twelve thousand three hund: forty six rup: & sixty five paisa only)				
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	400	@ Rs. 2,206.60	% Cft	Rs. 8,826
	(Twenty tow hund: six rup: & sixty paisa only)				
8	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	400	@ Rs: 2,197.52	% Sft	Rs: 8,790
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	400.00	@ Rs: 1,287.44	% Sft	Rs: 5,150
	(Twelve hundred eighty seven rupees & forty for paisa only)				



S #	Description	Qty	Rate	Unit	Amount
10	White wash two coats. (S.I. No. 26 P No. 54)				
		168.00	@ Rs. 425.00 % Sft (Four hundred twenty five rup: & paisa only)		Rs. 3,598
11	Primary coat of chalk distemper(S.I No. 23 P/53)				
		627	@ Rs: 442.75 % Sft (Four hundred forty two rupees & seventy five paisa only)		Rs: 2,776
12	Distempering two coats.(S.I No. 24(b) P/54)				
		567	@ Rs: 1,043.90 % Sft (One thousand forty three rup: & ninty paisa only)		Rs: 5,919
13	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick				
		80	@ Rs. 27,678.86 % Cft (Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)		Rs. 22,143
14	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)				
		252	@ Rs. 28,253.61 % P.Cwt (Twenty seven thousand seven hund: forty seve rupp: & six paisa only)		Rs. 71,199
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)				
		203	@ Rs. 30,509.77 % Sft (Thirty thousand five hund: nine rupees & seventy seven paisa only)		Rs. 61,935
16	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)				
		23.00	@ Rs: 337.00 P.Cft (Thirec hundred Thirty seven rup: only)		Rs: 7,751
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I. No. 8 (b) P/16)				
		1.129	@ Rs: 5,001.70 P.Cwt (Five thousand one rup: & seventy paisa only)		Rs: 5,647
18	Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. ... P/92)				
		68.00	@ Rs. 180.50 P. Sft		Rs. 12,274

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(One hundred eighty Five rupees & fifty Paise only)

19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel
 44 @ Rs: 226.00 P. Sft Rs: 9,944
 (Two hundred twenty six rupees only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c
 20 Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6
 and repairing the jambs. The cost also i/c all carriage, tools and pla
 7 @ Rs: 228.90 P. Rft Rs: 1,602
 (Two hundred twenty eight rupees & ninty paisa only)

1st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts
 21 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25
 P/60)
 6.00 @ Rs: 902.93 P. Sft Rs: 5,418
 (Nine hund: two rup: & ninty three paisa only)

Total Rs: 421,893



BIDDING DOCUMENT**29**


Issued to

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Integrated rehabilitation and provision of missing facilities to existing Elementary Schools Taluka Ratodero District Larkano (79 Units) at GBPS. Wasayo Jeho (balance work)**
(ADP No. 1233 of 2015-16)
- c) Procuring Agency's address:- Near Hgih Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 500,000
- e) Amount of Bid Security (2%) (paid in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 10,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 25,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

S.No. 29

Schedule-B

**INTEGRATED REHABILITATION AND PROVISION OF MISSING FACILITIES
TO EXISTING ELEMENTARY SCHOOLS TALUKA RATODERO DISTRICT
LARKANO (79 UNITS) UNDER LARKANA EDUCATION PACKAGE (REVISED)
@GBPS WASSAYO JEHO (BOUNDARY WALL).**

Name of Work:-

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	450	@ Rs: 3,176.25	% OCft	Rs: 1,429
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	150	@ Rs: 8,694.95	% Cft	Rs: 13,042
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	678.00	@ Rs: 11,948.36	% Cft	Rs: 81,010
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Supply and fixing sand under floor including plugging in to walls	2125	@ Rs: 1,141.25	% Cft	Rs: 24,252
	(Eleven hundred forty one rupees & twenty five paisa only)				
5	Providing and Laying 2" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	800.00	@ Rs: 4,411.82	% Sft	Rs: 35,295
	(Forry four hundred eleven rup: & eighty two paisa only)				
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	300.00	@ Rs: 12,346.65	% Cft	Rs 37,040
	(Twelve thousand three hund: forty six rup: & sixty five paisa only)				
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	400	@ Rs: 2,206.60	% Cft	Rs. 8,826
	(Twenty tow hund: six rup: & sixty paisa only)				
8	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	400	@ Rs: 2,197.52	% Sft	Rs: 8,790
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	400.00	@ Rs: 1,287.44	% Sft	Rs: 5,150
	(Twelve hundred eighty seven rupees & forty for paisa only)				



S #	Description	Qty	Rate	Unit	Amount
10	White wash two coats. (S.I. No. 26 P No. 54)	168.00	@ Rs. 425.00	% Sft (Four hundred twenty five rup: & paisa only)	Rs. 3,598
11	Primary coat of chalk distemper(S.I No. 23 P/53)	627	@ Rs: 442.75	% Sft (Four hundred forty two rupces & seventy five paisa only)	Rs: 2,776
12	Distemping two coats.(S.I No. 24(b) P/54)	567	@ Rs: 1,043.90	% Sft (One thousand forty three rup: & ninty paisa only)	Rs: 5,919
13	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement	80	@ Rs. 27,678.86	% Cft (Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)	Rs. 22,143
14	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)	252	@ Rs. 28,253.61	% P.Cwt (Twenty seven thousand seven hund: forty seve rupp: & six paisa only)	Rs. 71,199
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)	203	@ Rs. 30,509.77	% Sft (Thirty thousand five hund: nine rupees & seventy seven paisa only)	Rs. 61,935
16	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	23.00	@ Rs: 337.00	P.Cft (Three hundred Thirty seven rup: only)	Rs: 7,751
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	1.129	@ Rs: 5,001.70	P.Cwt (Five thousand one rup: & seventy paisa only)	Rs: 5,647
18	Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. ... P/92)	68.00	@ Rs. 180.50	P. Sft	Rs. 12,274

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

(One hundred eighty Five rupees & fifty Paise only)

19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel
 44 @ Rs: 226.00 P. Sft Rs: 9,944
 (Two hundred twenty six rupees only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c
 20 Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6
 and repairing the jambs. The cost also i/c all carriage, tools and pla
 7 @ Rs: 228.90 P. Rft Rs: 1,602
 (Two hundred twenty eight rupees & ninty paisa only)

1st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts
 21 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25
 P/60)
 6.00 @ Rs: 902.93 P. Sft Rs: 5,418
 (Nine hund: two rup: & ninty three paisa only)

Total Rs: 421,893



BIDDING DOCUMENT**30**


Issued to

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Construction of 2-roomed building & additional class rooms to existing Primary Schools Taluka Ratodero District Larkano (16 Units) at GBPS. Gharibabad Naudero (balance work)**
(ADP No. 1223 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 300,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 6,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 15,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR


 EXECUTIVE ENGINEER
 EDUCATION WORKS DIVISION
 LARKANO

Schedule-B 30

Name of Work:- **CONSTRUCTION OF TWO ROOMED BUILDING AND ADDITIONAL CLASS ROOMS TO EXISTING PRIMARY SCHOOLS TALUKA RATODERO DISTRICT LARKANO (16 UNITS) @GBP5 GHARIBABAD NAUDERO (BOUNDARY WALL).**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	225.00	@ Rs: 3,176.25	% 0Cft	Rs: 715
	(Thirty two Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick on stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	75.00	@ Rs: 8,694.95	% Cft	Rs: 6,521
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	339.00	@ Rs: 11,948.36	% Cft	Rs: 40,505
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Supply and fixing sand under floor including plugging in to walls	2125.00	@ Rs: 1,141.25	% Cft	Rs: 24,252
	(Eleven hundred forty one rupees & twenty five paisa only)				
5	Providing and Laying 2" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/51)	400.00	@ Rs: 4,411.82	% Sft	Rs: 17,647
	(Forry four hundred eleven rup: & eighty two paisa only)				
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	150.00	@ Rs. 12,346.65	% Cft	Rs. 18,520
	(Twelve thousand three hund: forty six rup: & sixty five paisa only)				
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	200.00	@ Rs. 2,206.60	% Cft	Rs. 4,413
	(Twenty tow hund: six rup: & sixty paisa only)				
8	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	200.00	@ Rs: 2,197.52	% Sft	Rs: 4,395
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	200.00	@ Rs: 1,287.44	% Sft	Rs: 2,575
	(Twelve hundred eighty seven rupees & forty for paisa only)				

10	White wash two coats. (S.I. No. 26 P No. 54)	168.00	@ Rs. 425.00 % Sft (Four hundred twenty five rup: & paisa only)	Rs.	714
11	Primary coat of chalk distemper (S.I No. 23 P/53)	567.00	@ Rs: 442.75 % Sft (Four hundred forty two rupees & seventy five paisa only)	Rs:	2,510
12	Distemping two coats.(S.I No. 24(b) P/54)	567.00	@ Rs: 1,043.90 % Sft (One thousand forty three rup: & ninty paisa only)	Rs:	5,919
13	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar	80.00	@ Rs. 27,678.86 % Cft (Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)	Rs.	22,143
14	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)	252.00	@ Rs. 28,253.61 % P.Cwt (Twenty seven thousand seven hund: forty seve rupp: & six paisa only)	Rs.	71,199
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)	35.00	@ Rs. 30,509.77 % Sft (Thirty thousand five hund: nine rupees & seventy seven paisa only)	Rs.	10,678
16	RCC work in roof slab beam, columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	23.00	@ Rs: 337.00 P.Cft (Three hundred Thirty seven rup: only)	Rs:	7,751
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	1.129	@ Rs: 5,001.70 P.Cwt (Five thousand one rup: & seventy paisa only)	Rs:	5,649
18	Supply & Fixing in Position iron/steer grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. compree (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. ... P/92)	68.00	@ Rs. 180.50 P. Sft (One hundred eighty Five rupees & fifty Paisa only)	Rs.	12,274



Sr	Description	Qty	Rate	Unit	Amount
19	P/F ornamental Cement pl 2" thick (1:2:4) Without steel	44.00	@ Rs: 226.00	P. Sft	Rs: 9,944 (Two hundred twenty six rupees only)
20	Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.	26.88	@ Rs. 14,429.25	% Cft	Rs. 3,879 (Fourteen thousand four hund: twenty nine rup: & twenty paisa only)
21	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla	7.00	@ Rs: 228.90	P. Rft	Rs: 1,602 (Two hundred twenty eight rupees & ninty paisa only)
22	1 st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)	6.00	@ Rs: 902.93	P. Sft	Rs: 5,418 (Nine hund: two rup: & ninty three paisa only)

Total Rs: 279,224



BIDDING DOCUMENT**31**


Issued to _____

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Construction of 2-roomed building & additional class rooms to existing Primary Schools Taluka Ratodero District Larkano (16 Units) at GBPS. Sethar at Nadar Shar (balance work)**
(ADP No. 1223 of 2015-16)
- c) Procuring Agency's address:- Near Hgih Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 300,000
- e) Amount of Bid Security (2%) (Fill in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 6,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 15,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No.dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR



EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

Schedule-B

SNO 31

Name of Work:- **CONSTRUCTION OF TWO ROOMED BUILDING AND ADDITIONAL CLASS ROOMS TO EXISTING PRIMARY SCHOOLS TALUKA RATODERO DISTRICT LARKANO (16 UNITS) @GBPS SETHAR AT NADAR SHAR (BOUNDARY WALL).**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	225.00	@ Rs: 3,176.25	% 0Cft	Rs: 715
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	75.00	@ Rs: 8,694.95	% Cft	Rs: 6,521
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	339.00	@ Rs: 11,948.36	% Cft	Rs: 40,505
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Supply and fixing sand under floor including plugging in to walls	2125.00	@ Rs: 1,141.25	% Cft	Rs: 24,252
	(Eleven hundred forty one rupees & twenty five paisa only)				
5	Providing and Laying 2" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	400.00	@ Rs: 4,411.82	% Sft	Rs: 17,647
	(Forry four hundred eleven rup: & eighty two paisa only)				
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	150.00	@ Rs. 12,346.65	% Cft	Rs. 18,520
	(Twelve thousand three hund: forty six rup: & sixty five paisa only)				
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	200.00	@ Rs. 2,206.60	% Cft	Rs. 4,413
	(Twenty tow hund: six rup: & sixty paisa only)				
8	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	200.00	@ Rs: 2,197.52	% Sft	Rs: 4,395
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	200.00	@ Rs: 1,287.44	% Sft	Rs: 2,575
	(Twelve hundred eighty seven rupees & forty for paisa only)				



S #	Description	Qty	Rate	Unit	Amount
10	White wash two coats. (S.I. No. 26 P No. 54)	168.00	@ Rs. 425.00	% Sft (Four hundred twenty five rup: & paisa only)	Rs. 714
11	Primary coat of chalk distemper(S.I No. 23 P/53)	567.00	@ Rs: 442.75	% Sft (Four hundred forty two rupees & seventy five paisa only)	Rs: 2,510
12	Distemping two coats.(S.I No. 24(b) P/54)	567.00	@ Rs: 1,043.90	% Sft (One thousand forty three rup: & ninty paisa only)	Rs: 5,919
13	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar	80.00	@ Rs. 27,678.86	% Cft (Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)	Rs. 22,143
14	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)	252.00	@ Rs. 28,253.61	% P.Cwt (Twenty seven thousand seven hund: forty seve rupp: & six paisa only)	Rs. 71,199
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)	35.00	@ Rs. 30,509.77	% Sft (Thirty thousand five hund: nine rupees & seventy seven paisa only)	Rs. 10,678
16	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	23.00	@ Rs: 337.00	P.Cft (Three hundred Thirty seven rup: only)	Rs: 7,751
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	1.129	@ Rs: 5,001.70	P.Cwt (Five thousand one rup: & seventy paisa only)	Rs: 5,649
18	Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. ... P/92)	68.00	@ Rs. 180.50	P. Sft (One hundred eighty Five rupees & fifty Paisa only)	Rs. 12,274

S #	Description	Qty	Rate	Unit	Amount
-----	-------------	-----	------	------	--------

19 P/F ornamental Cement jali 2" thick (1:2:4) Without steel
44.00 @ Rs: 226.00 P. Sft Rs: 9,944
(Two hundred twenty six rupees only)

20 Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering. Ratio 1:2:4.
26.88 @ Rs. 14,429.25 % Cft Rs. 3,879
(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)

P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges
21 & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs.
The cost also i/c all carriage, tools and pla
7.00 @ Rs: 228.90 P. Rft Rs: 1,602
(Two hundred twenty eight rupees & ninty paisa only)

1st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts
22 & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25
P/60)
6.00 @ Rs: 902.93 P. Sft Rs: 5,418
(Nine hund: two rup: & ninty three paisa only)

Total Rs: 279,224



BIDDING DOCUMENT**32**


Issued to

And charged Rs. 750/- only as tender cost

Vide D.R. No. _____ dt: ____/____/2015

- a) Name of Procuring Agency:- Executive Engineer, Education Works Division, Larkano
- b) Brief Description of Work:- **Construction of 2-roomed building & additional class rooms to existing Primary Schools Taluka Ratodero District Larkano (16 Units) at GBPS. Gulab Labano at Cheezalabad (balance work)**
(ADP No. 1223 of 2015-16)
- c) Procuring Agency's address:- Near High Court Building, CMC Road, Larkano
- d) Estimated Cost:- Rs. 300,000
- e) Amount of Bid Security (2%) (shall in lump sum amount or in %age of bid amount / estimated cost, but not exceeding 5%) Rs. 6,000
- f) Period of Bid Validity (days):- 28 Days
- g) Security Deposit (5%) (including bid security) in %age of bid amount / estimated cost equal to 10% Rs. 15,000
- h) Percentage, if any, to be deducted from bills (Income Tax as standing orders) Rs.
- i) Deadline for Submission of Bids along- As per NIT with time:-
- j) Venue, Time and Date of Bid Opening:- Office of the XEN, Edu: Works Division Larkano near High Court Building, CMC Road Larkano.
As per NIT
- k) Time for Completion from written order of commence:- 10 Months
- l) Liquidity damages:-
(0.05 of Estimated Cost or Bid Cost per day of delay, but total not exceeding 10%)
- m) Deposit Receipt No. dt:
- n) Rate quoted by Contractor PART-A= above/ below schedule items.
PART-B = above/

CONTRACTOR



EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
LARKANO

Schedule-B

32


CONSTRUCTION OF TWO ROOMED BUILDING AND ADDITIONAL CLASS ROOMS TO EXISTING PRIMARY SCHOOLS TALUKA RATODERO DISTRICT

Name of Work:-

**LARKANO (16 UNITS) @GBPS GULAB LABANO AT (CHEEZALABAD)
(BOUNDARY WALL).**

S #	Description	Qty	Rate	Unit	Amount
1	Excavation in foundation of building bridges & other structure member with excavated lead upto one chain & lift upto 5" ft in ordinary soil.	225.00	@ Rs: 3,176.25	% 0Cft	Rs: 715
	(Thirty one Hundred seventy six rup: & twenty five paisa only)				
2	Cement concrete brick or stone ballast 1-1/2" to 2" gauge ratio 1:5:10.(S.I No. 3(d) P/14)	75.00	@ Rs: 8,694.95	% Cft	Rs: 6,521
	(Eighty six hund: ninty four rup: & ninty five paisa only)				
3	Pacca brick work in foundation and plinth in cement sand mortar ratio 1:6.	339.00	@ Rs: 11,948.36	% Cft	Rs: 40,505
	(Eleven thousand nine hund: forty eight rup: & thirty six paisa only)				
4	Supply and fixing sand under floor including plugging in to walls	2125.00	@ Rs: 1,141.25	% Cft	Rs: 24,252
	(Eleven hundred forty one rupees & twenty five paisa only)				
5	Providing and Laying 2" thick topping cement concete (1:2:4) including Surface finishing and dividing into panels: (S.I. No. 16 P/41)	400.00	@ Rs: 4,411.82	% Sft	Rs: 17,647
	(Forry four hundred eleven rup: & eighty two paisa only)				
6	Pacca brick work other than building i/c striking of joints in cement sand mortar ratio 1:6.	150.00	@ Rs. 12,346.65	% Cft	Rs. 18,520
	(Twelve thousand three hund: forty six rup: & sixty five paisa only)				
7	Cement Plaster 1:6 up to 12" height. 1/2" Thick (S.I. No. 13 (b) P/51)	200.00	@ Rs. 2,206.60	% Cft	Rs. 4,413
	(Twenty tow hund: six rup: & sixty paisa only)				
8	Cement plaster 1:4 upto 12" height 3/8" thick. (S.I No. 11(a) P/51)	200.00	@ Rs: 2,197.52	% Sft	Rs: 4,395
	(Twenty one hund: ninty seven rup: & fifty two paisa only)				
9	Cement pointing & strik joints on walls ratio 1:2.(S.I. No. 19(a) P/52)	200.00	@ Rs: 1,287.44	% Sft	Rs: 2,575
	(Twelve hundred eighty seven rupees & forty for paisa only)				

S #	Description	Qty	Rate	Unit	Amount
10	White wash two coats. (S.I. No. 26 P No. 54)	168.00	@ Rs. 425.00	% Sft (Four hundred twenty five rup: & paisa only)	Rs. 714
11	Primary coat of chalk distemper(S.I No. 23 P/53)	567.00	@ Rs: 442.75	% Sft (Four hundred forty two rupees & seventy five paisa only)	Rs: 2,510
12	Distemping two coats.(S.I No. 24(b) P/54)	567.00	@ Rs: 1,043.90	% Sft (One thousand forty three rup: & ninty paisa only)	Rs: 5,919
13	Lying floor of approved white glazed tile 1/4" thick in white cement 1:2 over 3/4" thick cement mortar	80.00	@ Rs. 27,678.86	% Cft (Twenty seven thousand six hund:seventy eighty rup: & eighty six paisa only)	Rs. 22,143
14	White glazed tiles 1/4" thick dodo jointed in white cement & laid over 1:2 cement sand mortar 3/4" thick i/c finishing.(S.I No.24 P/45)	252.00	@ Rs. 28,253.61	% P.Cwt (Twenty seven thousand seven hund: forty seve rupp: & six paisa only)	Rs. 71,199
15	P/L tile glazed 6"x6" 1/4 on floor on wall facing required floor and pattern and stile specification joint in white cement and pigment over a base of 1:2 grey (S.I. P/46)	35.00	@ Rs. 30,509.77	% Sft (Thirty thousand five hund: nine rupees & seventy seven paisa only)	Rs. 10,678
16	RCC work in roof slab beam columns rafts lintel & other structure member laid in situ or pre cast laid in position complete in all respect ratio 1:2:4. (S.I. No. 6(a) P/15)	23.00	@ Rs: 337.00	P.Cft (Three hundred Thirty seven rup: only)	Rs: 7,751
17	Fabrication of tor steel reinforcement for cement concrete i/c cutting, bending & laying in position i/c the cost of binding wire also removal of rust from bars. (S.I .No. 8 (b) P/16)	1.129	@ Rs: 5,001.70	P.Cwt (Five thousand one rup: & seventy paisa only)	Rs: 5,649
18	Supply & Fixing in Position iron/stee grill of 3/4" X 1/4" Size flat iron of approved design including painting 3 coats etc. complee (weight not to be less than 3.7 Lbs./Sq. Foot of finished grill).(S.I No. ... P/92)	68.00	@ Rs. 180.50	P. Sft (One hundred eighty Five rupees & fifty Paisa only)	Rs. 12,274



S #	Description	Qty	Rate	Unit	Amount
19	P/F ornamental Cement jali 2" thick (1:2:4) Without steel	44.00	@ Rs: 226.00	P. Sft	Rs: 9,944
	(Two hundred twenty six rupees only)				
20	Cement concrete plain i/c placing, compacting, finishing & curing complete i/c screening & washing of stone aggregate without shuttering, Ratio 1:2:4.	26.88	@ Rs. 14,429.25	% Cft	Rs. 3,879
	(Fourteen thousand four hund: twenty nine rup: & twenty paisa only)				
21	P/F G.I frame ChowKats of size 7"x2" or 4 1/2" x3" for doors using 20 gauge G.I sheet i/c Velded hinges & fixing at site necessary hold fasts filling with cement sand slury of ratio1:6 and repairing the jambs. The cost also i/c all carriage, tools and pla	7.00	@ Rs: 228.90	P. Rft	Rs: 1,602
	(Two hundred twenty eight rupees & ninty paisa only)				
22	1 st class deodar wood wrought joinery in doors & windows etc fixed i/c Chow Kats, hold rings, iron bolts & cleats with hooks etc deodar panels or paneled & glazed of fully glazed (a) 1-1/4" thick. (S.I No. 25 P/60)	6.00	@ Rs: 902.93	P. Sft	Rs: 5,418
	(Nine hund: two rup: & ninty three paisa only)				

Total Rs: 279,224

