

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). **Name of Procuring Agency:-** Executive Engineer (Education Works)
Division Shikarpur.

DISTRICT ADP SCHEMES (2013-2014)

(b). **Brief Description of Works:-** ADP NO:2326 REHABILITATION OF EXISTING BUILDING
BOYS / GIRLS SECONDARY/ HIGHER
SECONDARY SCHOOL IN TALUKA & DISTRICT
SHIKARPUR 04 UNIT (2013-14) PROGRAMME.

Office Executive Engineer Education Works
Division Shikarpur. (Ext: Dev:)

(c). **Procuring Agency's address:-** Executive Engineer (Education Works) Division Shikarpur
Near GBHS No.II Shikarpur.

(d). **Estimated Cost:-** 0.200 (Millions).

(e). **Amount of Bid Security:-** 2% (Fill in lump sum amount or in % age of bid amount /estimated cost, but not exceeding 5%)

(f). **Period of Bid Validity (days):-** 60 Days (Not more than sixty days).

(g). **Security Deposit:-(including bid security):-** 10%
(in % age of bid amount /estimated cost equal to 10%)

(h). **Percentage, if any, to be deducted from bills:-** 7.50% Income tax

(i). **Deadline for Submission of Bids along with time :-** As Per NIT

(j). **Venue, Time, and Date of Bid Opening:-** Near GBHS II (Shikarpur As Per NIT).


(k). **Time for Completion from written order of commence: -** 03 Months

(L). **Liquidity damages:-** -NIL- (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).

(m). **Deposit Receipt No:** _____ **Date:** _____ **Amount:Rs:** _____
Bank _____

(n) **D.R.NO:** _____ **DATED:-** _____ **Amount 500/-**-(Rupees: Five Hundred only).

(o). **Tender issued to Mr. / M/s** _____ **Govt Contractor.**


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR

SCHEDULE "B".

NAME OF WORK: = REHABILITATION OF EXISTING BUILDING FOR BOYS/GIRLS
SECONDARY/HIGHER SECONDARY SCHOOL IN DISTRICT
SHIKARPUR(2015-2014 PROG: AT: OFFICE OF THE EXECUTIVE
ENGINEER, EDUCATION WORKS DIVISION SHIKARPUR:
(EXT: DEVELOPMENT):

SR: NO:	ITEM OF WORK:	QTY:	RATE:	UNIT:	AMOUNT:
1/.	Removing cement or lime plaster;	348.0	@RS: 121/-	%sft;	Rs: 421/-
2/.	Dismantling brick in cement sand moter;	12.0	@RS: 1285/63	%sft;	Rs: 154/00.
3/.	Removing windows and sky light with chowkats.	2.0 P;Nos;	@RS: =142/18	P;No;	Rs: 284/00.
4/.	Pacca brick work in foundation of building and plinth ratio 1:6; in cement sand moter;	12.0	@RS: =11948/36	%cft;	Rs: 1434/00.
5/.	Pacca brick work in G/Floor in cement sand moter ratio (1:6);	21.0	@RS: =12674/36	%sft;	Rs: 2662/00.
6/.	R.c.c. work in roof slab and columns rafts, lintels and other structural members laid in situ or precast laid in position etc completer in all respects ratio 1:2:4;	9.0	@RS: =337/00	P; cft;	Rs: 3033/00.
7/.	Reinforcement of mild steel reinforcement for cement concrete including cutting bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of rust from bars.	0.482.0	@RS: =5001/70	P; cwt;	Rs: 2411/00
8/.	Providing and fixing door Aldran 9"-12" depth including boxing with back shelves matters brass fitting etc completer;	63.0	@RS: =1748/-	P; sft;	Rs: 110124/00
9/.	Applying floating coat of cement 1/32" thick;	348.0	@RS: =660/00	%sft;	Rs: 2297/00.
10/.	cement plaster (1:6;) upto 20' height 1/2" thick;	432.0	@RS: =2206/60	%sft;	Rs: 9533/00.
11/.	cement plaster (1:4;) upto 20' height 3/8" thick;	432.0	@RS: =2197/52	%sft;	Rs: 9493/00.
12/.	First class deodar wood wrought joinery in doors and windows etc fixed in position chowkats hand posts hinges rion towers bolts nuts and cleats with hocks etc deodar wood 1-3/4" thick;	28.0	@RS: =1273/76	P; sft;	Rs: 35665/-
13/.	white wash Three coats.	420.0	@RS: =829/95	%sft;	Rs: 3486/00.

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency:- Executive Engineer (Education Works)
Division Shikarpur.

DISTRICT ADP SCHEMES (2013-2014)

(b). Brief Description of Works:- ADP NO: 2327 REHABILITATION OF EXISTING BUILDING
BOYS / GIRLS SECONDARY/ HIGHER SECONDARY
SCHOOL IN TALUKA & DISTRICT SHIKARPUR
(2013-14) PROGRAMME.

GBHS Jagon (Ext: Dev:)

(c). Procuring Agency's address:- Executive Engineer (Education Works) Division Shikarpur
Near GBHS No.II Shikarpur.

(d). Estimated Cost:- 0.400 (Millions).

(e). Amount of Bid Security:- 2% (Fill in lump sum amount or in % age of bid amount /estimated cost, but not exceeding 5%)

(f). Period of Bid Validity (days):- 60 Days (Not more than sixty days).

(g). Security Deposit:- (including bid security):- 10%
(in % age of bid amount /estimated cost equal to 10%)

(h). Percentage, if any, to be deducted from bills:- 7.50% Income tax

(i). Deadline for Submission of Bids along with time :- As Per NIT

(j). Venue, Time, and Date of Bid Opening:- Near GBHS II (Shikarpur As Per NIT).

(k). Time for Completion from written order of commence: - 03 Months

(L). Liquidity damages:- -NIL- (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).

(m). Deposit Receipt No: _____ Date: _____ Amount: Rs: _____

Bank _____

(n) D.R.NO: _____ DATED:- _____ Amount 1000/- (Rupees: One Thousand only).

(o). Tender issued to Mr. / M/s _____ Govt. Contractor.


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR

SCHEDULE "B".

NAME OF WORK: REHABILITATION OF EXISTING BUILDING FOR BOYS/GIRLS
SECONDARY/HIGHER SECONDARY SCHOOL IN TALUKA AND DISTT;
SHIKARPUR; UNDER (2013-2014 PROG: AT: G:B:H:S: "JAGON"
TALUKA AND DISTRICT SHIKARPUR; (EXT. DEVELOPMENT.).

SR: NO:	ITEM OF WORK:	QTY:	RATE:	UNIT:	AMOUNT:
1/.	Excavation in foundation of building bridges and other str; structure i/c degbelling dressing refilling around the surface with excavated earth watering and ramming lead upto 5'feet;	=120.0 %cft;	RS: 3176/25 %cft;		Rs: 381/-
2/.	Cement concrete brick or stone ballast 1-1/2" to 2" guage ratio 1;5;10	=60.0 %cft;	RS: 8694/95 %cft;		Rs: 5217/-
3/.	Pacca brick work in foundation and plinth in cement sand moter ratio 1;6;	=90.0 %cft;	RS: 11948/36 %cft;		Rs: 10754/=
4/.	Fabrication of mild steel reinforcement for cement concrete i/s cutting banding and laying in position i/c the cot of steel binding wire also i/c removal of rust from bars.	=0.446.0	RS: =5001/70 P; cwt;		Rs: 2231/-
5/.	R;C;C; work in roof slab beams columns rafts linele and other str; structural members laid in situ or precast laida in position etc compiter respect in c.c. (1;2;4); etc compiter;	10.0	RS: =337/- P; cft;		Rs: 3370/-
6/.	Cement plster (1;6;) upto 20'high 1/2" thick;	=122.0 %cft;	RS: =2206/60 %cft;		Rs: 2692/-
7/.	Cement plster (1;4;) upto 20'high 3/8" thick;	=7092.0 %cft;	RS: =2197/52 %cft;		Rs: 155848/=
8/.	White wash Three coats.	=3409.0 %cft;	RS: 829/95 %cft;		Rs: 28293/=
9/.	White wash Two coats.	=1676.0 %cft;	RS: 425/84 %cft;		Rs: 7137/=
10/.	Distemporing Two coats.	=8702.0 %cft;	RS: 1043/90 %cft;		Rs: 90840/=
11/.	Painting doors and windows any type old surface two coats.				
(a).	old surface Two coats.	= 705.0 %cft;	RS: =1160/06 %cft;		Rs: 8178/=
(b).	New Surface Three coats.	= 105.0 %cft;	RS: =2116/41 %cft;		Rs: 2222/-
12/.	Colour wash three coats.	= 7092.0 %cft;	RS: =859/90 %cft;		Rs: 60984/.
Total Rs: =					378,150/=


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR.

SCHEDULE OF (WATER SUPPLY & SANITARY)

Presented.

S.NO	DESCRIPTION	RATE	UNIT	AMOUNT
1/-	Providing & fixing squatting type white glazed of flushing cistern fitting & flush pipe with bond and making requisite numbers of holes in wall plinth & floor for pipe connections & cement concrete 1:2:4 (S.I.NO.1 P.NO.1). R.(i) W.C of not less than 10" clear opening between flushing riser and 3 gallons flushing tank with 4" C.I trap & C.I Thimble.	1.0	Rs:4802/60 Each	RS: 4802/-
2/-	Providing and fixing 4" dia C.I soil & vent pipes including Cutting and fitting and extra painting to match the colour of building.(S.I.NO.1 ,P.NO.8)	1.0	Rs:333/29 Each	RS: 333/-
3/-	Providing & fixing 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/8" thick and bolts & nuts and extra painting to match the colour of the building.(S.I.NO.5.P.NO.8)	1.0	Rs:270/60 Each	RS: 271/-
4/-	Providing G.I Pipes specials & clamps etc including fixing cutting and fitting complete with and l/c the cost of breaking through walls and roof .making good etc . Painting two coats after cleaning the pipe etc. with white zinc paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (S.I.NO.1 P.NO.11)			
	(iii) 1" dia G.I Pipe	10.0	Rs:120/55 Rft:	RS: 1286/-
	(i) 1/2" dia G.I Pipe	18.0	Rs: 73/21 Rft:	RS: 1087/-
	(ii) 3/4" dia G.I Pipe	15.0	Rs: 95/79 Rft:	RS: 1437/-
5/-	Supplying and fixing in position brass bib cock 3/4" dia (S.I.NO.15 P.NO.15)	2.0	Rs: 348/92 Each	RS: 698/-
6/-	Providing & fixing bal valve (with unsoldered copper ball) made to B.S. 1212 (S.I.NO.8 P.NO. 14)			
	(ii) 3/4" dia	1.0	Rs:290/84 Each	RS: 291/-
7/-	Providing R.C.C.pipe with collars class "B" and digging the trenches to required depth and fixing in position including cutting fitting and joining with maxphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe & refilling with excavated stuff. (S.I.NO .2 P.NO.21)			
	(c) 6" dia R.C.C pipe class "B"	10.0	Rs: 199/25 Rft:	RS: 1999/-
8/-	Supplying & Fixing Fiber Glass Tank of approved quality and design and wall thickness as specified l/c cost of nuts bolts and fixing in plate form of cement concrete 1:3:6 and making connections for inlet out & over flow inlet outlet flow pipes etc complete.(S.I.NO .3. P.NO.18) (250 GLB)	200.0	Rs:21989/61 P.Gallon	RS: 17592/-
9/-	Supplying & Fixing approved quality Electric motor pumping set (Javed Engineering made)1-1/4"x1" section and delivery with base plate and compiling one horsepower single phase motor (siemens make) 60 feet head pf 2800 RPM including the cost of nuts and bolts c.c (1:2:4)	1.0	Rs:12500/00 Each	RS: 12507/-
10/-	Providing and Installation of Hand pump 1-1/4" G.I pipe and colr syainer with wooden shap including cost of 4" feet above ground level embedd in C.C (1:2:4) with iron handle and required same shape with acc and fixing etc complete.			
	(a) Filter pipe	10.0	Rs:120/00 Rft:	RS: 1280/-
	(b) G.I pipe	30.0	Rs:110/00 Rft:	RS: 3368/-
	(c) H.P Machine	1.0	Rs:2500/00 P.NO	RS: 2508/-

	DESCRIPTION	RATE	UNIT	AMOUNT
	Providing and fixing 22"x16" lavatory basin in white glazed earthen ware complete with & 1/2 the cost of W.I or C.I cantilever brackets 6 inch built into wall. Painted white in two coat after a primary coat of red lead paint a pair of 1/2" dia chrome plated pillar traps 1-1/2" dia rubber plug chrome brass waste of approved pattern. 1-1/4" dia malleable iron cp union making and traps, malleable iron or brass requisite number of holes in wall plinth & floor for pipe connection and making good in cement concrete 1:2:4 (standard pattern) (S.I.NO.13.P.NO.3)	1.0 Rs: 4694/80	Each	RS: 4694/80
12/-	Add extra for labour for providing & fixing of earthen ware pedestal white or coloured glazed (standard pattern) (S.I.NO.9.P.NO.3)	1.0 Rs: 938/47	Each	RS: 938/47
13/-	(a) Supplying & Fixing swan type pillar cock of Superior quality single c.p head 1/2" dia (S.I.NO.18.P.NO.16)	1.0 Rs: 795/30	Each	RS: 795/30
14/-	Supplying & Fixing Bath room accessories (7 pieces) i/c towel rod, brush, holder, soap tray, Shelf of approved quality and design etc complete (S.I.NO.24.P.NO.16)	1.0 Rs: 8122/40	Each	RS: 8122/40
15/-	Construction manhole or inspection chamber for the required dia of circular sewer and 3"x6" (1067mm) dept with walls of D.B in cement mortar 1:3 cement plastered 1:3, 1/2" thick inside of walls and 1" (25mm) thick over benching and channel i/c fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457mm) of 1.75Cwt. (80.9 kg.) embedded in plain C.C 1:2:4 and fixing 1" (25mm) dia M.B steps 6" (150mm) wide projecting 4" (102mm) from the face of wall at 12" (305mm) C/C duly painted etc complete as per specifications and drawing No. D.P/I of Public Health Circle Southern Zone. (S.I.NO.1 P. NO.30)	— Rs: 14748/-	Each	RS: 14748/-
16/-	Providing & fixing 4" dia C.I Terminal guard including extra painting to match the colour of the building (S.I.NO.10.P.NO.9)	1.0 Rs: 389/70	Each	RS: 389/70
17/-	Providing and fixing in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection. (S.I.NO.23.P.NO.6)	1.0 Rs: 447/15	Each	RS: 447/15
18/-	Providing asbestos pipe with collar (Dadex or equivalent) i/c digging the trench to required depth and fixing to position and joining with rubber rings including testing to water pressure head of 200 feet. (S.I.NO.3.P.NO.21)	1.0 Rs: 188/44	Each	RS: 188/44
19/-	Providing & fixing 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden plate. (S.I.NO 3.P.NO.7)	— Rs: 1161/60	Each	RS: 1161/60
	a) Standard pattern			RS: 67510/60808

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR.

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). **Name of Procuring Agency:-** Executive Engineer (Education Works)
Division Shikarpur.

DISTRICT ADP SCHEMES (Electrical Works)

(b). **Brief Description of Works:-** ADP 2333 REHABILITATION OF EXISTING BUILDING FOR BOYS / GIRLS SECONDARY/HIGHER SECONDARY SCHOOLS OF DISTRICT SHIKARPUR TALUKA G.YASIN (2013-14) PROGRAMME.

GBHS Panhwar Bhutta (Ext: Dev:)

(c). **Procuring Agency's address:-** Executive Engineer (Education Works) Division Shikarpur
Near GBHS No.II Shikarpur.

(d). **Estimated Cost:-** 0.200 (Millions).

(e). **Amount of Bid Security:-** 2% (Fill in lump sum amount or in % age of bid amount /estimated cost, but not exceeding 5%)

(f). **Period of Bid Validity (days):-** 60 Days (Not more than sixty days).

(g). **Security Deposit:-(including bid security):-** 10%
(in % age of bid amount /estimated cost equal to 10%)

(h). **Percentage, if any, to be deducted from bills:-** 7.50% Income tax

(i). **Deadline for Submission of Bids along with time :-** As Per NIT

(j). **Venue, Time, and Date of Bid Opening:-** Near GBHS II (Shikarpur As Per NIT).

(k). **Time for Completion from written order of commence: -** 06 Months

(L). **Liquidity damages:-** -NIL- (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).

(m). **Deposit Receipt No:** _____ **Date:** _____ **Amount:Rs:** _____
Bank _____

(n) **D.R.NO:** _____ **DATED:** _____ **Amount 500/- (Rupees: Five Hundred only).**

(o). **Tender issued to Mr. / M/s** _____ **Govt: Contractor.**

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR

SCHEDULE "B".

NAME OF WORK: =

REHABILITATION OF EXISTING BUILDING FOR BOYS/GIRLS
SECONDARY/HIGHER SECONDARY SCHOOL IN TALUKA G:YASIN
DISTRICT SHIKARPUR; (2013-2014 PROG: AT: G:B:H:S:
PANWAR BHUTTA TALUKA G:YASIN:(EXT:DEVELOPMENT):)

SR:NO:	ITEM OF WORK:	QTY:	RATE:	UNIT:	AMOUNT:
1/	Excavation in foundation of building ridges and other str; i/c disgebellling dressing arround the lead upto 5'feet;	38.0	3176/15	%cft;	Rs:121/-
2/	Cement concrete brick or stone ballest 1 1/2" to 2" guege ratio 1;5;10	532.0	8694/95	%cft;	Rs: 46257/-
3/	Pacce brick work in foundation and plinth with ratio (1;6;);	45.0	11948/36	%cft;	Rs:5377/-
4/	Pacce brick work in G/Floor in cement sand moter ratio (1;6;);	56.0	12674/36	%cft;	Rs:7098/-
5/	R.c.c. work in roof slab beams columns rafts linele and other structural members laid in sattu or preet laid in position etc ratio 1;2;4;	6.0	337/-	P;cft;	Rs:2022/00
6/	Fabrication of mild steel reinfor cement for R.c.c. work i/c cutting bending and binding ere laying in position etc compiter;	0.267.0	5001/70	P:cwt;	Rs:1335/-
7/	Cement plster (1;6;) upto 20'high 1/2"thick;	68.0	2206/60	%cft;	Rs:1500/00.
8/	Cement plster (1;4;) upto 20'high 3/8"thick;	2996 sq	2197/52	%cft;	Rs:65838/=
9/	P/Lc.c.topping (1;2;4;) 3"thick dividing into pannels 3"thick;	1296.0	4411/82	%cft;	Rs:57177/=
10/	Making notice board with cement ratio (1;2;);	96.0	58/11	P; cft;	Rs:5579/-

Total Rs: 1,92304/00.


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR.

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency:- Executive Engineer (Education Works)
Division Shikarpur.

DISTRICT ADP SCHEMES

(b). Brief Description of Works:- ADP 2336 REHABILITATION OF EXISTING BUILDING
FOR BOYS / GIRLS PRIMARY / ELEMENTARY SCHOOLS
IN TALUKA GARHI YASIN & DISTRICT SHIKARPUR
(2013-14) PROGRAMME.
GBPS Bakar Shah (Ext: Dev.)

(c). Procuring Agency's address:- Executive Engineer (Education Works) Division Shikarpur
Near GBHS No.II Shikarpur.

(d). Estimated Cost:- 0.500 (Millions).

(e). Amount of Bid Security:- 2% (Fill in lump sum amount or in % age of bid amount /estimated cost, but not exceeding 5%)

(f). Period of Bid Validity (days):- 60 Days (Not more than sixty days).

(g). Security Deposit:-(including bid security):- 10%
(in % age of bid amount /estimated cost equal to 10%)

(h). Percentage, if any, to be deducted from bills:- 7.50% Income tax

(i). Deadline for Submission of Bids along with time :- As Per NIT

(j). Venue, Time, and Date of Bid Opening:- Near GBHS II (Shikarpur As Per NIT).

(k). Time for Completion from written order of commence: - 12 Months


(L). Liquidity damages:- -NIL- (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).

(m). Deposit Receipt No: _____ Date: _____ Amount:Rs: _____

Bank _____

(n). D.R.NO: _____ DATED: _____ Amount 1500/- (Rupees: One Thousand Five Hundred only).

(o). Tender issued to Mr. / M/s _____ Govt. Contractor.


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR

(SCHEDULE "B")

NAME OF WORK :- REHABILITATION OF EXISTING BUILDING FOR BOYS/GIRLS
PRIMARY/ELEMENTARY SCHOOLS IN TALUKA GARHI YASIN
DISTRICT SHIKARPUR (2013-14) PROG: (Distt:ADP:336/2336)
AT G.B.P.S. BAKAR SHAM

(E X T E R N A L D E V E L O P M E N T)

S.NO:	ITEM OF WORK.	QTY:	RATE.	UNIT.	AMOUNT.
1.	Excavation in foundation of building bridges and other structure i/c diabbelling dressing around the lead upto 5 ft:	27	3176/25	% Cft	86/-
2.	Cement Concrete brick or stone ballast 1 1/2" to 2" guage 1.5.10.ratio.	147	8694/95	% Cft	12782/-
3.	Pacca brick work in foundation and plinth with 1.6. ratio.	100	11948/36	% Cft	11948/-
4.	Filling watering ramming earth under floor with excavated from foundation of new earth out side lead upto 5 ft:	942	8655/20	% Cft	8153/-
5.	supplying and filling sand under floor plugging into walls.	324	1643/77	% Cft	5326/-
6.	P/L c.c. topping 1.2.4. ratio 3" thick dividing into pannals.	605	4411/82	% Sft	26692/-
7.	Laying floor of approved with glazed tiles 1/4" thick in white cement mortor 1.2. over 3/4" thick cement completed etc.	936	27678/86	% Sft	259074/-
8.	White glazed tiles 1/4" thick (dado) laid in pigment over 1.2. cement mortor 3/4" thick including finishing etc.	222	28299/30	% Sft	62824/-
9.	Cement plaster 1.6. ratio 1/2" thick upto 20 height.	107	2206/80	% Sft	2361/-
10.	Cement plaster 1.4. ratio 3/8" thick upto 20 height.	107	2197/20	% Sft	2351/-
11.	Supplying and fixing steel iron grill 3/8" sqt bars Diagonally fixied both way at 3" C.C. on 3/4" x3/4" 1/8" vangle iron frame i/c welding etc completed as per instructions given by the Executive Engineer (R..... A)	200 Rft	329/64	P:Sft	65928/-

Total Rs:4,57525/00

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR,

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). Name of Procuring Agency:- Executive Engineer (Education Works)
Division Shikarpur.

DISTRICT ADP SCHEMES (2013-2014)

(b). Brief Description of Works:- ADP NO: 2337 REHABILITATION OF EXISTING BUILDING FOR BOYS / GIRLS PRIMARY / ELEMENTARY SCHOOLS SCHOOLS IN TALUKA GARHI YASIN & DISTRICT SHIKARPUR 05 UNITS (2013-14) PROGRAMME.

GBPS Jawabpur

(c). Procuring Agency's address:- Executive Engineer (Education Works) Division Shikarpur
Near GBHS No.II Shikarpur.

(d). Estimated Cost:- 0.900 (Millions).

(e). Amount of Bid Security:- 2% (Fill in lump sum amount or in % age of bid amount /estimated cost, but not exceeding 5%)

(f). Period of Bid Validity (days):- 60 Days (Not more than sixty days).

(g). Security Deposit:- (including bid security):- 10%
(in % age of bid amount /estimated cost equal to 10%)

(h). Percentage, if any, to be deducted from bills:- 7.50% Income tax

(i). Deadline for Submission of Bids along with time :- As Per NIT

(j). Venue, Time, and Date of Bid Opening:- Near GBHS II (Shikarpur As Per NIT).

(k). Time for Completion from written order of commence: - 12 Months


(L). Liquidity damages:- -NIL- (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).

(m). Deposit Receipt No: _____ Date: _____ Amount:Rs: _____

Bank _____

(n). D.R.NO: _____ DATED: _____ Amount 2000/- (Rupees: Two Thousand only).

(o). Tender issued to Mr. / M/s _____ Govt. Contractor.


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR

SCHEDULE - B

NAME OF WORK:- REHABILITATION OF EXISTING BUILDING FOR BOYS/ GIRLS PRIMARY/ SECONDARY/ HIGHER SECONDARY SCHOOL IN TALUKA **GARKI YASIN** DISTRICT SHIKARPUR (2013-14) PROGRAM AT **G.B.P.S. JAWAB PUR** .

(A.D. NO:2337)

Sr.No:	DESCRIPTION	QNTY:	RATE	UNIT	AMOUNT IN Rs:
1.	Dismantling brick work in lime or cement mortar	625	@ Rs:1285.63	% Cft	8035/-
2.	Dismantling brick or flagged flooring without concrete foundation. S.I No.30 P.No.12	-	@ Rs:257.13	% Sft	-
3.	Dismantling cement concrete Plain (1:2:4)	10	@ Rs:3327.50	% Cft	333/-
4.	Dismantling Cement concrete Reinforced separating reinforcement from concrete cleaning & straightening The same	42	@ Rs:5445.0	% Cft	2287/-
5.	Dismantling second class tiles roofing	1025	@ Rs:378.13	% Sft	3876/-
6.	Removing doors with chowkats	02	@ Rs:142.18	P.No:	284/-
7.	Removing windows and sky light with chowkats	06	@ Rs:102.85	P.No:	617/-
8.	Removing ventilators and wooden sun shade etc.	-	@ Rs:51.43	P.No.	-
9.	Dismantling rolled steel beams, Iron Rails etc.	30.572	@ Rs:126.04	P.Cwt	3853/-
10.	Removing cement or lime plaster	995	@ Rs:121.00	%Sft	1204/-
11.	Dismantling cement concrete plain 1:3:6	-	@ Rs:1306.80	% Cft	-
12.	Excavation in foundation of building bridges and other structure I/C degbelling dressing refilling around the structure with excavated earth watering and ramming lead upto 5 ft. in ordinary soil.	-	@ Rs:3176.25	%0 Cft	-
13.	Cement concrete brick or stone ballast 1- 1/2 " to 2" guage i. Cement concrete (ratio 1: 5: 10:) ii. Cement concrete 1: 4: 8:	308	@ Rs:8694.95 @ Rs:9416.28	% Cft % Cft	26780/-
14.	Dry rammed brick or stone ballast 1/2 " thick to 2" guage	-	@ Rs:3327.50	% Cft	-
15.	Pacca brick work in foundation and plinth (cement sand mortar 1:6)	60	@ Rs:11948.36	% Cft	7169/-
16.	Fabrication of miled steel reim force ment for cement concrit I/C cutting, banding and lying in position I/c cost of steel binding wire also I/c removal of rust from bars (a) Tor Steel (b) Miled Steel	5.223	@ Rs:5001.70 @ Rs:4820.20	P: Cwt P: Cwt	26124/-
17.	R:C:C: work in roof slab beams columns rafts lintels and other structural members laid in situ, or precast laid in position complete in all respects C:C ratio (1: 2: 4:) S.I No.6A P.No.16	117	@ Rs:337.00	P: Cft.	39429/-
18.	Filling watering ramming earth in floor with surplus earth excavated from foundation lead upto one chain and lift upto 5ft.	-	@ Rs:1512.50	%0 Cft.	-
19.	Filling watering ramming earth under floor with new earth (excavated from outside) lead upto one chain and lift upto five ft.	-	@ Rs:8655.20	%0 C.ft	-
20.	Supplying and filling sand under floor and plugging in wells.	1920	@ Rs:1643.77	% C.ft	31560/-

Contd.....P/2

21.	Errection and removal of centering for R.C.C or plain cement concrete work of deodar wood (2nd: class)	-	@ Rs:7000.0	% S.ft	-	
22.	Pacca brick work on ground floor with (1:6 ratio)	G/F F/F	1073	@ Rs:12674.36 @ Rs:13112	% Cft % Cft	135996/- -
23.	Pacca brick work on other than building with 1:6 (ratio)	-	-	@ Rs:12346.65	% Cft	-
24.	S/fixing iron girder at site of work	5.017	@ Rs:3850.0	P.Cwt	19315/-	
25.	S/Fixing iron l-iron at site of work	26.924	@ Rs:3575.0	P.Cwt	26253/-	
26.	Errection of rolled steel beams or iron rails etc.	49.386	@ Rs:186.34	P.Cwt	9188/-	
27.	Second class tiles roofing consisting of 4" earth 1" mud plaster with gobri leeping over 1/2" thick cement plaster (1:6 cement mortar including 1:2 cement pointing under neath of tiles complete including curing etc. complete	1025	@ Rs:7607.25	% S.ft	77974/-	
28.	Providing and laying single por layer of polythin sheet 0.13 mm thick for Water proofing as per specification and instruction of Engineer Incharge	1025	@ Rs:10.70	P.Sft	10968/-	
29.	Providing and laying 1" thick topping cement concrete (1:2:4) i/c surface finishing and dlvding into panels (A) 3" thick (B) 2" thick	985 -	@ Rs:4411.82 @ Rs:3275.50	% S.ft % S.ft	39040/- -	
30.	Mud plaster on floor or roof 1" thick	-	@ Rs:555.0	% S.ft	-	
31.	Applying floating coat of cement 1/32" Thick	995	@ Rs: 660.0	% S.ft	6567/-	
32.	Cement plaster (1:6) upto 20' ft: height G/F 1/2" thick	3739	@ Rs: 2206.60 @ Rs: 2308.84	% S.ft % S.ft	82505/- -	
33.	Cement plaster 1:4 upto 20' ft; height G/F 3/8" thick.	3675	@ Rs: 2197.52 @ Rs: 2299.77	% S.ft % S.ft	80759/- -	
34.	Cement plaster 1:4 upto 20' ft; height. 1/2" thick	-	@ Rs: 3015.76	% S.ft	-	
35.	Cement pointing and stricking of joints on Walls ratio. 1: 2	980	@ Rs:1287.44	% S.ft	12617/-	
36.	Line Neru Plaster (1:2) Lime and Surkhi 1/2" thick.	-	@ Rs:1036.75	% S.ft	-	
37.	First Class deodar wood wrought jolnery in doors and windows etc: fixed in position i/c deodar panelled and glazed 1-3/4 thicks. (b) only shutters	12 16.75	@ Rs: 1273.76 @ Rs: 902.93	P.Sft P.Sft	15285/- 15124/-	
38.	Providing and fixing deodar wood Almirah 9-12" depth i/c boxing with back shalves shutter brass fitting etc complete (without box)	-	@ Rs: 1748.0	P.Sft	-	
39.	Fixing doors Including chowkats	02	@ Rs: 279.51	Each	559/-	
40.	Fixing windows Including chowkats	06	@ Rs: 139.76	Each	839/-	
41.	P/F G:I frames / chowkats of size 7" x 2" or 4-1/2"x3" for doors and window using 20 guage G.I sheet i/c welded hinges and fixing at site with necessary hold fasts, filling with cement sand slurry of ratio 1:6 and repairing the jambs. The cost also i/c all carriage , tools and plants used in making and fixing (a) for doors (b) for windows	-	@ Rs: 228.90 @ Rs: 240.50	P.Rft P.Rft	-	

Contd.....P/3

04. Providing and installation of Mand pump 1½ G.I. pipe and colors with wooden shoe 4" feet above ground level embended cement concrete 1.2.4. ratio.

(A) Filter pipe	10 Rft	120/-	P:Rft	1200/-
(B) Boring pipe	50 Rft	110/-	P:Rft	5500/-
(C) Machine	01 No	2500/-	P:NO:	2500/-
(D) Motor	01 No	12500/-	P:NO:	12500/-

Total Rs: 37,630/00


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR.

TOTAL (CSR:)

Part "A" %Above / Below _____ Total Amount _____

Part "B" %Above / Below _____ Total Amount _____

Part "C" %Above / Below _____ Total Amount _____

Total "A+B+C" _____

CONTRACTOR

EXECUTIVE ENGINEER
EDUCATION WORK DIVISION,
SHIKARPUR

BIDDING DATA

(This section should be filled in by the Engineer/Procuring Agency before issuance of the Bidding Documents).

(a). **Name of Procuring Agency:-** Executive Engineer (Education Works)
Division Shikarpur.

PROVINCIAL ADP SCHEMES

(b). **Brief Description of Works:-** ADP NO: 162 UP-GRADATION OF MIDDLE SCHOOLS & HIGH SCHOOLS TO HIGHER SECONDARY SCHOOLS IN SINDH (2007-08 PROGRAMME)

GGMS Sultankot (Remaining Work)

(c). **Procuring Agency's address:-** Executive Engineer (Education Works) Division Shikarpur
Near GBHS No.II Shikarpur.

(d). **Estimated Cost:-** 0.400 (Millions).

(e). **Amount of Bid Security:-** 2% (Fill in lump sum amount or in % age of bid amount /estimated cost, but not exceeding 5%)

(f). **Period of Bid Validity (days):-** 60 Days (Not more than sixty days).

(g). **Security Deposit:-(including bid security):-** 10%
(in % age of bid amount /estimated cost equal to 10%)

(h). **Percentage, if any, to be deducted from bills:-** 7.50% Income tax

(i). **Deadline for Submission of Bids along with time :-** As Per NIT

(j). **Venue, Time, and Date of Bid Opening:-** Near GBHS II (Shikarpur As Per NIT).

(k). **Time for Completion from written order of commence: -** 06 Months


(L). **Liquidity damages:-** -NIL- (0.05 of Estimated Cost or Bid cost per day of delay, but total not exceeding 10%).

(m). **Deposit Receipt No:** _____ **Date:** _____ **Amount:Rs:** _____

Bank _____

(n) **D.R.NO:** _____ **DATED:-** _____ . **Amount 750/-**(Rupees: Seven Hundred Fifty only).

(o). **Tender issued to Mr. / M/s** _____ **Govt: Contractor.**


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR

SCHEDULE "B".

NAME OF WORK: =

UP-GRADATION OF MIDDLE SCHOOL TO HIGH SCHOOL IN
SINDH AT G:G:M:S: SULTAN KOT TALUKA AND DISTRICT
SHIKARPUR: R/Work.

SR: NO:	ITEM OF WORK:	QTY:	RATE	UNIT:	AMOUNT:
	1/. Excavation in foundation of building bridges and other str; including degbelling dressing refilling around structure with excavte earth watering and ramming lead upto 5'feet;	400.0	3176/25	%cft;	Rs:1271/00.
	2/. cement concrete brick or stone ballast 1½" to 2" gage ratio 1;5;10	135.0	8694/95	%cft;	Rs:11738/=
	3/. Pacca brick work in foundation of building and plinth in ratio 1;6;	366.0	11948/36	%cft;	Rs:43731/00
	4/. R.c.c. work in roof slab beams rafts linels and other structural members laid in sitta or precast laid in position etc compiter in all respect cement concrete ratio (1;2;4;);	217.65	337/00	P; cft;	Rs:73348/00.
	5/. Fabrication of mild steel reinforcement for cement concrete work i/c cutting bending and laying in position including the cost of steel binding wire also removal from bars.	9.72.0	5001/70	P; cwt;	Rs:48617/00.
	6/. Pacca brick work in G/Floor in cement sand moter ratio (1;6;);	459.0	12674/36	%cft;	Rs:58175/00
	7/. Filling watering ramming earth in floor with surplus earth excavated from foundation lead upto one chain and lift upto 5'feet;	400.0	1512/50	%cft;	Rs:605/00.
	8/-Filling watering ramming earth under floor with New earth (Excavated from out side;)lead upto one chain and lift upto 5'feet;	206.0%	8655/20	%cft;	Rs:1783/00.
	9/. Cement plster (1;6;) upto 20'hight 1/2"thick;	1835.0	2206/60	%sft;	Rs:40491/00
	10/. cement plster (1;4;) upto 20'hight 3/8"thick;	1835.0	2197/52	%sft;	Rs: 40324/00
	11/. Cement concrete plain i/c placing compacting finishing and curring compiter i/c screening and washing of stone aggregate without shuttering ratio (1;2;4;); etc compiter;	17.0	14429/25	%cft;	Rs:2453/00.



12/. Providing and laying 1"thick topping cement concrete (1;2;4;) i/c surface finishing and dividing into pannels 3"thick; <u>3"thick;</u>	43.0	@RS:4411/82	%sft;	Rs:1897/00.
<u>2"thick;</u>	271.0	@RS: =3275/50	%sft;	Rs:8877/00.
13/. First class deodar wood wrought joinery in door and windows etc fixed in position i/c deodar panelled and glazed 1-3/4"thick; etc complete	70.0	@RS:1273/76	P; sft;	Rs:89163/00.
14/. Supplying and fixing steel Iron grill 3/8"sq; bars Diagonally fixed both way at 3" c.c. on 3/4"x3/4"x1/8"angle iron frame i/c welding etc complete as per instructions given by the Engineer Incharge (R.....A.).	21.0	@RS: =329/64	P; sft;	Rs:6922/00.
15/. supplying and fixing in position iron/steer grill of 3/4"x1/4"size flat iron of approved design including painting three coats etc complete (weight not to be less than 3.7 Lbs).	12.0	@RS: =180/50	P; sft;	Rs:2166/00.
16/. white glazed tiles 1/4"thick jointed in white cement (1;2;) over 3/4"thick cement moter (1;2;) etc complete;	105.0	@RS: =28253/61	%sft;	Rs:29666/00.
17/. Laying floor of white glazed tiles 1/4"thick jointed in white cement and over 3/4"thick bed (1;2;) ratio.	100.0	@RS: =27678/86	%sft;	Rs:27,679/00.
18/. White wash three coats.	155.0	@RS: =829/95	%sft;	Rs:1286/00.
19/. Primary coat of chalk undering.	155.0	@RS: =442/75	%sft;	Rs:586/00.
20/. Distempering three coats.	155.0	@RS: =1079/65	%sft;	Rs:1673/00.
21/. Painting doors and windows any type (New surfade)(Three coats.).	140.0	@RS: =2116/41	%sft;	Rs:2963/00.

Total Rs: = 495,514/00.


EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR.

SCHEDULE OF (WATER SUPPLY & SANITARY)

3- Seated.

S.NO	DESCRIPTION	RATE	UNIT	AMOUNT
1/-	Providing & fixing squatting type white glazed of flushline cistern fitting & flush pipe with bend and making requisite numbers of holes in wall plinth & floor for pipe connections & cement concrete 1:2:4 (S.I.NO.1 P.NO.1). B.(i) W.C of not less than 19" clear opening between flushing rims and 3 gallons flushing tank with 4" C.I trape & C.I Thumble.	3.0 Rs:4802/60	Each	RS: 14408/-
2/-	Providing and fixing 4" dia C.I soil & vent pipes including Cutting and fitting and extra painting to match the colour of building.(S.I.NO.1 ,P.NO,B)	3.0 Rs:333/29	Each	RS: 1000/-
3/-	Providing & fixing 4"x4"x4" dia C.I branch of the required degree with access doors, rubber washer 1/8" thick and bolts & nuts and extra painting to match the colour of the building.(S.I.NO.5.P.NO.8)	3.0 Rs:270/60	Each	RS: 810/-
4/-	Providing G.I Pipes specials & clamps etc including fixing cutting and fitting complete with and l/c the cost of breaking through walls and roof making good etc . Painting two coats after cleaning the pipe etc. with white zink paint with pigment to match the colour of the building and testing with water to a pressure head of 200 feet and handling. (S.I.NO.1 .P.NO.11)			
	(iii) 1" dia G.I Pipe	10.0 Rs:128/55	Rft:	RS: 1280/-
	(i) 1/2" dia G.I Pipe	30.0 Rs: 73/21	Rft:	RS: 2190/-
	(ii) 3/4" dia G.I Pipe	30.0 Rs: 95/79	Rft:	RS: 1916/-
5/-	Supplying and fixing in position brass bib cock 3/4" dia (S.I.NO.15 P.NO.15)	3.0 Rs: 348/92	Each	RS: 1068/-
6/-	Providing & fixing bal valve (with unsoldered copper ball) made to B.B S. 1212 (S.I.NO.8 P.NO. 14)			
	(ii) 3/4" dia	3.0 Rs:290/84	Each	RS: 873/-
7/-	Providing R.C.C pipe with collars class "B" and digging the trench to required depth and fixing in position including cutting fitting and joining with maphalt composition & cement mortar 1:1 and testing with water pressure to a head of 4 feet above the top of the highest pipe & refilling with excavated stuff. (S.I.NO .2 P.NO.21)			
	(c) 6" dia R.C.C pipe class "B"	20.0 Rs: 199/25	Rft:	RS: 3985/-
8/-	Supplying & Fixing Fiber Glass Tank of approved quality and design and wall thickness as soecified i/c cost of nuts bolts and fixing in plate form of cement concrete 1:3:6 and making connections for in-let out & over flow inlet .outlet flow pipes etc complete.(S.I.NO .3. P.NO.18) (250 GLS)	1.0 Rs:21999/61	P.Gallon	RS: 21999/-
9/-	Supplying & Fixing approved quality Eelectric motor pumping set (Javed Engineering made)1-1/4"x1" section and delievery with base plate and compiling one horsepower single phase motor (siemens make) 60'feet head pf 2800 RPM including the cost of nuts and bolts c.c (1:2:4)	1.0 Rs:12500/00	Each	RS: 12500/-
10/-	Providing and Installation of Hand pump 1-1/4" G.I pipe and colr syainer with wooden shap including cost of 4" feet above ground level embded in C.C (1:2:4) with iron handle and required same shape with acc and fixing etc complete.			
	(a) Filter pipe	10.0 Rs:120/00	Rft:	RS: 1200/-
	(b) G.I pipe	30.0 Rs:110/00	Rft:	RS: 3300/-
	(c) H.P Machine	1.0 Rs:2500/00	P.NO	RS: 2500/-

	DESCRIPTION	RATE	UNIT	AMOUNT
	Providing and fixing 22"x16" lavatory basin in white glazed earthen ware complete with & 1/2 the cost of W.I or C.I cantilever brackets 6 inch built into wall. Painted white in two coat after a primary coat of red lead paint a pair of 1/2" dia chrome plated pillar traps 1-1/2" dia rubber plug chrome brass waste of approved pattern. 1-1/4" dia malleable iron c.p union making and traps, malleable iron or brass requisite number of holes in wall plinth & floor for pipe connection and making good in cement concrete 1:2:4 (standard pattern) (S.I.NO.13.P.NO.3)	1.0 Rs: 4694/80	Each	RS: 4694/80
12/-	Add extra for labour for providing & fixing of earthen ware pedestal white or coloured glazed (standard pattern) (S.I.NO.9.P.NO.3)	1.0 Rs: 938/47	Each	RS: 938/47
13/-	(a) Supplying & Fixing swan type pillar cock of Superior quality single c.p head 1/2" dia(S.I.NO.18.P.NO.16)	1.0 Rs: 795/30	Each	RS: 795/30
14/-	Supplying & Fixing Bath room accessories (7 pieces) 1/2" towel rod ,brush,holder ,soap tray. Shelf of approved quality and design etc complete (S.I.NO.24 .P.NO.16)	1.0 Rs: 8122/40	Each	RS: 8122/40
15/-	Construction manhole or inspection chamber for the required dia of circular sewer and 3"x6" (1067mm) dept with walls of B.B in cement mortar 1:3 cement plastered 1:3, 1/2" thick inside of walls and 1" (25mm) thick over benching and channel 1/2" fixing C.I manhole cover with frame of clear opening 1-1/2"x1-1/2" (457x457mm) of 1.75Cwt. (80.9 kg.) embedded in plain C.C 1:2:4 and fixing 1" (25mm) dia M.S steps 6" (150mm) wide projecting 4" (102mm) from the face of wall at 12" (305mm) C/C duly painted etc complete as per specification and drawing No. D.P/I of Public Health Circle Southern Zone.(S.I.NO.1 P. NO.39)	1.0 Rs: 14748/-	Each	RS: 14748/-
16/-	Providing & fixing 4" dia C.I Terminal guard including extra painting to match the colour of the building (S.I.NO.10.P.NO.9)	Rs: 389/70	Each	RS: 389/70
17/-	Providing and fixing in position nylon connections complete with 1/2" dia brass stop cock with pair of brass nuts and lining joints to nylon connection. (S.I.NO.23 .P.NO.6)	1.0 Rs: 447/15	Each	RS: 447/15
18/-	Providing asbestos pipe with collar (Dadex or equivalent) 1/2" digging the trench to required depth and fixing to position and joining with rubber rings including testing to water pressure head of 200 feet. (S.I.NO.3. P.NO.21)	20 Rs: 188/44	Rft:	RS: 3769/
19/-	Providing & fixing 15"x12" beveled edge mirror of belgium glass complete with 1/8" thick hard board and C.P screws fixed to wooden pleat.(S.I.NO 3 .P.NO .7)			
	a) Standard pattern	Rs: 1161/60	Each	RS: 1161/60

EXECUTIVE ENGINEER
EDUCATION WORKS DIVISION
SHIKARPUR.