



**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(01)

BIDDING DATA

- | | | |
|-----|---|---|
| (a) | Name of procuring Agency: | Town Officer, Town Committee Sindhri |
| (b) | Brief Description of Works: | Construction of C.A. Road Village Aliali Bachayo Rahimoon UC Gilhera Shalif |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 9,80,000/- |
| (e) | Amount of Bid Security: | Rs. 19,600 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted from bills | 8% |
| (i) | Deadline for submission of Bids along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time and date of Bid Opening | 11-01-2016 at 03:00 pm, Town Committee Sindhri Office |
| (k) | Time for completion from written order of commence: | 3 Months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | _____ |


Taluka Officer, (I&S)
Town Committee Sindhri


Town Officer,
Town Committee Sindhri

26047



**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(02)

BIDDING DATA

- | | | |
|-----|---|---|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Earth Filling/Work at various villages of UC Khiraho |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 2,90,000/- |
| (e) | Amount of Bid Security: | Rs. 19,800 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted from bills | 8% |
| (i) | Deadline for submission of Bids along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of Bid Opening | 11-01-2016 at 03:00 pm. Town Committee Sindhri Office |
| (k) | Time for completion from written order of commence: | 3 Months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | ----- |


Taluka Officer, (I&S)
Town Committee Sindhri



Town Officer,
Town Committee Sindhri


**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(03)

BIDDING DATA

(a)	Name of Procuring Agency:	DEFUNCT TMA, TOWN COMMITTEE SINDHRI
(b)	Brief Description of Work:	land clearing work in village village of VV Khigora
(c)	Procuring Agency's address:	Town Committee Sindhri District Mirpurkhas
(d)	Telephone No.	9100000000
(e)	Amount of Bid Security:	Rs. 19,300
(f)	Period of Bid Validity (days)	45 Days
(g)	Security/ Call Deposit:	2%
(h)	Percentage, if any, to be deducted from bills	8%
(i)	Deadline for submission of Bids along with time:	11-01-2016 at 02:00 pm
(j)	Venue, Time, and date of Bid Opening	11-01-2016 at 03:00 pm, Town Committee Sindhri Office
(k)	Time for completion from written order of commencement:	3 Months
(l)	Liquidity Damages	0.1%
(m)	Deposit Receipt No./ Date/ Amount:	-----


Tawker Officer, (135)
Town Committee Sindhri


Town Officer,
Town Committee Sindhri

**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(0-1)

BIDDING DATA

- | | | |
|-----|---|---|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Earth Filling/Work at various villages of UC Ismail Jo Goth |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 9,90,000/- |
| (e) | Amount of Bid Security: | Rs. 19,800 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted from bills | 8% |
| (i) | Deadline for submission of Bids along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of Bid Opening | 11-01-2016 at 03:00 pm, Town Committee Sindhri Office |
| (k) | Time for completion from written order of commence: | 3 Months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | _____ |


Taluka Officer, (I&S)
Town Committee Sindhri


Town Officer,
Town Committee Sindhri

**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(05)

BIDDING DATA

- | | | |
|-----|---|---|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Earth Filling/Work at various villages of UC Phullahdy... |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 9,90,000/- |
| (e) | Amount of Bid Security: | Rs. 19,800 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted from bills | 8% |
| (i) | Deadline for submission of Bids along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of Bid Opening | 11-01-2016 at 03:00 pm, Town Committee Sindhri Office |
| (k) | Time for completion from written order of commence: | 3 Months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | |


**Taluka Officer, (I&S)
Town Committee Sindhri**


**Town Officer,
Town Committee Sindhri**



**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(06)

BIDDING DATA

- | | | |
|-----|---|---|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Earth Filling/Work at various villages of UC Gihore Sindhri |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 9,90,000/- |
| (e) | Amount of Bid Security: | Rs. 19,800 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted from bills | 8% |
| (i) | Deadline for submission of Bids along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of Bid Opening | 11-01-2016 at 03:00 pm, Town Committee Sindhri Office |
| (k) | Time for completion from written order of commence: | 3 months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | _____ |


**Taluka Officer, (I&S)
Town Committee Sindhri**


**Town Officer,
Town Committee Sindhri**

**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(07)

BIDDING DATA

- | | | |
|-----|---|---|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Remaining work of Drainage System Village Shah Bux Lashari UC Khiraho |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 5,00,000/- |
| (e) | Amount of Bid Security: | Rs. 10,000 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted from bills | 8% |
| (i) | Deadline for submission of Bids along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of Bid Opening | 11-01-2016 at 03:00 pm, Town Committee Sindhri Office |
| (k) | Time for completion from written order of commence: | 3 Months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | _____ |


**Taluka Officer, (I&S)
Town Committee Sindhri**


**Town Officer,
Town Committee Sindhri**


**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(08)

BIDDING DATA

- | | | |
|-----|--|---|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Construction of C.C Road Village Mian Bux
Khaskheli UC Khiraho |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 9,80,000/- |
| (e) | Amount of Bid Security: | Rs. 19,600 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted
from bills | 8% |
| (i) | Deadline for submission of Bids
along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of
Bid Opening | 11-01-2016 at 03:00 pm, Town Committee Sindhri
Office |
| (k) | Time for completion from written
order of commence: | 3 Months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | ----- |


Town Officer, (I&S)
Town Committee Sindhri


Town Officer,
Town Committee Sindhri

**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(09)

BIDDING DATA

- | | | |
|-----|--|--|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Construction of 2 No. Water Tank Village Hameero Kach:
Kolhi UC Khiraho |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 9,94,200/- |
| (e) | Amount of Bid Security: | Rs. 19,900 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted
from bills | 8% |
| (i) | Deadline for submission of Bids
along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of
Bid Opening | 11-01-2016 at 03:00 pm, Town Committee Sindhri
Office |
| (k) | Time for completion from written
order of commence: | 3 Months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | _____ |


Town Officer (I&S)
Town Committee Sindhri


Town Officer,
Town Committee Sindhri

**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(10)

BIDDING DATA

- | | | |
|-----|---|--|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Construction of 2 No. Water Tanks at various villages of UC Ringorno |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 9,94,200/- |
| (e) | Amount of Bid Security: | Rs. 19,900 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted from bills | 8% |
| (i) | Deadline for submission of Bids along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of Bid Opening | 11-01-2016 at 03:00 pm, Town Committee Sindhri Office |
| (k) | Time for completion from written order of commence: | 3 Months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | |


**Taluka Officer, (I&S)
Town Committee Sindhri**


**Town Officer,
Town Committee Sindhri**

**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(11)

BIDDING DATA

- | | | |
|-----|---|--|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Construction of 2 No. Water Tanks at various villages of UC Ismail Jo Goth |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 9,94,200/- |
| (e) | Amount of Bid Security: | Rs. 19,900 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security/ Call Deposit: | 2% |
| (h) | Percentage, if any, to be deducted from bills | 8% |
| (i) | Deadline for submission of Bids along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of Bid Opening | 11-01-2016 at 03:00 pm, Town Committee Sindhri Office |
| (k) | Time for completion from written order of commence: | 3 Months |
| (l) | Liquidity damages | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | _____ |



**Taluka Officer, (I&S)
Town Committee Sindhri**



**Town Officer,
Town Committee Sindhri**


**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(12)

BIDDING DATA

(a)	Name of Procuring Agency:	(DEFUNCT) TMA, TOWN COMMITTEE SINDHRI.
(b)	Brief Description of Works:	Construction of 2 No. Water Tanks at various villages of UC Pihallahdyoun
(c)	Procuring Agency's address:	Town Committee Sindhri District Mirpurkhas
(d)	Estimate Cost:	Rs. 9,94,200/-
(e)	Amount of Bid Security:	Rs. 19,900
(f)	Period of Bid Validity (days):	45 Days
(g)	Security/ Call Deposit:	2%
(h)	Percentage, if any, to be deducted from bills	8%
(i)	Deadline for submission of Bids along with time:	11-01-2016 at 02:00 pm
(j)	Venue, Time, and date of Bid Opening	11-01-2016 at 03:00 pm, Town Committee Sindhri Office
(k)	Time for completion from written order of commence:	3 Months
(l)	Liquidity damages	0.05%
(m)	Deposit Receipt No. Date: Amount:	-----


Taha Officer, (I&S)
Town Committee Sindhri


Town Officer,
Town Committee Sindhri





**OFFICE OF THE
TOWN OFFICER TOWN COMMITTEE SINDHRI
DISTRICT MIRPUR KHAS**

(13)

BIDDING DATA

- | | | |
|-----|---|--|
| (a) | Name of Procuring Agency: | (DEFUNCT) TMA, TOWN COMMITTEE SINDHRI |
| (b) | Brief Description of Works: | Construction of 2 No. Water Tanks at various villages of UC Girhore Sharif |
| (c) | Procuring Agency's address: | Town Committee Sindhri District Mirpurkhas |
| (d) | Estimate Cost: | Rs. 9,94,200/- |
| (e) | Amount of Bid Security: | Rs. 19,900 |
| (f) | Period of Bid Validity (days) | 45 Days |
| (g) | Security Cash Deposit: | 2/- |
| (h) | Percentage, if any, to be deducted from bill: | 8% |
| (i) | Deadline for submission of Bids along with time: | 11-01-2016 at 02:00 pm |
| (j) | Venue, Time, and date of Bid Opening: | 11-01-2016 at 03:00 pm, Town Committee Sindhri Office |
| (k) | Time for completion from written order of commence: | 3 Months |
| (l) | Iniquity damages: | 0.05% |
| (m) | Deposit Receipt No. Date: Amount: | _____ |


Taha Officer, (I&S)
Town Committee Sindhri


Town Officer
Town Committee Sindhri

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 01

NAME OF WORK: CONSTRUCTION OF C.C ROAD VILLAGE ALI AH BACHAYO RAHIMON
UC GIRHORE SHARIF

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	11918.00	Earth work for road embankment by bulldozers, including ploughing, mixing, C.C. breaking, grading, compacting with optimum moisture content. Lead upto 1.00 miles and lift upto 5.00 ft. in all types of soil except rock. (If earth work is done by other than departmental agency). Upto 85% Density Sch. of Rate, vol-III Part - VI, item No.3 (II - C), Page No. 2	3356.23	P.% Cft	40284.00
2	590.00	Erection and removal of centering for R.C.C. or plain cement concrete works of Partal wood (2nd class) (a) Vertical Schedule of Rate Vol: III Part - II = item 18 (b-ii) Page 21	3127.41	P.% Cft	18452.00
3	3148.00	Cement Concrete brick or stone ballast 1 1/2" to 2" gauge Ratio 1:5:10 Schedule of Rate Vol: III Part - II = item 4 (b) Page 17	3694.95	P.% Cft	273717.00
4	2361.00	Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate with water shunting) Form 10" Schedule of Rate Vol: III Part - II = item 5 (f) Page 18	14435.29	P.% Cft	340817.00

5 Supplying and fixing inauguration Stone at site of work including masonry work cartage of material etc complete.

1.00

5000.00

Each	5000.00
TOTAL	678270.00

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 02

NAME OF WORK: EARTH FILLING @ VILLAGE
UC

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	132050.00	Borrow pit excavation undressed lead upto 100' ft (b) ordinary soil.(G.S.I.No: 3 (a) P-1)	2117.50	P.%o Cft	279615.88
2	132050.00	Extra lead for 2 Miles Lead	5025.20	P.%o Cft	663577.66
3	132050.00	Laying earth 6" layers leveling dressing watering for compacton (Soft Ordinary or Hard Soil) (G.S.I.No: 13 (b) P-3)	354.00	P.%o Cft	46745.70
TOTAL					989939.24

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 03

NAME OF WORK: EARTH FILLING @ VILLAGE
UC

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	132050.00	Borrow pit excavation undressed lead upto 100' ft (b) ordinary soil.(G.S.I.No: 3 (a) P-1)	2117.50	P.%o Cft	279615.88
2	132050.00	Extra lead for 2 Miles Lead	5025.20	P.%o Cft	663577.66
3	132050.00	Laying earth 6" layers leveling dressing watering for compacton (Soft Ordinary or Hard Soil) (G.S.I.No: 13 (b) P-3)	354.00	P.%o Cft	46745.70
TOTAL					989939.24

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 04

NAME OF WORK: EARTH FILLING @ VILLAGE
UC

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	132050.00	Borrow pit excavation undressed lead upto 100' ft (b) ordinary soil.(G.S.I.No: 3 (a) P-1)	2117.50	P.%o Cft	279615.88
2	132050.00	Extra lead for 2 Miles Lead	5025.20	P.%o Cft	663577.66
3	132050.00	Laying earth 6" layers leveling dressing watering for compaction (Soft Ordinary or Hard Soil) (G.S.I.No: 13 (b) P-3)	354.00	P.%o Cft	46745.70
TOTAL					989939.24

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____% above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 05

NAME OF WORK: EARTH FILLING @ VILLAGE
UC

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	132050.00	Borrow pit excavation undressed lead upto 100' ft (b) ordinary soil.(G.S.I.No: 3 (a) P-1)	2117.50	P.‰o Cft	279615.88
2	132050.00	Extra lead for 2 Miles Lead	5025.20	P.‰o Cft	663577.66
3	132050.00	Laying earth 6" layers leveling dressing watering for compacton (Soft Ordinary or Hard Soil) (G.S.I.No: 13 (b) P-3)	354.00	P.‰o Cft	46745.70
TOTAL					989939.24

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 06

NAME OF WORK: EARTH FILLING @ VILLAGE
UC

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	132050.00	Borrow pit excavation undressed lead upto 100' ft (b) ordinary soil.(G.S.I.No: 3 (a) P-1)	2117.50	P.‰ Cft	279615.88
2	132050.00	Extra lead for 2 Miles Lead	5025.20	P.‰ Cft	663577.66
3	132050.00	Laying earth 6" layers leveling dressing watering for compacton (Soft Ordinary or Hard Soil) (G.S.I.No: 13 (b) P-3)	354.00	P.‰ Cft	46745.70
TOTAL					989939.24

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

QUANTITY BILLS

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 07

NAME OF WORK: CONSTRUCTION OF DRAINS @ VILLAGE SHAH BUX LASHARI UC
KHIRAHO

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
---------	-----	-------	------	------	--------

1		Excavation in foundation of Building, Bridges and other structures including dagbelling dressing, refilling around structure with excavated earth, watering and ramming, lead upto 5.00 ft. (In Ordinary soil) Schedule of Rate Vol: III Part - II = item 18 (b) Page 4&5			
	1506.00		3176.25	P.%o Cft	4783.43
2		Cement Concrete brick or stone ballast 1 1/2" to 2" gauge. Ratio 1:4:8 Schedule of Rate Vol: III Part - II = item 4 (b) Page 17			
	377.00		9416.28	P.%o Cft	35499.38
3		Pucca brick work in foundation and plinth in cement sand mortar Ratio 1:4 Schedule of Rate Vol: III Part - II = item 4 (i-c) Page 24			
	1501.00		12501.44	P.%o Cft	187648.16
4		Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering (Ratio 1:2:4) Schedule of Rate Vol: III Part - II = item 5 (f) Page 18			
	251.00		14429.25	P.% Cft	36217.42
5		Fabrication of mild steel reinforcement for cement concrete including cutting, bending, laying in position, making joints and fastenings including cost of binding wire (also includes removal of			
	1.97		4820.20	P.% Cwt	9495.79
6		Reinforced cement concrete work, including all labour and materials except the cost of steel reinforcement and its labour for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, shuttering, curing			
	377.00		337.00	P.% Cft	127049.00

7

879.00

Cement Plaster 1:3 upto 20.0' height. 1/2" thick.
Schedule of Rate Vol: III Part - II = item 10 (b) Page 58

2344.59

P.% Cft 20608.95
TOTAL 421299.00

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 08

NAME OF WORK: CONSTRUCTION OF C.C ROAD VILLAGE MIAN BUX KHASKHELI UC
KHIRAHO

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	11018.00	Earth work for road embankment by buldozers, including ploughing, mixing, clod breaking, dressing, compacting with optimum moisture content. Lead upto 1.00 miles and lift upto 5.00 ft. in all types of soil except rock. (If earth work is done by other than departmental agency). Upto 85% Density Sch. of Rate, vol-III Part - VI, item No.3 (II - C), Page No. 2	3656.23	P.%o Cft	40284.00
2	590.00	Erection and removal of centering for R.C.C. or plain cement concrete works of Partial wood (2nd class) (a) Vertical Schedule of Rate Vol: III Part - II = item 18 (b-ii) Page 21	3127.47	P.%o Cft	18452.00
3	3148.00	Cement Concrete brick or stone ballast 1 1/2" to 2" gauge. Ratio 1:5:10 Schedule of Rate Vol: III Part - II = item 4 (b) Page 17	3694.95	P.%o Cft	273717.00
4	2361.00	Cement concrete plain including placing, compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering (Ratio 1:2:4) Schedule of Rate Vol: III Part - II = item 5 (f) Page 18	14435.29	P.%o Cft	340817.00

Supplying and fixing inauguration Stone at site of work including
Masonry work cartage of material etc complete.

5

1.00

5000.00

Each	5000.00
TOTAL	678270.00

Taruka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Taruka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 09

NAME OF WORK: CONSTRUCTION OF WATER TANK @ VILLAGE UC
TALUKA SINDHRI

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	2607.75	Excavation for tanks reservoir in soft soil i/c trimming and dressing sides to true alignment/design section/profiles shape leveling of bed of tanks to correct level and grade i/c laying of earth in 6" layers for construction banks and dressing disposal of surplus excavated earth within one chain as directed by engineer incharge i/c providing fence guards lights flags wherever required lift upto 5'ft (1.52m) and lead upto one chain (30.52m) (PHSI No.1 page-67)	3000.00	P.%o Cft	7823.25
2	1091.35	Excavation for Tanks and reservoirs in wet soil clay or mud i/c trimming and dressing sides true alignment/ design section/ profile and sides and shape leveling of beds of tanks to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and disposal of surplus excavated earth within one chain as directed by Engineer incharge providing fence guards lights wherever resulting lift upto 5' ft and lead up to one chain (PHSI No. 14 Page – 74)	4800.00	P.%o Cft	5238.50
3	513.00	Excavation in foundation building bridges and other structures including level dressing refilling around structure with excavated earth watering and ramming lead upto 5' ft height (GSI No. 81 (B) Page- 04)	3176.25	P.%o Cft	1629.42
4	951.46	Stabilized layer of cement sand 1:3 2" thick on slope.(G.S.I.No:2 P-74)	1577.40	P.% Cft	15008.33
5	573.32	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (1:3:6) (GSI No: 5H Page – 17)	12595.00	P.% Cft	72209.34
6	602.63	Cement Concrete plain (1:2:4) i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (G.S.I.No:5F, P-17)	14429.25	P.% Cft	86954.99
7	359.20	Pacca Brick work in foundation and plinth in cement sand mortar (1:6) (GSI No. 4 (I) Page – 21)	11948.36	P.% Cft	42918.66
8	286.38	Pacca brick other than building i/c striking of joints upto 20' ft height in cement mortar (1:6) (GSI No. 7 (I) Page –22)	12346.65	P.% Cft	35358.34

9	2260.80	Cement plaster (1:4) upto 20' ft height 1/2" thick (GSI No. 1 (b) Page- 52)	2283.93	P.% Sft	51635.09
10	100.00	Providing RCC pipes and collars of class "B" digging the trenches to required depth & fixing in position i/c cutting fitting & jointing with asphalt composition cement mortar 1:1 & testing with water pressure to a height of 4 ft above the top of the highets pipe & refilling with asphalt excavated stuff.(G.S.I.No:2 (c) P-21)	163.00	P.Rft	16300.00
11	24.00	Making and fixing steel grateel door and Window with 1/16 thick sheeting i/c angle iron frame 2"x2"x3/8 and 3/4" square bars 4" c/c with locking arrangements. (S.No: 23 P-91)	594.57	P.Sft	14269.68
12	193.23	Damp proof course with (cement sand and shingle concrete (1:2:4) i/c 2 coats of asphaltic mixture (GSI No. 28 (b) P-19)	3912.85	P.% Sft	7560.80
13	100.00	Providing G.I. Pipe Specials clps: etc fixing cutting fitting complete.(WSS I No: P-)	153.19	P.Rft	15319.00
14	1.00	Providing & Installing hand pumps with all assement 1:1 1/4" dia co staler wooden sho i/c basing fitting & fixing etc complete. (RA).	3550.00	P.Each	3550.00
15	2260.80	Distempering two coats.(G.S.I.No:24 (p) P-50)	1043.90	P.% Cft	23600.49
					TOTAL 309375.97

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____% above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 10

NAME OF WORK: CONSTRUCTION OF WATER TANK @ VILLAGE UC
TALUKA SINDHRI

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	2607.75	Excavation for tanks reservoir in soft soil i/c trimming and dressing sides to true alignment/design section/profiles shape leveling of bed of tanks to correct level and grade i/c laying of earth in 6" layers for construction banks and dressing disposal of surplus excavated earth within one chain as directed by engineer incharge i/c providing fence guards lights flags wherever required lift upto 5'ft (1.52m) and lead upto one chain (30.52m) (PHSI No.1 page-67)	3000.00	P.% Cft	7823.25
2	1091.35	Excavation for Tanks and reservoirs in wet soil clay or mud i/c trimming and dressing sides true alignment/ design section/ profile and sides and shape leveling of beds of tanks to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and disposal of surplus excavated earth within one chain as directed by Engineer incharge providing fence guards lights wherever resulting lift upto 5' ft and lead up to one chain (PHSI No. 14 Page – 74)	4800.00	P.% Cft	5238.50
3	513.00	Excavation in foundation building bridges and other structures including level dressing refilling around structure with excavated earth watering and ramming lead upto 5' ft height (GSI No. 81 (B) Page- 04)	3176.25	P.% Cft	1629.42
4	951.46	Stabilized layer of cement sand 1:3 2" thick on slope.(G.S.I.No:2 P-74)	1577.40	P.% Cft	15008.33
5	573.32	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (1:3:6) (GSI No: 5H Page – 17)	12595.00	P.% Cft	72209.34
6	602.63	Cement Concrete palin (1:2:4) i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (G.S.I.No:5F, P-17)	14429.25	P.% Cft	86954.99
7	359.20	Pacca Brick work in foundation and plinth in cement sand mortar (1:3) (GSI No. 4 (I) Page – 21)	11948.36	P.% Cft	42918.66
8	286.38	Pacca brick other than building i/c striking of joints upto 20' ft height in cement mortar (1:6) (GSI No. 7 (I) Page –22)	12346.65	P.% Cft	35358.34

9	2260.80	Cement plaster (1:2) upto 20' ft height 1" thick (GSI No. 1 (b) Page- 52)	2283.93	P.% Sft	51635.09	
10	100.00	Providing RCC pipes and collars of class "B" digging the trenches to required depth & fixing in position i/c cutting fitting & jointing with asphalt composition cement mortar 1:1 & testing with water pressure to a head of 4 ft above the top of the highets pipe & refilling with asphalt excavated stuff.(G.S.I.No:2 (c) P-21)	163.00	P.Rft	16300.00	
11	24.00	Making and fixing steel grateel door and Window with 1/16 thick sheeting i/c angle iron frame 2"x2"x3/8 and 3/4" square bars 4" c/c with locking arrangements. (S.No: 23 P-91)	594.57	P.Sft	14269.68	
12	193.23	Damp proof course with (cement sand and shingle concrete (1:2:4) i/c 2 coats of asphaltic mixture (GSI No. 28 (b) P-19)	3912.85	P.% Sft	7560.80	
13	100.00	Providing G.I. Pipe Specials clps: etc fixing cutting fitting complete.(WSS I No: P-)	153.19	P.Rft	15319.00	
14	1.00	Providing & Installing hand pumps with all assement 1:1 1/4" dia co staler wooden sho i/c basing fitting & fixing etc complete. (I&S).	3550.00	P.Each	3550.00	
15	2260.80	Distempering two coats.(G.S.I.No:24 (b) P-50)	1043.90	P.% Cft	23600.49	
					TOTAL	300375.98

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 11

NAME OF WORK: CONSTRUCTION OF WATER TANK @ VILLAGE UC
TALUKA SINDHRI

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	2607.75	Excavation for tanks reservoir in soft soil i/c trimming and dressing sides to true alignment/design section/profiles shape leveling of bed of tanks to correct level and grade i/c laying of earth in 6" layers for construction banks and dressing disposal of surplus excavated earth within one chain as directed by engineer incharge i/c providing fence guards lights flags wherever required lift upto 5'ft (1.52m) and lead upto one chain (30.52m) (PHSI No.1 page-67)	3000.00	P.%o Cft	7823.25
2	1091.35	Excavation for Tanks and reservoirs in wet soil clay or mud i/c trimming and dressing sides true alignment/ design section/ profile and sides and shape leveling of beds of tanks to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and disposal of surplus excavated earth within one chain as directed by Engineer incharge providing fence guards lights wherever resulting lift upto 5' ft and lead up to one chain (PHSI No. 14 Page – 74)	4800.00	P.%o Cft	5238.50
3	513.00	Excavation in foundation building bridges and other structures including level dressing refilling around structure with excavated earth watering and ramming lead upto 5' ft height (GSI No. 81 (B) Page- 04)	3176.25	P.%o Cft	1629.42
4	951.46	Stabilized layer of cement sand 1:3 2" thick on slope.(G.S.I.No:2 P-74)	1577.40	P.% Cft	15008.33
5	573.32	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (1:3:6) (GSI No: 5H Page – 17)	12595.00	P.% Cft	72209.34
6	602.63	Cement Concrete palin (1:2:4) i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (G.S.I.No:5F, P-17)	14429.25	P.% Cft	86954.99
7	359.20	Pacca Brick work in foundation and plinth in cement sand mortar (1:6) (GSI No. 4 (I) Page – 21)	11948.36	P.% Cft	42918.66
8	286.38	Pacca brick other than building i/c striking of joints upto 20' ft height in cement mortar (1:6) (GSI No. 7 (I) Page –22)	12346.65	P.% Cft	35358.34

9	2260.80	Cement plaster (1:4) upto 20' ft. Height 1/2" thick (GSI No. 1 (b) Page- 52)	2283.93	P.% Sft	51635.09
10	100.00	Providing RCC pipes and collars of class "B" digging the trenches to required depth & fixing in position i/c cutting fitting & jointing with asphalt composition cement mortar 1:1 & testing with water pressure to a head of 4 ft above the top of the highets pipe & refilling with asphalt excavated stuff.(G.S.I.No:2 (c) P-21)	163.00	P.Rft	16300.00
11	24.00	Making and fixing steel grateel door and Window with 1/16 thick sheeting i/c angle iron frame 2"x2"x3/8 and 3/4" square bars 4" c/c with locking arrangements. (S.No: 23 P-91)	594.57	P.Sft	14269.68
12	193.23	Damp proof course with (cement sand and shingle concrete (1:2:4) i/c 2 coats of asphaltic mixture (GSI No. 28 (b) P-19)	3912.85	P.% Sft	7560.80
13	100.00	Providing G.I. Pipe Specials clps: etc fixing cutting fitting complete.(WSS I No: P-)	153.19	P.Rft	15319.00
14	1.00	Providing & Installing hand pumps with all assement 1:1 1/4" dia co staler wooden snc i/c basing fitting & fixing etc complete. (RA)	3550.00	P.Each	3550.00
15	2260.80	Distempering two coats.(G.S.I.No:24 (b) P-80)	1043.90	P.% Cft	23600.49
				TOTAL	300375.88

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____% above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 12

NAME OF WORK: CONSTRUCTION OF WATER TANK @ VILLAGE UC
TALUKA SINDHRI

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	2607.75	Excavation for tanks reservoir in soft soil i/c trimming and dressing sides to true alignment/design section/profiles shape leveling of bed of tanks to correct level and grade i/c laying of earth in 6" layers for construction banks and dressing disposal of surplus excavated earth within one chain as directed by engineer incharge i/c providing fence guards lights flags wherever required lift upto 5'ft (1.52m) and lead upto one chain (30.52m) (PHSI No.1 page-67)	3000.00	P.%o Cft	7823.25
2	1091.35	Excavation for Tanks and reservoirs in wet soil clay or mud i/c trimming and dressing sides true alignment/ design section/ profile and sides and shape leveling of beds of tanks to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and disposal of surplus excavated earth within one chain as directed by Engineer incharge providing fence guards lights wherever resulting lift upto 5' ft and lead up to one chain (PHSI No. 14 Page – 74)	4800.00	P.%o Cft	5238.50
3	513.00	Excavation in foundation building bridges and other structures including level dressing refilling around structure with excavated earth watering and ramming lead upto 5' ft height (GSI No. 81 (B) Page- 04)	3176.25	P.%o Cft	1629.42
4	951.46	Stabilized layer of cement sand 1:3 2" thick on slope.(G.S.I.No:2 P-74)	1577.40	P.% Cft	15008.33
5	573.32	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (1:3:6) (GSI No: 5H Page – 17)	12595.00	P.% Cft	72209.34
6	602.63	Cement Concrete palin (1:2:4) i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (G.S.I.No:5F, P-17)	14429.25	P.% Cft	86954.99
7	359.20	Pacca Brick work in foundation and plinth in cement sand mortar (1:6) (GSI No. 4 (I) Page – 21)	11948.36	P.% Cft	42918.66
8	286.38	Pacca brick other than building i/c striking of joints upto 20' ft height in cement mortar (1:6) (GSI No. 7 (I) Page –22)	12346.65	P.% Cft	35358.34

9	2260.80	Cement plaster (1:4) upto 20' ft height 1/2" thick (GSI No. 1 (b) Page- 52)	2283.93	P.% Sft	51635.09	
10	100.00	Providing RCC pipes and collars of class "B" digging the trenches to required depth & fixing in position i/c cutting fitting & jointing with asphalt composition cement mortar 1:1 & testing with water pressure to a height of 4 ft above the top of the highets pipe & refilling with asphalt excavated stuff.(G.S.I.No:2 (c) P-21)	163.00	P.Rft	16300.00	
11	24.00	Making and fixing steel grateel door and Window with 1/16 thick sheeting i/c angle iron frame 2"x2"x3/8 and 3/4" square bars 4" c/c with locking arrangements. (S.No: 23 P-91)	594.57	P.Sft	14269.68	
12	193.23	Damp proof course with (cement sand and shingle concrete (1:2:4) i/c 2 coats of asphaltic mixture (GSI No. 28 (b) P-19)	3912.85	P.% Sft	7560.80	
13	100.00	Providing G.I. Pipe Specials clps: etc fixing cutting fitting complete.(WSS I No: P-)	153.19	P.Rft	15319.00	
14	1.00	Providing & Installing hand pumps with all assement 1:1 1/4" dia cu sta'er wooden sro i/c basing fitting & fixing etc complete. (RA)	3550.00	P.Each	3550.00	
15	2260.80	Distempereing two coats.(G.S.I.No:24 (d) P-58)	1043.90	P.% Cft	23600.49	
					TOTAL	309375.98

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

BILLS QUANTITY/ SCHEDULE "B"

NIT NO. TC-SINDHRI/ /2015 Dated

SCHEME NO. 13

NAME OF WORK: CONSTRUCTION OF WATER TANK @ VILLAGE UC
TALUKA SINDHRI

NAME OF AGENCY: _____

Sr. No.	QTY	ITEMS	RATE	UNIT	Amount
1	2607.75	Excavation for tanks reservoir in soft soil i/c trimming and dressing sides to true alignment/design section/profiles shape leveling of bed of tanks to correct level and grade i/c laying of earth in 6" layers for construction banks and dressing disposal of surplus excavated earth within one chain as directed by engineer incharge i/c providing fence guards lights flags wherever required lift upto 5'ft (1.52m) and lead upto one chain (30.52m) (PHSI No.1 page-67)	3000.00	P.%o Cft	7823.25
2	1091.35	Excavation for Tanks and reservoirs in wet soil clay or mud i/c trimming and dressing sides true alignment/ design section/ profile and sides and shape leveling of beds of tanks to correct level and grade i/c laying of earth in 6" layers for construction of banks and dressing and disposal of surplus excavated earth within one chain as directed by Engineer incharge providing fence guards lights wherever resulting lift upto 5' ft and lead up to one chain (PHSI No. 14 Page – 74)	4800.00	P.%o Cft	5238.50
3	513.60	Excavation in foundation building bridges and other structures including level dressing refilling around structure with excavated earth watering and ramming lead upto 5' ft height (GSI No. 81 (B) Page- 04)	3176.25	P.%o Cft	1629.42
4	951.46	Stabilized layer of cement sand 1:3 2" thick on slope.(G.S.I.No:2 P-74)	1577.40	P.% Cft	15008.33
5	573.32	Cement concrete plain i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (1:3:6) (GSI No: 5H Page – 17)	12595.00	P.% Cft	72209.34
6	602.63	Cement Concrete plain (1:2:4) i/c placing compacting finishing and curing complete i/c screening & washing of stone aggregate without shuttering (G.S.I.No:5F, P-17)	14429.25	P.% Cft	86954.99
7	359.20	Pacca Brick work in foundation and plinth in cement sand mortar (1:6) (GSI No. 4 (I) Page – 21)	11948.36	P.% Cft	42918.66
8	286.38	Pacca brick other than building i/c striking of joints upto 20' ft height in cement mortar (1:6) (GSI No. 7 (I) Page –22)	12346.65	P.% Cft	35358.34

9	2260.80	Concrete slabs of 110' into 20' 9" light 12" thick (GSI No. 1 (b) Page- 52)	2283.93	P.% Sit	51635.09
10	100.00	Providing RCC pipes and collars of class "B" digging the trenches to required depth & fixing in position i/c cutting fitting & jointing with asphalt composition cement mortar 1:1 & testing with water pressure to a head of 4 ft above the top of the highets pipe & refilling with asphalt excavated stuff.(G.S.I.No:2 (c) P-21)	163.00	P.Rft	16300.00
11	24.00	Making and fixing steel grateel door and Window with 1/16 thick sheeting i/c angle iron frame 2"x2"x3/8 and 3/4" square bars 4" c/c with locking arrangements. (S.No: 23 P-91)			

12	193.23	Damp proof course with (cement sand and shingle concrete (1:2:4) i/c 2 coats of asphaltic mixture (GSI No. 28 (b) P-19)	3912.85	P.% Sft	7560.80	
13	100.00	Providing G.I. Pipe Specials clps; etc fixing cutting fitting complete.(WSS I No: P-)	153.19	P.Rft	15319.00	
14	1.00	Providing & Installing hand pumps with all assement 1:1 1/4" dia co staler wooden shor/c basing lining & fixing etc complete. (P-)	3550.00	P.Each	3550.00	
15	2260.80	Distemper painting two coats.(G.S.I.No.24 (b) P-39)	1043.90	P.% Cft	23600.49	
					TOTAL	90975.80

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas

I am agreed to do above said work at the _____ % above/Below of S.R

CONTRACTOR

Taluka Officer, (I&S)
Town Committee Sindhri
District Mirpurkhas