

ADDENDUM NO. 1

Issued on March 25, 2016.

PROJECT: CONSTRUCTION OF BRICK MASONRY RETAINING WALL ALONG MC-02, MC-03 PERIPHERY AND EXIT GATE ALONG WITH GATE OFFICE.

SUBJECT: ADDENDUM-1.

THE FOLLOWING SHALL BE CONSIDERED AS AN ADDENDUM TO THE TENDER DOCUMENTS OF THE SUBJECT PROJECT AND SHALL FORM A PART OF THE CONTRACT DOCUMENTS.

1. Bill of Quantities

Following item to be included in Brick Masonry Retaining Wall BOQ in Part-B (Non-Schedule):-

SR. No:	DESCRIPTION	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
13	Providing and fixing new periphery fence made from 50x4mm wire net fixed to 50mm dia x 10 swg G.I pipe frame panels of 2400 x 1700 mm size fixed with each other with 50mm x 5mm holdfasts vertically at three points. The G.I pipe supports to be embedded into RCC 1:2:4 pedestals of size 600 x 250 x to required height over RCC 1:2:4 footings of size 1000 x 500 x 300 mm high. Top of pedestal to match as per existing, including excavation, lean concrete, etc. Complete in all respect as per drawings, specifications and direction of the Engineer.	125	Rm.		

END OF ADDENDUM NO.1

