

**SINDH COAL AUTHORITY**  
**Various New Roads Links , Bypasses and Improvement /Widening /Rehabilitation of Existing**  
**Roads in Districts Tharparkar and Mirpurkhas**  
**Contract Package A. Construction of road from Mithi Intersection to Naukot (up to ADB Project**  
**End Point) (42.0kms), ADP SCHEME NO: 2233/2016-17**

**BILL OF QUANTITIES**

<b>Bill 6 - ANCILLARY WORKS</b>						
<b>Sr No.</b>	<b>Spec Ref</b>	<b>ITEM DESCRIPTION</b>	<b>UNIT</b>	<b>QUANTITY</b>	<b>RATE (PKR)</b>	<b>AMOUNT (PKR)</b>
6.1	605a	Concrete Beam Guard Rail	M	5,641		
6.2	605c	Concrete Post for Guard Rail and Guard Rail End Pieces	Each	1,411		
6.3	607a	Traffic Road Signs Category 1, size 900mm	Each	90		
6.4	607b	Traffic Road Signs Category 2, size 900mm	Each	110		
6.5	607c	Traffic Road Signs Category 3 (a)	Each	130		
6.6	607d	Traffic Road Signs Category 3 (b)	Each	40		
6.7	607e	Traffic Road Signs Category 3 (c)	SM	24		
6.8	608h	Pavement marking in reflective TP paint for Line of 15 cm width	M	24,000		
6.9	608i	Pavement marking in reflective TP paint for Line of 20 cm width	M	84000		
6.10	609d	Reflectorized pavement Studs (raised profile type double)	Each	6450		
6.11	610c	Kilometer Post	Each	43		
<b>TOTAL FOR BILL 6 CARRIED FORWARD TO SUMMARY :</b>						