



Karachi Water & Sewerage Board

Office of the Executive Engineer

Hub Division Civil

Hub Pumping Station Bund Murad Road Deh Halkani

NO. E. E/HDC/KW&SB/ACCTT/2018/101


Dated : 21/03/2018

CORRIGENDUM

SUBJECT: REPAIRING / REPLACING DAMAGED PORTION OF 8" DIA & 12" DIA M.S. WATER SUPPLY LINE FEEDING TO KW&SB STAFF COLONY & COOLING SYSTEM OF HUB PUMPING STATION. (SPPR SR. # 37080)

In continuation of this office letter No. E. E/HDC/Acctt/KWSB/2018/154, dated 27-02-2018, it is intimated that Item at **Sr. # 9 of BOQ** i.e. Hire Charges of Truck (5 Tons i/c all charges but excluding POL) have been deleted which is enclosed herewith and **Sr. # 12 of NIT 2nd attempt** issue date may be read as "**from 1st date of hoisting to 11-04-2018**", instead of "**from 1st date of hosting to 22-03-2018**", which was typing mistake.

Other terms & condition will remain same.


Executive Engineer
(Hub Division Civil),
KW&SB.

Distribution :-

All Concerned.

**OFFICE OF THE EXECUTIVE ENGINEER
HUB DIVISION CIVIL, KW&SB**


B.O.Q.

SUBJECT: REPAIRING / REPLACING DAMAGED PORTION OF 8" DIA & 12" DIA M.S. WATER SUPPLY LINE FEEDING TO KW&SB STAFF COLONY & COOLING SYSTEM OF HUB PUMPING STATION.

ITEM NO.	DESCRIPTION OF ITEMS	QTY	RATE		PER	AMOUNT
			Word	Figure		
Item 1	Jungle clearance (cutting & removing within a distance of 100 feet b) Thick	344900 Sft			%Sft	
Item 2	Excavation for pipe line in trenches and pits in wet soil clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade, cutting joints, holes and disposal of surplus earth within one chain as directed by the Engineer Incharge providing fence guards, lights, flags and temporary crossing for non-vehicular traffic wherever required lift upto 5'-0" and lead upto one chain (a) Lift upto 5'-0"	4476.88 Cft			%0Cft	
Item 3	Full hire charges of pumping set per day inclusive of wages of driver assistant or electric energy plate form require for placing out water found at various depth from trenches i/c the cost of erecting and dismantling after completion of the job. Hire charges of pumping set of upto 10 Hp pumping out water from 10'-0" depth.	92 Days			P/Day	
Item 4	Hire charges of Gas Cutter i/c wages of driver, helper with cartage and all other accessories.	16 Days			P/Day	
Item 5	Hire charges of welding plant.	128 Hours			P/Hour	
Item 6	Welding rod	400 Nos.			Each	
Item 7	Welder	16 Days			P/Day	
Item 8	Beldar	32 Days			P/Day	
Item 9	Earth or mud	31754.60 Cft			%Cft	
Item 10	Carriage of 100 Cft / 5 tons of all materials like stone aggregate, spawl, coal, lime, surkhi etc B.G. Rail fastening points and crossing bridge, girders, pipes, sheets rail, M.S. Bars etc or 150 Cft of timber or 100 mounds of fuel wood by	31754.60				

ITEM NO.	DESCRIPTION OF ITEMS	QTY	RATE		PER	AMOUNT
			Word	Figure		
Item 11	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	4476.88 Cft			%0Cft	
Item 12	Laying earth in 6" layer leveling dressing and watering for compaction etc complete.	31754.60 Cft			%0Cft	
					Total Rs.	
Amount in words ()

I / We hereby quoted the cost of Rs. _____
for execution of the above work and I / We hereby undertaking
to accept all clauses of SPPR, 2010.


Executive Engineer,
(HDC), KWSB.

Signature of Contractor
with Name of Firm & Seal

Address : _____

Contact # _____