

CORRECTED

GOVERNMENT OF SINDH



IRRIGATION DEPARTMENT

MODIFIED

PC-I PROFORMA

INSTALLATION OF 50NOS: NEW TUBEWELLS UNDER DIRECTIVES I/C DEH FAREEDABAD BARANI DISTRICT DADU & RE-BORING OF 13NOS: BORE FAILURE TUBEWELL & RESTORATION OF 70NOS: TUBEWELLS CLOSED DUE TO TRANSFORMERS DEFECT & 48NOS: CLOSED DUE TO 11KVA LINE I/C REHABILITATION OF RUK, GHARHI YASEEN & MASITI PUMPING STATION.

AMOUNT TO RS: 575.752 MILLION

IN

Larkana Drainage Division Larkana

OF

SCARP IRRIGATION PROJECT SUKKUR

OF

IRRIGATION DEVELOPMENT REGION-I HYDERABAD

JANUARY 2015

**PROVINCIAL
IRRIGATION DEPARTMENT**

(Rs. In million)

Gen. Sr. No.	Sector / Sub-sector / Name of Scheme	Location of Scheme / District	Status Date of Approval	Target Date for Completion	Estimated Cost	Actual Expenditure up to June 13	Revised Allocation 2013-14		Estimated Expenditure up to June 14	Theoretical as on 01-07-14	Allocation for 2014-15			PPA	Financial Progress % up to		Financial Progression 2013-14	2014-15	2015-16	2016-17
							Total	PPA			Capital	Revenue	Total		Jan'14	Jan'15				
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19		
1009	Rehabilitation of SCARP Columns, Drains, Left Over Pockets and Allied Structures work in Larkana-Shikarpur Drainage Project and Construction of Karamang wall along EL Sub Drain parallel to Shabdan Jy Mezar Ghari Khanda Box Bhutta.	Larkana / Shikarpur	Up- Approved	June-17	1191.000	0.000	0.000	0.000	0.000	1191.000	5.000	0.000	5.000	0.000	0	0	500.000	686.000		
1010	Installation of 20 Nos. T/Walls under Districts W.D. District Dadu and Kachhlog of 13 Nos. Bore Feeder T/Walls and Restoration of 79 T/Walls closed due to transformer's defect and 48 Nos. closed due to 11 KVA Line including Rehabilitation of Kach Ghazi Yaxson & Masai Pumping Station.	Larkana, Shikarpur, Dadu	Up- Approved	June-17	600.000	0.000	0.000	0.000	0.000	600.000	5.000	0.000	5.000	0.000	0	1	200.000	395.000		
1011	Construction of Sub-Drain (CL) of Fakhroo Main Drain System RD-0 to 12+500 in Doh Lakhia Khasi Meonho & Excavation of Ghar Main Drain from Thorhi Bajar to Sodhar Village & Excavation of Fakhroo Drain System with Damage Structure.	Larkana	Up- Approved	June-17	600.000	0.000	0.000	0.000	0.000	600.000	5.000	0.000	5.000	0.000	0	1	200.000	395.000		
1012	Construction of Pumping Station, 5m Nales at Doh New Darhoon, Doh Mad Ahoon, Taluka Kanliero & Bhira, District Naushahro Feroze.	N. Feroze	Up- Approved	June-17	183.467	0.000	0.000	0.000	0.000	183.467	5.000	0.000	5.000	0.000	0	3	100.000	78.467		

GOVERNMENT OF SINDH



IRRIGATION DEPARTMENT

MODIFIED

PC-I PROFORMA

INSTALLATION OF 100 NOS:

NEW TUBEWELLS

AMOUNT TO RS: 560.60 MILLION

IN

Larkana Drainage Division Larkana

OF

SCARP IRRIGATION PROJECT SUKKUR

OF

IRRIGATION DEVELOPMENT REGION-I HYDERABAD

DECEMBER 2014

**PROVINCIAL
IRRIGATION DEPARTMENT**

(Rs. in million)

Qm. Sr. No.	Sector / Sub-sector / Name of Scheme	Location of Scheme/ District	Status Date of Approval	Target Date for Completion	Estimated Cost	Actual Expenditure upto June, 13	Revised Allocation 2013-14		Estimated Expenditure upto June, 14	Targeted as on 01-07-14	Allocation for 2014-15			FPA	Financial Progress % upto		Financial Projection	
							Total	F.P.A.			Capital	Revenue	Total		Jun'14	Jun'15	2015-16	2016-17
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
1033	Rectification of Nagan Dhoro South Drain from RD-0 to 134, Salsol Branch Drain from RD-0 to 73 and Barboro Branch Drain from RD-0 to 107.0	Thatta	Un-Approved	June-17	650,000	0,000	0,000	0,000	0,000	650,000	5,000	0,000	5,000	0,000	0	1	300,000	345,000
1034	Construction of Surface Drainage Scheme for Doh Albaria, Doh Therkh, Doh Puzakars and Doh Wabdar son, Doh Uplandi Wadh, Taluka Jati including Doh Chah / Jahan Khan, Doh Shahban and Doh Ash Samoon, Taluka Shah Bandar.	Sogawal	Un-Approved	June-17	150,000	0,000	0,000	0,000	0,000	150,000	5,000	0,000	5,000	0,000	0	3	70,000	75,000
1035	Construction of Surface Drain (Kanday Chakki Branch Drain) Sibi Drain II, Kanday Chakki in Structures for Disposal of Water Kanday Chakki Flood Area in K.N. Shah	Dadu	Un-Approved	June-16	82,085	0,000	0,000	0,000	0,000	82,085	5,000	0,000	5,000	0,000	0	6	77,085	0,000
1036	Installation of 100 New Tubewells	Larkana / Shikarpur / Sukkur / Larkana	Un-Approved	June-17	500,000	0,000	0,000	0,000	0,000	500,000	5,000	0,000	5,000	0,000	0	1	200,000	295,000
1037	Rehabilitation / Restoration of Drainage Infrastructure and Construction of Retaining Wall around Larkana City on various Drains including IR, 2K and IR-C Sub Drain of Larkana South System, IR Char Sub Drain and Reconstruction of Structures including VIB, VBC, Water Course X-caps, Inlets, Junction covers etc.	Larkana	Un-Approved	June-17	1,000,000	0,000	0,000	0,000	0,000	1,000,000	5,000	0,000	5,000	0,000	0	1	400,000	595,000



GOVERNMENT OF SINDH
IRRIGATION DEPARTMENT

Karachi dated the March 2015

ORDER

NO.10/2198-SO(PL)/14:- Administrative Approval of the Government of Sindh is hereby accorded in favour to Chief Engineer Irrigation, Development Region in Sindh, Hyderabad, for execution of ADP scheme namely "Installation of 100 New Tubewells" (ADP No.1036, 2014-15) approved at the cost of Rs.560.600 million (Rupees Five Hundred Sixty Million Six Hundred Thousand) only with FEC Nil.

2. The expenditure involved will be debited to the head of account "04-Economic Affair (Cap)042-Agriculture, Food, Irrigation, Forestry and Fishing 0422-Irrigation-042203-Canal Irrigation". The plan period of the scheme is up to the financial year 2015-2016.

3. The scheme has been approved by PDWP in its meeting held on 27-01-2015 at Karachi.

(SYED ZAHEER HYDER SHAH)
SECRETARY TO GOVERNMENT OF SINDH

NO.FD.SO(DEV-II) 7(32) / 2014-15 Karachi dated the 24th March 2015

Copy forwarded to the Accountant General Sindh, Karachi, for information and necessary action.

(ABDUL HAMEED KHASKHELI)
SECTION OFFICER (DEV-II)
FOR SECRETARY TO GOVT: OF SINDH
FINANCE DEPARTMENT

ABDUL HAMEED KHASKHELI
Section Officer (Dev-II)
Government of Sindh
Finance Department
Karachi

Cont'd P/2



GOVERNMENT OF SINDH
IRRIGATION DEPARTMENT

Karachi dated the

March 2015

ORDER

NO.10/2260-SO(PL)/14:- Administrative Approval of the Government of Sindh is hereby accorded in favour to Chief Engineer Irrigation, Development Region in Sindh, Hyderabad, for execution of ADP scheme namely "Installation of 50 Nos. T/Wells under Directives i/c Deh Fareedabad Barani District Dadu and Re-boring of 13 Nos. Bore Failure T/Wells and Restoration of 70 T/Wells closed due to transformers defect and 48 Nos. closed due to 11 KVA Line including Rehabilitation of Ruk Gharhi Yaseen & Masiti Pumping Station" (ADP No.1010, 2014-15) approved at the cost of Rs.575.752 million (Rupees Five Hundred Seventy Five Million Seven Hundred Fifty Two Thousand) only with FEC Nil.

2. The expenditure involved will be debited to the head of account "04-Economic Affair (Cap)042-Agriculture, Food, Irrigation, Forestry and Fishing 0422-Irrigation-042203-Canal Irrigation". The plan period of the scheme is up to the financial year 2016-2017.

3. The scheme has been approved by PDWP in its meeting held on 27-01-2015 at Karachi.

(SYED ZAHEER HYDER SHAH)
SECRETARY TO GOVERNMENT OF SINDH

NO.FD.SO(DEV-II) 7(125)20(14-15) Karachi, dated the 24th March 2015

Copy forwarded to the Accountant General Sindh, Karachi, for information and necessary action.

(ABDUL HAMEED KHASKHELI)
SECTION OFFICER (DEV-II)
FOR SECRETARY TO GOVT: OF SINDH
FINANCE DEPARTMENT

ABDUL HAMEED KHASKHELI
Section Officer (Dev-II)
Government of Sindh
Finance Department
Karachi

Cont'd P/2

Annex 2

OFFICE OF THE EXECUTIVE ENGINEER LARKANA DRAINAGE DIVISION LARKANA.

PROCUREMENT PLAN-2014-15
(Development / Capital)

Serial No. ADP No.	Name of Scheme & Estimated Cost	Amount in PK Rs. Millions									
		Allocate d Funds	Cost of ongoing works (Expenditure already incurred)	Funds Earmarked for ongoing works	Cost of new Works (Component s)	Funds for New Works (C- e)	Nature of Procurement	Method of Procurement	Anticipated / Actual date of Advertisement	Anticipated / Actual Date of Start	Anticipated / Actual Date of Completion
01/1007	Rehabilitation of SCARP Drains & Allied Structures Works in Larkana Shikarpur Drainage Project. Approved cost 800 million.	5.00			800.00	5.00	National Competitive Bidding	Single Stage one envelope	17/3/2015	28/05/2015	December 2015 (18 months)
02/1008	Construction of Retaining Wall along 2R Sub Drain of SKT System from RD-30 to 37 NIP side & construction of Pumping Station @ RD-38 of Mirakhan Main Drain near Dost Ali Bungalow over Waran Canal. Approved cost Rs.178.369 millions	5.00			178.369	5.00	National Competitive Bidding	Single Stage one envelope	18/3/2015	28/05/2015	December 2015 (18 months)
03/1010	Installation of 50 Nos. New Tubewells under Directives i/c Deh Fareedabad Barani District Dadu & Re-boring of 13 Nos. Bore Failure tubewell & Restoration of 70 Nos. Tubewells closed Due to Transformers Defect & 48 No. Closed due to 11 KVA Line i/c Rehabilitation of Ruk, Gharni, Yaseen & Masti Pumping Station. Approved cost Rs.575.752 millions	5.00			575.752	5.00	National Competitive Bidding	Single Stage one envelope	18/3/2015	28/05/2015	December 2015 (18 months)
04/1036	Installation of 100 Nos. New Tubewells in Larkana Drainage Division Larkana. Approved cost Rs.560.60 millions.	5.00			560.60	5.00	National Competitive Bidding	Single Stage one envelope	18/3/2015	28/05/2015	December 2015 (18 months)
05/1037	Rehabilitation/Restoration of Drainage infrastructures & Construction of Retaining wall around Larkana City on various Drains i/c 1R, 2R & 12C Sub Drain of Larkana South System JR Ghar Sub Drain & Reconstruction of Structures i/c VRB's VRC's water Course X-ing Junction culverts etc. Approved cost Rs.800.000 millions.	5.00			560.60	5.00	National Competitive Bidding	Single Stage one envelope	18/3/2015	28/05/2015	December 2015 (18 months)


Executive Engineer
Larkana Drainage Division
Larkana.

BID EVALUATION REPORT

1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No.	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	:-	Construction of Pumping Station & Allied Works i/c Staff Quarter and Generator Room at RD 38 of Miro Khan Main Drain near Dost Ali Bungalow.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	3Nos:
7	Total Bid Received.	:-	2Nos:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Eid Muhammad Brohi & Co.	141442813	1st Lowest	+2.04% Above	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (ammended 2013)
2	Haji Dilmurad Mangal	144254987	2nd Lowest	+4.07% Above	Accepted in Terms	Responsive
3	M/S Ali Dost Buriro	Not Tendered				

Signature of the Members of the Procurement Committee

(Abdul Ghafoor Soomro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)

(Ghulam Mujtaba Dhamrah)
Executive Engineer
North Dadu Drainage Division
Larkana
(Member)

(Abdul Wahab Sahito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)

Rafiq Ahmed Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-1

NIT No: TC/G-55/700
Date of issue of tender
Date of receipt & opening of tender

Date: 18/03/2015.
Date: 10/04/2015.
Date: 10/04/2015.

Name of Work: - Construction of Pumping Station & Allied Works i/c Staff Quarter and Generator Room at RD 38 of Miro Khan Main Drain near Dost Ali Bungalow.

RATES QUOTED BY GOVERNMENT CONTRACTORS

S. No	Item	Quantity	Unit	M/S Eid Muhammad Brohi & Co:		Haji Dilmurad Mangal		M/S All Dost Burro	
				Rate	Amount	Rate	Amount	Rate	Amount
1	Supplying & Installation of PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works	10 Nos.	Each	8795500	87955000	8950000	89500000		
2	Supplying of chain pully 5 tons 20 meters chain.	1No.	Each	49900	49900	65000	65000		Not Tendered
3	Providing & Fixing of Transformer (630KVA) Siemens or equilent i/c all accessories.	2Nos.	Each	4299500	8599000	4450000	8900000		
4	Supplying of 4 core copper wire 37/083 (240 mm).	600 Meters	P Meeter	6450	3870000	7175	4305000		
5	Supplying & Installation of 1No Diesel Generator set (450 to 500 KVA) with all accessories.	1No.	Each	19950000	19950000	20150000	20150000		
Total Part-A Rs:					120423900		122920000		

PART - B Schedule Item							
1	Schedule "B" Rs: 15803694/-	Schedule "B" Rs: 15803694/-	33% Above	5215219	35% Above	5531293	Not Tended
2	Cartage Rs: 2381399/-	Add. Schedule "B" Amount		15803694		15803694	
3	Non Schedule Items Rs: 120423900/-	Non Schedule Items		120423900		122920000	
	Total Estimate Cost Rs: 138608993/-	Bid Amount		141442813		144254987	
		(-) Estimated Cost		138608993		138608993	
		Difference		2833820		5645994	
			$\frac{2833820 \times 100}{138608993}$ Above over the estimate	2.04%	$\frac{5645994 \times 100}{138608993}$ Above over the estimate	4.07%	

The rates quoted by M/S Eid Muhammad Brohi & Co: Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval.

Rafiq Ahmed Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana

Abdul Ghaffar Soomro
Executive Engineer
Larkana Drainage Division
Larkana

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-2

NIT No: TC/G-55/700
Date: 18/03/2015.
Date of issue of tender: 10/04/2015.
Date of receipt & opening of tender: 10/04/2015.

Name of Work: -

Rehabilitation / Installation of New Pumps @ Larkana North (Shahmir), Larkana South (Mashori) & Naudero (Mahota) Pumping Stations.

RATES QUOTED BY GOVERNMENT CONTRACTORS

S. No	Item	Quantity	Unit	M/S Madani Engineering Construction Co:		Amount
				Rate	Amount	
1	Replacement of old KSB Turbine pumps with new KSB pumps, PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works. 2Nos. Pumps @ Naudero (Mahota) 1No. Pump @ Larkana North (Shahmir) & 1No. Pump @ Larkana South (Mashori) Pumping Stations.	4	Each	8800000	35200000	
2	Providing & Fixing of Transformer (400 KVA) Siemens or equivalent i/c all accessories @ Various Pumping Stations	2	Each	3300000	6600000	
3	Supplying of 4 core copper wire 37/083 (240 mm) @ Various Pumping Stations.	200	P Meter	6500	1300000	
4	S/F change over switch 1000 AMP	5	Each	325000	1625000	
5	S/F change over switch 1500 AMP	2	Each	475000	950000	
Total Rs:						45675000

The rates quoted by M/S Madani Engineering Construction Co: Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval.

Rafiq Ahmed
Divisional Accounts Officer
Larkana Drainage Division
Larkana

Abdul Qasim
Executive Engineer
Larkana Drainage Division
Larkana


BID EVALUATION REPORT


1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	:-	Rehabilitation / Installation of New Pumps @ Larkana North (Shahmir), Larkana South (Mashori) & Naudero (Mahota) Pumping Stations.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	1No;
7	Total Bid Received.	:-	1No;
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	45675000	Single Bid	Estimated Rate	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (ammended 2013)

Signature of the Members of the Procurement Committee


(Abdul Ghaffar Soomro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)


(Ghulam Murtaza Dhamrah)
Executive Engineer
North Dadu Drainage Division
Larkana
(Member)


(Abdul Wahab Sahito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)


Rafiq Ahmad Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-3

NIT No: TC/G-55/700
Date of issue of tender
Date of receipt & opening of tender

Date: 18/03/2015.
Date: 10/04/2015.
Date: 10/04/2015.

Name of Work: - Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.

S. No	Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS			
				M/S Madani Engineering Construction Co. Rate	M/S Sher Muhammad Mughari & Co. Rate	Amount	
PART -A Non-Schedule Item							
1	Drilling of bore hole 22" DIA for Tubewell up to depth of 220 Lf.	10500	P Lf	2400	25200000	2410	25305000
2	Furnishing & installation of fiber glass housing casing 14" dia 0.20" thick.	3500	P Rft	5525	19337500	5548	19418000
3	Furnishing & installation of fiber glass reducer 8"X14" dia.	50	Each	37500	1875000	37657	1882850
4	Furnishing & installation of fiber glass stainer 8" dia slot size 0.04"	5850	P Rft	5500	32175000	5523	32309550
5	Furnishing & installation of fiber glass casing blank 8" dia.	500	P Rft	2850	1425000	2862	1431000
6	Furnishing & placing gravel shrouding with annular space as per specification.	22500	P Ch	565	12712500	568	12780000
7	Furnishing & placing gravel shrouding in over drilled hole.	5000	P Ch	565	2825000	568	2840000
8	Providing & Fixing Bail Plug	50	Each	500	25000	500	25000
9	Tubewell Development by Air Lifting Method.	50	Each	125000	6250000	125000	6250000
10	Furnishing & installing Centralizer.	250	Each	2900	725000	3000	750000
11	Further Development and well capacity testing with turbine pump as per specification.	50	Each	112000	5600000	112000	5600000
12	Security Cap 14" dia MS & 3' long 5mm with top cap.	50	Each	16500	825000	17000	850000
13	Furnishing & installation pump type B-12 B/1 saline pump of 1.5 c/s capacity 50" head turbine type with pump setting depth of 40" with column pipe 7" dia internal and column shaft 25mm dia and suction and delivery pipe 7" dia internal all make and installed with 15HP motor of latest model make by Siemens company. i.e all fittings and fixtures discharge head, bowl assembly etc complete i.e testing for discharge. Also furnishing and installing of MCU Siemens make for 20HP motor i.e discharge. Also furnishing and installing of MCU Siemens make for 20HP motor i.e discharge.	50	Each	2050000	102500000	2230000	111500000
14	Internal electrification of pump house and Duty Room.	50	Each	20000	1000000	20000	1000000
15	Furnishing & installing PVC 4core copper 7/054 wire required for 20HP motor between transformer and motor control unit etc, furnishing installing most pipe 2" dia installed over pump room. The rate also includes conductor covered with flexible pipe for connecting motor unit and motor i.e stay wire.	1500	P Rft	960	1440000	950	1425000
16	Making earth connection for electric installation line transformer trussed poles to motor control unit and pump.	50	Each	10000	500000	10000	500000
17	Final acceptance test of equipment with power line or generator.	50	Each	75000	3750000	75000	3750000
Total Rs:					218185000		227616400

PART -B Non-Schedule Item							
1	Construction of Pump House & Duty Room	12/63	P Sit	2250	28716750	2300	29354900
Total Rs:					28716750		29354900
Total Part A & B Rs:					246881750		256971300
PART -C Schedule Item							
1	Schedule "B"	Schedule "B" Rs: 4054669/-		51% Above	2067881	53% Above	2148975
2	Cartage	Rs: 1258465/-	Add: Schedule "B" Amount		4054669		4054669
3	Non Schedule Items	Rs: 246881750/-	Non Schedule Items		246881750		256971300
Total Estimate Cost Rs: 252194884/-			Bid Amount		253004300		263174944
			(-) Estimated Cost		252194884		252194884
			Difference		809416		10980060
				$809416 \times 100 = 0.32\%$		$10980060 \times 100 = 4.35\%$	
				Above over the estimate		Above over the estimate	

The rates quoted by M/S Madani Engineering Construction Co: Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval.

Rafiq Ahmed Malik
 Divisional Accounts Officer
 Larkana Drainage Division
 Larkana

Abdul Qadir Soomro
 Executive Engineer
 Larkana Drainage Division
 Larkana

BID EVALUATION REPORT

1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	:-	Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	2Nos:
7	Total Bid Received.	:-	2Nos:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No. of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	253004300	1st Lowest	+0.32% Above	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (amended 2013)
2	M/S Sher Muhammad Mughari & Co:	263174944	2nd Lowest	+4.35% Above	Accepted in Terms	Responsive

Signature of the Members of the Procurement Committee

(Abdul Ghafoor Soomro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)

(Ghulam Mujtaba Dhamrah)
Executive Engineer
North Dadu Drainage Division
Larkana
(Member)

(Abdul Wahab Sahito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)

Rafiq Ahmed Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-4

NIT No: TC/G-55/700
Date of issue of tender
Date of receipt & opening of tender

Date: 18/03/2015.
Date: 10/04/2015.
Date: 10/04/2015.

Name of Work: - Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.

S. No	Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS	
				M/S Madani Engineering Construction Co. Rate	Amount
PART -A Non-Schedule Item					
1	Drilling of bore hole 22" DIA for Tubewell up to depth of 220 Lft.	10500	P Lft	2400	25200000
2	Furnishing & installation of fiber glass housing casing 14" dia 0.20" thick.	3500	P Rft	5525	19337500
3	Furnishing & installation of fiber glass reducer 8"X14" dia	50	Each	37500	1875000
4	Furnishing & installation of fiber glass stainer 8" dia slot size 0.04"	5850	P Rft	5500	32175000
5	Furnishing & installation of fiber glass casing blank 8" dia	500	P Rft	2850	1425000
6	Furnishing & placing gravel shrouding with annular space as per specification.	22500	P Ch	565	12712500
7	Furnishing & placing gravel shrouding in over drilled hole.	5000	P Ch	565	2825000
8	Providing & Fixing Bail Plug.	50	Each	500	25000
9	Tubewell Development by Air Lifting Method	50	Each	125000	6250000
10	Furnishing & installing Centralizer.	250	Each	2900	725000
11	Further Development and well capacity testing with turbine pump as per specification.	50	Each	112000	5600000
12	Security Cap 14" dia MS & 3" long 5mm with top cap	50	Each	16500	825000
13	Furnishing & installation pump type B-12 B/1 saline pump of 1.5 c/s capacity 507 head turbine type with pump setting depth of 40' with column pipe 7" dia internal and column shaft 25mm dia and suction and delivery pipe 7" dia internal all make and installed with 15HP motor of latest model make by Siemens company. I.e all fittings and fixtures discharge head, bowl assembly etc complete I.e testing for discharge. Also furnishing and installing of MCU Siemens make for 20HP motor I.e	50	Each	2050000	102500000
14	Internal electrification of pump house and Duty Room.	50	Each	20000	1000000
15	Furnishing & installing PVC 4core copper 7/064 wire required for 20HP motor between transformer and motor control unit etc, furnishing installing most pipe 2" dia installed over pump room. The rate also includes conductor covered with flexible pipe for connecting motor unit and motor I.e stay wire.	1500	P Rft	960	1440000
16	Making earth connection for electric installation line transformer trussed poles to motor control unit and pump.	50	Each	10000	500000
17	Final acceptance test of equipment with power line or generator.	50	Each	75000	3750000
Total Rs:					218165000

PART -B Non-Schedule Item					
1	Construction of Pump House & Duty Room	12763	P. Sit	2250	28716750
	Total Rs:				28716750
	Total Part A & B Rs:				246881750
	PART -C Schedule Item				
1	Schedule "B" Rs: 4054669/-	Schedule "B" Rs: 4054669/-		51% Above	2067881
2	Cartage Rs: 1258465/-	Add: Schedule "B" Amount			4054669
3	Non Schedule Items Rs: 246881750/-	Non Schedule Items			246881750
	Total Estimate Cost Rs: 252194884/-	Bid Amount			253004300
		(-) Estimated Cost			252194884
		Difference			809416
				$\frac{809416 \times 100}{252194884}$	0.32%
				Above over the estimate	

The rates quoted by M/S Madani Engineering Construction Co: Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval.

Rafiq Ahmed Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana

Abdul Qayyum Bux
Executive Engineer
Larkana Drainage Division
Larkana


BID EVALUATION REPORT


1	Name of Procuring Agency	: -	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	: -	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	: -	Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.
4	Method Procurement.	: -	Single Stage One Envelope Bidding Procedure
5	Tender Published.	: -	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	: -	1No:
7	Total Bid Received.	: -	1No:
8	Technical Bid opening date (If Applicable)	: -	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	: -	Not Applicable
10	Bid (s) Rejected (If Applicable)	: -	
11	Financial Bid opening date.	: -	10/4/2015
12	Bid Evaluation Report.	: -	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	253004300	Single Bid	+0.32% Above	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (ammended 2013)

Signature of the Members of the Procurement Committee


 (Abdul Ghafur Soomro)
 Executive Engineer
 Larkana Drainage Division
 Larkana
 (Chairman)


 (Ghulam Mujtaba Dhamrah)
 Executive Engineer
 North Dadu Drainage Division
 Larkana
 (Member)


 (Abdul Wahab Sahito)
 Executive Engineer
 Public Health Engineering
 Division-1 Larkana
 (Member)



 Rafiq Ahmed Malik
 Divisional Accounts Officer
 Larkana Drainage Division
 Larkana


BID EVALUATION REPORT


1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	:-	Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	1No:
7	Total Bid Received.	:-	1No:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	


S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	253004300	Single Bid	+0.32% Above	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (ammended 2013)

Signature of the Members of the Procurement Committee


(Abdul Ghafoor Soomro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)


(Ghulam Mujtaba Dhamrah)
Executive Engineer
North Dadu Drainage Division
Larkana
(Member)


(Abdul Wahab Sahito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)


Rafiq Ahmed Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-5

NIT No: TC/G-55/700

Date of issue of tender

Date of receipt & opening of tender

Date: 18/03/2015.

Date: 10/04/2015.

Date: 10/04/2015.

Name of Work: - Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.

S. No	Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS	
				M/S Madani Engineering Construction Co: Rate	Amount
PART - A Non-Schedule Item					
1	Drilling of bore hole 22" DIA for Tubewell up to depth of 220 Lt	10500	P Lt	2400	25200000
2	Furnishing & installation of fiber glass housing casing 14" dia 0.20" thick.	3500	P RH	5525	19337500
3	Furnishing & installation of fiber glass reducer 8"X14" dia.	50	Each	37500	1875000
4	Furnishing & installation of fiber glass stainer 8" dia slot size 0.04"	5850	P RH	5500	32175000
5	Furnishing & installation of fiber glass casing blank 8" dia	500	P RH	2850	1425000
6	Furnishing & placing gravel shrouding with annular space as per specification.	22500	P CH	565	12712500
7	Furnishing & placing gravel shrouding in over drilled hole	5000	P CH	565	2825000
8	Providing & Fixing Ball Plug	50	Each	500	25000
9	Tubewell Development by Air Lifting Method.	50	Each	125000	6250000
10	Furnishing & installing Centralizer	250	Each	2900	725000
11	Further Development and well capacity testing with turbine pump as per specification.	50	Each	112000	5600000
12	Security Cap 14" dia MS & 3' long 5mm with top cap.	50	Each	16500	825000
13	Furnishing & installation pump type B-12 B/1 saline pump of 1.5 c/s capacity 50' head turbine type with pump setting depth of 40' with column pipe 7" dia internal and column shaft 25mm dia and suction and delivery pipe 7" dia internal all make and installed with 15HP motor of latest model make by Siemens company. i.e all fittings and fixtures discharge head, bowl assembly etc complete i.e testing for discharge. Also furnishing and installing of MCU Siemens make for 20HP motor i.e	50	Each	2050000	102500000
14	Internal electrification of pump house and Duty Room.	50	Each	20000	1000000
15	Furnishing & installing PVC 4core copper 7/064 wire required for 20HP motor between transformer and motor control unit etc. furnishing installing most pipe 2" dia installed over pump room. The rate also includes conductor covered with flexible pipe for connecting motor unit and motor i.e stay wire.	1500	P RH	960	1440000
16	Making earth connection for electric installation line transformer trussed poles to motor control unit and pump.	50	Each	10000	500000
17	Final acceptance test of equipment with power line or generator	50	Each	75000	3750000
Total Rs:					218165000

PART -B Non-Schedule Item					
1	Construction of Pump House & Duty Room	12763	P. SH	2250	28716750
	Total Rs:				28716750
	Total Part A & B Rs:				246881750
	PART -C Schedule Item				
1	Schedule "B" Rs. 4054669/-	Schedule "B" Rs. 4054669/-		51% Above	2067881
2	Cartage Rs. 1258465/-	Add. Schedule "B" Amount			4054669
3	Non Schedule Items Rs. 246881750/-	Non Schedule Items			246881750
	Total Estimate Cost Rs: 252194884/-	Bid Amount			253004300
		(-) Estimated Cost			252194884
		Difference			809416
				$\frac{809416 \times 100}{252194884} =$	0.32%
				Above over the estimate	

The rates quoted by M/S Madani Engineering Construction Co: Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval.

Rafiq Ahmed Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana

Abdul Qayyum Bano
Executive Engineer
Larkana Drainage Division
Larkana

BID EVALUATION REPORT

1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	:-	Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	1No:
7	Total Bid Received.	:-	1No:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	253004300	Single Bid	+0.32% Above	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (amended 2013)

Signature of the Members of the Procurement Committee

(Abdul Ghafoor Soomro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)

(Ghulam Mujtaba Dhamrah)
Executive Engineer
North Dadu Drainage Division
Larkana
(Member)

(Abdul Wahab Sahito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)


Rafiq Ahmad Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana


BID EVALUATION REPORT


1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	:-	Installation of New Pumps @ Ruk, Gharhi Yaseen & Masiti Pumping Stations in Shikarpur Drainage Division Shikarpur.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	2Nos:
7	Total Bid Received.	:-	2Nos:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	


S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	203100000	1st Lowest	Estimated Rate	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (ammended 2013)
2	M/S Sher Muhammad Mughari	208650000	2nd Lowest	Estimated Rate	Accepted in Terms	Responsive

Signature of the Members of the Procurement Committee


(Abdul Ghafoor Soomro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)


(Ghulam Mujtaba Dhamrah)
Executive Engineer
North Dadu Drainage Division
Larkana
(Member)


(Abdul Wahab Sahito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)


Rafiq Ahmed Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-6

NIT No: TC/G-55/700
Date of issue of tender
Date of receipt & opening of tender

Date: 18/03/2015.
Date: 10/04/2015.
Date: 10/04/2015.


Name of Work: -

Installation of New Pumps @ Ruk, Gharhi Yaseen & Masiti Pumping Stations in Shikarpur Drainage Division Shikarpur.

S. No	Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS		Rate	Amount
				M/S Madant Engineering Construction Co.	M/S Sher Muhammad Mughari		
				Rate	Amount	Rate	Amount
A							
Installation of New Pumps @ Ruk Pumping Station in Shikarpur Drainage Division Shikarpur (Mechanical Work).							
1	Supplying & Installation of PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works	10	Each	8800000	88000000	9020000	90200000
2	Supplying of chain pully 5 tons 20 meters chain	1	Each	50000	50000	50000	50000
3	Providing & Fixing of Transformer (630KVA) Siemens or equilent i/c all accessories.	2	Each	4300000	8600000	4400000	8800000
4	Supplying of 4 core copper wire 37/083 (240 mm).	600	P Meeter	6500	3900000	7000	4200000
				Total Rs:-		100550000	
B							
Installation of New Pumps @ Gharhi Yaseen Pumping Station in Shikarpur Drainage Division Shikarpur (Mechanical Work).							
1	Supplying & Installation of PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works	6	Each	8800000	52800000	9020000	54120000
2	Supplying of chain pully 5 tons 20 meters chain.	1	Each	50000	50000	50000	50000
3	Providing & Fixing of Transformer (630KVA) Siemens or equilent i/c all accessories.	1	Each	4300000	4300000	4400000	4400000
4	Supplying of 4 core copper wire 37/083 (240 mm).	500	P Meeter	6500	3250000	7000	3500000
				Total Rs:-		604000000	
				Total Rs:-		620700000	

C Installation of New Pumps @ Masiti Pumping Station in Shikarpur Drainage Division Shikarpur (Mechanical Work).							
1	Supplying & Installation of PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories l/c civil works	4	Each	8900000	35200000	9020000	36080000
2	Supplying of chain pully 5 tons 20 meters chain	1	Each	50000	50000	50000	50000
3	Providing & Fixing of Transformer (630KVA) Siemens or equilent l/c all accessories	1	Each	4300000	4300000	4400000	4400000
4	Supplying of 4 core copper wire 37/083 (240 mm).	400	P Meter	6500	2600000	7000	2600000
Total Rs:-					42150000		43330000
G: Total A + B + C Rs:					203100000		208650000

The rates quoted by M/S Madani Engineering Construction Co: Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval.


Rafiq Ahmed Malik
 Divisional Accounts Officer
 Larkana Drainage Division
 Larkana


Abdul Wahid Saeed
 Director Engineer
 Larkana Drainage Division
 Larkana


"Annexure "B")
NIT No.TC/G-55/700,
Dated 18-03-2015


Justification for accepting the work "Rehabilitation/Installation of New Pumps @ Larkana North (Shahmir) Larkana South (Mashori) & Naudero (Mahota) Pumping Station"

Sr. No.	Item	Rate Quoted by Contractor M/S Madni	Market Quotation Rates
01.	Replacement of old KSB Turbine Pumps with new KSB pumps PNW 500-470 Turbular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens) copper cable 37/063 (4 core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works, 2 Nos. Pumps @ Naudero (Mahota) 1 No. Pump @ Larkana North (Shahmir) & 1 No. Pump @ Larkana South (Mashori) Pumping Stations.	8800000/- each	Rates quoted by contractor M/S Eid Muhammad Brohi & Co: under NIT No: --- -- is Rs: 8795500/-

Certified that above prices quoted by M/S Madni Engineering Construction Company under serial No: 2 of this office NIT No: TC/G-55/700 dated: 18/03/2015 as compared with the lowest prices quoted by M/S Eid Muhammad Brohi & Co: being 1st lowest bid comparatively accepted are nearly same as quoted by M/S Madni Engineering construction Co: for similar work / item at S.No: 2 works of same NIT and are accepted in terms of Rule 48 of SPP Rules 2010 (amended 2013) being single bid.


Ghulam Mujtaba Dhamrah
Executive Engineer
North Dadu Drainage Division
Larkana
Member


Abdul Wahab Khoso
Executive Engineer
Public Health Engineering
Division Larkana
Member


Abdul Ghafoor Soomro
Executive Engineer
Larkana Drainage Division
Larkana
Chairman

Justification for accepting the work "Installation of 50 Nos. New Tubewells of 1.5 C/S Construction of Pumps House, Duty Room & Construction of Pacca Link Water Courses / Disposal Channel & discharge Box in Larkana Drainage Division Larkana"

Sr. No.	Item	Rate Quoted by Contractor M/S Madni	Market Quotation Rates
01.	Drilling of bore hole 22" dia for Tubewell up to depth of 220 Lft	2400 Per Lft	
02.	Furnishing & Installation of fiber glass housing casing 14" dia 0.20" thick	5525 Per Rft	
03.	Furnishing & Installation of fiber glass reducer 8"x14" dia	37500 Each	
04.	Furnishing & Installation of fiber glass stainer 8" dia slot size 0.04"	5500 Per Rft	
05.	Furnishing & Installation of fiber glass casing blank 8" dia	2850 Per Rft	
06.	Furnishing & placing gravet shrouding with annular space as per specification	565 Per Cft	
07.	Furnishing & placing gravet shrouding in over drilling hole	565 per Cft	
08.	Providing & Fixing Bail Plug	500 Each	
09.	Tubewell Development by Air Lifting Method	125000 Each	
10.	Furnishing & Installing Centrallizer	2900 Each	
11.	Further Development and well capacity testing with turbine pump as per specification	112000 Each	
12.	Security Cap 14" dia MS & 3' long 5mm with top cap	16500 Each	
13.	Furnishing & Installation of Pump type B-12 B/1 saline pump of 1.5 c/s capacity 50' head turbine type with pump setting depth of 40' with column pipe 7" dia internal and column shaft 25mm dia and suction and delivery pipe 7" dia internal all make and installed with 15HP motor of latest model make by Siemens company, i.e all fittings and fixtures discharge head bowl assembly etc complete i.e testing for discharge. Also furnishing and installing of MCU Siemens or equivalent make for 20HP motor.	2050000 Each	
14.	Internal electrification of pump house and Duty Room	20000 Job	
15.	Furnishing & installing PVC 4 core copper wire 7/064	960 Per Rft	
16.	Making earth connection for electric installation	10000 Each	
17.	Final acceptance test of equipment with power line or generator.	75000 Each	

Certified that for similar works under serial No: 3 the rates quoted by M/S Madni Engineering Construction Company found lowest comparatively and for package No: 4 has been accepted in term of Rule 48 of SPP Rule 2010 amended 2013 being single.

Ghulam Mujtaba Dhamrah
Executive Engineer
North Dadu Drainage Division
Larkana
Member

Abdul Wahab Khoso
Executive Engineer
Public Health Engineering
Division Larkana
Member

Abdul Ghafoor Soomro
Executive Engineer
Larkana Drainage Division
Larkana
Chairman

Amended - c

OFFICE OF THE CHIEF ENGINEER IRRIGATION DEVELOPMENT REGION-1 HYDERABAD

No.CEI/DEV-I/WB/965
Hyderabad Dated: 13/3/2015
Phone # 022-9200275
Fax # 022-9200271

- READ: - Secretary to Government of Sindh, Irrigation Department Karachi letter No.11/19-SO (PL)/2013-14, dated 08-10-2013 regarding Authorization to Notify the Procurement Committee under SPP Rules 2010.
- READ: - Secretary to Government of Sindh, Irrigation Department Karachi letter No.11/19-SO (PL)/2013-14, dated 13-12-2013 regarding Authorization to nominate Co-opt Member of the Procurement Committee under SPP Rules 2010.

NOTIFICATION.

With the approval of Competent Authority and supersession of this office Notification No.CEI/DEV/WB/202, dated 16-01-2015, Procurement Committee Comprising of following Officers is hereby reconstituted for procurement of goods, works in the office of Executive Engineer, Larkana Drainage Division Larkana for the year 2015.

- | | |
|---|-------------------------|
| 1. Mr. Abdul Ghafoor Soomro,
Executive Engineer,
Larkana Drainage Division Larkana | Chairman |
| 2. Mr. Ghulam Mujtaba Dhamrah,
Executive Engineer,
North Dadu Drainage Division,
Larkana. | Member/Secretary |
| 3. Mr. Abdul Wahab Shito,
Executive Engineer,
Public Health Engineering,
Division No.1 Larkana. | Member |

The Divisional Accounts Officer, Larkana Drainage Division Larkana is hereby nominated as Co-opt Member to assist the committee.

T.O.R

- i) Preparing Bidding Documents.
- ii) Carrying out Technical as well as Financial Evaluation of the Bids.
- iii) Preparing Evaluation Report as provided in Rule 45 of SPP.
- iv) Making recommendation for the award of contract to the Competent Authority.
- v) Perform any other function ancillary and incidental to the above.

(DHANO MAL)
CHIEF ENGINEER
Irrigation Development Region-1
Hyderabad

CCto:-

- 1/- The Secretary, Irrigation Department, Government of Sindh Karachi with reference to letter No. cited above (Attention Section Officer (Planning)).
- 2/- The Managing Director Sindh Public Procurement Regulatory Authority Karachi with the request to up hoist the Notification on SPPRA website.
- 3/- The Project Director Scarp Sukkur with reference to letter No. PD/SS/AB/NIT/2014-15/611 Dated 12-03-2015.
- 4/- The Executive Engineer, Larkana Drainage Division Larkana
- 5/- Mr. Abdul Wahab Sahito, Executive Engineer, Public Health Engineering Division 1 Larkana
- 6/- Mr. Ghulam Mujtaba Dhamrah Executive Engineer, North Dadu Drainage Division Larkana.

(DHANO MAL)
CHIEF ENGINEER
Irrigation Development Region-1
Hyderabad

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Annexure - D

Package-3

Name of Work: - Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water

Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.


NIT No: TC/G-55/700
Date of issue of tender
Date of receipt & opening of tender

Date: 18/03/2015.
Date: 10/04/2015.
Date: 10/04/2015.

S. No	Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS			
				M/S Madani Engineering Construction Co: Rate	Amount	M/S Sher Muhammad Mughari & Co: Rate	Amount
PART -A Non-Schedule Item							
1	Drilling of bore hole 22" DIA for Tubewell up to depth of 220 Lt.	10500	P Lt	2400	25200000	2410	25305000
2	Furnishing & installation of fiber glass housing casing 14" dia 0.20" thick.	3500	P Rft	5525	19337500	5548	19418000
3	Furnishing & installation of fiber glass reducer 8"X14" dia.	50	Each	37500	1875000	37657	1882850
4	Furnishing & installation of fiber glass stainer 8" dia slot size 0.04".	5850	P Rft	5500	32175000	5523	32309550
5	Furnishing & installation of fiber glass casing blank 8" dia.	500	P Rft	2850	1425000	2862	1431000
6	Furnishing & placing gravel shrouding with annular space as per specification.	22500	P Cft	565	12712500	568	12780000
7	Furnishing & placing gravel shrouding in over drilled hole.	5000	P Cft	565	2825000	568	2840000
8	Providing & Fixing Bail Plug.	50	Each	500	25000	500	25000
9	Tubewell Development by Air Lifting Method.	50	Each	125000	6250000	125000	6250000
10	Furnishing & installing Centralizer.	250	Each	2900	725000	3000	750000
11	Further Development and well capacity testing with turbine pump as per specification.	50	Each	112000	5600000	112000	5600000
12	Security Cap 14" dia MS & 3' long 5mm with top cap.	50	Each	16500	825000	17000	850000
13	Furnishing & installation pump type B-12 B/1 saline pump of 1.5 c/s capacity 50" head turbine type with pump setting depth of 40" with column pipe 7" dia internal and column shaft 25mm dia and suction and delivery pipe 7" dia internal all make and installed with 15HP motor of latest model make by Siemens company. i.e all fittings and fixtures discharge head, bowl assembly etc complete i.e testing for discharge. Also furnishing and installing of MCU Siemens make for 20HP motor i.e	50	Each	2050000	102500000	2230000	111500000
14	Internal electrification of pump house and Duty Room.	50	Each	20000	1000000	20000	1000000
15	Furnishing & installing PVC 4core copper 7/064 wire required for 20HP motor between transformer and motor control unit etc. furnishing installing most pipe 2" dia installed over pump room. The rate also includes conductor covered with flexible pipe for connecting motor unit and motor i.e stay wire.	1500	P Rft	960	1440000	950	1425000
16	Making earth connection for electric installation line transformer trussed poles to motor control unit and pump.	50	Each	10000	500000	10000	500000
17	Final acceptance test of equipment with power line or generator.	50	Each	75000	3750000	75000	3750000
Total Rs:					218165000		227616400

PART -B Non-Schedule Item							
1	Construction of Pump House & Duty Room	12763	P. Sit	2250	28716750	2300	29354900
	Total Rs:				28716750		29354900
	Total Part A & B Rs:				245881750		256971300
PART -C Schedule Item							
1	Schedule "B"						
	Rs: 4054669/-			51% Above	2067881	53% Above	2148975
2	Cartage				4054669		4054669
	Rs: 1258465/-						
3	Non Schedule Items				246981750		256971300
	Rs: 246981750/-						
	Total Estimate Cost Rs: 252194884/-						
					Bid Amount		253004300
					(-) Estimated Cost		252194884
					Difference		809416
					$809416/100 = 0.32\%$		$10980060/100 = 4.35\%$
					Above over the estimate		Above over the estimate

The rates quoted by MIS Madani Engineering Construction Co: Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval.

(Abdul Ghafoor) 
 Executive Engineer
 Larkana Drainage Division
 Larkana
 (Chairman)

(Ghulam Mustafa Dhamrah) 
 Executive Engineer
 North Drainage Division
 Larkana
 (Member)

(Abdul Wahab Shahid) 
 Executive Engineer
 Public Health Engineering
 Division-1 Larkana
 (Member)

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Annexure - D

Package-4

NIT No: TC/G-55/700
Date of issue of tender
Date of receipt & opening of tender

Date: 18/03/2015.
Date: 10/04/2015.
Date: 10/04/2015.

Name of Work: - Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.

S. No	Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS	
				M/S Madani Engineering Construction Co. Rate	Amount
PART A Non-Schedule Item					
1	Drilling of bore hole 22" DIA for Tubewell up to depth of 220 Lft.	10500	P.Lft	2400	25200000
2	Furnishing & installation of fiber glass housing casing 14" dia 0.20" thick.	3500	P.Rft	5525	19337500
3	Furnishing & installation of fiber glass reducer 8"X14" dia	50	Each	37500	1875000
4	Furnishing & installation of fiber glass stainer 8" dia slot size 0.04"	5850	P.Rft	5500	32175000
5	Furnishing & installation of fiber glass casing blank 8" dia.	500	P.Rft	2850	1425000
6	Furnishing & placing gravel shrouding with annular space as per specification.	22500	P.Ct	565	12712500
7	Furnishing & placing gravel shrouding in over drilled hole.	5000	P.Ct	565	2825000
8	Providing & Fixing Ball Plug	50	Each	500	25000
9	Tubewell Development by Air Lifting Method.	50	Each	125000	6250000
10	Furnishing & installing Centralizer.	250	Each	2900	725000
11	Further Development and well capacity testing with turbine pump as per specification.	50	Each	112000	5600000
12	Security Cap 14" dia MS & 3' long 5mm with top cap.	50	Each	16500	825000
13	Furnishing & installation pump type B-12 B/1 saline pump of 1.5 c/s capacity 50" head turbine type with pump setting depth of 40" with column pipe 7" dia internal and column shaft 25mm dia and suction and delivery pipe 7" dia internal all make and installed with 15HP motor of latest model make by Siemens company, i.e all fittings and fixtures discharge head, bowl assembly etc complete i.e testing for discharge. Also furnishing and installing of MCU Siemens make for 20HP motor i.e internal electrification of pump house and Duty Room.	50	Each	20000	1000000
14	Furnishing & installing PVC 4core copper 7/064 wire required for 20HP motor between transformer and motor control unit etc. furnishing installing most pipe 2" dia installed over pump room. The rate also includes conductor covered with flexible pipe for connecting motor unit and motor i.e stay wire.	1500	P.Rft	990	1440000
15	Making earth connection for electric installation line transformer trussed poles to motor control unit and pump.	50	Each	10000	500000
16	Final acceptance test of equipment with power line of generator.	50	Each	75000	3750000
Total Rs:					218165000

PART -B Non-Schedule Item		PART -C Schedule Item	
1	Construction of Pump House & Duty Room	12763	P. Sft 2250
Total Rs:			28716750
Total Part A & B Rs:			246881750
1	Schedule "B" Rs: 4054669/-	Schedule "B" Rs: 4054669/-	51% Above 2067881
2	Cartage Rs. 1258465/-	Add. Schedule "B" Amount	4054669
3	Non Schedule Items Rs. 246881750/-	Non Schedule Items	246881750
Total Estimate Cost Rs: 252194884/-		Bid Amount	253004300
		(-) Estimated Cost Difference	252194884
			809416
			$809416 \times 100 = 0.32\%$
			252194884
			Above over the estimate

The rates quoted by **M/S Madani Engineering Construction Co: Government Contractor** encircled in red have been found lowest are reasonable hence recommended for approval.

(Abdul Ghafoor Soorro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)

(Ghulam Mujib Dhamrah)
Executive Engineer
North Dad/ Drainage Division
Larkana
(Member)

(Abdul Wahab Sarito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-5

NIT No: TC/G-55/700
Date of issue of tender
Date of receipt & opening of tender

Date: 18/03/2015.
Date: 10/04/2015.
Date: 10/04/2015.

Name of Work: - Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.

S. No	Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS	
				M/S Madani Engineering Construction Co. Rate	Amount
PART - A Non-Schedule Item					
1	Drilling of bore hole 22" DIA for Tubewell up to depth of 220 Lt.	10500	P Lt	2400	25200000
2	Furnishing & installation of fiber glass housing casing 14" dia 0.20" thick.	3500	P Rft	5525	19337500
3	Furnishing & installation of fiber glass reducer 8" X 14" dia	50	Each	37500	1875000
4	Furnishing & installation of fiber glass stainer 8" dia slot size 0.04"	5850	P Rft	5500	32175000
5	Furnishing & installation of fiber glass casing blank 8" dia	500	P Rft	2850	1425000
6	Furnishing & placing gravel shrouding with annular space as per specification.	22500	P Ct	565	12712500
7	Furnishing & placing gravel shrouding in over drilled hole	5000	P Ct	565	2825000
8	Providing & Fixing Bail Plug	50	Each	500	25000
9	Tubewell Development by Air Lifting Method	50	Each	125000	6250000
10	Furnishing & installing Centralizer	250	Each	2900	725000
11	Further Development and well capacity testing with turbine pump as per specification	50	Each	112000	5600000
12	Security Cap 14" dia MS & 3' long 5mm with top cap	50	Each	16500	825000
13	Furnishing & installation pump type B-12 B/1 saline pump of 1.5 c/s capacity 50" head turbine type with pump setting depth of 40" with column pipe 7" dia internal and column shaft 25mm dia and suction and delivery pipe 7" dia internal all make and installed with 15HP motor of latest model make by Siemens company. i.e all fittings and fixtures discharge head, bowl assembly etc complete i.e testing for discharge. Also furnishing and installing of MCU Siemens make for 20HP motor i.e	50	Each	2050000	102500000
14	Internal electrification of pump house and Duty Room	50	Each	20000	1000000
15	Furnishing & installing PVC 4core copper 7/064 wire required for 20HP motor between transformer and motor control unit etc. furnishing installing most pipe 2" dia installed over pump room. The rate also includes conductor covered with flexible pipe for connecting motor unit and motor i.e stay wire	1500	P Rft	960	1440000
16	Making earth connection for electric installation, line transformer trussed poles to motor control unit and pump	50	Each	10000	500000
17	Final acceptance test of equipment with power line or generator	50	Each	75000	3750000
Total Rs.:					218165000

Answer - 1)

PART -B Non-Schedule Item					
1	Construction of Pump House & Duty Room	12763	P Sh	2250	28716750
Total Rs:					28716750
Total Part A & B Rs:					246881750
PART -C Schedule Item					
1	Schedule "B" Rs: 4054669/-	Schedule "B" Rs: 4054669/-		51% Above	2067881
2	Cartage Rs: 1258485/-	Add: Schedule "B" Amount			4054669
3	Non Schedule Items Rs: 246881750/-	Non Schedule Items			246881750
Total Estimate Cost Rs: 252194884/-		Bid Amount			253004300
		(-) Estimated Cost			252194884
		Difference			809416
				809416x100 = 252194884	0.32%
				Above over the estimate	

The rates quoted by M/S Madani Engineering Construction Co: Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval

(Abdul Ghafoor Soomro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)

(Ghulam Mujtaba Dhamrah)
Executive Engineer
North Dard Drainage Division
Larkana
(Member)

(Abdul Wahab Saito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)

OFFICE OF THE EXECUTIVE ENGINEER LARKANA DRAINAGE DIVISION
LARKANA



☎: 074-9410081
Fax #: 074-9410079

No: TC/G-55/ **887** /of 2015.
Larkana Dated: **10 / 04 / 2015.**

NIT NR: TC / G-55 / 700 of 2015 dated: 18 / 03 / 2015

Method & Procedure of Procurement: - National Competitive Bidding
(Single Stage & Single Envelope)

MINUTES OF BID OPENING MEETING

A Meeting of Procurement Committee of this Division was held on 10/04/2015 for opening bid received in respect of subject NIT till the dead lines of submission. The meeting was attended by the following members of Procurement Committee and representative of bidders (Attendance sheet in enclosed).

01)	Abdul Ghafoor Soomro	Chairman
02)	Ghulam Mujtaba Dhamrah	Member
03)	Abdul Wahab Sahito	Member

The following bidders submitted their bid till the dead line of submission: -

- 01) M/S Eid Muhammad Brohi & Co:
- 02) Haji Dilmurad Mangal
- 03) M/S Madani Engineering Construction Co:
- 04) M/S Sher Muhammad Mughari


The bids were opened @ 4.00 P.M in presence of above mentioned participants & the rate quoted by bidders were read aloud & encircled by Chairman of the Procurement Committee. All Members of Procurement Committee signed each & every page of Financial Proposal / Bid. The bid do not contain ant over writing or cutting.


Following in the details of bid announced.


S.#	Name of Bidder	Offered Price	Amount Bid Security	Pay Order / Call Deposit Date
Package – 1				
1	M/S Eid Muhammad Brohi & Co:	141442813	3000000	First Women B. Larkana FWDC No: 0345331 dated: 10/4/2015
	Haji Dilmurad Mangal	144254987	3000000	First Women B. Larkana FWDC No: 0345333 dated: 10/4/2015
	M/S Ali Dost Buriro	Not Tendered		
Package – 2				
1	M/S Madani Engineering Construction Co:	45675000	969456	U.B.L Hyderabad SD No: 3066412 dated: 10/4/2015
Package – 3				
1	M/S Madani Engineering Construction Co:	253004300	5062601	U.B.L Hyderabad SD No: 3066413 dated: 10/4/2015
2	M/S Sher Muhammad Mughari & Co:	263174944	5280000	U.B.L Hyderabad SD No: 3066417 dt: 10/4/2015
Package – 4				
1	M/S Madani Engineering Construction Co:	253004300	5062642	U.B.L Hyderabad SD No: 3066414 dated: 10/4/2015
Package – 5				
1	M/S Madani Engineering Construction Co:	253004300	5062601	U.B.L Hyderabad SD No: 3066415 dated: 10/4/2015
Package – 6				
1	M/S Madani Engineering Construction Co:	203100000	4069800	U.B.L Hyderabad SD No: 3066416 dated: 10/4/2015
2	M/S Sher Muhammad Mughari & Co:	208650000	4175000	U.B.L Hyderabad SD No: 3066418 dt: 10/4/2015

The committee shall examine all the bids as per criteria provided in bidding documents, arithmetical checks and verify the documents & bid security submitted by bidders.

The meeting ended with the vote of thanks to and from the chairs.


(Abdul Ghaffar Soomro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)


(Ghulam Mujtaba Dhamrah)
Executive Engineer
North Dadu Drainage Division
Larkana
(Member)



(Abdul Wahab Sahito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)

BID EVALUATION REPORT


1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015
3	Tender Description / Name of work / Item	:-	Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.
4	Method Procurement:	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published:	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	2Nos:
7	Total Bid Received:	:-	2Nos:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date:	:-	10/4/2015
12	Bid Evaluation Report:	:-	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	253004300	1st Lowest	+0.32% Above	Accepted in Terms	Being 1st lowest bid recommended for award of contract.
2	M/S Sher Muhammad Mughari & Co:	263174944	2nd Lowest	+4.35% Above	Accepted in Terms	Responsive

Signature of the Members of the Procurement Committee


 (Abdul Ghaffar Soomro)
 Executive Engineer
 Larkana Drainage Division
 Larkana
 (Chairman)


 (Ghulam Mujtaba Dhamrah)
 Executive Engineer
 North Dadu Drainage Division
 Larkana
 (Member)



 (Abdul Wahab Sahito)
 Executive Engineer
 Public Health Engineering
 Division-1 Larkana
 (Member)


BID EVALUATION REPORT


1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	:-	Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	1No:
7	Total Bid Received.	:-	1No:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	253004300	Single Bid	+0.32% Above	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (amended 2013)

Signature of the Members of the Procurement Committee


 (Abdul Ghaffoor Soomro)
 Executive Engineer
 Larkana Drainage Division
 Larkana
 (Chairman)


 (Ghulam Mutaba Dhamrah)
 Executive Engineer
 North Dadu Drainage Division
 Larkana
 (Member)



 (Abdul Wahab Sahito)
 Executive Engineer
 Public Health Engineering
 Division-1 Larkana
 (Member)


BID EVALUATION REPORT


1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015
3	Tender Description / Name of work / Item	:-	Installation of 50 Nos: New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses / Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	1No:
7	Total Bid Received.	:-	1No:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	253004300	Single Bid	+0.32% Above	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (ammended 2013)

Signature of the Members of the Procurement Committee


 (Abdul Ghafoor Soomro)
 Executive Engineer
 Larkana Drainage Division
 Larkana
 (Chairman)


 (Ghulam Muftaba Dhamrah)
 Executive Engineer
 North Dadu Drainage Division
 Larkana
 (Member)


 (Abdul Wahab Sahito)
 Executive Engineer
 Public Health Engineering
 Division-1 Larkana
 (Member)

Amir Muhammad E 20

THE NEWS

Friday, March 20, 2015



OFFICE OF THE EXECUTIVE ENGINEER LARKANA DRAINAGE DIVISION LARKANA

NOTICE INVITING TENDERS

1. Executive Engineer Larkana Drainage Division Larkana invites sealed tenders on Composite Schedule of Rates (CSR) / on Standard Bidding Documents from interested Contractors/Firms as per SPP Rules 2010 (amended 2013).

Sr. No.	Name of Work	Estimated Cost	Earnest Money	Tender Fee	Completion Period
01	Construction of Pumping Station & Allied Works i/c Staff Quarter and Generator Room at RD 38 of Miro Khan Main Drain near Dost Ali Bungalow.	Quoted Rates	2% Quoted Rate	3000	18 Months
02	Rehabilitation/Installation of New Pumps at Larkana North (Shahmir), Larkana South (Mashori) & Naudero (Mahota) Pumping Stations.	Quoted Rates	2% Quoted Rate	3000	18 Months
03	Installation of 50 Nos. New Tubewells of 1.5 c/s, construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses/Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.	Quoted Rates	2% Quoted Rate	3000	18 Months
04	Installation of 50 Nos. New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses/Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.	Quoted Rates	2% Quoted Rate	3000	18 Months
05	Installation of 50 Nos. New Tubewells of 1.5 c/s, Construction of Pump House, Duty Room, & Construction of Pacca Link Water Courses/Disposal Channel & Discharge Box in Larkana Drainage Division Larkana.	Quoted Rates	2% Quoted Rate	3000	18 Months
06	Installation of New Pumps at Ruk, Gharhi Yaseen & Masiti Pumping Stations in Shikarpur Drainage Division Shikarpur.	Quoted Rates	2% Quoted Rate	3000	18 Months

2. **Eligibility:** Valid Registration with tax authorities Pakistan Engineering Council in relevant category and discipline Sindh Revenue Board valid NTN by FBR.

3. **Method of Procurement:** Single Stage Single Envelope.

4. **Bidding/Tender Documents:**

(i) **Issuance:** Documents will be issued from date of publication to 10-04-2015 up to 5:00 P.M. on payment of tender fee (Non-refundable-mentioned against each item in the list).

(ii) **Submission:** Last date will be 11-04-2015 at 1:00 P.M.

(iii) **Opening:** will be opened on 11-04-2015 at 1:45 P.M.

(iv) **Place of issuance, submission, inquiries and opening will be:**

Address (Postal) : Executive Engineer Larkana Drainage Division Larkana, SCARP Irrigation Colony near Mirokhan Chowk, Hatodero Road, Larkana.

Telephone Numbers(s) : 074-9410081

Fax Number : 074-9410081

E-mail Address (if available) : waheedalichanna@gmail.com

(v) **Un-responded tenders** will be again issued/submitted/opened on following dates:

2nd Attempt: (a) up to 27-04-2015 up to 5:00 P.M. (b) 28-04-2015 at 1:00 P.M. and opening 29-04-2015 at 1:45 P.M.

5. **Terms & Conditions:**

(a) Under following conditions bid will be rejected:

(i) conditional and telegraphic bids/tenders.

(ii) Bids not accompanied by bid security of required amount and form.

(iii) Bids received after specified date and time.

(iv) Black listed firms.

(b) **Bid validity Period: 90 days**

(c) Procuring Agency may reject all or any bids subject to the relevant provisions of Sindh Public Procurement Rules 2010

(d) **Responsive Bidder is required to submit following documents with bids:**

(i) List of similar assignments with cost (mention number of projects with their cost) under-taken over the past 03 years;

(ii) Details of equipments, machineries and transport owned by firm/contractor;

(iii) Financial Statement (Summary) and Income Tax Return for the last 03 years;

(iv) Affidavit that firm has never been black listed.

Sd/-
EXECUTIVE ENGINEER
LARKANA DRAINAGE DIVISION
LARKANA

INF/KRY-1015/15

Say No to Drugs live Happily.

Annexure - G

OFFICE OF THE EXECUTIVE ENGINEER LARKANA DRAINAGE DIVISION
LARKANA



☎ : 074-9410081

No: TC/G-55/ 720 /of 2015.
Larkana Dated: 20 / 3 /2015.

To,

The Managing Director,
Sindh Public Procurement Regularity Authority
Karachi

SUBJECT: BIDDING DOCUMENTS

Ref. i) This office NIT No: TC / G-55 / 682 dt: 17.03.2015
ii) This office NIT No: TC / G-55 / 700 dt: 18.03.2015

The bidding documents for the tenders to be issued for works against N.I.T's under reference (copy enclosed) are submitted herewith for keeping the same on web-site of the Department.

D.....A
As above







(Abdul Ghafoor Soomro)
Executive Engineer
Larkana Drainage Division
Larkana

ATTENDANCE SHEET OF PARTICIPANTS

NTN No: TC / G-55 / 700 Dated: 18 / 03 / 2015
Date: 10 / 04 / 2015.

S.#	Name with Designation	Telephone No:	Signature
1	Abdul Ghafoor Soomro Executive Engineer Larkana Drainage Division Larkana (Chairman)	074-9410081	
2	Ghulam Mujtaba Dhamrah Executive Engineer North Dadu Drainage Division Larkana (Member)	074-9410063	
3	Abdul Wahab Sahito Executive Engineer Public Health Engineering Division-1 Larkana (Member)	074-9410326	
4	Rezaqul Ahmed Malik (member) D.A.O	0300/9316356	

S.#	Name of Bidders/ Contractors	Telephone No:	Signature
1	M/S Eid Muhammad Brohi & Co:	03003407098	
2	Haji Dilmurad Mangal	—	
3	M/S Madani Engineering Construction Co:	0333-7272531	
4	M/S Sher Muhammad Mughari	0333-7824178	

BID EVALUATION REPORT

1	Name of Procuring Agency	: -	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	: -	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	: -	Construction of Pumping Station & Allied Works i/c Staff Quarter and Generator Room at RD 38 of Miro Khan Main Drain near Dost Ali Bungalow.
4	Method Procurement.	: -	Single Stage One Envelope Bidding Procedure
5	Tender Published.	: -	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	: -	3Nos:
7	Total Bid Received.	: -	2Nos:
8	Technical Bid opening date (If Applicable)	: -	10/4/2015.
9	No: of Bid Technically qualified (If Applicable)	: -	Not Applicable
10	Bid (s) Rejected (If Applicable)	: -	
11	Financial Bid opening date.	: -	10/4/2015
12	Bid Evaluation Report.	: -	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Eid Muhammad Brohi & Co.	141442813	1st Lowest	+2.04% Above	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (ammended 2013)
2	Haji Dilmurad Mangal	144254987	2nd Lowest	+4.07% Above	Accepted in Terms	Responsive
3	M/S Ali Dost Buriro	Not Tendered				

Signature of the Members of the Procurement Committee

(Abdul Ghafar Soomro)
Executive Engineer
Larkana Drainage Division
Larkana
(Chairman)

(Ghulam Mujtaba Dhamrah)
Executive Engineer
North Dadu Drainage Division
Larkana
(Member)

(Abdul Wahab Sahito)
Executive Engineer
Public Health Engineering
Division-1 Larkana
(Member)

Rafiq Ahmed Malik
Divisional Accounts Officer
Larkana Drainage Division
Larkana

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-1

NIT No: TC/G-55/700

Date: 18/03/2015.

Date of issue of tender

Date: 10/04/2015.

Date of receipt & opening of tender

Date: 10/04/2015.

Name of Work: - Construction of Pumping Station & Allied Works i/c Staff Quarter and Generator Room at RD 38 of Miro Khan Main Drain near Dost Ali Bungalow.

S. No	Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS							
				M/S Eid Muhammad Brohi & Co:		Haji Dilmurad Mangal		M/S Ali Dost Buriro			
				Rate	Amount	Rate	Amount	Rate	Amount		
1	PART -A Non-Schedule Item Supplying & Installation of PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works	10 Nos.	Each	8795500	87955000	8950000	89500000				
2	Supplying of chain pully 5 tons 20 meters chain.	1No.	Each	49900	49900	65000	65000				Not Tendered
3	Providing & Fixing of Transformer (630KVA) Siemens or equilent i/c all accessories.	2Nos.	Each	4299500	8599000	4450000	8900000				
4	Supplying of 4 core copper wire 37/083 (240 mm).	600 Meeters	P Meeter	6450	3870000	7175	4305000				
5	Supplying & Installation of 1No Diesel Generator set (450 to 500 KVA) with all accessories.	1No.	Each	19950000	19950000	20150000	20150000				
	Total Part-A Rs:				120423900		122920000				

PART -B Schedule Item							
1	Schedule "B" Rs: 15803694/-	Schedule "B" Rs: 15803694/-	33% Above	5215219	35% Above	5531293	
2	Cartage Rs: 2381399/-	Add: Schedule "B" Amount		15803694		15803694	
3	Non Schedule Items Rs: 120423900/-	Non Schedule Items		120423900		122920000	
	Total Estimate Cost Rs: 138608993/-	Bid Amount		141442813		144254987	
		(-) Estimated Cost		138608993		138608993	
		Difference		2833820		5645994	
				$2833820 \times 100 = 2.04\%$		$5645994 \times 100 = 4.07\%$	
				Above over the estimate		Above over the estimate	
							Not Tendered

The rates quoted by M/S Eid Muhammad Brohi & Co: Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval.


Rafiq Ahmed Malik
 Divisional Accounts Officer
 Larkana Drainage Division
 Larkana


Abdul Ghaffar Soomro
 Executive Engineer
 Larkana Drainage Division
 Larkana

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-2

NIT No: TC/G-55/700

Date: 18/03/2015.

Date of issue of tender

Date: 10/04/2015.


Date of receipt & opening of tender

Date: 10/04/2015.

Name of Work: - Rehabilitation / Installation of New Pumps @ Larkana North (Shahmir), Larkana South (Mashori) & Naudero (Mahota) Pumping Stations.

S. No	Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS	
				M/S Madani Engineering Construction Co:	
				Rate	Amount
1	Replacement of old KSB Turbine pumps with new KSB pumps, PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works. 2Nos: Pumps @ Naudero (Mahota) 1No: Pump @ Larkana North (Shahmir) & 1No: Pump @ Larkana South (Mashori) Pumping Stations.	4	Each	8800000	35200000
2	Providing & Fixing of Transformer (400 KVA) Siemens or equivalent i/c all accessories @ Various Pumping Stations.	2	Each	3300000	6600000
3	Supplying of 4 core copper wire 37/083 (240 mm) @ Various Pumping Stations.	200	P Meeter	6500	1300000
4	S/F change over switch 1000 AMP	5	Each	325000	1625000
5	S/F change over switch 1500 AMP	2	Each	475000	950000
Total Rs:					45675000

The rates quoted by **M/S Madani Engineering Construction Co:** Government Contractor encircled in red have been found lowest are reasonable hence recommended for approval.


Rafiq Ahmed Wazir
 Divisional Accounts Officer
 Larkana Drainage Division
 Larkana



Abdul Qasim Soomro
 Executive Engineer
 Larkana Drainage Division
 Larkana


BID EVALUATION REPORT


1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	:-	Rehabilitation / Installation of New Pumps @ Larkana North (Shahmir), Larkana South (Mashori) & Naudero (Mahota) Pumping Stations.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	1No:
7	Total Bid Received.	:-	1No:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No. of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	45675000	Single Bid	Estimated Rate	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (ammended 2013)

Signature of the Members of the Procurement Committee


 (Abdul Ghaffar Soomro)
 Executive Engineer
 Larkana Drainage Division
 Larkana
 (Chairman)


 (Ghulam Mustafa Dhamrah)
 Executive Engineer
 North Dadu Drainage Division
 Larkana
 (Member)


 (Abdul Wahab Sahito)
 Executive Engineer
 Public Health Engineering
 Division-1 Larkana
 (Member)



 Rafiq Ahmad Malik
 Divisional Accounts Officer
 Larkana Drainage Division
 Larkana

BID EVALUATION REPORT


1	Name of Procuring Agency	:-	Executive Engineer Larkana Drainage Division Larkana
2	Tender reference No:	:-	N.I.T No: TC/G-55/ 700 dated: 18/03/2015.
3	Tender Description / Name of work / Item	:-	Installation of New Pumps @ Ruk, Gharhi Yaseen & Masiti Pumping Stations in Shikarpur Drainage Division Shikarpur.
4	Method Procurement.	:-	Single Stage One Envelope Bidding Procedure
5	Tender Published.	:-	SPPRA Website S.No: 23263 dated: 18 / 03 / 2015.
6	Total Bid Documents	:-	2Nos:
7	Total Bid Received.	:-	2Nos:
8	Technical Bid opening date (If Applicable)	:-	10/4/2015.
9	No. of Bid Technically qualified (If Applicable)	:-	Not Applicable
10	Bid (s) Rejected (If Applicable)	:-	
11	Financial Bid opening date.	:-	10/4/2015
12	Bid Evaluation Report.	:-	

S.#	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in Terms of cost	Comparison with Estimated Cost	Reason for Acceptance / rejection	Remarks
1	M/S Madani Engineering Construction Co:	203100000	1st Lowest	Estimated Rate	Accepted in Terms	Recommended for award of Contract in terms of Rule 48 of SPP Rules 2010 (ammended 2013)
2	M/S Sher Muhammad Mughari	208650000	2nd Lowest	Estimated Rate	Accepted in Terms	Responsive

Signature of the Members of the Procurement Committee


 (Abdul Ghaffar Soomro)
 Executive Engineer
 Larkana Drainage Division
 Larkana
 (Chairman)


 (Ghulam Mujtaba Dhamrah)
 Executive Engineer
 North Dadu Drainage Division
 Larkana
 (Member)


 (Abdul Wahab Sahito)
 Executive Engineer
 Public Health Engineering
 Division-1 Larkana
 (Member)


 Rafiq Ahmed Malik
 Divisional Accounts Officer
 Larkana Drainage Division
 Larkana

COMPARATIVE STATEMENT (FINANCIAL REVIEW)

Package-6

NIT No: TC/G-55/700 Date: 18/03/2015.
 Date of issue of tender Date: 10/04/2015.
 Date of receipt & opening of tender Date: 10/04/2015.

Name of Work: - Installation of New Pumps @ Ruk, Gharhi Yaseen & Masiti Pumping Stations in Shikarpur Drainage Division Shikarpur.

S. No		Item	Quantity	Unit	RATES QUOTED BY GOVERNMENT CONTRACTORS			
					M/S Madani Engineering Construction Co:		M/S Sher Muhammad Mughani	
					Rate	Amount	Rate	Amount
A		Installation of New Pumps @ Ruk Pumping Station in Shikarpur Drainage Division Shikarpur (Mechanical Work).						
1	Supplying & Installation of PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works	10	Each	88000000	880000000	9020000	902000000	
2	Supplying of chain pully 5 tons 20 meters chain.	1	Each	50000	50000	50000	50000	
3	Providing & Fixing of Transformer (630KVA) Siemens or equivalent i/c all accessories.	2	Each	4300000	8600000	4400000	8800000	
4	Supplying of 4 core copper wire 37/083 (240 mm).	600	P Meeter	6500	3900000	7000	4200000	
		Total Rs:			100550000		103250000	
B		Installation of New Pumps @ Gharhi Yaseen Pumping Station in Shikarpur Drainage Division Shikarpur (Mechanical Work).						
1	Supplying & Installation of PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works	6	Each	88000000	528000000	9020000	54120000	
2	Supplying of chain pully 5 tons 20 meters chain.	1	Each	50000	50000	50000	50000	
3	Providing & Fixing of Transformer (630KVA) Siemens or equivalent i/c all accessories.	1	Each	4300000	4300000	4400000	4400000	
4	Supplying of 4 core copper wire 37/083 (240 mm).	500	P Meeter	6500	3250000	7000	3500000	
		Total Rs:			604000000		620700000	

Installation of New Pumps @ Masiti Pumping Station in Shikarpur Drainage Division Shikarpur (Mechanical Work).						
C	1	Supplying & Installation of PNW 500-470 Tubular casing of 30 cusecs discharge with head as per site, water lubricated & delivery pipe required as per site of (470mm dia & 6.47mm thick) with 100 HP Electric Motor 960 RPM & MCU (of Siemens), copper cable 37/083 (4core) 120mm of 440 volt & bus bar required at site in respect with all accessories i/c civil works	4	Each	8800000	36080000
	2	Supplying of chain pully 5 tons 20 meters chain.	1	Each	50000	50000
	3	Providing & Fixing of Transformer (630KVA) Siemens or equivalent i/c all accessories.	1	Each	4300000	4400000
	4	Supplying of 4 core copper wire 37/083 (240 mm).	400	P Meeter	6500	2800000
		Total Rs:			42150000	43330000
		G: Total A + B + C Rs:			203100000	208650000

The rates quoted by **M/S Madani Engineering Construction Co: Government Contractor** encircled in red have been found lowest are reasonable hence recommended for approval.


Rafiq Ahmed Malik
 Divisional Accounts Officer
 Larkana Drainage Division
 Larkana


Abdul Wafoor Soomro
 Executive Engineer
 Larkana Drainage Division
 Larkana