



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)


BID EVALUATION REPORT

1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.17502 I.D No. /2013
3	Tender Description/Name of Work/Item	REPAIRING OF 12" DIA PRCC WATER LINE AT OPPOSITE DHOBI GHAT PUMPING STATION FOR THE IMPROVEMENT WATER SUPPLY IN ADJACENT AREA OF LYARI TOWN (WATER).
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site
6	Total Bid Documents Sold	2 Nos
7	Total Bid Received	2 Nos
8	Technical Bid Opening Date (if applicable)	N/A .
9	No. of Bid Technically Qualified (if applicable)	N/A .
10	Bid (s) rejected	Nil
11	Financial Bid Opening Date	24/10/2013
12	Bid Evaluation Report	


S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. S.Qayyum & Sons	Rs. 993,076/-	1st Lowest	@ 0.1015% Below	Substantially Responsive	P.O # 7466171 Dt: 23/10/2013 Rs 20,000/- UBL Rashid Minhas Road Br
2	M/s. H.R Brothers	Rs. 1,003,889/-	2nd Lowest	@ 0.9862% Above	Un-Responsive bid due to 2% P.O are Short	P.O # 8399395 Dt: 20/05/2013 Rs 20,000/- HBL Malir Cant.Br


The all concerned bidder are being informed accordingly.

The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. Qayyum & Sons declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.


(Muhammad Nawaz Khan)
Accounts Officer (South)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Muhammad Arif)
Chief Engineer (South)
Member


(Abdul Rahim Khatti)
Chief Engineer (IPD),
(Convener)

COMPARATIVE STATEMENT

NAME OF WORK: REPAIRING OF 12" DIA PRCC WATER LINE AT OPPOSITE DHOBI GHAT PUMPING STATION FOR THE IMPROVEMENT WATER SUPPLY IN ADJACENT AREA OF LYARI TOWN (WATER).

S.No	Description of Work	Engineer's Estimate				M/s. S.Gayum & Sons		M/s. H.R Brothers	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
1	Dismantling and removing road mantling Excavation for pipe line in trenches & pits in all kind of soil of muram i/c trimming and dressing sides to the true alignment & shape leveling of beds of trenches to correct level and grade cutting joints holes & disposal of surplus earth with in a one chain as directed by Engineer incharge providing fence guard light flag, and temporary crossing for non-vehicle traffic where ever required lift up to 5ft (1.52m) and lead up to on chain (30.5m) up to 0' to 5' up to 5' to 8'	1624 Cft	605.00	% Cft	9,825.20	604.00	9,808.96	608.00	9,873.92
2	Full hire charges of pumping set i/c wages of driver and Assistant fuel or electric energy plate form required for placing or at lower depths with suction and delivery pipes for pumping and water found at carious depth form trenches i/c cost of erection and dismantling after completion of the job. (i) Hire charges of pumping set of upto 10 H.P pumping out water for 10 feet deep trench	8320 Cft 2270.7 Cft	4,650.00 5,200.00	% 0 Cft % 0 Cft	38,688.00 11,807.64	4,645.00 5,200.00	38,648.40 11,807.64	4,650.00 5,250.00	38,688.00 11,921.18
3	Repairing & Fixing MS tail piece on PRCC pipe fabricated with 3/8 thick MS plate both caulking and reducer ends 9" wide provide with 1/2" thick square bar at caulking end having at total weight as mentioned against each item. It includes the cost of labour and caulking & sealing material etc complete.	14 Day	1,500.00	P/Day	21,000.00	1,500.00	21,000.00	2,000.00	28,000.00
4	12" Dia Net weight 51.81 Kgs 15" Dia Net weight 65.26 Kgs	2 No 1 No	9,438.00 11,591.00	Each Each	18,876.00 11,591.00	9,430.00 11,500.00	18,860.00 11,500.00	9,435.00 13,000.00	18,870.00 13,000.00

11/11/11
25/10/11

NAME OF WORK: REPAIRING OF 12" DIA PRCC WATER LINE AT OPPOSITE DHOBIGHAT PUMPING STATION FOR THE IMPROVEMENT WATER SUPPLY IN ADJACENT AREA OF LYARI TOWN (WATER).

S.No	Description of Work	Engineer's Estimate				M/s. S. Qayyum & Sons		M/s. H.R Brothers	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
5	Providing Laying and jointing, P.E pipe in trenches i/c fitting, jointing and testing etc complete in all respect HOPE-100) for conforming ISO 4427/DIN 8074/8075 B:S 3580 & PSI 3051 (PN-10). 315MM	340 Rft	1,998.00	P/Rft	679,320.00	1,996.00	678,640.00	1,999.00	679,660.00
6	Manufacturing Supplying and fixing. black Steel MS pipe made out of MS Sheet conforming to APL grade X-42. ERW and externally as phat coated with fib ring less 5.6 mm thick internally 8mm thick (AWWWA) Specification i/c with Helical welding in trenches i/c the cost of bands of any degree & testing with water specification pressure for different dia of pipe as below 5/6 mm thick. 12" Dia	25 Rft	2,458.81	P/Rft	61,470.25	2,455.50	61,387.50	2,460.20	61,505.00
7	P/F MS split collar on PRCC pipe, 18" wide fabricated with 3/8" thick MS plate 1 Y4" wide 3/8" thick- ring and center, 3/4" thick MS square bar on both ends with a total weight as mentioned against each item. It includes the cost of 4 Nos- 3/4" thick flanges, nuts, & bolts rubber packing labour and the sealing material 12" Dia Net weight 80.88 Kgs 18" Dia Net weight 102.88 Kgs	1 Nos 3 Nos	15,572.00 19,769.00	Each Each	15,572.00 59,307.00	15,550.00 19,750.00	15,550.00 59,250.00	16,000.00 19,770.00	16,000.00 59,310.00
8	Repair of leaking joints (External vana) on PRCC pipe of various diamete it i/c the cost of excavation, labor, sealing materia 1 gunny bags de-watering and refilling of the excavated stuff etc. complete... 12" dia.18" dia	1 Nos 2 Nos	9,716.00 13,841.00	Each Each	9,716.00 27,682.00	9,715.00 13,840.00	9,715.00 27,680.00	9,725.00 14,000.00	9,725.00 28,000.00

Handwritten signature/initials

NAME OF WORK: REPAIRING OF 12" DIA PRCC WATER LINE AT OPPOSITE DHOBI GHAT PUMPING STATION FOR THE IMPROVEMENT WATER SUPPLY IN ADJACENT AREA OF LYARI TOWN (WATER).

S.No	Description of Work	Engineer's Estimate			M/s. S.Qayyum & Sons		M/s. H.R Brothers		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
9	Refilling the excavated stuff in trenches 6" th l/c layer including watering ramming to full compaction etc. complete	10590.70	2,760.00	% 0 CH	29,230.33	2,760.00	29,230.33	2,770.00	29,396.24
					994,085.42		993,075.83		1,003,889.33
	Say				994,085		993,076		1,003,889

25/11/11
 (Muhammad Nawaz Khan)
 Accounts Officer (South)
 Member/Secretary

[Signature]
 (Muhammad Arif)
 Chief Engineer (South)
 Member

[Signature]
 (Saif-ul-Haque)
 Additional Director Internal
 Audit - KMC Member

[Signature]
 (Abdul Rahim Khattai)
 Chief Engineer (IPD), (Convener)

[Signature]
 (Maqsood Ahmed Shaikh)
 Superintending Engineer (KMC)
 Member