

KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)


BID EVALUATION REPORT

1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.17773 I.D No. /2013
3	Tender Description/Name of Work/Item	REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through website
6	Total Bid Documents Sold	02 Nos
7	Total Bid Received	02 Nos
8	Technical Bid Opening Date (if applicable)	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) rejected	Nil
11	Financial Bid Opening Date	20/11/2013


S#	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. Al-Maqbool Associates	Rs. 792,209/-	1st Lowest	@ 2.1069% Below	Substantially Responsive	P.O # 6577788 Dt: 18-11-2013 Rs.16,000/- HBL Rizvia Society Nazimabad Br
2	M/s. Safoer Enterprises	Rs. 801,709/-	2nd Lowest	@ 0.9330% Below	Substantially Responsive	P.O # 6577787 Dt: 12-11-2013 Rs.16,000/- HBL Rizvia Society Nazimabad Br

The all concerned bidder are being informed accordingly.


The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. Al-Maqbool Associates. declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.



(Aishah Ali)
Accounts Officer (West)
Member/Secretary


(Saiful-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Malik)
Chief Engineer (West)
Member


(Abdul Rahim Khattai)
Chief Engineer (IPD),
(Convener)


IMDAD HUSSAIN
Executive Engineer
SITE Division (West)
KWSB




KARACHI WATER & SEWERAGE BOARD
OFFICE OF THE CHIEF ENGINEER (IP&D)


BID OPENING REPORT


1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No. 17773 I.D No. /2013
3	Tender Description/Name of Work/Item	REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through website
6	Total Bid Documents Sold	02 Nos
7	Total Bid Received	02 Ncs
8	Technical Bid Opening Date (if applicable)	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Financial Bid Opening Date	20/11/2013
11	Bid Opening Report	


S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	REMARKS
1	M/s. Al-Maqbool Associates	Rs. 792,209/-	1st Lowest	P.O # 6577788 Dt: 18-11-2013 Rs. 16,000/- HBL Rizvia Society Nazimabad Br
2	M/s. Safer Enterprises	Rs. 801,709/-	2nd Lowest	P.O # 6577767 Dt: 12-11-2013 Rs. 16,400/- HBL Rizvia Society Nazimabad Br


M/s. Al-Maqbool Associates, declared as the lowest responsive bidder



(Masood Ali)
Accounts Officer (West)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Masood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Malik)
Chief Engineer (West)
Member


(Abdul Rahim Khattak)
Chief Engineer (IPD),
(Convener)


IMDAR
Karachi

COMPARATIVE STATEMENT


NAME OF WORK: REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN

S.No	Description of Work	Engineer's Estimate			M/s. Al-Maqbool Associates		M/s. Safeer Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
1	Rewinding of electric Motor 3 Phase 400/440V 50 cycle with best quality insulated copper wire of Required gauge i/c Testing on head with satisfactory result up to one week Time opening & Refitting & Replacing the bolts if necessary Exceeding the cost of worn out Material (Pg No-II 0 item No.97 Pb-52) SCR 2012	1 Nos	40,280.00	Each	40,280.00	40,280.00	40,280.00	40,280.00	40,280.00
2	P/F Manufacturing of motor contract unit to operate 40 HP motor and pump i/c all relevant access ries i/e panel box contractor over load relay, timer CTS etc complete as per direction of EI	1 Nos	160,054.00	Each	160,054.00	160,054.00	160,054.00	160,054.00	160,054.00
3	PVC 40 mtr shalled with three core copper conductor 600/1000 volts size 50 mm2 page no.-09 item no.72 Pb No.56 SCR 2012	40 mtr	2,526.00	P/Mtr	101,040.00	2,480.00	99,200.00	2,500.00	100,000.00
4	PIF Circuit breaker 15,20,30,40,50,60,75 & 100 amp TP (xs 100 NS) on prepared board as required	1 Nos	9,261.00	Each	9,261.00	8,500.00	8,500.00	9,000.00	9,000.00
5	Dis/Reassembling of centrifugal pump	1 Nos	4,375.00	Each	4,375.00	4,000.00	4,000.00	4,300.00	4,300.00
6	Com pt. repairing of lapeller (Bronze) i/c welding machining upto the correct size and position	1 Nos	3,075.00	Each	3,075.00	3,075.00	3,075.00	3,075.00	3,075.00
7	PIF ball bearing 7322 FAG for set No.I-3 100 HP	2 Nos	62,175.00	Each	124,350.00	60,000.00	120,000.00	61,000.00	122,000.00

[Handwritten Signature]
 11/1/11
 (OWATE K.A.I.)

NAME OF WORK: REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN

S.No	Description of Work	Engineer's Estimate			M/s. Al-Maqbool Associates		M/s. Safeer Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
8	Providing 8" dia sluice valve imported test pressure 100 LBS flanged type with gun metal spindle and wearing parts double and square threaded com. Quiet	3 Nos	17,940.00	Each	53,820.00	17,500.00	52,500.00	17,800.00	53,400.00
9	Fixing of sluice valve with 2 cast iron two tail pieces one end flanged and other with socket i/c the cost of nut bolts and rubber packing labour etc complete.								
10	P/F 8" dia Non Return valve	3 Nos	2,790.00	Each	8,370.00	2,500.00	7,500.00	2,700.00	8,100.00
11	P/F magnetic contractor FC 130 N as required as per instruction of EI for main and del ta set No.3 PNo.37 PbNo.56 Item No.257 SCR 2012	1 Nos	10,325.00	Each	10,325.00	8,500.00	8,500.00	10,000.00	10,000.00
12	Construction of CC block Masonry chamber of size 8x8x8(inside dimension) with 24x24" CI Cover frame weight (65kg) fixed RCC 1:2:4 slabs 6" thick with steel Y2 dia tor main bar @ 6" thick CC 1 :3:6 flooring 1/2" cement plaster 1:6 to all inside wall surface 1 feet deep upto Roof slab i/c MS foot rest 5/8" dia bars at every 2' deep curring, excavation, dewatering filling etc complete	2 Nos	32,860.00	Each	65,720.00	31,800.00	63,600.00	32,000.00	64,000.00
		2 Nos	86,333.00	Each	172,666.00	85,000.00	170,000.00	86,000.00	172,000.00


 HEAD OFFICE
 EXCISE
 SITE

NAME OF WORK: REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN

S.No	Description of Work	Engineer's Estimate			M/s. Al-Maqbool Associates		M/s. Safer Enterprises	
		Quantity	Rate	Unit	Rate	Amount	Rate	Amount
13	Construction of CC block Masonry chamber of size 6x6x6(inside dimension) with 24x24" CI Cover frame weight (65kg) fixed RCC 1:2.4 slabs 6" thick with steel Y2 dia for main bar@ 6" thick CC 1:3:6 flooring 112" cement plaster 1:6 to all inside wall surface 1 feet deep upto Roof slab ilc MS foot rest 5/8"dia bars at every 1:2' deep curring, excavation, dewatering filling etc complete	1 Nos	55,923.00	Each	55,000.00	55,000.00	55,500.00	55,500.00
	Total Quoted / Corrected Cost				809,259.00	792,209.00		801,709.00

(Signature)
 Accounts Officer (West)
 Member/Secretary

(Signature)
 (Saif-ul-Haque)
 Additional Director Internal
 Audit - KMC Member

(Signature)
 (Maqsood Ahmed Shaikh)
 Superintending Engineer (KMC)
 Member

(Signature)
 (Owais Malik)
 Chief Engineer (West)
 Member

(Signature)
 (Abdul Razim Khattai)
 Chief Engineer (IPD), (Convener)

RECEIVED
 EXECUTIVE SITE
 11/11/2011



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT

1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No 17773 I.D No. /2013
3	Tender Description/Name of Work/Item	REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through website
6	Total Bid Documents Sold	02 Nos
7	Total Bid Received	02 Nos
8	Technical Bid Opening Date (if applicable)	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) rejected	Nil
11	Financial Bid Opening Date	20/11/2013

12 Bid Evaluation Report


S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. Al-Maqbool Associates	Rs. 792,209/-	1st Lowest	@ 2.1069% Below	Substantially Responsive	P.O # 6577788 Dt: 18-11-2013 Rs. 16,000/- HBL Rizvia Society Nazimabad Br
2	M/s. Safeer Enterprises	Rs. 801,709/-	2nd Lowest	@ 0.9330% Below	Substantially Responsive	P.O # 6577767 Dt: 12-11-2013 Rs. 16,400/- HBL Rizvia Society Nazimabad Br

The all concerned bidder are being informed accordingly.


The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. Al-Maqbool Associates, declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.


(Aisha Ali)
Accounts Officer (West)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Malik)
Chief Engineer (West)
Member


(Abdul Rahim Khattai)
Chief Engineer (IPD),
(Convener)



KARACHI WATER & SEWERAGE BOARD


OFFICE OF THE CHIEF ENGINEER (IP&D)

BID OPENING REPORT


1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.17773 I.D No. /2013
3	Tender Description/Name of Work/Item	REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through website
6	Total Bid Documents Sold	02 Nos
7	Total Bid Received	02 Nos
8	Technical Bid Opening Date (if applicable)	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Financial Bid Opening Date	20/11/2013
11	Bid Opening Report	

S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	REMARKS
1	M/s. Al-Maqbool Associates	Rs. 792,209/-	1st Lowest	P.O # 6577788 Dt: 18-11-2013 Rs 16,000/- HBL Rizvia Society Nazimabad Br
2	M/s. Safer Enterprises	Rs. 801,709/-	2nd Lowest	P.O # 6577767 Dt: 12-11-2013 Rs 16,400/- HBL Rizvia Society Nazimabad Br

M/s. Al-Maqbool Associates, declared as the lowest responsive bidder


(Arshaid Ali)
Accounts Officer (West)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Malik)
Chief Engineer (West)
Member


(Abdul Rahim Khattai)
Chief Engineer (IP&D),
(Convener)

COMPARATIVE STATEMENT
NAME OF WORK: REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN

S.No	Description of Work	Engineer's Estimate			M/s. Al-Maqbool Associates		M/s. Safeer Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
1	Rewinding of electric Motor 3 Phase 400/440V 50 cycle with best quality insulated copper wire of Required gauge i/c Testing on head with satisfactory result up to one week Time opening & Refitting & Replacing the bolts if necessary Exceeding the cost of worn out Material (Pg No-11 0 item No.97 Pb-52) SCR 2012	1 Nos	40,280.00	Each	40,280.00	40,280.00	40,280.00	40,280.00	40,280.00
2	P/F Manufacturing of motor contract unit to operate 40 HP motor and pump i/c all relevant access ries i/e panel box contractor over load relay, timer CTS etc complete as per direction of EI	1 Nos	160,054.00	Each	160,054.00	160,054.00	160,054.00	160,054.00	160,054.00
3	P/L (main or sub main) PVC insulated and PVC 40 mtr shaled with three core copper conductor 600/1000 volts size 50 mm ² page no.-09 item no 72 Pb No.56 SCR 2012	40 mtr	2,526.00	P/Mtr	101,040.00	2,480.00	99,200.00	2,500.00	100,000.00
4	PIF Circuit breaker 15,20,30,40,50,60,75 & 100 amp TP (xs 1 00 NS) on prepared board as required	1 Nos	9,261.00	Each	9,261.00	8,500.00	8,500.00	9,000.00	9,000.00
5	Dis/Reassembling of centrifugal pump	1 Nos	4,375.00	Each	4,375.00	4,000.00	4,000.00	4,300.00	4,300.00
6	Com pt. repairing of lapeller (Bronze) i/c welding machining upto the correct size and position	1 Nos	3,075.00	Each	3,075.00	3,075.00	3,075.00	3,075.00	3,075.00
7	PIF ball bearing 7322 FAG for set No.1-3 100 HP	2 Nos	62,175.00	Each	124,350.00	60,000.00	120,000.00	61,000.00	122,000.00


NAME OF WORK: REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN

S.No	Description of Work	Engineer's Estimate				M/s. Al-Maqbool Associates		M/s. Safer Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
8	Providing 8" dia sluice valve imported test pressure 100 LBS flanged type with gun metal spindle and wearing parts double and square threaded com. Qiete	3 Nos	17,940.00	Each	53,820.00	17,500.00	52,500.00	17,800.00	53,400.00
9	Fixing of sluice valve with 2 cast iron two tail pieces one end flanged and other with socket i/c the cost of nut bolts and rubber packing labour etc complete.	3 Nos	2,790.00	Each	8,370.00	2,500.00	7,500.00	2,700.00	8,100.00
10	P/F 8" dia Non Return valve	1 Nos	10,325.00	Each	10,325.00	8,500.00	8,500.00	10,000.00	10,000.00
11	P/F magnetic contractor FC 130 N as required as per instruction of EI for main and del ta set No.3 PNo.37 PbnNo.56 Item No.257 SCR.2012	2 Nos	32,860.00	Each	65,720.00	31,800.00	63,600.00	32,000.00	64,000.00
12	Construction of CC block Masonry chamber of size 8x8x8(inside dimension) with 24X24" CI Cover frame weight (65kg) fixed RCC 1:2:4 slabs 6" thick with steel Y2 dia tor main bar @ 6" thick CC 1 :3:6 flooring 1/2" cement plaster 1:6 to all inside wall surface 1 feet deep upto Roof slab i/c MS foot rest 5/8" dia bars at every 2' deep curring, excavation, dewatering filling etc complete	2 Nos	86,333.00	Each	172,666.00	85,000.00	170,000.00	86,000.00	172,000.00

NAME OF WORK: REPAIRING, REWINDING, INSTALLATION OF 40 HP PUMP/MOTOR BOOSTING AT METROVILLE PUMPING STATION OF SITE TOWN


S.No	Description of Work	Engineer's Estimate				M/s. Al-Maqbool Associates		M/s. Safer Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
13	Construction of CC block Masonry chamber of size 6x6x6(inside dimension) with 24X24" CI Cover frame weight (65kg) fixed RCC 1:2.4 slabs 6" thick with steel Y2 dia for main bar@ 6" thick CC 1:3:6 flooring 112" cement plaster 1:6 to all inside wall surface 1 feet deep upto Roof slab ilc MS foot rest 5/8"dia bars at every 1:2' deep curring, excavation, dewatering filling etc complete	1 Nos	55,923.00	Each	55,923.00	55,000.00	55,000.00	55,500.00	55,500.00
	Total Quoted / Corrected Cost				809,259.00		792,209.00		801,709.00


 (Farshad Ali)
 Accounts Officer (West)
 Member/Secretary


 (Owais Malik)
 Chief Engineer (West)
 Member


 (Saf-ul-Haque)
 Additional Director Internal
 Audit - KMC Member


 (Magsood Ahmed Shaikh)
 Superintending Engineer (KMC)
 Member


 (Abdul Raqim Khattai)
 Chief Engineer (IPD), (Convener)