


**IMPROVEMENT OF MAJOR FISHERMEN'S SETTLEMENTS AND REHABILITATION OF
FLOOD AFFECTED AREAS IN COASTAL AREAS OF THATTA, SUJAWAL & BADIN DISTRICTS**


Bid Evaluation Report


- 1 Name of Procuring Agency: Sindh Coastal Development Authority
- 2 Tender Reference No: 026
- 3 Tender Description / Name of Work / Item: Construction of Road from Mori-Keti Khosa Road Mile 0/5 to Village Allah Dino Otho Road Mile 0/0-0/6 = 1.20 Kms, Taluka Jati District Sujawal.
- 4 Method of Procurement: N C B
- 5 Tender Published: SPPRA Website at Serial No. 37249 dated 13-03-2018
- 6 Total Bid Documents Sold: 9
- 7 Total Bids Received: 6
- 8 Technical Bid Opening Date: 3-Apr-18
- 9 No. of Bid Technically Qualified: 2
- 10 Bid(s) Rejected: 4
- 11 Financial Bid Opening Date: 3-Apr-18


12 Bid Evaluation Report

S. No.	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of Cost	Comparison with Estimated Cost	Reasons for Acceptance / Rejection	Remarks
0	1	2	3	4	5	6
1	M/s. Mumtaz Ali Khatti	5,985,735	1	31% Below	Insufficient Bid	Non Responsive / Below 30% Threshold
2	M/s. Rajgan Enterprises	6,072,484	2	30% Below	Lowest / Best Evaluated Bidder	Recommended for Award of Contract
3	M/s. Abdul Rehman Khan	6,303,271	3	27.34% Below	Technically Disqualified	Rejected
4	M/s. K. S Enterprises	6,541,039	4	24.60% Below	4th Lowest	Responsive
5	M/s Ali Muhammad Soomro	7,414,951	5	14.52% Below	Technically Disqualified	Telegraphic / Rejected
6	M/s Fayaz Traders	No Rates Filled	-	-	-	Disqualified


Muhammad Ali Memon
Deputy Director PPP - Unit
Member Procurement Committee IMFS
Finance Department


Shaharyar Akhtar Kazi
Project Manager / Chairman
Procurement Committee IMFS


Zamir Hussain Ujjan
Deputy Director (Agri)
Member / Secretary
Procurement Committee IMFS


Riaz Ahmed Memon
Assistant Engineer
Education Works, Sub Division
Lyari, Karachi


Kashif Raza
Assistant Engineer (IMFS)
Sindh Coastal Development Authority

BID OPENING SHEET

Construction of Road from Mori-Keti Khosa Road Mile 0/5 to Village Allah Dino Otho Road Mile 0/0-0/6 = 1.20 Kms, Taluka Jati District Sujawal.

S. No.	Name of Firm / Bidder	Total Amount of the Bid	Amount of call Deposit with name of Bank	Signature
1	K.S Enterprises	= 6541039/-	361000/-	
2	Abdul Rehman Khan	6303271/-	365000/-	
3	Mumtaz Ali	5985734/82	360080/-	
4	Fayaz Faiders	5% below (not valid) Philo state consultant		
5	Rajgan Enterprises	6072484/-	= 243000/-	
6	Ali Muhammad Soomro	7414951/-	122000/ (+) 182000/-	
7				Technical: A NO PEC, NO FBR.
8				
9				
10				
11				
12				

Muhammad Ali Memon
Deputy Director PPP - Unit
Member Procurement Committee IMFS
Finance Department

Shaharyar Akhtar Kazi
Project Manager / Chairman
Procurement Committee IMFS

Kashif Raza
Assistant Engineer (IMFS)
Sindh Coastal Development Authority

Zamir Hussain Ujjan
Deputy Director (Agri)
Member / Secretary
Procurement Committee IMFS

Bid Opening Checklist						
Construction of Road from Mori-Keti Khosa Road Mile 0/5 to Village Allah Dino Otho Road Mile 0/0-0/6 = 1.20 Kms, Taluka Jati District Sujawal.						
S.No	ITEM	Name of Bidders				
		M/s. Mumtaz Ali Khattai	M/s. Rajgan Enterprises	M/s. Abdul Rehman Khan	M/s. K. S Enterprises	M/s Ali Muhammad Soomro
1	Is Envelope Sealed ?	Yes	Yes	Yes	Yes	Yes
2	Required Amount of Bid Security	Yes	Yes	Yes	Yes	Yes
3	Required Bid Validity Period	Yes	Yes	No	No	No
4	Authority of signing	Yes	Yes	No	Yes	No
5	Alternate Bid if any	No	No	No	No	No
6	Withdrawal,	No	No	No	No	No
7	Substitution or Modifications, if any	No	No	No	No	No
8	Any discounts (if any)	No	No	No	No	No
9	Price Read Out	Yes	Yes	Yes	Yes	No
10	Form of Tender signed or not	Yes	Yes	No	No	No
11	Other Documents attached (PEC valid Registration in required discipline and category)	Yes	Yes	Yes	Yes	Yes
12	Valid Income Tax Registration & Registration with Sindh Revenue Board	Yes	Yes	Yes	Yes	Yes
13	Experience in the similar assignment at least 3 years	Yes	Yes	No	No	No
14	Annual Financial Turnover of 3 years	Yes	Yes	No	No	No
12	Any other detail	Insufficient Bid	-	-	-	No rates filled & No Pay Order of Bid Security


Muhammad Ali Memon


Deputy Director PPP - Unit
Member Procurement Committee IMFS
Finance Department


Shaharyar Akhtar Kazi

Project Manager / Chairman
Procurement Committee IMFS


Riaz Ahmed Memon

Assistant Engineer
Education Works, Sub Division
Lyari, Karachi


Amir Hussain Ujjan
Deputy Director (Agri) SCDA
Member / Secretary
Procurement Committee IMFS


Kashif Raza

Assistant Engineer (IMFS)
Sindh Coastal Development Authority


Financial Proposals After Correction

**Construction of Road from Mori-Keti Khosa Road Mile 0/5 to Village Allah Dino Otho Road Mile 0/0-0/6 =
1.20 Kms, Taluka Jati District Sujawal.**

S. No. (a)	Firm / Bidder (b)	Pay Order Amount & Bank (c)	Quoted Bid Cost (d)	Arithmetically Corrected Cost (e)	Discount Amount / Percentage (f)	Corrected Bid Cost (g)= e - f
1	M/s. Mumtaz Ali Khatti	360080 UBL	5,985,735	-	-	5,985,735
2	M/s. Rajgan Enterprises	243000 UBL	6,072,484	-	-	6,072,484
3	M/s. Abdul Rehman Khan	365000 HBL	6,303,271	-	-	6,303,271
4	M/s. K. S Enterprises	361000 ABL	6,541,039	-	-	6,541,039
5	M/s Ali Muhammad Soomro	304000 MCB	7,414,951	-	-	7,414,951
3	M/s Fayaz Traders	-	-	-	-	-


Muhammad Ali Memon

Deputy Director PPP - Unit
Member Procurement Committee IMFS
Finance Department


Zameer Hussain Ujjan
Deputy Director (Agri)

Member / Secretary
Procurement Committee IMFS


Shaharyar Akhtar Kazi

Project Manager / Chairman
Procurement Committee IMFS


Riaz Ahmed Memon

Assistant Engineer
Education Works, Sub Division
Lyari, Karachi


Kashif Raza

Assistant Engineer (IMFS)
Sindh Coastal Development Authority

Cost Comparison and Recommendations

Construction of Road from Mori-Keti Khosa Road Mile 0/5 to Village Allah Dino Otho Road Mile 0/0-0/6 = 1.20 Kms, Taluka Jati District Sujawal.

S. No.	Firm / Bidder's Name	Financial Tender Cost	Comparison with Engineering Estimate	Remarks and Recommendations	Ranking
1	M/s. Mumtaz Ali Khatti	5,985,735	31% Below	Insufficient Bid	1
2	M/s. Rajgan Enterprises	6,072,484	30% Below	Lowest / Best Evaluated Bidder	2
3	M/s. Abdul Rehman Khan	6,303,271	27.34% Below	Technically Disqualified	3
4	M/s. K. S Enterprises	6,541,039	24.60% Below	4th Lowest	4
5	M/s Ali Muhammad Soomro	7,414,951	14.52% Below	Technically Disqualified	5
6	M/s Fayaz Traders	No Rates Filled	-	-	-



Muhammad Ali Memon
Deputy Director PPP-Unit
Member Procurement Committee IMFS
Finance Department



Jamir Hussain Ujjan
Deputy Director (Agri)
Member / Secretary
Procurement Committee IMFS



Shafaryar Akhtar Kazi
Project Manager / Chairman
Procurement Committee IMFS



Riaz Ahmed Memon
Assistant Engineer
Education Works, Sub Division
Lyari, Karachi



Kashif Raza
Assistant Engineer (IMFS)
Sindh Coastal Development Authority

ATTENDANCE SHEET

Construction of Road from Mori-Keti Khosa Road Mile 0/5 to Village Allah Dino Otho Road Mile 0/0-0/6 = 1.20 Kms, Taluka Jati District Sujawal.

BID OPENING 03-04-2018 AT 02:30 PM

S. No.	Name of Firm / Bidder	Representative Name	Signature
✓ 1	Rajjan Enterprises	Ziaullah	[Signature]
✓ 2	Jaffer Khan Marwaha Jaffer	Jaffer	[Signature]
3	Hassan Khan Marwaha Hassan Khan	Hassan Khan	[Signature]
✓ 4	A. Rehman	Self	[Signature]
5	Mehmood Khan	Self	[Signature]
✓ 6	Munoz Khan	-	[Signature]
✓ 7	K.S Enterprises	Khalid Ahmed d	[Signature]
8	M/S Ghulam Mustafa	Zohaib Raza Shah	[Signature]
✓ 9	Fayyaz Traders	Aamir	[Signature]
10			
11			
12			

[Signature]

Muhammad Ali Memon
Deputy Director PPP- Unit
Member Procurement Committee IMFS
Finance Department

[Signature]

Zamir Hussain Ujjan
Deputy Director (Agri)
Member / Secretary
Procurement Committee IMFS

[Signature]

Shaharyar Akhtar Kazi
Project Manager / Chairman
Procurement Committee IMFS

[Signature]

Riaz Ahmed Memon
Assistant Engineer
Education Works, Sub Division
Lyari, Karachi

[Signature]

Kashif Raza
Assistant Engineer (IMFS)
Sindh Coastal Development Authority

FINANCIAL REVIEW

Comparison with Rough Cost Estimate (RCE/PC-1)


Construction of Road from Mori-Keti Khosa Road Mile 0/5 to Village Allah Dino Otho Road Mile 0/0-0/6 = 1.20 Kms, Taluka Jati District Sujawal.


Provision as per Rough Cost Estimate (RCE)						Recommended Tender	Excess / Saving	Remarks
S. No.	Item	Quantity	Rate	Unit	Amount	Amount	Difference	Excess/Saving Percentage (%)
1	2	3	4	5	6	7	8=7-6	
PART A – ROAD WORKS								
1	Earth Work for road embankment by bulldozers including ploughing, mixing clod breaking, ramming, dressing & compacting with optimum moisture content 85% density. Lead up to 100' Ft & lift up to 5' Ft in all type of soil except Rock.	361800	3656.23	%CFT	1,322,824	2,800,000	1477176	111.67%
2	Earth Work for road embankment by bulldozers including ploughing, mixing clod breaking, ramming & dressing the same & compacting Optimum Moisture content up to 95% density. Lead up to 100' ft & lift up to 5.0' ft in all type of soil except rock.	65300	6190.17	%CFT	404,218	600,000	195782	48.43%
3	Preparing Sub-Base Course by supplying and spreading stone metal of approved quality & gauge 1 1/2" to 2" of approved quarry in required thickness to proper camber and grade including hand packing filling voids with 20 CFT pit / canal and having plasticity not more than 6% of suitable quality watering and compacting to achieve 98~100% density as per modified AASHO specifications. Rate includes all cost of materials, T&P and carriage to site of work.	24500	7285.36	%CFT	1,784,913	1,000,000	-784913	-43.97%
4	Laying on Brick on end edging including supply of 9" x 4 1/2" x 3" 1st class well burnt bricks excavation for laying edging with small side parallel to the road. Rate includes all costs of materials, labour & carriage to the site of work.	8200	2896.68	%RFT	237,528	55,000	-182528	-76.84%
5	Providing surface dressing (3 Coats) on new or existing surface with 40+25+14 = 79 Lbs of Bitumen of 80/100 penetration & Crushed Bajri 5.50+2.75+1.50 = 9.75 CFT, Bajri of 3/4" to 1/2" gauge including cleaning the road surface rolling after each coat with power roller etc. complete. Rate includes all costs of materials, labour and carriage up to site of work.	48900	4068.21	%SFT	1,989,355	500,000	-1489355	-74.87%
6	Preparing Base Course by supplying and spreading stone metal of approved quarry properly graded to maximum size of 1 1/2" in required thickness to proper camber and grade including supplying and spreading 15 CFT screening & non plastic quarry fines filling depressions with stone metal after initial rolling i/c watering and compacting to achieve 100% density as per modified AASHO specifications. Rate includes all costs of materials, labour and carriage up to site of work.	24500	8280.3	%CFT	2,028,674	500,000	-1528674	-75.35%
7	Earth Work for road embankment from barrow pits including laying in 6" layers clod breaking, etc. complete. Lead upto 100' and lift up to 5' (in ordinary soil).	66900	2208.37	%CFT	147,740	85,676	-62064	-42.01%
	Total Part-A				7,915,251	5,540,676	-2,374,575	-30.00%


[Signature]


[Signature] *[Signature]* *[Signature]*


No. 1	Item 2	Quantity 3	Rate 4	Unit 5	Amount 6	Amount 7	Difference 8=7-6	Excess/Saving Percentage (%)
	PART B – 3' SPAN CULVERTS							
1	Excavation in foundation of buildings, bridges and other structure i/c dag belling dressing around structures with excavated earth watering and compacting lead up to 100' ft and lift up to 5' ft (in ordinary Soil).	1090	3176.25	% CFT	3,462	2,423	-1039	-30.01%
2	Cement concrete brick or stone ballast 1 1/2" to 2" gauge ratio 1:4:8.	213	9416.28	% CFT	20,057	14,040	-6017	-30.00%
3	Coursed Ruble masonry including hammer dressing 1:4 in plinth and foundation (in cement sand mortar)	553	27034.98	% CFT	149,503	104,652	-44851	-30.00%
4	Cement concrete plain including placing compacting to finishing and curing etc, complete (including screening & washing of stone aggregate without shuttering). Ratio: 1:2:4.	131	14429.25	% CFT	18,902	13,231	-5671	-30.00%
5	Fabrication of mild steel reinforcement concrete including bending cutting laying in position making joints and fastening including cost of bending wire etc, complete also includes removal of rust from bars.	5.79	4820.2	CWT	27,909	19,536	-8373	-30.00%
6	R.C.C work including all labor & material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. The rate also includes all kinds of forms moulds, lifting, shuttering, curing and finishing the exposed surface including screening & washing of shingle R.C.C. work in roof slab, beams, columns, lintels and other structure members laid in situ or precast laid in position complete in all respect Ratio: 1:2:4	79	337	CFT	26,623	18,636	-7987	-30.00%
7	Pointing on stone work raised in cement sand mortar ratio. 1:3	185	1758.08	%SFT	3,252	2,277	-976	-30.00%
8	Erection and removal of centering for R.C.C or plain cement concrete works vertical of Deodar Wood. (2nd Class)	113	3127.41	%SFT	3,534	2,474	-1060	-30.00%
	Total Part- B x 3 Culverts				759,729	531,808	-227,921	-30.00%
	Grand Total				8,674,980	6,072,484	-2,602,496	-30.00%


 Muhammad Ali Memon
 Deputy Director PPP-Unit
 Member Procurement Committee IMFS
 Finance Department


 Shaharyar Akhtar Kazi
 Project Manager / Chairman
 Procurement Committee IMFS


 Amir Hussain Ujjan
 Deputy Director (Agri)
 Member / Secretary
 Procurement Committee IMFS


 Kashif Raza
 Assistant Engineer (IMFS)
 Sindh Coastal Development Authority


 Riaz Ahmed Memon
 Assistant Engineer
 Education Works, Sub Division
 Lyari, Karachi