



KARACHI WATER & SEWERAGE BOARD
OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT


1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.17716 I.D No. /2013
3	Tender Description/Name of Work/Item	IMPROVEMENT OF SEWERAGE SYSTEM IN MEHMOODABAD K E C.H.S AND LAC-II BY CLEANING OF 24" DIA, 18" DIA AND 12" DIA SEWERAGE LINE THROUGH WINCHING MACHINE, JAMSHED TOWN (SEWERAGE)-I
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site
6	Total Bid Documents Sold	3 Nos
7	Total Bid Received	3 Nos
8	Technical Bid Opening Date (if applicable)	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) rejected	Nil
11	Financial Bid Opening Date	19/11/2013

12. Bid Evaluation Report

S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. Saim & Co.	Rs. 979,630/-	1st Lowest	@ 0.1855% Below	Substantially Responsive	P.O # 5844992 Dt: 27/09/2013 Rs. 20,000/- Bank Al-Habib Malir Halt Br.
2	M/s. Honest Associates	Rs. 984,393/-	2nd Lowest	@ 0.2996% Above	Substantially Responsive	P.O # 9194220 Dt: 25/09/2013 Rs. 20,000/- HBL Sindh Secret Br.
3	M/s. Tooba Enterprises	Rs. 987,824/-	3rd Lowest	@ 0.6493% Above	Substantially Responsive	P.O # 58097 Dt: 09/10/2013 Rs. 20,000/- Sindh Bank University Road Br.

The all concerned bidder are being informed accordingly.


The E E Concerned for compliance of rule 45 of SPPRA 2010 M/s. Saim & Co. declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.


(Muhammad Nawaz Khan)
Accounts Officer (South)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Muhammad Arif)
Chief Engineer (South)
Member


(Abdul Rabim Khattai)
Chief Engineer (IPD),
(Convener)

COMPARATIVE STATEMENT

NAME OF WORK: IMPROVEMENT OF SEWERAGE SYSTEM IN MEHMOODABAD K.E.C.H.S AND LAC-II BY CLEANING OF 24" DIA, 18" DIA AND 12" DIA SEWERAGE LINE THROUGH WINCHING MACHINE, JAMSHED TOWN (SEWERAGE-I)

S.N	Description of Work	Engineer's Estimate			M/s. Saim & Co.		M/s. Honest Associates		M/s. Tooba Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount		
1	Providing M/H 4ft inside with CI frame (15 kg) and 5 feet clear depth 1.2.4 cast in situ in 9 inch thick wall 1.4.8 cement concrete in 6ft dia and 6" inch thick in foundation 1.2.4 c/c in ben ching. W' thick cement plastering with 1.3 cement mortar on inside wall and surface of channel/benching i/c making required Nos of main and branch channels. 'Y4" dia bar footrest at 12" C/C i/c cost of excavation of all kinds of soil, backfilling and disposal of excavated stuff etc complete, as per design and instruction of the Engineer Incharge.	3.00 Nos	14,529.29	Each	43,587.87	14,530.00	43,590.00	14,535.00	43,605.00	14,540.00	43,620.00
11	Add/deduct per ft depth	10.00 ft	2,538.62	P/ft	25,386.20	2,540.00	25,400.00	2,540.00	25,400.00	2,545.00	25,450.00
2	Manufacturing and supplying of 21 inch diameter RCC Manhole Covers cast in 1.2.4 cement concrete ratio (50% graded balm and 50% crush) 3"inch deep at centre ram- forced with 'Y2" dia M.S. tor bars with 4" c/c welded to a3/16" thick 2" wide M.S.Flat and tow hook of 3/8" dia tor bars including compacting, curing and transportation within 10 miles etc.	50.00 Nos	913.63	Each	45,681.50	915.00	45,750.00	915.00	45,750.00	916.00	45,800.00
	a) 21" Dia	25.00 Nos	1,051.25	Each	26,281.25	1,055.00	26,375.00	1,055.00	26,375.00	1,056.00	26,400.00
	b) 24" Dia										

M/S/20/21

COMPARATIVE STATEMENT

NAME OF WORK: IMPROVEMENT OF SEWERAGE SYSTEM IN MEHMOODABAD K.E.C.H.S AND LAC-II BY CLEANING OF 24" DIA, 18" DIA AND 12" DIA SEWERAGE LINE THROUGH WINCHING MACHINE, JAMSHED TOWN (SEWERAGE)-I

S.No	Description of Work	Engineer's Estimate				M/s. Saim & Co.		M/s. Honest Associates		M/s. Tooba Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount
3	Manufacturing & supplying of RCC ring slab 21" dia (inside) and 36" dia outside 7.5 width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted 1:1 1/2:3 concrete with embedded 15 Kg C.I frame in perfect position i/c transportation charges for an average lead of 20KM per trip from casting yard to town offices (A minimum of 25 slabs per trip will be transported)	25.00 Nos	1,906.60	Each	47,665.00	1,910.00	47,750.00	1,910.00	47,750.00	1,912.00	47,800.00
4	Shifting to the site and fixing of 36" dia Ring slab in perfect position on damaged Manhole i/c cutting of damaged portion in proper shape and laying of cement mortar of 2" thickness and disposal of debris.	25 Nos	563.09	Each	14,077.25	565.00	14,125.00	565.00	14,125.00	566.00	14,150.00
5	Cement concrete plain including placing compacting, fitting finishing and curing, complete (including screening and washing at store aggregate without shattering Ratio 1:2:4	320.33 Cft	14,429.25	% Cft	46,221.22	14,435.00	46,239.64	14,450.00	46,287.69	14,455.00	46,303.70

m/20/11

COMPARATIVE STATEMENT

NAME OF WORK: IMPROVEMENT OF SEWERAGE SYSTEM IN MEHMOODABAD K.E.C.H.S AND LAC-II BY CLEANING OF 24" DIA, 18" DIA AND 12" DIA SEWERAGE LINE THROUGH WINCHING MACHINE, JAMSHED TOWN (SEWERAGE-I)

S.No	Description of Work	Engineer's Estimate			M/s. Saim & Co.		M/s. Honest Associates		M/s. Tooba Enterprises			
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount	Rate	Amount	
6	Cleaning inside sewerage lines completely restoring original slit free space / diameter of pipe lines by labour and equipment (Mechanically / Electrically driven) including accessories like pulley's steel rope buckets and draggers sizing from 6" to 18" dia later to and fro pulling action (No. of passes shall be as many as required) would be undertaken in two phases (First phase entire length from down stream to up stream) bringing down peak hours sewerage to flow inside pipe line (as free flow) and in second phase from up stream to down stream of entire length dia pipe to ensure perfect cleaning the job includes all the hire / cost of equipment accessories of above winching machine / devices along with / Engines with winching drum set having steel rope pulley mounted over it steel bucket from 6" dia to 18" dia hooks and other protection likes safety barriers traffic signs, traffic cones ensuring no damage to pipe line alongwith ensuring safety to labour and other public property / lives and removal of silts / solid during desilting and clearance of site etc as per full satisfaction of site engineer.											
	12" Dia	1200.00	Rt	80.50	P/Rt	96,600.00	82	98,400.00	83	99,600.00	84.00	100,800.00
	18" Dia	2500.00	Rt	128.80	P/Rt	322,000.00	128	320,000.00	130	325,000.00	132.00	330,000.00
	24" Dia	1500.00	Rt	209.30	P/Rt	313,950.00	208	312,000.00	207	310,500.00	205.00	307,500.00
	Total Quoted / Corrected Cost					981,450		979,630		984,393		987,824

(Signature)
 (Muhammad Nawaz Khan)
 Accounts Officer (South)
 Member/Secretary

(Signature)
 (Saif-ul-Haque)
 Additional Director Internal
 Audit - KMC Member

(Signature)
 (Mansoor Ahmed Shaikh)
 Superintending Engineer (KMC)
 Member

(Signature)
 (Muhammad Arif)
 Chief Engineer (South)
 Member

(Signature)
 (Abdul Rahim Khattai)
 Chief Engineer (TPD),
 (Convener)