



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.27130 I.D # _____
3	Tender Description/Name of Work/Item:	REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT BL-2 PECHS, MEHMOODABAD BL-6, HILL AREA UC-4, SIR SYED ROAD, JAMSHED TOWN (SEWERAGE)-I
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	SPPRA Web Site
6	Total Bid Documents Sold:	3 Nos
7	Total Bid Received:	3 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	02 Nos
11	Financial Bid Opening Date:	15-04-2016

12 BID EVALUATION REPORT

S #	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.A. Dawood Shah & Co.	Rs.4,49,268/-	1 st Lowest	@0.169% Below	Pay Order and required documents are available. P.O # 00552989 dt: 25-03-16 Rs.1,000/- from Bank Al Habib Ltd Gulshan Block-2 Branch & P.O # 00810999 Rs.2,000/- & P.O # 00810998 Rs.2,000/- & P.O # 00810997 Rs.2,000/- & P.O # 00810996 Rs.2,000/- Dt: 24-02-2016 from Bank Al Habib Ltd. Malir Cantt Branch Karachi.	Substantially Responsive
2	M/s.Nawab & Co.	Rs.4,51,244/-	-	@0.270% Above	Pay order and required documents are not available.	Un Responsive
3	M/s.Ali Muhammad & Sons	Rs.4,52,553/-	-	@0.561% Above	Pay order and required documents are not available.	Un Responsive

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.A. Dawood Shah & Co.** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

(Amir Halim)
D.A.O (District East)
Member / Secretary

(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member





(Ghulam Qadir Abbas)
S.E (District East)
Member

(Fahim Akhter Zaidi)
Director (Design & Estimate)
Convener

COMPARATIVE STATEMENT

Name of Work: REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT BL-2 PECHS, MEHMOODABAD BL-6, HILL AREA UC-4, SIR SYED ROAD, JAMSHED TOWN (SEWERAGE)-I

Item No	Description of Work	Estimated Cost					M/s.A. Dawood Shah & Co.	
		Quantity	Rate	Per	Amount	Rate	Amount	
1	Dismantling and removal road matting	1615.00	Cft	605.00	%Cft	9,770.75	600.00	9,690.00
2	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). i. Lift 00' - 05'ft ii. Lift 05' - 08' iii. Lift 05' - 08' iv. Lift 05' - 08'	6460.00	Cft	4650.00	%0Cft	30,039.00	4645.00	30,006.70
3	Providing M/H 4' feet inside with C.I Frame (15 Kg) and 5 feet clear depth 1:2:4 cast in situ with in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" C/C i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of Engineer Incharge.	3624.76	Cft	5200.00	%0Cft	18,848.75	5150.00	18,667.51
3(i)	Add or deduct for extra / less depth then 5ft to 4ft dia manhole i/c footrest.	799.92	Cft	5750.00	%0Cft	4,599.54	5750.00	4,599.54
4	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	6.00	Nos	14529.29	Each	87,175.74	14525.00	87,150.00
5	Providing, & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure.	14.67	(+)Ft	2538.62	P/Ft	37,241.56	2535.00	37,188.45
5	08" Dia	10.00	Days	1500.00	P/Day	15,000.00	1500.00	15,000.00
	12" dia	214.00	Rft	206.00	P/Rft	44,084.00	206.00	44,084.00
	15" dia	220.00	Rft	367.00	P/Rft	80,740.00	367.00	80,740.00
		120.00	Rft	436.00	P/Rft	52,320.00	436.00	52,320.00







Name of Work: REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT BL-2 PECHS, MEHMOODABAD BL-6, HILL AREA UC-4, SIR SYED ROAD, JAMSHED TOWN (SEWERAGE)-I


Item No	Description of Work	Estimated Cost				M/s. A. Dawood Shah & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	
6	Manufacturing and supplying of 21 inch diameter RCC Manhole Covers cast in 1:2:4 cement concrete ratio 3" inch deep at centre rein-forced with 1/2" dia M.S tor bars with 4" c/c welded to a 3/16" thick 2" wide M.S Flat and tow hook of 3/8" dia tor bars including compacting, curing and transportation within 10 miles etc. 21" dia	6.00	Nos	913.63	Each	5,481.78	910.00	5,460.00
7	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	6.00	Nos	180.00	Each	1,080.00	180.00	1,080.00
8	Carriage of 100 Cft / 5 Tons of all materials like stone aggregate, spawal, coal, lime, sukhi etc B.G Rail fastening points and crossing bridge, Girders, Pipes, Sheets Rail, M.S Bars etc 1000 Nos: bricks, 10"x6"x2" or 150 Cft or timber or 100 Mounds of fuel wood by trucks any other means owned by the Contractors. Upto 5 Mile	1692.22	Cft	714.29	%Cft	12,087.36	714.00	12,082.45
9	Sand Haro or any other source sand of same modules of the fineness (Hill Sand)	1080.00	Cft	2425.00	%Cft	26,190.00	2400.00	25,920.00
10	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	9192.46	Cft	2760.00	%0Cft	25,371.19	2750.00	25,279.27
	TOTAL QUOTED / CORRECTED COST					450,030		452,553


(Amir Halim)
D.A.O (Distt. East)
Member / Secretary


(Saif-ul-Haque)
Addl. Director Internal Audit
KMC - Member


(Magsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member


(Ghulam Qadir Abbas)
S.E (District East)
Member


Fahim Akhter Zaidi
Director (Design & Estimate)
Convener

NIT No. SPPRA Serial No.27130

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT BL-2 PECHS, MEHMOODABAD BL-6, HILL AREA UC-4, SIR SYED ROAD, JAMSHED TOWN (SEWERAGE)-I

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 15-04-2016 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. **(Attendance sheet is enclosed).**

2. Three bidders submitted their bids till the deadline of submission.

- i. M/s. A. Dawood Shah & Co.
- ii. M/s. Nawab & Co.
- iii. M/s. Ali Muhammad & Sons


3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.A. Dawood Shah & Co.	Rs.4,49,268/-	Rs.9,000/-	P.O # 00552989 dt: 25-03-16 Rs 1,000/- from Bank Al Habib Ltd Gulshan Block-2 Branch & P.O # 00810999 Rs.2,000/- & P.O # 00810998 Rs.2,000/- & P.O # 00810997 Rs.2,000/- & P.O # 00810996 Rs.2,000/- Dt: 24-02-2016 from Bank Al Habib Ltd. Malir Cantt Branch Karachi.
02	M/s.Nawab & Co.	Rs.4,51,244/-	-	Pay order not attached.
03	M/s.Ali Muhammad & Sons	Rs.4,52,553/-	-	Pay order not attached.


4. The bids do not contain any over-writing or cutting.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the vote of thanks to and from the chair.


(Amir Halim)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Ghulam Qadir Abbas)
S.E (District East)
Member


(Fahim Akhter Zaidi)
Director (Design & Estimate)
Convener

NIT No. SPPRA Serial No.27130

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)


Description of work: **REPLACEMENT OF 8" DIA, 12" DIA & 15" DIA RCC SEWERS AT BL-2 PECHS, MEHMOODABAD BL-6, HILL AREA UC-4, SIR SYED ROAD, JAMSHED TOWN (SEWERAGE)-I**


Date of Opening: 15-04-2016


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:

S. No.	Eligibility / Qualification Criteria	Bidders' Name		
		M/s.A. Dawood Shah & Co.	M/s.Nawab & Co.	M/s.Ali Muhammad & Sons
1.	Registration with PEC (if applicable)	N/A	N/A	N/A
2.	NTN	Yes	No	No
3.	Sales Tax Registration (FBR)	N/A	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	No	No
	Qualification Criteria:			
5.	Minimum three years' experience of relevant field.	Yes	No	No
6.	Turnover of at least last three years	Yes	No	No
7.	Required Bid Security is attached.	Yes	No	No
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A	N/A
10.	Qualified/ d/squalified	Qualified	Disqualified	Disqualified


(Amir Halim)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Ghulam Qadir Abbas)
S.E (District East)
Member


(Fahim Akhter Zaidi)
Director (Design & Estimate)
Convener



KARACHI WATER & SEWERAGE BOARD

HUMAN RESOURCES DEVELOPMENT AND ADMINISTRATION DEPARTMENT
PHONE NO. 021 - 99231464 - 021 - 99231463

No. KW&SB/SR. DIR./HRD&A/397

Dated 14th April 2016

OFFICE ORDER


The Procurement Committee-I is re-constituted as per Rule-07 of Sindh Public Procurement Rules-2010, for performing the functions prescribed in Rule-08 of Rules ibid for the works for which evaluation report required to be hoisted on Sindh Public Procurement Authority as under:

Sr. No.	Nominee	Position in P.C.
1.	Director Design & Estimate	Convener / Chairman
2.	Superintending Engineer (Concerned)	Member
3.	Representative of D.G. (TS), KMC	Member
4.	Representative of Finance Advisor, KMC	Member
5.	A.O. / D.A.O. / A.A.O. (Concerned)	Member/Secretary

The office of the Director Design shall be headquarter for Procurement Committee-I.

The Concerned Superintending Engineer shall maintain the record of Procurement proceedings as required under Rule-9 of SPPRA-2010.

This issues on the recommendation of Chief Engineer (IPD)/O.M.D (Planning) KW&SB and with the approval of Managing Director, KW&SB vide para 5/N.


SR DIRECTOR (HR)
KW&SB

DISTRIBUTION

1. Dy. Managing Director (TS) / C.E. (BT&D) / C.E. (WTM) KW&SB
2. Dy. Managing Director (Planning) / C.E. (IPD) KW&SB
3. Chief Engineer (W/S) KW&SB
4. Director Design & Estimate / Convener / Chairman Committee
5. All Members of the Committee.
6. Sr. Director (Finance) KW&SB
7. Director (IT) KW&SB
8. Director (I&C) M.D Sectt: KW&SB
9. Staff Officer to Vice Chairman, KW&SB
10. AD (LFA) KW&SB
11. AO (ESTT) KW&SB
12. AO (Budget) KW&SB
13. IAO-II KW&SB
14. Office Copy.
15. Master File.

c.c. to Managing Director, KW&SB

OO-2016