



# KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)


## BID EVALUATION REPORT


1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	SPPRA Serial No.19746 I.D No. /2014
3	Tender Description/Name of Work/Item	PROVIDING LAYING 03" DIA & 06" DIA UPVC PIPE AT A-ONE COTTAGES AND FROM A-01 TO A-30 BLOCK-09 FOR IMPROVEMENT OF WATER SUPPLY IN GULBERG TOWN WATER
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Web Site
6	Total Bid Documents Sold	02 Nos
7	Total Bid Received	02 Nos
8	Technical Bid Opening Date ( if applicable)	N/A .
9	No. of Bid Technically Qualified ( if applicable)	N/A .
10	Bid (s) rejected	Nil
11	Financial Bid Opening Date	25/04/2014
12	Bid Evaluation Report	


S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. Hashir Enterprises	Rs. 956,000/-	1st Lowest	@ 0.0058% Below	Substantially Responsive	P.O # 00759208 Dt:24-04-2014 Rs.20,000/- Soneri Bank Enquiry Office Nazimabad No.2.Br
2	M/s. Al Rehman Associates	Rs. 956,393/-	2nd Lowest	@ 0.0352% Below	Substantially Responsive	P.O # 284944 Dt:24-04-2014 Rs.20,000/- Summit Bank Karimabad .Br

The all concerned bidder are being informed accordingly.


The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. Hashir Enterprises, declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.

  
(Abdul Jabbar Shaikh)  
Accounts Officer (Central)  
Member/Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit - KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Syed Fahim Akhtar Zaidi)  
Chief Engineer (Central)  
Member

  
(Abdul Rahim Khatti)  
Chief Engineer (IPD),  
(Convener)

# BIDDERS QUALIFICATION REPORT

## Rule-46(i) (a) Single Stage One Envelope Procedure

Opening Date: 25-04-2014

Name of Work: **PROVIDING LAYING 03" DIA & 06" DIA UPVC PIPE AT A-ONE COTTAGES AND FROM A-01 TO A-30 BLOCK-09 FOR IMPROVEMENT OF WATER SUPPLY IN GULBERG TOWN WATER.**

Name of Bidder M/s. Hashir Enterprises.

S.No	Eligibility	Yes	No
1	Relevant experience		
2	Turnover Statement		
3	Registration with Income Tax		
4	Registration with Sales Tax where applicable.		

Name of Bidder M/s. Al Rehman Associates.


S.No	Eligibility	Yes	No
1	Relevant experience		
2	Turnover Statement		
3	Registration with Income Tax		
4	Registration with Sales Tax where applicable.		




(Abdul Jabbar Shaikh)  
Accounts Officer (Central)  
Member / Secretary



(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member



(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member



(Syed Fahim Akhtar Zaidi)  
Chief Engineer (Central)  
Member



(Abdul Raheem Khattij)  
Chief Engineer (IPD)  
Convener

NIT Sr. No. 19746

Method of Procurement: Single Stage Single Envelope.

Name of Work: PROVIDING LAYING 03" DIA & 06" DIA UPVC PIPE AT A-ONE COTTAGES AND FROM A-01 TO A-30 BLOCK-09 FOR IMPROVEMENT OF WATER SUPPLY IN GULBERG TOWN WATER.

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 25-04-2014 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.

- i. M/s. Hashir Enterprises.
- ii. M/s. Al Rehman Associates.


3. The bids were opened at 02:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s. Hashir Enterprises	Rs. 956,000/-	Rs.20,000/-	P.O # 00759208 Dt:24-04-2014 Soneri Bank Enquiry Office Nazimabad No.2.Br
02	M/s. Al Rehman Associates	Rs. 956,393/-	Rs.20,000/-	P.O # 284944 Dt:24-04-2014 Summit Bank Karimabad .Br

4. The bids do not contain any over-writing or cutting.

5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the note of thanks to and from the chair.

  
(Abdul Jabbar Shaikh)  
Accounts Officer (Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member





  
(Syed Fahim Akhtar Zaidi)  
Chief Engineer (Central)  
Member

  
(Abdul Raheem Khattai)  
Chief Engineer (IPD)  
Convener

## COMPARATIVE STATEMENT

**NAME OF WORK: PROVIDING LAYING 03" DIA & 06" DIA UPVC PIPE AT A-ONE COTTAGES AND FROM A-01 TO A-30 BLOCK-09 FOR IMPROVEMENT OF WATER SUPPLY IN GULBERG TOWN WATER**

S.No	Description of Work	Engineer's Estimate			M/s. Hashir Enterprises		M/s. Al Rehman Associates		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
1	Dismantling Cement Concrete plain 1:4:8.	3000 Cft	1,663.75	% Cft	49,912.50	1,663.75	49,912.50	1,663.75	49,912.50
2	Dismantling and removing road metalling	4250 Cft	605.00	% Cft	25,712.50	605.00	25,712.50	605.00	25,712.50
3	Excavation for pipe lines in trenches and pits in all kind of soil of murum i/c trimming and dressing side to true alignment and shape levelling of beds of trenches to correct level and grade, cutting joint holes and disposal of surplus earth with in a one chain as directed by the engineer incharge providing fence guards, lights, flags and temporary crossings for non-vehicular traffic where ever required lift upto 5 ft (1.52m) and lead upto one chain								
4	Providing Laying UPVC Pipes of Class "C" fixing in trenches i/c cutting fitting and jointing with solvent cement i/c 91.5 testing with water to a head 300	29000.00 Cft	4,650.00	% Cft	134,850.00	4,650.00	134,850.00	4,650.00	134,850.00
	3" Dia	3250 Rft	107.00	P/Rft	347,750.00	107.00	347,750.00	107.00	347,750.00
	6" Dia	300 Rft	370.00	P/Rft	111,000.00	370.00	111,000.00	370.00	111,000.00
5	Providing and fixing split collar tee on "PRCC" pipe 18" wide fabricated with 3/8" thick M.S plate 1 1/4" wide 3/8" thick ring at central 3/4" M.S square bar on both ends 04 Nos 3/4" thick M.S flanges i/c cost of nuts, bolts, packing, labour, and sealing material etc complete. WT=102.88 Kg 18" Dia	1 Nos	24,521.00	Each	24,521.00	24,500.00	24,500.00	24,600.00	24,600.00

**NAME OF WORK: PROVIDING LAYING 03" DIA & 06" DIA UPVC PIPE AT A-ONE COTTAGES AND FROM A-01 TO A-30 BLOCK-09 FOR IMPROVEMENT OF WATER SUPPLY IN GULBERG TOWN WATER**

S.No	Description of Work	Engineer's Estimate				M/s. Hashir Enterprises		M/s. Al Rehman Associates	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
6	Providing and fixing M.S Split Collar 0.9" A.C Pipe Fibreclated with 1/4" thick M.S plate weight ment it i/c the cost of 4 nos flanges nuts & bolts rubber packing labour and sealing material etc complete (10.49 kg) 6" Dia	4 No	2,129.00	Each	8,516.00	2,130.00	8,520.00	2,130.00	8,520.00
7	Providing and fixing 0.9" long 3/8" thick M.S neck to existing M.S Pipe to a Split Collar tee having a total weight as mentioned against each item i/c cost of fabrication and welding the split collar tee.	4 No	895.00	Each	3,580.00	900.00	3,600.00	900.00	3,600.00
	3" Dia	1 No	1,984.00	Each	1,984.00	1,980.00	1,980.00	2,000.00	2,000.00
8	P/F M.S Flangs made of M.S plate having a thickness made of M.S Plate having and total weight renth i/c the cost of nuts bolts rubber packing with Tee (1/2" thick M.S Plate)	4 No	945.00	Each	3,780.00	945.00	3,780.00	945.00	3,780.00
	6" Dia ( 3,232 Kg)	1 No	1,520.00	Each	1,520.00	1,520.00	1,520.00	1,600.00	1,600.00
9	Full hire charges of pumping set per day inclusive of the wages of driver and assistant, fuel and electric energy plate form required for placing the pump etc, at lower depth with suction and delivery pipe for pumping out water pound at various depth from trenches including the cost of erection and dismantling after completion of job of 10 HP pumping out water from 10 ft deep trenches.	30.00 Day	1,500.00	P/Day	45,000.00	1,500.00	45,000.00	1,500.00	45,000.00
10	C.I sluice valve heavy pattern test pressure								
	21.0Kg/sq or 300 lb/sq inch (imported)								
	6" Dia	4 No	4,290.00	Each	17,160.00	4,290.00	17,160.00	4,290.00	17,160.00
	4" Dia	1 No	9,360.00	Each	9,360.00	9,350.00	9,350.00	9,500.00	9,500.00

*[Handwritten signatures and initials]*

**NAME OF WORK: PROVIDING LAYING 03" DIA & 06" DIA UPVC PIPE AT A-ONE COTTAGES AND FROM A-01 TO A-30 BLOCK-09 FOR IMPROVEMENT OF WATER SUPPLY IN GULBERG TOWN WATER**

S.No	Description of Work	Engineer's Estimate			M/s. Hashir Enterprises		M/s. Al Rehman Associates		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
11	Fixing of slice valve with 2 cost iron picese one flanged and other with socket including the cost of nuts bolts and rubber packing, labour etc.Complete.								
	6" Dia	4 No	1,254.00	Each	5,016.00				
	4" Dia	1 No	1,886.00	Each	1,886.00	1,250.00	5,000.00	1,250.00	5,000.00
12	Construction of C.C block masonry chamber of 4x4x4 (inside dimantion) with 24"x24" C.i cover & frame (weight-65 Kg) fixed on RCC 1:2:4 slab 6" thick with steel 1/2" Dia main bars 06" C/C & 1/4" dia @ 8" C.C distribution bars 6" thick C.C 1:3:6 block masonry wall set in 1:6 C.M 6" thick 1:4:8 in foundation 2" thick C.C 1:2:4 flooring 1/2" thick C.Plaster 1:6 to all in side wall surface top & bottom slab outer side wall surface 1'-0" deep up to roof slab MS foot rest 5/8" dia bars every 2' 0" deep etc.								
13	Refilling the excavated stuff in trenches 6" layer i/c watering ramming to full compaction etc complete.	3 Nos	28,357.00	Each	85,071.00	28,350.00	85,050.00	28,357.00	85,071.00
	Total Quoted / Corrected Cost	28781.67 Cft	2,760.00	% 0 Cft	79,437.41	2,760.00	79,437.41	2,760.00	79,437.41
	Say				956,056.41		956,000.41		956,393.41
					956,056		956,000		956,393

(Abdul Jabbar Shaikh)  
 Accounts Officer (Central)  
 Member/Secretary

(Saif-ul-Haque)  
 Additional Director Internal  
 Audit - KMC Member

(Syed Fahim Akhtar Zaidi)  
 Chief Engineer (Central)  
 Member

(Maqsood Ahmed Shaikh)  
 Superintending Engineer (KMC)  
 Member

(Abdul Rahim Khattii)  
 Chief Engineer (IPD), (Convener)