



# KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

## BID EVALUATION REPORT


1	Name of Procuring Agency :	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	KWSB/DPR/2016/23 published in daily "Sindh Affairs" "Ummat" dt: 22-03-2016 and daily "Regional Times" dt: 23-03-2016. SPPRA Serial No.27306 I.D No.
3	Tender Description/Name of Work/Item:	<b>REPLACEMENT &amp; PROVIDING / LAYING 15" DIA, 12" DIA &amp; 8" DIA SEWERAGE LINE AT BLOCK NO.7 AND CLEANING &amp; RESTORING THE CHOCKING SEWER 24" DIA, 18" DIA &amp; 15" DIA FROM SCHON CIRCLE TO FAROOQ-E-AZAM MASJID, BLOCK NO.7, CLIFTON / SADDAR TOWN, DISTRICT SOUTH</b>
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>Through Press Publication / SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>3 Nos</u>
7	Total Bid Received:	<u>3 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>02 Nos</u>
11	Financial Bid Opening Date:	13-04-2016


## 12 BID EVALUATION REPORT


S #	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARIS ON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1.	M/s.Alladin	Rs.24,98,723/-	1 <sup>st</sup> Lowest	@1.735% Below	Pay order and other required documents are available. P.O # 0165.2109805 dt:12-04-2016 Rs.52,000/-from Meezan Bank Al-Hilal Society Branch Karachi	Substantially Responsive
2	M/s.Al-Siraj Builders	Rs.25,44,180/-	-	@0.053% Above	Pay order attached other documents are not available. P.O # 0851735 dt:12-04-2016 Rs.53,000/-from Dubai Islamic Bank Pakistan Ltd. Hassan Square Branch Karachi	Un-Responsive
3	M/s.Deen Muhammad	Rs.25,46,273/-	-	@0.135% Above	Pay order and other documents are not available.	Un-Responsive


The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Alladin** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

  
(Muhammad Nawaz Khan)  
D.A.O (Dist. South)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Syed Muhammad Jamil Akhter)  
Chief Engineer (W&S)  
Member

  
(Syed Mashkoor-ul-Hasnain)  
Chief Engineer (IPD)  
Convener

## COMPARATIVE STATEMENT

**Name of Work: REPLACEMENT & PROVIDING/LAYING 15" DIA, 12" DIA & 8" DIA SEWERAGE LINE AT BLOCK NO.7 AND CLEANING & RESTORING THE CHOCKING SEWER 24" DIA, 18" DIA & 15" DIA FROM SCHON CIRCLE TO FAROOQ-E-AZAM MASJID, BLOCK NO.7, CLIFTON / SADDAR TOWN, DISTRICT SOUTH**

Item No	Description of Work	Estimated Cost				M/s. Alladin		M/s. Al-Siraj Builders		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Scarifying the Existing road Surface.	2700.00	Sft	116.16	%Sft	3,136.32	110.00	2,970.00	116.32	3,140.64
2	Dismantling and removal road matting	2700.00	Cft	605.00	%Cft	16,335.00	600.00	16,200.00	605.20	16,340.40
3	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). Lift 0' - 5ft	10800.00	Cft	4650.00	%0Cft	50,220.00	4610.00	49,788.00	4650.15	50,221.62
	Lift upto 05' - 08'	5400.00	Cft	5200.00	%0Cft	28,080.00	5000.00	27,000.00	5200.20	28,081.08
	Lift upto 08' - 11'	1400.00	Cft	5750.00	%0Cft	8,050.00	5200.00	7,280.00	5750.20	8,050.28
4	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. (i)Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	40.00	Days	1500.00	P/Day	60,000.00	1300.00	52,000.00	1500.25	60,010.00
5	Providing & Laying of RCC Pipes with Rubber Ring joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 15" Dia Pipe	200.00	Rft	436.00	P/Rft	87,200.00	410.00	82,000.00	436.15	87,230.00
	12" Dia Pipe	300.00	Rft	367.00	P/Rft	110,100.00	360.00	108,000.00	367.20	110,160.00
	08" Dia Pipe	200.00	Rft	206.00	P/Rft	41,200.00	202.00	40,400.00	206.20	41,240.00

*Handwritten signature*

*Handwritten signature*

*Handwritten signature*

*Handwritten signature*

*Handwritten signature*

7/1/15

**Name of Work: REPLACEMENT & PROVIDING / LAYING 15" DIA, 12" DIA & 8" DIA SEWERAGE LINE AT BLOCK NO.7 AND CLEANING & RESTORING THE CHOCKING SEWER 24" DIA, 18" DIA & 15" DIA FROM SCHON CIRCLE TO FAROOQ-E-AZAM MASJID, BLOCK NO.7, CLIFTON / SADDAR TOWN, DISTRICT SOUTH**

Item No	Description of Work	Estimated Cost			M/s. Atadin		M/s. Al-Siraj Builders			
		Quantity	Rate	Per	Amount	Rate	Amount			
6	Providing manhole 4' feet (inside) and 5 feet clear depth with C.I Frame (15 Kg) cast in situ with 1:2:4 CC in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of engineer incharge.	14.00	Nos	14529.29	Each	203,410.06	14500.00	203,000.00	14529.40	203,411.60
7	Add or deduct for extra / less depth then 5ft to 4ft dia manhole i/c footrest.	38.00	(+)Ft	2538.62	P/Ft	96,467.56	2480.00	94,240.00	2538.80	96,474.40
8	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	8.00	Nos	180.00	Each	1,440.00	380.00	3,040.00	180.15	1,441.20
9	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.									
10	Sand Haro or any other source sand of same modules of the fineness (Hill Sand)	10062.60	Cft	2760.00	%0Cft	27,772.78	2680.00	26,967.77	2760.20	27,774.79
11	Carriage of 100 Cft / 5 Tons of all materials like stone aggregate, spawl, coal, lime, surkhi etc B.G Rail fastening points and crossing bridges, Girders, pipes sheet Rail, M.S Bars etc. or 1000 Nos bricks, 10"x5"x3" or 1000 Nos: tiles, 12" x6"x2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the Contractors.	6708.40	Cft	2425.00	%Cft	162,678.70	2390.00	160,330.76	2425.20	162,692.12
	Carriage for 07 Miles	7537.40	Cft	804.52	%Cft	60,639.89	800.00	60,299.20	804.70	60,653.46






20/11/15

**Name of Work: REPLACEMENT & PROVIDING / LAYING 15" DIA, 12" DIA & 8" DIA SEWERAGE LINE AT BLOCK NO.7 AND CLEANING & RESTORING THE CHOCKING SEWER 24" DIA, 18" DIA & 15" DIA FROM SCHON CIRCLE TO FAROOQ-E-AZAM MASJID, BLOCK NO.7, CLIFTON / SADDAR TOWN, DISTRICT SOUTH**

Item No	Description of Work	Estimated Cost				M/s. Alhadin		M/s. At-Siraj Builders		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
12	Cleaning inside Sewerage line completely restoring original silt free space / diameter of pipe lines by labour and equipment (Mechanically / Electrically driven). Including accessories like pulley's steel rope, buckets and draggers sizing from 6" to 18" dia their "to and fro" pulling action (No of passes shall be as many as required) would be undertaken in two phases (First phase entire length from down stream to up stream) bringing down peak hours sewage to flow inside pipe line (as free flow) and in 2nd phase from up stream to down stream of entire length using no silt to observed in bucket (6" dia to 18" dia) except only sewage water finally passing a ball of 12" lesser than the diameter of pipe but no exceeding 48" dia ball even for larger dia pipe to ensure perfect cleaning.									
	The job including all the hire / cost of equipment and accessories of above winching machine / devises alongwith / Engine with winching drum set having, steel rope pulley mounted over it, steel bucket 6" to 18" dia hocks and other protection like safety barriers, traffic signs, traffic cones ensuring no damages to pipe line alongwith ensuring safety to labour and other public property / lives and removal of silts / solid during desilting and clearance of site etc complete as per full satisfaction of site Engineer.									
	24" dia	3000.00	Rft	209.30	P/Rft	627,900.00	209.00	627,000.00	209.50	628,500.00
	18" Dia	2500.00	Rft	128.80	P/Rft	322,000.00	123.00	307,500.00	128.90	322,250.00
	15" dia	1200.00	Rft	96.60	P/Rft	115,920.00	92.00	110,400.00	96.80	116,160.00

*mk.*

*[Signature]*

*[Signature]*

**Name of Work: REPLACEMENT & PROVIDING / LAYING 15" DIA, 12" DIA & 8" DIA SEWERAGE LINE AT BLOCK NO.7 AND CLEANING & RESTORING THE CHOCKING SEWER 24" DIA, 18" DIA & 15" DIA FROM SCHON CIRCLE TO FAROOQ-E-AZAM MASJID, BLOCK NO.7, CLIFTON / SADDAR TOWN, DISTRICT SOUTH**

Item No	Description of Work	Estimated Cost			M/s. Alladin		M/s. Al-Siraj Builders			
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
13	Manufacturing and supplying of RCC Ring Slab of 21" dia (inside) and 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted in 1:1 1/2" concrete with embedded 15 Kg C.I. Frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office. (A minimum of 25 slabs per trip will be transported.	150.00	Nos	1906.60	Each	285,990.00	1906.70	286,005.00	1906.60	285,990.00
14	Shifting to the site and Fixing of 36" dia Ring Slab in perfect position on damaged manholes i/c cutting of the position of damaged manhole in layer of C.M in 2" thickness and disposal of debris.	150.00	Nos	563.09	Each	84,463.50	563.09	84,463.50	563.30	84,495.00
15	Manufacturing and supplying of 21" dia RCC Manhole covers cast in situ 1:2:4 concrete ratio 3" deep at centre, reinforced with 1/2" dia tor steel bars at 4" C/C welded to a 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting i/c cutting and transportation with in 10 miles. 21" dia cover.	164	Nos	913.63	Each	149,835.32	913.65	149,838.60	913.80	149,863.20
	<b>TOTAL QUOTED / CORRECTED COST</b>					<b>2,542,839</b>		<b>2,498,723</b>		<b>2,544,180</b>

(Muhammadi Nawaz Khan)  
D.A.O (Distt. South)  
Member / Secretary

(Saif-ul-Haque)  
Addl. Director Internal Audit  
KMC - Member

(Magsodd Ahmed Shaikh)  
Superintending Engineer (K.M.C)  
Member

(Syed Muhammad Jamil Akhter)  
Chief Engineer (W&S)  
Member

(Syed Mashkoor-ul-Hasnain)  
Chief Engineer (I.P.D)  
Member

NIT Sr. No. SPPRA Serial No.27304

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT & PROVIDING / LAYING 15" DIA, 12" DIA & 8" DIA SEWERAGE LINE AT BLOCK NO.7 AND CLEANING & RESTORING THE CHOCKING SEWER 24" DIA, 18" DIA & 15" DIA FROM SCHON CIRCLE TO FAROOQ-E-AZAM MASJID, BLOCK NO.7, CLIFTON / SADDAR TOWN, DISTRICT SOUTH

**MINUTES OF BID OPENING MEETING.**

A meeting of the procurement committee of this department was held on 13-04-2016 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders.


**(Attendance sheet is enclosed).**

2. Three bidders submitted their bids till the deadline of submission.
  - i. M/s. Alladin
  - ii. M/s. Al-Siraj Builders
  - iii. M/s. Deen Muhammad
3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
1.	M/s.Alladin	Rs.24,98,722.82	Rs.52,000/-	P.O # 0165.2109805 dt:12-04-2016 from Meezan Bank Al-Hilal Society Branch Karachi
2.	M/s.Al-Siraj Builders	Rs.25,44,178.68	Rs.53,000/-	P.O # 0851735 dt:12-04-2016 from Dubai Islamic Bank Pakistan Ltd. Hassan Square Branch Karachi
3.	M/s.Deen Muhammad	Rs.25,46,273.22	-	Pay Order not Attached


4. The bids do not contain any over-writing or cutting.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the vote of thanks to and from the chair.

  
(Muhammad Nawaz Khan)  
D.A.O (Dist. South)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Syed Muhammad Jamil Akhter)  
Chief Engineer (W&S)  
Member

  
(Syed Mashkoor-ul-Hasnain)  
Chief Engineer (IPD)  
Convener

**NIT No. SPPRA Serial No. 27306**

**Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)**


Description of work: **REPLACEMENT & PROVIDING / LAYING 15" DIA, 12" DIA & 8" DIA SEWERAGE LINE AT BLOCK NO.7 AND CLEANING & RESTORING THE CHOCKING SEWER 24" DIA, 18" DIA & 15" DIA FROM SCHON CIRCLE TO FAROOQ-E-AZAM MASJID, BLOCK NO.7, CLIFTON / SADDAR TOWN, DISTRICT SOUTH**


Date of Opening: **13-04-2016**


**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name		
		M/s.Alladin	M/s.Al Siraj Builders	M/s.Deen Muhammad
1.	Registration with PEC (if applicable)	N/A	N/A	N/A
2.	NTN	Yes	No	No
3.	Sales Tax Registration	N/A	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	No	No
	<b>Qualification Criteria:</b>			
5.	Minimum three years' experience of relevant field.	Yes	No	No
6.	Turnover of at least last three years	Yes	No	No
7.	Required Bid Security is attached.	Yes	Yes	No
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A	N/A
10.	Qualified/ disqualified	Qualified	Disqualified	Disqualified

  
(Muhammad Nawaz Khan)  
D.A.O (Dist. South)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Syed Muhammad Jamil Akhter)  
Chief Engineer (W&S)  
Member

  
(Syed Mashkoor-ul-Hashain)  
Chief Engineer (IPD)  
Convener

