

CONSTRUCTION OF INFRASTRUCTURE WORK AT KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)

TECHNICAL & FINANCIAL BID OPENING MEETING ON MARCH 15, 2017 FOR THE FOLLOWING PROJECTS


- (a) Brick Masonry Retaining Wall & Exit Gate along with Gate Office
 - (b) Construction of Tube Well & Pump House
 - (c) Construction of Effluent Pipe Line from STP out falling to Rohri Canal Rd : 85+263
 - (d) Construction of Main Electrical Sub-Station
-

PARTICIPANTS OF PROCUREMENT COMMITTEE:

- Dr. Farhan Farooq Project Director, KSEZ
- Mr. Yousuf Shiekh Asst. Commissioner, Commissioner Office, New Sukkur
- Ms. Sana Umair Ali Asst. Manager Contracts, National Industrial Parks

- 1 Meeting started with introduction of all participants. Attendance sheet was signed by the bidders who attended the Bid Opening of respective work. Attendance Sheet was verified and signed by Procurement Committee. Copy of Attendance Sheet for each work is attached.
- 2 Procurement Committee was informed by NIP representatives that all bids were submitted before the announced deadline.
- 3 Three bids were received for Retaining wall work. All bids were opened and the price of each bid was announced loudly and noted in the bid opening statement after the confirmation of any applicable discount. Bid Securities were also checked and found appropriate. Bid Security details submitted by each bidder were filled in Bid Opening Statement and signed by the Procurement Committee.
- 4 One bid was received for Tube Well and Pump House work. The only bid was opened and the price was announced loudly and noted in the bid opening statement after the confirmation of any applicable discount. Bid Security was also checked and found appropriate. Bid Security details were filled in Bid Opening Statement and signed by the Procurement Committee.
- 5 Two bids were received for Effluent Pipe Line work. Both bids were opened and the price of each bid was announced loudly and noted in the bid opening statement after the confirmation of any applicable discount. Bid Securities were also checked and found appropriate. Bid Security details submitted by both bidder were filled in Bid Opening Statement and signed by the Procurement Committee.

- 6 Three bids were received for Construction of Main Sub-Station work. All bids were opened and the price of each bid was announced loudly and noted in the bid opening statement after the confirmation of any applicable discount. Bid Securities were also checked and found appropriate. Bid Security details submitted by each bidder were filled in Bid Opening Statement and signed by the Procurement Committee.
- 7 It was conveyed to the bidders that they will be informed later for results after scrutiny. All bids were sent to Consulting Firm for further scrutiny and evaluation. The meeting concluded with a vote of thanks.



Dr. Farhan Farooq
Project Director
Khairpur Special Economic Zone (KSEZ)



Mr. Yousuf Shiekh
Assistant Commissioner
Commissioner Office, New Sukkur



Ms. Sana Umair Ali
Assistant Manager Contracts
National Industrial Parks




KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)

NATIONAL INDUSTRIAL PARKS DEVELOPMENT & MANAGEMENT COMPANY


"Brick Masonry Retaining Wall along with MC-02, MC-03 Periphery and Exit Gate along with Gate Office"


ATTENDANCE SHEET

TECHNICAL AND FINANCIAL BID OPENING (March 15, 2017; 3:00 P.M)

S.N	Name of Firm	Representative's Name	Contact Number	Representative signature.	Remarks.
1	M/s Nariman Const. Co	_____	Not Participated	_____	_____
2	M/s Rehmatullah Shaikh	Shakeel Ahmed	0333-759568		OK
3	M/s Nippon Builders	_____	Not Participated	_____	_____
4	M/s Sikandar Ali Khokhar	Farhan Ali Khokhar	0300-2404937		OK
5	M/s Blue Stone	/			/
6	M/s Kashif Constructors	/	Not Participated		/
7	M/s M. Abdullah & Brothers	/			/
8	M/s Bhatti Enterprises	Noor Mohd	03009318435		OK
9	M/s Khan Babar & Brothers	_____	NOT Participated	_____	_____


Project Director
Khairpur Special Economic Zone (KSEZ)


Assistant Manager Contracts
National Industrial Parks


Assistant Commissioner
Commissioner Office, New Sukkur
Rep of Commissioner Sukkur

KHAIRPUR SPECIAL ECONOMIC ZONE

National Industrial Parks Development & Management Company

"Construction of Stone & Brick Masonary Retaining Wall Along MC-02, MC-03 Periphery and Gate Along with Gate Office"

Date: March 15, 2017 Time: 3:00 p.m.

Bid Opening Statement

S.N	Name of Contractor	Bid Details	Bid Amount (Rs.)	Rebate Amount (Rs)	Net Bid Amount(Rs)	Submitted Bid Security Amount (Rs)	Bid Security Detail	Remarks
1	M/s Nariman Const. Co							
2	M/s Rehmatullah Shaikh	1 original + 1 copy	29,279,590/-	-	29,279,590/-	600,000/-	PO.1603.3084229 (15-03-17) Meezan Bank	PEC & NT not updated
3	M/s Nippon Builders							
4	M/s Sikandar Ali Khokhar	1 original + 1 copy	20,106,984/-	-	20,106,984/-	425,000/-	EDR: 00243527 (13-03-17) Sik Bank	OK
5	M/s Blue Stone							
6	M/s Kashif Constructors							
7	M/s M. Abdullah & Brothers							
8	M/s Bhatti Enterprises	1 Profile + 1 tender BOA	25,818,839/-	1493878	24,324,961/-	580,000/-	SD: 05748297 ; UBL ; (03-03-17)	copy of Affidavit.
9	M/s Khan Babar & Brothers							

*Required Bid Security is 2%

Kashif
15-3-17
Project Director
Khairpur Special Economic Zone (KSEZ)

M. Yousaf
Assistant Commissioner
Commissioner Office, New Sukkur

Rep: Commissioner Sukkur


S. Singh
Assistant Manager Contracts
National Industrial Parks

Bid Evaluation Report

1. Name of Procuring Agency: **KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)**
2. Tender Reference No: **Nil**
3. Tender Description/Name of work/item: **Construction of Brick Masonry Retaining Wall along MC-02, MC-03 Periphery & Exit Gate along with Gate Office**
4. Method of Procurement: **Single Stage – Single Envelope**
5. Tender Published: **The News, Jang and Kawish dated Feb. 17, 2017**
6. Total Bid documents Sold; **09 (Nine)**
7. Total Bids Received: **03 (Three),**
8. Technical Bid Opening date: **March 15, 2017**
9. No. of Bid technically qualified: **02 (Two)**
10. Bid(s) Rejected: **01 (One), due to the reasons given below**
11. Financial Bid Opening date: **March 15, 2017**

12. Bid Evaluation Report:

S N	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/ rejection	Remarks
1	M/s Sikandar Ali Khokhar	20,052,984/-	1 st Lowest	17.27% below	Qualified as per criteria/ Responsive Bid	Recommended for Award of work
2	M/s Bhatti Enterprises	24,324,961/-	2 nd Lowest	0.35% above	Qualified as per criteria	Responsive Bid
3	M/s Rehmatullah Shaikh	29,279,590/-	None	20.79% above	Not meeting Eligibility Criteria	Non-Responsive



Dr. Farhan Farooq
Project Director
Khairpur Special Economic Zone (KSEZ)



Mr. Yousuf Shiekh
Assistant Commissioner,
Commissioner Office, New Sukkur



Ms. Sana Umair Ali
Assistant Manager Contracts
National Industrial Parks

PROJECT OFFICE KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ), KHAIRPUR
 BID EVALUATION REPORT
 FOR CONSTRUCTION OF BRICK MASONRY RETAINING WALL ALONG MC-02, MC-03

Results of Preliminary Examination Requirements / **TECHNICAL EVALUATION**

S.No	Description	M/s Sikandar Ali Khokhar	M/s Bhatti Enterprises	M/s Rehmatullah Shaikh
1	2	1	2	3
a	1. Bid Submission Requirements: Cover Letter	Not Provided	Not Provided	Not Provided
b	Bid Form	Provided	Filled without witness	Not Filled & Signed
a	2. Eligibility Criteria: (As per NIT) Valid Pakistan Engineering Council (PEC) registration in Category "C6" and above in discipline CE-10	C3 & CE-10 Provided	C5 & CE-10 Provided	C4 & CE-10 Provided But Expired 31-12-16
b	Valid NTN certificate from Income Tax Authorities	Provided	Provided	Provided
c	Affidavit that the firm is not Blacklisted or engaged in any Litigation on any Project.	Provided	Provided	Provided
d	Should have completed 2 contracts of similar nature and value of Pak Rs 20.00 million in the last 5 years.	Provided	Provided	Not Provided
	3. Substantial Responsiveness	Yes	Yes	No
	4. Accepted for Detailed Examination	Yes	Yes	No

Farhan

DR. FARHAN FAROOQ
 Project Director (KSEZ)

Yousuf

MR. YOUSUF SHEIKH
 Assistant Commissioner,
 Commissioner Office,
 New Sukkur

Sana Umair Ali

MS. SANA UMAIR ALI
 Assistant Manager Contracts
 (NIP)

COMPARATIVE STATEMENT
GRAND SUMMARY

S.No	DESCRIPTION	Engineer's Estimate	M/s Sikandar Ali Khokhar	M/s Bhatti Enterprises	M/s Rehmatullah Shaikh
		AMOUNT (Rs.)	AMOUNT (Rs.)	AMOUNT (Rs.)	AMOUNT (Rs.)
A	SUBMITTED AMOUNT	-	20,106,984	24,324,961 (After Rebate)	29,279,590
B	AFTER ARITHMETIC CHECK				
1	Civil Works				
i	Brick Masonry Retaining Wall Along The Road MC-02 & MC-03	19,922,778	16,277,162	21,890,194	24,199,174
ii	Gate Office	4,056,850	3,482,972	3,792,037	4,838,106
2	Electrical Works (Gate Office)	260,765	292,850	136,608	242,310
TOTAL COST OF THE PROJECT (Before Rebate)		24,240,393	20,052,984	25,818,839	29,279,590
Less Rebate if any		-	00.00 %	5.786 %	00.00 %
TOTAL COST OF THE PROJECT (After Rebate)		24,240,393	20,052,984	24,324,961	29,279,590
Difference (B - A)			(54,000)	(0)	-
% below/above Engineer's Estimate ----->			-17.27%	0.35%	20.79%
% above Lowest Bidder ----->			-	21.30%	46.01%

Laubha
DR. FARHAN FAROOQ
P.O (KSE2)

Yousuf
MR. YOUSUF SHAIKH
Asst Comm
↑
SIGN

Sana Uddin Ali
MS. SANA UDDIN ALI
Asst manager contract (NIP)

S.No		GOVT. OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	ENGINEER'S ESTIMATE CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	M/S SIKENDER AL KHOKHER Rate (Rs)	Amount (Rs)	M/S SHARI ENTERPRISES Rate (Rs)	Amount (Rs)	M/S KHAMMULI SHAIKH Rate (Rs)	Amount (Rs)
PARCELS (SCHEDULE ITEMS)													
1		Item # 18(b)+18(i.ii)/ P-4+75/ Vol. III, Part II & III, (General & PHEW)	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation in foundation and dewatering in all kind of soil of building, bridges and other structures including daggbellling dressing refilling around structure with (suitable) excavated earth watering, ramming complete and disposal of surplus excavated material to designated area i/c all lead & lift, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	3432	M ³	303.92	1,043,053.44	339.00	1,163,448	335.00	1,149,720	390.00	1,338,480
2		Item # 22+13 (b+cii)/P-3 & 4/Vol-III, Part-II, (General)	IMPORTED EARTH FILLING FROM OUTSIDE SOURCES Supplying and filling watering and ramming earth under floor with new earth excavated from outside in 150mm layers leveling dressing and watering for compaction and to obtain 95% modified AASHTO density. Complete including all lead & lifts etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	3413	M ³	167.42	571,404.46	187.00	638,231	236.00	805,468.00	380.00	1,296,940.00
3		Item # 20 / P-10 /Vol-II, Part-II, (General)	DSMANTLING OF EXISTING COLUMN Dismantling cement concrete reinforced separating reinfor cement from concrete cleaning and slaightening the same etc complete in all respect as per standard specification, drawing and entire satisfaction of the Engineer.	54	M ³	1923.17	103,851.18	2153.00	116,262	2192.00	118,368	3600.00	194,400
4		Item # 5(h) / P-16 /Vol-III, Part-II, (General)	PCC CONCRETE (1:3:6) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing at stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.										
a)			Below foundation, plinth beam and floor and where required etc.	154	M ³	4448.55	685,076.70	4981.00	767,074	5204.00	801,416	6500.00	1,001,000
5		Item # 19b (i+ii)/2 / P-18 /Vol-III, Part-II, (General)	WOODEN FORMWORKS/SHUTTERING Providing, fixing, erecting and removal of partial wood centering (shuttering / formwork) of approved quality for RCC or plain cement concrete works etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.										
i			Form work for 1:3:6 concrete	342	M ²	361.31	123,568.02	404.00	138,168	400.00	136,800	450.00	153,900

Farhan
DR. FARHAN FAROOQ
P.O (KSE2)

Yousuf Shaikh
MR. YOUSUF SHAIKH
ASST. COMM

Ms. Sania Ullah Ali
Ms. SANIA ULLAH ALI
Asst. manager contract (NIP)

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs)	Amount (Rs)	Rate (Rs)	Amount (Rs)	Rate (Rs)	Amount (Rs)
6	Item # 6a(iii) / P-16,17 / Vol-III, Part-II, (General)	RCC CONCRETE Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and Vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. RCC Concrete Cylindrical strength 21 Mpa (3000 Psi) Extension of Column (at required level.)	171	M ³	12326.68	2,107,862.28	13805.00	2,360,655	13786.00	2,357,406	15000.00	2,565,000
7	Item # 8b / P-17 / Vol-III, Part-II, (General)	STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	14	Ton	100034.00	1,400,476.00	120000.00	1,680,000	114000.00	1,596,000	125000.00	1,750,000
8	Item # 5(1b) / P-21 / Vol-III, Part-II, (General)	BRICK MASONRY Providing and laying pacca brick masonry work (1st class quality) in ground floor super structure up to any height and at any floor etc. laid and jointed with 1:3 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	1234	M ³	4844.28	5,977,841.52	5425.00	6,694,450	5473.00	6,753,682	5651.00	6,973,334
9	Item # 11c / P-52 / Vol. III, Part-II, (General)	PLASTER (EXTERNAL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to external walls, columns, beams, etc. with cement mortar 1:4 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height). (S.R cement to be used)	2077	M ²	324.50	673,986.50	362.00	751,874	342.00	710,334	410.00	851,570
Total of Schedule Items						12,687,120.10		14,310,162.00		14,429,194.00		16,124,624.00
% above / below on Schedule items					30%	3,806,136.03						
Total Amount of Schedule Items-A						16,493,256.13		14,310,162.00		14,429,194.00		16,124,624.00

DR. FARHAN FAROOQ
P.O (KSG2)

M/s. YOUSUF SHIKH
Asst comm

Ms. SANJA UMAIR ARI
Asst Manager cantt (WIP)

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	ENGINEER'S ESTIMATE		M/s Sikandar Ali Krokhar		M/s Bhatti Enterprises		M/s Rehmatullah Shaikh	
					CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs)	Amount (Rs)	Rate (Rs)	Amount (Rs)	Rate (Rs)	Amount (Rs)
PART-B (NON-SCHEDULE ITEMS)												
9		REMOVING & RE-FIXING OF FENCE Removing of existing fence including Chiseling, cutting of existing column consisting of (G.I wire net, G.I pipe 10swg, nuts & bolt, flat, hold fast) etc, and where required as shown in the drawings cutting of fence with gas cutter including cleaning, debris stacking at appropriate place and dispose off at locations which approved by the the Engineer with all leads and lift etc. complete as per drawing and specifications and approval of the Engineer.	1821	M ²	161.00	293,181.00	500.00	910,500	900.00	1,638,900	2000.00	3,642,000
10		REMOVING & RE-FIXING OF FOOTPATH Removing of existing foot path paver and staking at site as per instruction of the engineer including re fixing of these after completion masonry work, refilling and compaction work complete as per (Case-1) drawing and specifications and approval of the Engineer.	504	M ²	1291.00	650,664.00	500.00	252,000	2900.00	1,461,600	700.00	352,800
11		75mm Thick C.C Coping Providing and laying (1:3) plain cement sand mortar coping concrete over brick masonry or where required including all formwork, rodding, leveling, compacting curing and finishing etc. complete as per drawing and specifications and approval of the Engineer.	29	M ³	9713.00	281,677.00	500.00	14,500	12000.00	348,000	9000.00	261,000
12		BRICK MASONRY WORK (Bricks Supplied by the Client) Providing and laying pacca brick masonry work in ground floor super structure up to any height and at any floor etc. laid and jointed with 1:3 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. NOTE: Bricks are provided by the client at site, only laying rate is required with CS mortar)	900	M ³	1060.00	954,000.00	600.00	540,000	3000.00	2,700,000	2900.00	2,610,000

DR. FARHAN FAROOQ
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst Comm

Ms. SANIA UNWAIR ALI
Asst manager contact (MWP)

S.No	GOVT. OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs)	Amount (Rs)	M/s Shari Enterprises		M/s Rehmatullah Shaikh	
	Item #/Page#/ Vol.sched ref.								Rate (Rs)	Amount (Rs)	Rate (Rs)	Amount (Rs)
13		Providing and fixing new periphery fence made from 50x4mm wire net fixed to 50mm dia x 10 swg G.I pipe frame panels of 2400 x 1700 mm size fixed with each other with 50mm x 5mm holdfasts vertically at three points. The G.I pipe supports to be embedded into RCC 1:2:4 pedestals of size 600 x 250 x to required height over RCC 1:2:4 footings of size 1000 x 500 x 300 mm high. Top of pedestal to matched as per existing, including excavation, lean concrete, etc. Complete in all respect as per drawings, specifications and direction of the Engineer.	125	Rm	10000.00	1,250,000.00	2000.00	250,000.00	10500.00	1,312,500.00	9670.00	1,208,750.00
Total Amount of Non-Schedule Items-B						3,429,522.00		1,967,000		7,461,000		8,074,550
TOTAL CARRIED TO GRAND SUMMARY (A + B)						19,922,776.13		16,277,162		21,890,194		24,199,174

Zarhan
DR. FAROQ FATHAN
 P.O (KSG2)

Yusuf Shaikh
MR. YUSUF SHIEKH
 Asst Comm

Sana Ullah Ali
MS. SANA ULLAH ALI
 Asst Manage contractor (NIP)

S.No	GOVT. OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikander Ali Khokhar		M/s Bhatti Enterprises		M/s Rehmatullah Sheikh	
					CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)
PART-A (SCHEDULE ITEMS)												
1	Item # 18(b)+18(i.ii)/ P-4+75/ Vol. III, Part-II & III, (General & PHEW)	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation in foundation and dewatering in all kind of soil of building, bridges and other structures including daggbellling dressing refilling around structure with (suitable) excavated earth watering, ramming complete and disposal of surplus excavated material to designated area i/c all lead & lift. etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	155	M ³	303.92	47,107.60	339	52,545.00	360	55,800.00	394	61,070.00
2	Item # 22+13 (b+cii)/P-3 & 4/Vol-III, Part-II, (General)	IMPORTED EARTHFILLING FROM OUTSIDE SOURCES Supplying and filling watering and ramming earth under floor with new earth excavated from outside in 150mm layers leveling dressing and watering for compaction and to obtain 95% modified AASHTO density. Complete including all lead & lifts etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	27	M ³	167.42	4,520.34	187	5,049.00	236	6,372.00	529	14,283.00
3	Item # 2 / P-15 /Vol-III, Part-II, (General)	STONE SOLING Providing and laying dry rammed brick or stone ballast / soling 1-1/2" to 2" gauge from approved quarry including hand packing & filling voids with sprawls & chips, consolidating & compacting with power or hand roller, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	30	M ²	1175.27	35,258.10	1316	39,480.00	1224	36,720.00	1540	46,200.00
4	Item # 5(I) / P-16 /Vol-III, Part-II, (General)	PCC CONCRETE (1:4:8) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing at stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.										
a)		Below foundation, plinth beam and floor and where required etc.	12	M ²	3987.19	47,846.28	4465	53,580.00	4100	49,200.00	5300	63,600.00

DR. FARHAN FAROOQ
P.O (KSE2)

Mr. YUSUF SHEKH
Asst. Comm

Ms. SANVA Unair Ali
Asst Manager Control (NTP)

S.No.	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Dharti Enterprises		M/s Rahmatullah Shaikh	
					CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)
5	Item # 5(h) / P-16 /Vol-III,Part-II, (General)	PCC CONCRETE (1:3:6) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing at stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	3	M ³	4448.55	13,345.65	4981.00	14,943.00	4550.00	13,650.00	6500.00	19,500.00
6	Item # 19b(i+ii/2) / P-18 /Vol-III,Part- II, (General)	WOODEN FORMWORKS/SHUTTERING Providing, fixing, erecting and removal of partial wood centering (shuttering / formwork) of approved quality for RCC or plain cement concrete works etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.										
i		Form work for 1:4:8 concrete	22	M ²	361.31	7,948.82	404	8,888.00	410	9,020.00	430	9,460.00
ii		Form work for 1:3:6 concrete	5	M ²	361.31	1,806.55	404	2,020.00	410	2,050.00	450	2,250.00
7	Item # 6a(ii) / P- 16,17 /Vol-III,Part- II, (General)	RCC CONCRETE SUB-STRUCTURE-Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.										
		RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)										
i)		Footing and Concrete Pads	25	M ³	12326.68	308,167.00	13805	345,125.00	12900	322,500.00	15300	382,500.00
ii)		Plinth Beams	7	M ³	12326.68	86,286.76	13805	96,635.00	12900	90,300.00	13200	92,400.00
iii)		Column up to Plinth level	3	M ³	12326.68	36,980.04	13805	41,415.00	12900	38,700.00	16000	48,000.00

[Handwritten Signature]

[Handwritten Signature]

DR. FARHAN FAROOQ
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst. Comm

MS. SARVA UMAIR ALI
Asst manger contracts (NIP)

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khelchar		M/s Bhatti Enterprises		M/s Rehmatullah Shaikh	
					CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)
8	Item # 8b / P-17 /Vo-III,Part-II, (General)	STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting,bending,laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	4	Ton	100034.00	400,136.00	120000.00	480,000.00	114000.00	456,000.00	125000.00	500,000.00
9	Item # 9 / P-71 /Vo-III,Part-II, (General)	BITUMEN COATING Providing and applying industrial bitumen paint/coating to plastered or cement concrete surface etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	270	M ²	83.72	22,604.40	92.00	24,840.00	100.00	27,000.00	110.00	29,700.00
10	Item # 28b / P-19 /Vo-III,Part-II, (General)	(D.P.C) DAMP PROOF COURSE Providing and laying DPC damp proof course with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture with leveling, curing, finishing etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	5	M ²	421.02	2,105.10	471.00	2,355.00	430.00	2,150.00	470.00	2,350.00
11	Item # 92 / P-109 /Vo-III,Part-II, (General)	TERMITE TREATMENT Providing Anti-Termite treatment by spraying / sprinkling / spreading Neptachlar 0.5% Emulsion as an overall pre construction treatment in slab type construction under the slab and along attached perches or entrances etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (Plinth area will be measured one time for payment whereas the number of applications will be three times on all horizontal & vertical surfaces of the excavations for termite proofing).	20	M ²	104.80	2,096.00	116.00	2,320.00	120.00	2,400.00	130.00	2,600.00

DR FARHAN FAROOQ
AO (KSE2)

MR. YOUSUF SHAIKH
Asst. comm

MS. SANA UMAIR ALI
Asst manager contract (NIP)

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Bhatti Enterprises		M/s Rehmatullah Shaikh	
					CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)
12	Item # 6a(ii) / P-16,17 /Vol-III,Part-II, (General)	RCC CONCRETE SUPER-STRUCTURE-Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid seperately.This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)										
i)		Column	9	M ³	12326.68	110,940.12	13805	124,245.00	12900	116,100.00	16000	144,000.00
ii)		Beams, Lintels, Projections, Pads, brackets and Sills	4	M ³	12326.68	49,306.72	13805	55,220.00	12900	51,600.00	13200	52,800.00
iii)		Slab i/c Projection	4	M ³	12326.68	49,306.72	13805	55,220.00	12900	51,600.00	13500	54,000.00
13	Item # 8b / P-17 /Vol-III,Part-II, (General)	STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting,bending,laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	2	Ton	100034.00	200,068.00	120000.00	240,000.00	114000.00	228,000.00	125000.00	250,000.00
14	Item # 5(1e) / P-21 /Vol-III,Part-II, (General)	BRICK MASONRY Providing and laying pucca brick masonry work (1st class quality) in ground floor super structure up to any height and at any floor etc. laid and jointed with 1:6 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	14	M ³	4476.58	62,672.12	5013.00	70,182.00	4500.00	63,000.00	5651.00	79,114.00

DR. FARHAN FAROOQ
P.O (KSE2)

MR. YOUSUF SHAIKH
Asst Comm

MS SANAA UMAR ALI
Asst manger contract (NIP)

S.No	GOVT. OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Shafi Enterprises		M/s Rehmatullah Sheikh	
					CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)
15	Item # 4(1c) / P-21 / Vol.III, Part-II, (General)	BRICK MASONRY STEPS Providing and laying pucca brick work (1st class quality) in foundation and plinth for entrance steps laid and jointed with 1:4 cement sand mortar using approved quality screened sand masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. For Steps and where required	1	M ³	4415.50	4,415.50	4944.00	4,944.00	4500.00	4,500.00	6315.00	6,315.00
16	Item # 84(a) / P-108 / Vol.III, Part-II, (General)	ALUMINIUM WINDOWS / VENTILATORS Supplying & fixing in position Aluminium channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminium fly screen 1/c handles stoppers & locking arrangement etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	5	M ²	17137.34	85,686.70	19193.00	95,965.00	17500.00	87,500.00	19300.00	96,500.00
17	Item # 13c / P-52 / Vol. III, Part-II, (General)	PLASTER (INTERNAL WALL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to internal walls, columns, beams, etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	42	M ²	278.74	11,707.08	311.00	13,062.00	300.00	12,600.00	320.00	13,440.00
18	Item # 30a+b / P-73 / Vol.III, Part II, (General)	PAINT (INTERNAL WALL SURFACE) Providing and applying painting on all internal wall surface with Enamel Paint of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	42	M ²	152.98	6,425.16	170.00	7,140.00	175.00	7,350.00	310.00	13,020.00
19	Item # 11b / P-52 / Vol. III, Part-II, (General)	PLASTER (INTERNAL CEILING SURFACE) Providing and applying 12mm (1/2") thick cement plaster to internal ceiling, soffits of beams and projections etc. with cement mortar 1:4 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	25	M ²	245.75	6,143.75	274.00	6,850.00	295.00	7,375.00	402.00	10,050.00

19
 Dr. FARHAN FAROOQ
 P.O (KSE2)

MR. YOUSUF SHEIKH
 Asst Comm

MS. SARA UMMAIR ALI
 Asst manager contracts (NIP)

S.No	GOVT. OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Bhatti Enterprises		M/s Rehmatullah Shaikh	
					CSR SINDH SCHD. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)
24	Item # 5d(i,ii)/ P-70 / Vol.III, Part II, (General)	PAINT (ON MS WORKS) Providing and applying preparing the surface and painting in all types of MS guard bars, gates of iron bars, grating, railings (including standard braces etc) and similar open work with priming coat / enamel coating of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (At any height)	262	M ²	136.74	35,825.88	152.00	39,824.00	150.00	39,300.00	210.00	55,020.00
Total of Schedule Items						3,018,059.09	3,408,272.00	3,492,437.00	4,611,612.00			
% ___ above / below on Schedule items					30%	905,417.73						
Total Amount of Schedule Items-A						3,923,476.82	3,408,272.00	3,492,437.00	4,611,612.00			
PART-B (NON-SCHEDULE ITEMS)												
25		ROOF PROTECTION Provide and lay roof treatment as per specifications, and shown in drawings and details shown consisting of following items (For payment only Tile area will be measured) etc. complete in all respects and as directed by the Engineer. 1-1/2" thick tiles grouted with cement sand Mortar including making slope, curing, hacking and chipping of existing surface for bonding where necessary, etc. complete i) 2 layers of water proofing 3" mud filling / plaster with husk with curing etc. ii) 2 layers of polythene sheets 004"-005" thick iv) Bitumen flood coat 10/20 grade 35 lbs / 100 sft v) Bitumen flood coat 70/90 grade 5 lbs / 100 sft	26	M ²	1614.00	41,964.00	600.00	15,600.00	2700.00	70,200.00	3700.00	96,200.00

DR. FARHAN FAROOK
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst Comm

MS. SANVA UMAIR-ALI
Asst manager contract (NIP)

Construction of Gate Office

S.No	GOVT.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Bhatti Enterprises		M/s Rehmatullah Shaikh	
					CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)
26		DOOR SHUTTER Providing and fixing 38mm thick solid core soft wood filling flush door shutters with 1/8" thick commercial ply on either sides complete cross band of standard specification with 5/8" thick edge solid Red maranti wood lipping all around, as produced by standard manufacturers under power driven hydraulic press as approved by the Engineer-in charge including 11/ 2" x 1/2" Red maranti wood beading / Architraves, approved Local Lock, 9" Tower bolt, Door Stopper etc., painting 3 coats with approved enamel paint over a coat of primer (at any floor & height) as per drawing and specifications and to the entire satisfaction of the Engineer.	3	M ²	5380.00	16,140.00	800.00	2,400.00	32000.00	96,000.00	12300.00	36,900.00
27		FLOORING Providing and laying 9 mm thick floor of Porcelain tiles Matt size 300 x 300 in grey cement, bedding material with cement sand mortar (1:6) including setting the tiles with cement slurry over mortar, jointing and washing the tiles with cement slurry of matching color, grinding, rubbing, polishing and curing etc. complete as per drawings, specifications and approval of the Engineer.	16	M ²	3228.00	51,648.00	1800.00	28,800.00	2950.00	47,200.00	2240.00	35,840.00
28		SKIRTING Providing and fixing Porcelain tiles Matt 12" x 12" x 1/4" (or equivalent in mm) on skirting in grey cement, with cement sand mortar base (1:6) including setting the tiles with cement slurry over mortar, jointing and matching color, and curing etc. complete as per drawings, specifications and approval of the Engineer.	16	RM	492.00	7,872.00	1400.00	22,400.00	1450.00	23,200.00	2809.00	44,944.00
29		RAIN WATER DRAIN Providing and fixing 75 mm dia UPVC pipe for rain water drain of approved class and make complete with SS jali and all required necessary clamps, fittings, jointing material and mastic filling silicon etc. complete in all respects as per drawing, specifications and as directed by the Engineer. (up to any height).	5	RM	1969.00	9,845.00	500.00	2,500.00	1800.00	9,000.00	1550.00	7,750.00

Lambani

 DR. FARHAN FAROOQ
 P.O (KSEZ)

 MR. YOUSUF SHIEKH
 ASST COMM

 Ms. SANVA UMAIR ALI
 ASST manager contract (NIP)

Construction of Gate Office

S.No	GOVT.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Bhatti Enterprises		M/s Rehmatullah Shaikh	
					CSR SINDH SCHED. 2012 RATE / Non Schedule Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)	Rate (Rs.)	AMOUNT (Rs.)
30		G.I DOOR FRAME Providing, making and fixing G.I molded sheet 16 Swg door frame size 2"x5" including steel hinges 3 Nos. fixing with cements sand mortar (1:6) painting 3 coats with approved enamel paint over a coat of primer (at any floor & height) as per drawing and specifications and to the entire satisfaction of the Engineer. (Door frame)	6	RM	984.00	5,904.00	500.00	3,000.00	9000.00	54,000.00	810.00	4,860.00
Total Amount of Non-Schedule Items - B						133,373.00		74,700.00		299,600.00		226,494.00
TOTAL CARRIED TO GRAND SUMMARY (A + B)						4,056,850		3,482,972		3,792,037		4,838,106

Lakhan
DR. FARHAN FAROOQ
P.D (KSE2)

Yousuf Shaikh
MR YOUSUF SHAIKH
Asst Comm

Sana Umair Ali
Ms. SANA Umair Ali
Asst manger comm (M/P)

Item Nos.	Description	Unit	Qty.	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Bhatti Enterprises		M/s Rehmatullah Shaikh		
				Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	
NON SCHEDULE ITEMS												
1	LIGHTING FIXTURES Supply, installation, testing and commissioning of following light fixtures complete with Electronic ballast (unless mention otherwise), lamps, lamps holder, mounting accessories etc. or as per specification, complete in all respects. Lighting fixtures Sample must be submitted to consultant for approval.											
	a) Wall mounted Fluorescent Light Fixture Philips TMS Type with 1 x 36W TLD. Color 84	Nos.	2	3,500	7,000	1,500	3,000			-	1,600	3,200
	b) Wall mounted Flood Light Fixture Philips CON TEMPO RVP-250 Type weatherproof (IP 65) with 1 x 150W SON-T Lamp.	Nos.	4	20,200	80,800	1,500	6,000			-	14,000	56,000
	c) Wall mounted Light Fixture Philips type weatherproof with 18W CFL Lamp (IP-54)	Nos.	3	5,300	15,900	1,200	3,600			-	800	2,400
2	L.V DISTRIBUTION BOARDS Supply, installation, testing & commissioning of wall mounted LV Distribution Boards (DB's) as per single line diagram, dust protected, vermin proof housing coated with approved color including all mounting accessories as per specification & drawing complete in all respect.											
	i Distribution Board (DB-GR)	Job	1	40,950	40,950	100,000	100,000			-	30,000	30,000
3	LOW VOLTAGE CABLES Supply, installation, testing and commissioning of following size of multi core PVC insulated, PVC sheathed unarmoured copper conductor 0.6 kV/1 kV voltage grade cable in already laid raceways or in trench including all accessories lugs, cable gland etc. as per drawings and specification.											
	i 1 x 4 Core - 16 Sq.mm PVC/PVC + 1 x 1-core 16 Sq.mm PVC as ECC	Rm	10	1,700	17,000	1,200	12,000			-	1,400	14,000

DR. FARHAN FAROOQ
P.O (KSF2)

MR. YOUSUF SHIEKH
Asst Comm

MS. SANA UMAIR KHAN
Asst manger contract (WIP)

Item Nos.	Description	Unit	Qty.	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Bhatti Enterprises		M/s Rehamatullah Shaikh	
				Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)
4	WIRINGS										
a	Supply, installation, testing & commissioning of Circuit wiring from DB to switch board with 3x2.5 sq.mm single core, Cu. conductor PVC insulated wires including 20 mm dia. PVC conduit surface / recessed in wall, column, ceiling, etc., complete with all accessories as per specification, complete in all respect.	No.	1	6,440	6,440	800	800			2,000	2,000
b	Supply, installation, testing & commissioning of Point wiring from switch board to light point with 3x1.5 sq.mm. wires in 20 mm dia PVC conduit, surface / recessed with all accessories, or as per specification, complete in all respect.	Nos.	5	2,380	11,900	600	3,000			2,100	10,500
c	Supply, installation, testing & commissioning of Circuit wiring from DB to Flood Light point with 3x2.5 sq.mm single core, Cu. conductor PVC insulated wires including 20 mm dia. PVC conduit surface / recessed in wall, column, ceiling, etc., complete with all accessories as per specification and drawing, complete in all respect.	No.	1	6,440	6,440	800	800	3,000	3,000	2,000	2,000
d	Supply, installation, testing & commissioning of Point wiring for flood light point to flood light point with 3x2.5 sq.mm. wires in 20 mm dia PVC conduit, surface / recessed with all accessories, or as per specification, complete in all respect.	Nos.	3	3,080	9,240	3,000	9,000	9,786	29,358	2,500	7,500
5	LIGHTING CONTROL SWITCH										
	Supply, installation, testing and commissioning of following 10 Amps switches, including 16 SWG sheet steel powder coated back boxes, recessed on wall with all accessories, as per drawing and specification, complete in all respects.										
i	Five gang switch	No.	1	935	935	500	500	7,300	7,300	1,200	1,200
ii	One gang dimmer with switch 10A	No.	1	1,720	1,720	250	250	3,500	3,500	450	450

Zachar
DR FARHAN FAROOQ
P.O (KSG2)

M. Yousof Shaikh
MR. YOUSUF SHAIKH
Asst. Comm

S. Sana Umair Ali
Ms. SANA UMAIR ALI
Asst manager Cantt-vel (CWSIP)

Item Nos.	Description	Unit	Qty.	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Bhatti Enterprises		M/s Rehmatullah Shaikh	
				Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)
6	SWITCH SOCKET OUTLET Supply, installation, testing and commissioning of following 3 pin, 5 Amps, switch socket outlets including 16 SWG sheet steel powder coated back boxes, recessed on wall with all accessories, complete in all respects. i 5A, 3 Pin Universal switched socket outlet	No.	1	840	840	700	700	1,800	1,800	750	750
7	CONDUIT Supply & installation of following size (inner dia) PVC conduit as race ways with all accessories recessed/ surface on wall / column / under floor for Power. As per relevant specification, complete in all respect. i 20 mm dia	Rm	10	85	850	500	5,000	1,900	19,000	80	800
8	FAN a Supply, installation, testing and commissioning of 56" Sweep ceiling fan with hook including all connecting accessories as per drawings, specifications, complete in all respects.	No	1	5,600	5,600	4,200	4,200	4,700	4,700	4,500	4,500
9	EARTHING Supply, installation, testing and commissioning of following items for complete earthing system including all connecting accessories as per drawings & specifications complete in all respects. i Earth pit with Rod type earth electrode, 20mm dia 3 meter long copper rod including earthing lead 2x70 sq.mm Bare copper conductor. ii 1 x 1 Core - 16 Sq.mm as ECC	Job	1	35,000	35,000	90,000	90,000	4,900	4,900	50,000	50,000
10	uPVC Pipe Providing and laying of size of 50 mm internal dia uPVC class "D" pipe. Buried in ground as per drawing. Including excavation for laying of pipe and backfilling with clean sand (under and above pipe), compaction nylon rope 5mm and plugging of conduits ends etc. as shown on drawing complete in all respect.	Rm	20	600	12,000	300	6,000	180	3,600	1,968	39,360

Farooq
DR FARHAN FAROOQ
P.O (KSE2)

Yousuf
MR YOUSUF SHIEKH
Asst Comm

Sana
MS. SANA UNAIR ALI
Asst. manger contracts (NIP)

Item Nos.	Description	Unit	Qty.	Engineer's Estimate		M/s Sikandar Ali Khokhar		M/s Bhatti Enterprises		M/s Rehmatullah Shaikh	
				Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)
11	TELECOMMUNICATION SYSTEM										
a	Providing, fixing, testing & commissioning of RJ-11 Telephone outlet (simplex) Weatherpoof type with 16 SWG back box, complete in all respect.	No	1	850	850	8,000	8,000	50,000	50,000	1,550	1,550
b	Providing, fixing, testing & commissioning of wiring 2 pair CAT-5 cable in 25mm dia PVC Conduit from TJB to Telephone outlet as per drawing or as per specification, complete in all respect.	Rm	20	140	2,800	350	7,000	300	6,000	670	13,400
GRAND TOTAL FOR ONE UNIT						260,765		292,850		136,608	242,310

Farooq
DR. FARHAN FAROOQ
 P.D (KSEZ)

Yousuf Sheikh
MR. YOUSUF SHEKH
 Asst. Comm

Sana Ullah Ali
Ms. SANA ULLAH ALI
 Asst. Manager Contracts/WIP


KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)

NATIONAL INDUSTRIAL PARKS DEVELOPMENT & MANAGEMENT COMPANY


"Construction of Tube Well & Pump House"


ATTENDANCE SHEET

TECHNICAL AND FINANCIAL BID OPENING (March 15, 2017; 3:00 P.M)

S.N	Name of Firm	Representative's Name	Contact Number	Representative signature.	Remarks.
1	M/s Nariman Const. Co	NOT PARTICIPATED			
2	M/s Rehmatullah Shaikh				
3	M/s Sikandar Ali Khokhar	Tasique Hussain	0300-2904927		OK
4	M/s Blue Stone	NOT PARTICIPATED			


Project Director
Khairpur Special Economic Zone (KSEZ)


Assistant Commissioner
Commissioner Office, New Sukkur
Rep: Commr Sub


Assistant Manager Contracts
National Industrial Parks

KHAIRPUR SPECIAL ECONOMIC ZONE

National Industrial Parks Development & Management Company

"Construction of Tube Well & Pump House"

Date: March 15, 2017 Time: 3:00 p.m.

Bid Opening Statement

S.N	Name of Contractor	Bid Details	Bid Amount (Rs.)	Rebate Amount (Rs)	Net Bid Amount(Rs)	Submitted Bid Security Amount (Rs)	Bid Security Detail	Remarks
1	M/s Nariman Const. Co	}	_____	NOT	PARTICIPATED	_____	_____	}
2	M/s Rehmatullah Shaikh							
3	M/s Sikandar Ali Khokhar	1 original + 2 copies	23,755,394/-	-	23,755,394/-	550,000/-	CDR:00243526 (13-03-17) Silk Bank	OK
4	M/s Blue Stone	_____	_____	NOT	PARTICIPATED	_____	_____	_____

*Required Bid Security is 2%


Project Director
Khairpur Special Economic Zone (KSEZ)



Assistant Commissioner
Commissioner Office, New Sukkur
Rep: Commissioner Sukkur


Assistant Manager Contracts
National Industrial Parks


Bid Evaluation Report

1. Name of Procuring Agency: **KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)**
2. Tender Reference No: **Nil**
3. Tender Description/Name of work/item: **Construction of Tube Well & Pump House**
4. Method of Procurement: **Single Stage – Single Envelope**
5. Tender Published: **The News, Jang and Kawish dated Feb. 17, 2017**
6. Total Bid documents Sold; **04 (Four)**
7. Total Bids Received: **01 (One)**
8. Technical Bid Opening date: **March 15, 2017**
9. No. of Bid technically qualified: **None**
10. Bid(s) Rejected: **The only bid, due to the reasons given below**
11. Financial Bid Opening date: **March 15, 2017**
12. Bid Evaluation Report:

S.N	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/ rejection	Remarks
1	M/s Sikandar Ali Khokhar	28,109,411/-	Only Bidder	19.25 % below	Not meeting Eligibility Criteria	Non-Responsive



Dr. Farhan Farooq
Project Director
Khairpur Special Economic Zone (KSEZ)



Mr. Yousuf Shiekh
Assistant Commissioner,
Commissioner Office, New Sukkur




Ms. Sana Umair Ali
Assistant Manager Contracts
National Industrial Parks


PROJECT OFFICE KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ), KHAIRPUR
 BID EVALUATION REPORT
 FOR CONSTRUCTION OF TUBE WELL PUMP HOUSE


ANNEXURE - D

Results of Preliminary Examination Requirements / **TECHNICAL EVALUATION**

Description	M/s Sikandar Ali Khokhar
2	1
1. Bid Submission Requirements: Cover Letter	Not Provided
Bid Form	Provided
2. Eligibility Criteria: (As per NIT) Valid Pakistan Engineering Council (PEC) registration in Category "C5" and above in discipline CE-9 & CE-10	C3 & CE-10 Provided
Valid NTN certificate from Income Tax Authorities	Provided
Should be in Construction Business for the last 5 years or more	Provided
Affidavit that the firm is not Blacklisted or engaged in any Litigation on any Project.	Provided
Should have completed 2 contracts of similar nature and value of Pak Rs 30.00 million in the last 5 years.	Provided 11.9 million work
3. Substantial Responsiveness	No
4. Accepted for Detailed Examination	Yes


 DR. FARHAN FAROOQ
 Project Director
 (KSEZ)


 MR. YOUSUF SHIEKH
 Asst. Commissioner,
 Commissioner Office,
 New SUKKUR


 Ms. SANA ULLAH
 Asst Manager Contracts
 (NIP)

GRAND SUMMARY

Sl.No	DESCRIPTION	Engineer's Estimate	M/s Sikandar Ali Khokhar
		AMOUNT (Rs.)	AMOUNT (Rs.)
A	SUBMITTED AMOUNT	-	23,755,394
B	AFTER ARITHMETIC CHECK		
1	Civil Works		
	Construction of Tube Well	2,050,809	1,335,600
	Construction of Pump House	3,439,004	3,918,156
2	Pipe and Fittings Works	28,367,515	22,155,655
3	Electrical Works (Pump House)	952,000	700,000
		34,809,328	28,109,411
	Difference (B - A)		4,354,017
	% below/above Engineer's Estimate ----->		-19.25%

Zabban

DR. FARHAT FAROQ
P.O (KSEZ)

Yousuf

MR. YOUSUF SHIEKH
Asst comm

Sikandar Ali

MS. SANIA UMMAIR ALI
Asst Manager Construction

Construction of Tube Well

GOVT. OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar	
				CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
Item #/Page#/ Vol. sched. ref.							
PART-A (SCHEDULE ITEMS)							
Item # 1(g) P-41 / Vol-III, Part- II, Public Health Eng. Works	DRILLING AND BORING Boring for tube well in all types of water bearing soils from ground level upto 100 ft. or 30.5 meter depth including sinking and with drawing of casing pipe etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. 300 mm (12" dia)	31	RM	2,437.78	75,571	2,925.00	90,675
Item # 2(e) P-42 / Vol-III, Part- II, Public Health Eng. Works	Boring for tube well in all types of water bearing soils from depth (100.10 to 200 ft) or 30.51 meter below ground level including sinking and with drawing of casing pipe etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. 300 mm (12" dia)	31	RM	2,785.57	86,353	3,343.00	103,633
Item # 3(e) P-42 / Vol-III, Part- II, Public Health Eng. Works	Boring for tube well in all types of water bearing soils from depth (200.10 to 300 ft) or (60.01 to 91.50) meter below ground level including sinking and with drawing of casing pipe etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. 300 mm (12" dia)	18	RM	3,244.91	58,408	3,894.00	70,092
Item # 13(g) P-45 / Vol-III, Part- II, Public Health Eng. Works	GRAVEL SHROUDING BETWEEN BOREHOLE AND PIPE Providing and filling Shrouding with graded bajri size (3/8" to 1/8") or (3. to 9 mm) in between bore hole & blind pipe etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	80	RM	633.23	50,658	760.00	60,800
Total Amount of Schedule Items-A (01 NO)					270,991		325,200
PART-B (NON-SCHEDULE ITEMS)							
	UPVC SCREEN PIPE CASING Providing, fixing and installation of screen & blind 200 mm dia uPVC pipe class "C" including all required necessary fittings and accessories (M.S Cone, nuts, screw, solution, centralizers, coupling and plug or cap etc.) with overlapping etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	80	RM	5,157.65	412,612	1,500.00	120,000
Total Amount of Non-Schedule Items-B (01 NO)					412,612		120,000
Total Amount of A+B (For 01 NO)					683,603		445,200
TOTAL CARRIED TO GRAND SUMMARY FOR (03 NOS)				3	2,050,809	3	1,335,600

Zahid
DR. FARHAN FAROOQ
 P.O (KSEZ)

Yousuf
MR. YOUSUF SHIKH
 Asst Comm

Sikandar Ali
MR. SANAM AIR
 Asst Manager (Civil)

Construction of Pump House

S.No	GOVT.OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar	
					CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)	CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
PART A (SCHEDULED ITEMS)								
1	Item # 18(b)-18(c) / P-4-75 / Vol-III, Part-II, (General & PHEW)	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation in foundation and dewatering in all kind of soil of building, bridges and other structures including dogbelling dressing refilling around structure with (suitable) excavated earth watering, ramming complete and disposal of surplus excavated material to designated area i/c all lead & lift, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	39	M ³	303.92	11,853	340.00	13,260
2	Item # 22+13 (b+ci) / P-3 & 4 / Vol-III, Part-II, (General)	IMPORTED EARTH FILLING FROM OUTSIDE SOURCES Supplying and filling watering and ramming earth under floor with new earth excavated from outside in 150mm layers leveling dressing and watering for compaction and to obtain 95% modified AASHTO density. Complete including all lead & lifts etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	64	M ³	167.42	10,715	188.00	12,032
3	Item # 2 / P-15 / Vol-III, Part-II, (General)	STONE SOLING Providing and laying dry rammed brick or stone ballast / soling 1-1/2" to 2" gauge from approved quarry including hand packing & filling voids with spraws & chips, consolidating & compacting with power or hand roller, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	33	M ²	1,175.27	38,784	1,316.00	43,428
4	Item # 5(i) / P-16 / Vol-III, Part-II, (General)	PCC CONCRETE (1:4:8) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing at stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	7	M ³	3,987.19	27,910	4,465.00	31,255
5	Item # 5(h) / P-16 / Vol-III, Part-II, (General)	PCC CONCRETE (1:3:6) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing at stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	6	M ³	4,448.55	26,691	4,983.00	29,898
6	Item # 19b(i+ii/2) / P-18 / Vol-III, Part-II, (General)	WOODEN FORMWORKS/SHUTTERING Providing, fixing, erecting and removal of partial wood centering (shuttering / formwork) of approved quality for RCC or plain cement concrete works etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	11	M ²	361.31	3,974	405.00	4,455
		Form work for 1:4:8 concrete	44	M ²	361.31	15,898	405.00	17,820

Lashan
DR. FARHAN FAROOQ
P. O (KSEZ)

Yousuf Shiekh
MR. YOUSUF SHIEKH
Asst. Comm

S. S. Ali
MR. SANJIV UNAG ALI
Asst. Manager (Civil)

COMPARATIVE STATEMENT

Sl#	GOVT. OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
	Item # 60iii / P-1617 / Vol-III, Part-II, (General)	RCC CONCRETE SUB-STRUCTURE- Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
		RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)						
		Footing and Concrete Pads	6	M ³	12,326.68	73,960	13,806.00	82,836
		Plinth Beams	2	M ³	12,326.68	24,653	13,806.00	27,612
		Column up to Plinth level	1	M ³	12,326.68	12,327	13,806.00	13,806
	Item # 8b / P-17 / Vol-III, Part-II, (General)	STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
			1	Ton	100,034	100,034	120,000	120,000
	Item # 9 / P-71 / Vol-III, Part-II, (General)	BITUMEN COATING Providing and applying industrial bitumen paint/coating to plastered or cement concrete surface etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
			110	M ²	83.72	9,209	94.00	10,340
	Item # 28b / P-19 / Vol-III, Part-II, (General)	(D.P.C) DAMP PROOF COURSE Providing and laying DPC damp proof course with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture with levelling, curing, finishing etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
			4	M ²	421.02	1,684	472.00	1,888
	Item # 92 / P-109 / Vol-III, Part-II, (General)	TERMITE TREATMENT Providing Anti-Termite treatment by spraying / sprinkling / spreading Neptachlor 0.5% Emulsion as an overall pre-construction treatment in slab type construction under the slab and along attached perches or entrances etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (Plinth area will be measured one time for payment whereas the number of applications will be three times on all horizontal & vertical surfaces of the excavations for termite proofing).						
			22	M ²	104.80	2,306	117.00	2,574

Farooq

DR. FARHAN FAROOQ
P.D (KSEZ)

Yousuf

MR. YOUSUF SHICKH
Asst. comm

Sana

MS SANA UMAIR ALI
Asst. manager (Civil)

GOV.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar	
				CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
Item #/Page#/ Vol/sched ref.							
					8 = (4 x 6)		8 = (4 x 6)
	RCC CONCRETE						
	SUPER-STRUCTURE -Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately.This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
Item # 6a(ii) / P-16,17 / Vol-III, Part-II, (General)	RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)						
	Column	2	M ³	12,326.68	24,653	13,806.00	27,612
	Beams, Lintels, Projections, Pads, brackets and Sills	2	M ³	12,326.68	24,653	13,806.00	27,612
	Slab i/c Projection	8	M ³	12,326.68	98,613	13,806.00	110,448
	STEEL REINFORCEMENT						
	Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
Item # 8b / P-17 / Vol-III, Part-II, (General)		1	Ton	100,034	100,034	120,000	120,000
	BRICK MASONRY						
	Providing and laying pacca brick masonry work (1st class quality) in ground floor super structure up to any height and at any floor etc. laid and jointed with 1:6 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
Item # 5(1e) / P-21 / Vol-III, Part-II, (General)		12	M ³	4,476.58	53,719	5,015.00	60,180
	BRICK MASONRY STEPS						
	Providing and laying pacca brick work (1st class quality) in foundation and plinth for entrance steps laid and jointed with 1:4 cement sand mortar using approved quality screened sand masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
Item # 4(1c) / P-23 / Vol-III, Part-II, (General)	For Steps and where required	1	M ³	4,415.50	4,416	4,945.00	4,945
	ROOF TREATMENT						
	Provide and lay roof treatment over roof & skirting as per specifications, as shown in drawings & details, consisting of following items.						
Item # 16c+75 / P-42.50 / Vol-III, Part-II, (General)	Provide and laying 2" (50 mm) thick topping cement concrete 1:2:4 screed floor including surface finishing, leveling curing and dividing into panels with P/fixing glass strip 4mm for flooring up to 1" depth of specified pattern & design etc.	37	M ²	472.53	17,483	530.00	19,610
Item # 13 / P-35 / Vol-III, Part-II, (General)	Provide and apply 2 coats of bitumen laid hot using @ 34 lbs for % sfl over roof screed and blinded with sand at one CfI.Per % sfl	37	M ²	203.08	7,514	228.00	8,436

Larigan

DR. FARHAN FAROOQ
P.O (KSEZ)

Yousuf Shikhan

MR. YOUSUF SHIKHAN
Asst Comm

C.S. Page No. 3

Sikandar Ali Khokhar

MS. SANA KHAN ALI
Asst manager (N/A)

Sl. No.	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Silkandar Ali Kholchar	
					CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)	CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
		RCC CONCRETE						
12	Item # 6a(ii) / P-16,17 / Vol-III, Part-II, (General)	<p>SUPER-STRUCTURE-Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds, lifting, fixing of shuttering and its removal and vibrating, curing, reworking and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p> <p>RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)</p>						
		Column	2	M ³	12,326.68	24,653	13,806.00	27,612
		Beams, Lintels, Projections, Pads, brackets and Sills	2	M ³	12,326.68	24,653	13,806.00	27,612
		Slab i/c Projection	8	M ³	12,326.68	98,613	13,806.00	110,448
		STEEL REINFORCEMENT						
		Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
13	Item # 8b / P-17 / Vol-III, Part-II, (General)		1	Ton	100,034	100,034	120,000	120,000
		BRICK MASONRY						
		Providing and laying pacca brick masonry work (1st class quality) in ground floor super structure up to any height and at any floor etc. laid and jointed with 1:6 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
14	Item # 5(1e) / P-21 / Vol-III, Part-II, (General)		12	M ³	4,476.58	53,719	5,015.00	60,180
		BRICK MASONRY STEPS						
		Providing and laying pacca brick work (1st class quality) in foundation and plinth for entrance steps laid and jointed with 1:4 cement sand mortar using approved quality screened sand masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.						
15	Item # 4(1c) / P-21 / Vol-III, Part-II, (General)	For Steps and where required	1	M ³	4,415.50	4,416	4,945.00	4,945
		ROOF TREATMENT						
		Provide and lay roof treatment over roof & skirting as per specifications, as shown in drawings & details, consisting of following items.						
		Provide and laying 2" (50 mm) thick topping cement concrete 1:2:4 screed floor including surface finishing, levelling curing and dividing into panels with P/fixing glass strip 4mm for flooring up to 1" depth of specified pattern & design etc.	37	M ²	472.53	17,483	530.00	19,610
16	Item # 16c+75 / P-42,50 / Vol. III, Part-II, (General)		37	M ²	472.53	17,483	530.00	19,610
		Provide and apply 2 coats of bitumen laid hot using @ 34 lbs for % sfl over roof screed and blinded with sand at one Cfl. Per % sfl	37	M ²	203.08	7,514	228.00	8,436

Lashan

DR. FARHAN FAROQI
P.O (KSEZ)

Yousuf Shiekh
MR. YOUSUF SHIEKH
Asst. Comm

Silkan Ali Kholchar
Ms. SANA Umeer Ali
Asst manager (M/P)

S.No	GOVT.OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
17	Item # 16c+75 / P-42.50 / Vol. III,Part-II, (General)	FLOORINGS Providing and laying 2" (50 mm) thick topping cement concrete 1:2:4 floor including surface finishing, leveling curing and dividing into panels with P/fixing glass strip 4mm for flooring up to 1" depth of specified pattern & design with steel trowel finished maintaining proper level etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	19	M ²	472.53	8,978	530.00	10,070
18	Item # 13c / P- 52 / Vol. III,Part- II,(General)	PLASTER (INTERNAL WALL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to internal walls, columns, beams, etc. with cement mortar 1:6 ic all corners, recesses, jambs, raking out joints of masonry, scaffolding etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	70	M ²	278.74	19,512	313.00	21,910
19	Item # 30a+b / P-73 / Vol.III,Part II, (General)	PAINT (INTERNAL WALL SURFACE) Providing and applying painting on all internal wall surface with Enamel Paint of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	70	M ²	152.98	10,709	172.00	12,040
20	Item # 11b / P- 52 / Vol. III,Part- II,(General)	PLASTER (INTERNAL CEILING SURFACE) Providing and applying 12mm (1/2") thick cement plaster to internal ceiling, soffits of beams and projections etc. with cement mortar 1:4 ic all corners, recesses, jambs, raking out joints of masonry, scaffolding etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	18	M ²	245.75	4,424	276.00	4,968
21	Item # 23+24a+b+c / P- 54 / Vol.III,Part II, (General)	PAINT (INTERNAL CEILING SURFACE) Providing and applying painting on all internal ceiling surface with Berger Robbialac or equivalent Oil Bound Distemper of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	18	M ²	340.94	6,137	382.00	6,876
22	Item # 13c / P- 52 / Vol. III,Part- II,(General)	PLASTER (EXTERNAL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to external walls, columns, beams, etc. with cement mortar 1:6 ic all corners, recesses, jambs, raking out joints of masonry, scaffolding etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	106	M ²	278.74	29,546	313.00	33,178

Zarbin
DR. FARHAD FAROQ
P.O (KSEZ)

M. Yousuf Shiekh
MR. YOUSUF SHIEKH
Asst. Comm

S. Sana Umair Ali
MS. SANA UMAIR ALI
Asst manager (N/A)

Sl No	GOVT OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
23	Item # 38a+b+b / P-56 / Vol.III, Part II, (General)	PAINT (WEATHERSHIELD ON EXTERNAL SURFACE) Providing and applying preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick /sand paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire satisfaction of MS WORKS	106	M ²	276.31	29,289	310.00	32,860
24	Item # 2+3 / P-91/ Vol.III, Part II, (General)	Providing, fabrication, erecting and fitting in position of heavy steel works with (angles,tees,flat iron, round iron and sheet iron for making trusses, girders, tanks etc.including cutting tanks etc. including cutting, drilling, riveting, handling assembling and fixing in position etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. i For MS Louvered Door ii For MS Windows iii For MS Girder (Size 150X100)	215 255 84	Kg Kg Kg	103.99 103.99 103.99	22,358 26,518 8,735	117.00 117.00 117.00	25,155 29,835 9,828
25	Item # 5d(i,ii)/ P-70 / Vol.III, Part II, (General)	PAINT (ON MS WORKS) Providing and applying preparing the surface and painting in all types of MS guard bars, gales of iron bars, grating, railings (including standard braces etc) and similar open work with priming coat / enamel coating of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire	18	M ²	136.74	2,461	154.00	2,772
Total Amount of Schedule Items-A (01 NO)						859,751		979,539
TOTAL CARRIED TO GRAND SUMMARY FOR (04 NOS)					4	3,439,004	4	3,918,154

Farooq
DR. FARHAN FAROOQ
P.O (KSEZ)

Yousuf Sultkh
MR. YOUSUF SULTKH
Asst Comm

Sana Umaid Ali
MS. SANA UMAID Ali
Asst Manager (Civil)

COMPARATIVE STATEMENT

PIPE AND FITTINGS

to	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol. sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
PART A (SCHEDULE ITEMS)								
	m # 18007 75/ Vol. III, PHEW)	EXCAVATIONS INCLUDING DEWATERING Excavation for pipe line in trenches, and test pits upto 1.5m depth in all kind of soft soils i/c trimming and dressing sides to true alignment, and slope, leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within a one chain as directed by the Engineer, providing fence guard light flags and temporary crossing for non vehicular traffic where ever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5 m) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	263	M ³	318.85	83,858	358.00	94,154
	Item # 29 /P-26/Vol-III, Part- II, (General)	SAND BEDDING Supplying and filling sand under and around the pipe floor and plugging in walls with watering, leveling and dressing including all lead & lifts etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	26	M ³	403.09	10,480	453.00	11,778
	Item # 24 / P-77 /Vol III, Part-III, 'EW)	BACKFILLING Refilling the excavated stuff in trenches 6". thick layer i/c watering ramming to full compaction etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	232	M ³	97.46	22,611	110.00	25,520
	/ P- art-II,	THRUST BLOCK (RATIO 1:2:4 WITH 3000 Psi) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing of stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	1	M ³	4,448.55	4,449	4,983.00	4,983
	m # ii/2) / P-18 of-III, Part-II, (General)	WOODEN FORMWORKS/SHUTTERING FOR THRUST BLOCK Providing, fixing, erecting and removal of partial wood centering (shuttering / formwork) of approved quality for RCC or plain cement concrete works etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	40	M ²	361.31	14,453	406.00	16,240
		Form work for 1:2:4 concrete Thrust Block						

Farhan

DR. FARHAN FAROOQ
P.D (KSEZ)

Yousuf Shiekh
MR. YOUSUF SHIEKH
Asst. Comm

Sikandar Ali
Ms. SANAM UMEED ALI
Asst manager (M/P)

COMPARATIVE STATEMENT

PIPES AND FITTINGS

Sl. No.	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol. scheduled ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
		MS PIPE Manufacturing, supplying & fixing Black Steel M.S Pipe made out of M.S sheet conforming to API 5L grade X-42 ERW and externally asphalt coated with fiber glass 5mm thick and internally C.C lining 8mm thick having 1:3 cement mortar (AWWA specification), i/c laying, jointing with helical welding in trenches i/c cost of bends of any degree and testing with water specified pressure for different dia of pipe as mentioned etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. 150 mm I.D (5.6mm thick)	331	RM	4,232.16	1,400,845	5,080.00	1,681,480
Total Amount of Schedule Items-A						1,536,695		1,834,155
		MS FITTINGS Providing, Laying and jointing, testing and disinfection of M.S fittings with flange for M.S pipes in trenches to correct alignment complete in all respect as indicated in the drawing and specifications including nuts, bolts, washers, rubber gaskets, etc. and all other accessories, equipment for laying and jointing etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. Bends 150 mm I.D (90° Degree) 150 mm I.D (22.5° Degree). Puddle Flange For 150 mm Dia Pipe GATE VALVE Providing, fixing, jointing and testing of Gate valve with extra flanges of approved quality, including nut, bolts gasket and washers etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. 150 mm I.D. NON RETURN VALVE Provide and install imported flanged non return valve with flanges required from approved manufacturers of Japan/Europe/USA including etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. 150 mm I.D CHAIN PULLEY Providing, installation and testing of lifting devices i.e. hoists including chain pulley jacks, Hooks etc having capacity 2500 kg complete set in the drawings and specifications. Lifting devices to be connected to hook of the hoist / crane/Tripod stand and shall be as per specifications and Engineers Recommendation, etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	17	No	3,000.00	51,000	8,000.00	136,000
			1	No	1,500.00	1,500	10,000.00	10,000
			4	No	9,000.00	36,000	12,000.00	48,000
			4	No	37,015.00	148,060	9,000.00	36,000
			4	No	91,440.00	365,760	9,000.00	36,000
			4	Set	20,000.00	80,000	185,000.00	740,000

Zarfar
DR. FARHAN FAROOQ
P.O (KSEZ)

Zyamin
MR. YOUSUF SHIEKH
Asst Comm

Sikandar Ali
Ms. SANJA Umai Ali
Asst manager (A/E)

COMPARATIVE STATEMENT

PIPE AND FITTINGS

Sl. No.	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol. sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Sikandar Ali Kholchar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
11		MS CLAMP Providing and fixing MS clamp for pipe support including nuts, bolts and all required accessories etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	33	Each	4,500.00	148,500	3,500.00	115,500
12		INSTALLATION OF PUMPING MACHINERY Providing, installing testing and commissioning of Deep well turbine pump including cost of motor of approved quality and required H.P. having rpm not exceeding 1450, i/c the cost of all fittings and accessories & also i/c the cost of electrical panels with all electrical fittings and fixture for a complete operating pump set for discharge and head etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. Pumps 102.0 m ³ /hr (374 GPM) and head of 115 m (1 duty).	4	No	6,500,000	26,000,000	4,800,000	19,200,000
Total Amount of Non-Schedule Items-B						26,830,820		20,321,500
TOTAL CARRIED TO GRAND SUMMARY (A+B)						28,367,515		22,155,655

Farhan
DR. FARHAN FAROOQ
P.O (KSEZ)

Yousuf
MR. YOUSUF SHIEKH
Asst Comm

Sikandar Ali Kholchar
M/s. SANAA Umair Ali
Asst manager (N/A)

Item Ref.	Description	Unit	Quantity	Engineer's Estimate		M/s Silcandar Ali Khokhar	
				Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)
NON-SCHEDULED ITEMS							
1.0	ELECTRIFICATION OF PUMP ROOM						
a)	Supply, installation, testing & commissioning of all Electrical Works for Pump Room as per drawing and specification, complete in all respect.	Job.	1	238,000	238,000	175,000	175,000
TOTAL AMOUNT (Rs.)					238,000		175,000
TOTAL CARRIED TO GRAND SUMMARY FOR (04 NOS)			4		952,000		700,000

Zarqin

DR. FARHAN FAROQI
P.O (KSEZ)

Yousuf

MR. YOUSUF SHIEKH
Asst. Comm

Silcandar Ali

MS. SANIA UMAIR ALI
Asst Manager (Inv)



KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)

NATIONAL INDUSTRIAL PARKS DEVELOPMENT & MANAGEMENT COMPANY

**"Construction of Effluent Pipeline from STP out Falling to Rohri Cana
Rd:85+263"**

ATTENDANCE SHEET

TECHNICAL AND FINANCIAL BID OPENING (March 15, 2017; 3:00 P.M)

S.N	Name of Firm	Representative's Name	Contact Number	Representative signature.	Remarks.
1	M/s Nariman Const. Co	Not Participated			
2	M/s Sikandar Ali Khokhar	Tarique Hussain	0300-290437		OK
3	M/s Blue Stone	Aamir	0300 2338188		OK
4	M/s M. Abdullah & Brothers	Not Participated			


Project Director
Khairpur Special Economic Zone (KSEZ)


Assistant Commissioner
Commissioner Office, New Sukkur

Rep: Commr Sukkur


Assistant Manager Contracts
National Industrial Parks

KHAIRPUR SPECIAL ECONOMIC ZONE

National Industrial Parks Development & Management Company

"Construction of Effluent Pipeline from STP out Falling to Rohri Cana Rd:85+26"

Date: March 15, 2017 Time: 3:00 p.m.

Bid Opening Statement

S.N	Name of Contractor	Bid Details	Bid Amount (Rs.)	Rebate Amount (Rs)	Net Bid Amount(Rs)	Submitted Bid Security Amount (Rs)	Bid Security Detail	Remarks
1	M/s Nariman Const. Co							
2	M/s Sikandar Ali Khokhar	1 original + 2 copies	39,214,707/-	-	39,214,707	1,400,000	CDR: 00243525 (13-03-17) Silk Bank	OK
3	M/s Blue Stone	1 profile + 1 original + 2 copies	30,671,372/-	-	30,671,372	625,000	PO: 50606580 (15-3-17) Sind Bank	OK
4	M/s M. Abdullah & Brothers							

*Required Bid Security is 2%

Farhan
Project Director
Khairpur Special Economic Zone (KSEZ)

My name
Assistant Commissioner
Commissioner Office, New Sukkur


Rep: commr Sukkur

S. M. Khan
Assistant Manager Contracts
National Industrial Parks

Bid Evaluation Report

1. Name of Procuring Agency: **KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)**
2. Tender Reference No: **Nil**
3. Tender Description/Name of work/item: **Construction of Treated Effluent Pipeline from STP out Falling to Rohri Canal Rd: 85+263**
4. Method of Procurement: **Single Stage – Single Envelope**
5. Tender Published: **The News, Jang and Kawish dated Feb. 17, 2017**
6. Total Bid documents Sold; **04 (Four)**
7. Total Bids Received: **02 (Two)**
8. Technical Bid Opening date: **March 15, 2017**
9. No. of Bid technically qualified: **02 (Two)**
10. Bid(s) Rejected: **None**
11. Financial Bid Opening date: **March 15, 2017**
12. Bid Evaluation Report:

S N	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/ rejection	Remarks
1	M/s Blue Stone	30,671,372/-	1 st Lowest	10.94 % below	Qualified as per criteria/ Responsive Bid	Recommended for Award of work
2	M/s Sikandar Ali Khokhar	39,214,708/-	2 nd Lowest	13.87% above	Qualified as per criteria	Responsive Bid



Dr. Farhan Farooq
Project Director
Khairpur Special Economic Zone (KSEZ)



Mr. Yousuf Shiekh
Assistant Commissioner,
Commissioner Office, New Sukkur



Ms. Sana Umair Ali
Assistant Manager Contracts
National Industrial Parks

Results of Preliminary Examination Requirements / **TECHNICAL EVALUATION**

S.No	Description	M/s Blue Stone Associate	M/s Sikandar Ali Khokhar
1	2	1	1
a	1. Bid Submission Requirements: Cover Letter	Provided	Not Provided
b	Bid Form	Provided	Provided
a	2. Eligibility Criteria: (As per NIT) Valid Pakistan Engineering Council (PEC) registration in Category "C5" and above in discipline CE-9 & CE-10	Provided	C3 & CE-9 & 10 Provided
b	Valid NTN certificate from Income Tax Authorities	Provided (Online Verification Page)	Provided
c	Should be in Construction Business for the last 5 years or more	Provided	Provided
d	Affidavit that the firm is not Blacklisted or engaged in any Litigation on any Project.	Provided	Provided
e	Should have completed 2 contracts of similar nature and value of Pak Rs 30.00 million in the last 5 years.	Provided	Provided
f	Average Annual Construction Turn Over for the last three years of Pak Rs 50 million	Provided	Provided
	3. Substantial Responsiveness	Yes	Yes
	4. Accepted for Detailed Examination	Yes	Yes

Farhan
DR. FARHAN FAROOQ
Project Director (KSE2)

Yousuf
Mr. YOUSUF SHIEKH
Assistant Commissioner,
Commissioner Office,
New SUKKUR

Sikandar Ali
Ms. SANA UMAIR ALI
Assistant Manager contracts
(NIP)

7/7

GRAND SUMMARY

S.No	DESCRIPTION	Engineer's Estimate	M/s Blue Stone Associate	M/s Sikandr Ali Khokhar
		AMOUNT Rs.	AMOUNT Rs.	AMOUNT Rs.
A	SUBMITTED AMOUNT	-	30,671,372	39,214,707
B	AFTER ARITHMETIC CHECK			
1	Civil Works Construction of Pump Room & Under ground Tank	3,623,165	3,824,972	4,871,240
2	Pipe Works	30,603,890	26,227,400	34,243,468
3	Electrical Works (Pump House)	212,000	619,000	100,000
		34,439,055	30,671,372	39,214,708
	Difference (B - A)		-	1
	% below/above Engineer's Estimate ----->		-10.94%	13.87%
	% above Lowest Bidder ----->		-	27.85%

DR. FARHAN FAROOQ
P.D. (KSE2)

MR. YOUSUF SHIEKH
Asst. Comm

Ms. SANJA Umaid Ali
Asst manager (NIP)



Construction of Pump Room & U.G Tank

S.No	GOVT.OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6=(4x5)	7	8=(7x5)	9	10=(9x6)	
PART-A (SCHEDULE ITEMS)										
1	Item # A(1)+18(i.ii)/ P-60+75/ Vol. III,Part-III, PHEW)	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation in foundation and dewatering in all kind of soil of building, bridges and other structures including dagbelling dressing refilling around structure with (suitable) excavated earth watering, ramming complete and disposal of surplus excavated material to designated area i/c all lead & lift. etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	326	M ³	303.92	99,078	300.00	97,800	341.00	111,166
2	Chapter-4 Item #.5(i) / P- 16 /Vol-III,Part-II, (General)	PCC CONCRETE (1:4:8) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing at stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.								
a)		Below foundation, plinth beam and floor and where required etc.	6	M ³	3,987.19	23,923	4,200.00	25,200	4,466.00	26,796

Farhan

Yousuf

Sana

DR. FARHAN FAROOQ
P.O.(KSE2)

MR. YOUSUF SHAIKH
Asst. Comm

Ms. SANA UMAIR ALI
Asst Manager (NIP)

S.No	GOVT.OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6	7	8	9	10	11
3	Chapter-4 Item # 19b(i+ii/2) / P-18 /Vol-III,Part-II, (General)	WOODEN FORMWORKS/SHUTTERING Providing, fixing, erecting and removal of partial wood centering (shuttering / formwork) of approved quality for RCC or plain cement concrete works etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. Form work for 1:4:8 concrete	3.25	M ²	361.31	1,174	290.00	942	406.00	1,320
4	Chapter-4 Item # 6a(ii) / P- 16,17 /Vol- III,Part-II, (General)	RCC CONCRETE (Sub -Structure) Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid seperately.This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. RCC Concrete Cylindrical strength 21 Mpa (3000 Psi) U.G Tank (Top & Bottom Slab + Wall)	90	M ³	12,326.68	1,109,401	11,900.00	1,071,000	13,807.00	1,242,630

Carson
DR. FARHAN FAROOQ
P.O (KSE2)

Yousuf Sheikh
MR. YOUSUF SHEIKH
Asst Comm

Sana Unnair Ali
MS. SANA UNNAIR ALI
Asst Manager Contract (NIP)

S.No	GOVT.OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6 = (4 x 5)	7	8 = (6 x 7)	9	10 = (8 x 9)	
5	Chapter-4 Item # 8b / P-17 /Vol-III,Part-II, (General)	STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	14.7	Ton	100.034	1,470,500	110,000	1,617,000	120,000	1,764,000
6	Chapter-11 Item # 9 / P-71 /Vol-III,Part-II, (General)	BITUMEN COATING Providing and applying industrial bitumen paint/coating to plastered or cement concrete surface etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	168	M ²	83.72	14,065	200.00	33,600	95.00	15,960

Farhan

Yousuf Shiekh

Sikandr Ali

DR. FARHAN FAROOQ
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst. Comm

Ms. SANA Umaid Ali
Asst Manager contract (NIP)

S.No	GOVT.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikañdr Ali Khokhar			
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)		
1	2	3	4	5	6 = (4x5)	7	8 = (6x7)	9	10 = (8x9)			
7	Chapter-4 Item # 6a(ii) / P- 16,17 /Vol- III,Part-II, (General)	<p>RCC CONCRETE</p> <p>SUPER-STRUCTURE-Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid seperately.This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p> <p>RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)</p>										
			i)	Pump Room (Slab & Beam)	9	M³	12,326.68	110,940	12,300.00	110,700	13,806.00	124,254
			ii)	Column	2	M³	12,326.68	24,653	12,300.00	24,600	13,806.00	27,612
			iii)	For Ramp	0.2	M³	12,326.68	2,465	12,300.00	2,460	13,806.00	2,761
8	Chapter-4 Item # 8b / P-17 /Vol-III,Part-II, (General)	<p>STEEL REINFORCEMENT</p> <p>Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting,bending,laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>										
					1.9	Ton	100,034	190,065	110,000	209,000	120,000	228,000

Farooq
DR. FARHAN FAROOQ
P.O (KSE2)

Yusuf
MR. YUSUF SHIEKH
Asst. Comm

Sana
Ms. SANA UMAIR ALI
Asst. Manager contract (NIP)

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6 = (5*3)	7	8 = (7*3)	9	10 = (9*3)	
9	Chapter-4 Item # 23 / P-19 /Vol-III,Part-II, (General)	BLOCK MASONRY (For Walls & Steps) Providing and laying Block masonry work in ground floor super structure up to any height and at any floor etc. laid and jointed with 1:6 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	40	M ³	5,164.29	206,572	5,350.00	214,000	5,785.00	231,400
10		ROOF TREATMENT Provide and lay roof treatment over roof & skirting as per specifications, as shown in drawings & details, consisting of following items.								
i)	Chapter-8 Item # 16c+75 / P-42,50 / Vol. III,Part-II, (General)	Provide and laying 2" (50 mm) thick topping cement concrete 1:2:4 screed floor including surface finishing, leveling curing and dividing into panels with P/fixing glass strip 4mm for flooring up to 1" depth of specified pattern & design etc.	34	M ²	472.53	16,066	580.00	19,720	530.00	18,020
ii)	Chapter-7 Item # 13 / P-35 / Vol. III,Part-II, (General)	Provide and apply 2 coats of bitumen laid hot using @ 34 lbs for % sft over roof screed and blinded with sand at one Cft.Per % sft	34	M ²	203.08	6,905	200.00	6,800	228.00	7,752

Farhan

Yousuf

Sikandr Ali

DR FARHAN FAROOQ
A.O (KSE2)

MR. YOUSUF SHIEKH
Asst Comm

Mrs. SANA UMAIR ALI
Asst Manager Contract (NIP)

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
					1	2	3	4	5	6
11	Chapter-8 Item # 16c+75 / P-42,50 / Vol. III,Part-II, (General)	FLOORINGS Providing and laying 2" (50 mm) thick topping cement concrete 1:2:4 floor including surface finishing, leveling curing and dividing into panels with P/fixing glass strip 4mm for flooring up to 1" depth of specified pattern & design with steel trowel finished maintaining proper level etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	21	M ²	472.53	9,923	550.00	11,550	528.00	11,088
12	Chapter-9 Item # 13c / P- 52 / Vol. III,Part- II,(General)	PLASTER (INTERNAL WALL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to internal walls, columns, beams, etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	79	M ²	278.74	22,020	430.00	33,970	311.00	24,569
13	Chapter-10 Item # 30a+b / P-73 / Vol.III,Part II; (General)	PAINT (INTERNAL WALL SURFACE) Providing and applying painting on all internal wall surface with Enamel Paint of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	79	M ²	152.98	12,085	310.00	24,490	170.00	13,430

DR. FARHAN FAROOQ
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst. comm

Ms. SANA UMair Ali
Asst. Manager Contract (NIP)

S.No	GOVT.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6 = (4x3)	7	8 = (6x3)	9	10 = (8x3)	
14	Chapter-9 Item # 13b / P-52 / Vol.III,Part-II,(General)	PLASTER (INTERNAL CEILING SURFACE) Providing and applying 12mm (1/2") thick cement plaster to internal ceiling, soffits of beams and projections etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	21	M ²	237.43	4,986	380.00	7,980	265.00	5,565
15	Chapter-9 Item # 23+24a+b+c / P-54 / Vol.III,Part II,(General)	PAINT (INTERNAL CEILING SURFACE) Providing and applying painting on all internal ceiling surface with Berger Robbialac or equivalent Oil Bound Distemper of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the	21	M ²	340.94	7,160	290.00	6,090	380.00	7,980
16	Item # 13c / P-52 / Vol. III,Part-II,(General)	PLASTER (EXTERNAL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to external walls, columns, beams, etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	108	M ²	278.74	30,104	480.00	51,840	311.00	33,388

Zarhin
DR. FARHAN FAROOQ
P.O (KSE2)

Yousuf Shiekh
MR. YOUSUF SHIEKH
Asst. Comm

S. Sana Umair
Ms. SANA UMMAIR AHMAD
Asst Manager Contract (NIP)

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6	7	8	9	10	11
17	Item # 38a+b / P-56 / Vol.III,Part II, (General)	PAINT (WEATHERSHIELD ON EXTERNAL SURFACE) Providing and applying preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick /sand paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (At any height)	115	M ²	276.31	31,776	290.00	33,350	128.00	14,720
18	Chapter - 17 Item # 2+3 / P- 91 / Vol.III,Part II, (General)	MS WORKS Providing, fabrication, erecting and fitting in position of heavy steel works with (angles,tees,flat iron, round iron and sheet iron for making trusses, girders, tanks etc.including cutting tanks etc. including cutting, drilling, rivefing, handling assembling and fixing in position etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.								
i		For MS Louvered Door	150	Kg	103.99	15,599	140.00	21,000	115.00	17,250
ii		For MS Windows	325	Kg	103.99	33,797	140.00	45,500	115.00	37,375
iii		For MS Girder (SizeW 12 x 30)	200	Kg	103.99	20,798	140.00	28,000	115.00	23,000

[Handwritten Signature]

[Handwritten Signature]

DR. FARHAN FAROOQ
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst Comm

Ms. SANVA Umair Ali
Asst Manager contracts (NIP)

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
					7	8 = (7*9)	7	8 = (7*9)	7	8 = (7*9)
19	Item # 5d(i,ii)/ P-70 / Vol.III,Part II, (General)	PAINT (ON MS WORKS) Providing and applying preparing the surface and painting in all types of MS guard bars, gates of iron bars, grating, railings (including standard braces etc) and similar open work with priming coat / enamel coating of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (At any height)	18	M ²	136.74	2,461	460.00	8,280	153.00	2,754
Total Amount of Schedule Items-A						3,466,515		3,704,872		3,992,990
PART-B (NON-SCHEDULE ITEMS)										
1		Providing and applying 20mm (3/4") thick cement plaster to walls of U.G Tank with cement mortar 1:4 mixed with Pudlo-ic all corners, recesses, jambs, raking out joints of masonry, scaffolding etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	150	M ²	550.00	82,500	450.00	67,500	490.00	73,500
2		Providing and laying 2" (50 mm) thick cement concrete 1:2:4 floor including surface finishing, leveling curing finish with steel trowel maintaining proper level etc complete in all respects as per standard specification, drawing and entire	50	M ²	685.00	34,250	520.00	26,000	16,000.00	80,000

DR. FARHAN FAROOQ
P.O (KSEZ)

MR. YOUSUF SHIEKH
ASST COMM

Ms. SANA UMMAH ALI
ASST Manager

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
3		Providing and fixing 20 mm M.S. Steel Rung Epoxy coated embedded in wall complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	38	Nos	1,050.00	39,900	700.00	26,600	125.00	4,750
Total Amount of Non-Schedule Items						156,650		120,100		878,250
Grand Total Amount of Schedule & Non-Schedule Items (A + B)						3,623,165		3,824,972		4,871,240

DR. FARHAN FAROOQ
P.D (KSE2)

MR. YOUSUF SHIEKH
Asst. Comm

Ms. SANA UMMAIR ALI
Asst Manager (NIP)

55

Construction of Treated Effluent

S. No.	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
PART-A (SCHEDULE ITEMS)										
1	Item # A(1)+18(i.ii)/ P-60+75/ Vol. III,Part-III, PHEW)	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation for pipe line in trenches, and test pits (upto 1.5m depth) in all kind of soft soils i/c trimming and dressing sides to true alignment, and shape, leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth with in a one chain as directed by the Engineer, providing fence guard light flags and temporary crossing for non vehicular traffic where ever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5 m) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.								
a)		Trench Depth (0.0-1.5) m	7,119	M ³	318.85	2,269,893	310.00	2,206,890	356.00	2,534,364
b)	Item # A(1)+18(i.ii)+16/ P-60+75+74	Trench Depth(1.5-2.5) m	4,214	M ³	338.27	1,425,470	330.00	1,390,620	378.00	1,592,892
2	Chapter-1 Item # 29 P-26/ Vol. III,Part II	SAND BEDDING Supplying and filling sand under floor, in trench around pipe and pugging in walls etc complete in all respect as per drawings and specification and as directed by the Engineer Incharge.	716	M ³	403.09	288,612	390.00	279,240	340.00	243,440

Farhan

Yousuf Shiekh

Sikandr Ali Khokhar

DR FARHAN FAROOQ
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst. Comm

MS. SARBA UMAIR ALI
Asst manager contr. (NIP)

S. No.	GOVT. OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
	Item #/Page#/ Vol.sched ref.				CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
3		PCC CONCRETE (1:2:4) FOR THRUST BLOCK (PROVISIONAL) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening, Shuttering and washing at stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.								
a)	Item # 5(f) / P-16 /Vol-III,Part-II, (General)	Below NGL	2	M ³	4,448.55	8,897	4,200.00	8,400	4,981.00	9,962
4	Chapter-2 Item # 5(f) o / P-25 /Vol-III,Part-III, (PHEW)	PIPES (HDPE) Providing , laying ,fixing in trench i/c fitting, jointing & testing etc .complete in all respect the high density polyethylene (P.E) Pipe(HDPE 100) for W/S confirming ISO-4427/DIN8074/8075 BS 3580 & PSI 3051.								
a)		250mm (OD) and 226mm (ID)	5,885	R.M	3,422.08	20,138,941	3,150.00	18,537,750	4,106.00	24,163,810
Total Amount of Schedule Items-A						24,131,813		22,422,900		28,544,458

DR. FARHAN FAROOQ
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst Comm

Ms. SANA UDDIN ALI
Asst. Manager contract (AIP)

S. No.	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
PART-B (NON SCHEDULE ITEMS)										
5		FITTINGS (HDPE) Supplying, installing, jointing and fixing all fittings (tees, bends etc.)confirming to ISO - 4427, ISO -1167 DIN 8074/75 & PS 3580: 1994 & DVS 2207 -1, of approved manufacturer's specification and standard etc .complete in all respect as per drawings and specification and as directed by the Engineer Incharge.								
5.1		BENDS (Provisional)								
		11.25degree/250mm dia	9	Nos	8,198	73,780	17,000	153,000	7,000	63,000
		45degree/250mm dia	7	Nos	7,453	52,168	16,000	112,000	8,000	56,000
		90degree/250mm dia	5	Nos	9,316	46,580	17,000	85,000	8,000	40,000
5.2		TEE (UNEQUAL)								
		250mm X 250mm X 75mm	10	Nos	11,179	111,793	27,000	270,000	12,500	125,000
6		GATE VALVES Providing, fixing, jointing and testing of Cast Iron flanged Gate valve with extra flanges of approved quality, including all accessories such as nut, bolts gasket and washers etc .complete in all respect as per drawings and specification. and as directed by the Engineer In charge.								
a)		250mm dia(PN-10)	2	Nos	103,015	206,030	90,000	180,000	15,000	30,000

DR FARHAN FAROOQ
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst Comm

MS SANA Umaid Ali
Asst manger contract (NIP)

G.S. Form No. 15

S. No.	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
7		AIR RELIEF VALVES Providing, fixing, testing and commissioning and installing imported double acting flanged Air Relief Valve with extra flanges required from approved manufacturers including 50mm dia isolating flanged gate valve, C.I Adapter, Nut, bolt, gasket, pipe piece with flanges etc. complete in all respect as per drawings and specification and as directed by the Engineer In charge.								
a)		75mm dia	10	Nos	68,580	685,800	40,000	400,000	10,000	100,000
8		WASH OUT VALVES Providing and installing washout arrangement with extra flanges required for draining out the lines including pipe, fittings etc complete in all respect as per drawings and specification and as directed by the Engineer In charge.								
a)		250mm dia	4	Nos	154,000	616,000	80,000	320,000	5,000	20,000
9		NON RETURN VALVE Providing, fixing, testing and commissioning of flanged non return valve with extra flanges, required from approved manufacturers including all accessories such as nuts, bolt, washer and rubber gaskets etc. complete in all respect as per drawings and specification and as directed by the Engineer Incharge.								
a)		250mm dia	1	Nos	100,000	100,000	80,000	80,000	15,000	5,000

DR. FARHAN FAROON
P.O (KSE2)

MR. YOUSUF SHIEKH
Asst Comm

MB. SANA UMAIRA
Asst Manager Contracts (U/P)

S. No.	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION.	QTY	UNIT	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
					CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
12		ROAD CUTTING AND REINSTATEMENT (Provisional) Dismantling of road hard crust in full thickness including bitumen carpet, road metalling, soling etc from existing road surface i/c its removal. & disposal of dismentled materials and reinstatement as per original condition complete in all respects as directed by the Engineer.	31	M ²	6,000	186,000	4,500	139,500	30,000	930,000
13		OUTFALL CONNECTION WITH EXISTING CANAL Providing, making & constructing of stone pitching wall & R.C.C. Structure i/c Excavation; Backfilling, Reinforced Cement Concrete with shuttering, steel reinforcement & Flap valve as shown in drawing or specified location of approved design all works etc, complete in all respect, as per specifications & relevant drawings and all works to the entire satisfaction of the Engineer.	1	Job	50,000	50,000	400,000	400,000	750,000	750,000
Total Amount of Non-Schedule items						6,472,077		3,804,500		5,699,000
Grand Total Amount of Schedule & Non-Schedule Items (A + B)						30,603,890		26,227,400		34,243,452

DR. FAHIM PAROOL
P.O.(KSE2)

MR. YOUSUF SHAIKH
Asst. comm

MS. SANA UMMAID
Asst Manager Contracts (Civil)

Item Ref.	Description	Unit	Quantity	Engineer's Estimate		M/s Blue Stone Associate		M/s Sikandr Ali Khokhar	
				Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)	Rate (Rs.)	Amount (Rs.)
NON SCHEDULE ITEMS									
1.0	ELECTRIFICATION OF PUMP ROOM								
a)	Supply, installation, testing & commissioning of all Electrical Works for Pump Room as per drawing and specification, complete in all respect.	Job.	1	212,000	212,000	619,000	619,000	100,000	100,000
TOTAL AMOUNT (Rs.)					212,000		619,000		100,000

Farhan
 DR FARHAN FAROOQ
 P.O (KSE2)

Yousuf
 MR. YOUSUF SHIKH
 Asst. comm

S. Sana
 Ms. SANA UMAIR ALI
 Asst. Manager contracts (NIP)

KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)

NATIONAL INDUSTRIAL PARKS DEVELOPMENT & MANAGEMENT COMPANY

"Main Electrical Sub-Station, Complete Civil and Electrical Works including Sub-Station Equipments"

ATTENDANCE SHEET

TECHNICAL AND FINANCIAL BID OPENING (March 15, 2017; 3:00 P.M)

S.N	Name of Firm	Representative's Name	Contact Number	Representative signature.	Remarks.
1	M/s Barqtron Engg. Solutions	/	NOT PARTICIPATED		/
2	M/s Nariman Const. Co	/			/
3	M/s Blue Stone	Azmi Mughal	0300 233 8188	Azmi	OK
4	M/s Kashif Constructors	Kashif	0312 873167	Kashif	OK
5	M/s Mehran Associate	Mehboob	0332 360555	Mehboob	OK
6	M/s M. Abdullah & Brothers	/	NOT PARTICIPATED		/

Carsham
15-3-17

Project Director
Khairpur Special Economic Zone (KSEZ)

[Signature]

Assistant Commissioner
Commissioner Office, New Sukkur
Rep: *Comms Sukkur*

[Signature]

Assistant Manager Contracts
National Industrial Parks

KHAIRPUR SPECIAL ECONOMIC ZONE

National Industrial Parks Development & Management Company

"Construction of Main Electrical Sub-Station, Complete Civil and Electrical Works including Sub-Station Equipments"

Date: March 15, 2017 Time: 3:00 p.m.

Bid Opening Statement

S.N	Name of Contractor	Bid Details	Bid Amount (Rs.)	Rebate Amount (Rs)	Net Bid Amount(Rs)	Submitted Bid Security Amount (Rs)	Bid Security Detail	Remarks
1	M/s Barqtron Engg. Solutions	/	/	/	NOT PARTICIPATED	/	/	/
2	M/s Nariman Const. Co	/	/	/	NOT PARTICIPATED	/	/	/
3	M/s Blue Stone	1 Profile + 2 copies 1 original	68,966,920/-	-	68,966,920/-	1,400,000/-	PO. 50606581 (15-03-17)	Saint Bank OK
4	M/s Kashif Constructors	1 Profile + 1 copy 1 original	66,122,300/-	-	66,122,300/-	1,350,000/-	BBB 12324241 (15-03-17)	ABL OK
5	M/s Mehran Associate	1 Profile + 1 original	76,582,640/-	-	76,582,640/-	1,610,000/-	800,000/- BCA 330551 MCB (15-03-17)	OK.
6	M/s M. Abdullah & Brothers	/	/	/	NOT PARTICIPATED	/	13197651 UBL (15-03-17)	OK.

*Required Bid Security is 2%

Carsh qin
5-3-17
Project Director
Khairpur Special Economic Zone (KSEZ)

By opening
Assistant Commissioner
Commissioner Office, New Sukkur
Rep. Comr. Sukkur


S. J. H.
Assistant Manager Contracts
National Industrial Parks

Bid Evaluation Report

1. Name of Procuring Agency: **KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)**
2. Tender Reference No: **Nil**
3. Tender Description/Name of work/item: **Construction of Main Electrical Sub-Station, Complete Civil and Electrical Works including Sub-Station Equipments**
4. Method of Procurement: **Single Stage – Single Envelope**
5. Tender Published: **The News, Jang and Kawish dated Feb. 17, 2017**
6. Total Bid documents Sold; **06 (Six)**
7. Total Bids Received: **03 (Three)**
8. Technical Bid Opening date: **March 15, 2017**
9. No. of Bid technically qualified: **None**
10. Bid(s) Rejected: **03 (Three), due to the reasons given below**
11. Financial Bid Opening date: **March 15, 2017**

12. Bid Evaluation Report:

SN	Name of Firm or Bidder	Cost offered by the Bidder	Ranking in terms of cost	Comparison with Estimated cost	Reasons for acceptance/ rejection	Remarks
1	M/s Kashif Constructors	66,122,300/-	---	15.00 % below	Not meeting Eligibility Criteria	Non-Responsive
2	M/s Blue Stone	68,966,920/-	---	11.34 % below	Not meeting Eligibility Criteria	Non-Responsive
3	M/s Mehran Associates	76,582,440/-	---	1.55% below	Not meeting Eligibility Criteria	Non-Responsive



Dr. Farhan Farooq
Project Director
Khairpur Special Economic Zone (KSEZ)



Mr. Yousuf Shiekh
Assistant Commissioner,
Commissioner Office, New Sukkur



Ms. Sana Umair Ali
Assistant Manager Contracts
National Industrial Parks

Results of Preliminary Examination Requirements / **TECHNICAL EVALUATION**

S.No	Description	M/s Kashif Constructors	M/s Blue Stone Associates	M/s Mehran Associates
1	2	1	2	3
a	1. Bid Submission Requirements: Cover Letter	Provided	Provided	Provided
b	Bid Form	Provided	Provided	Not Filled & Signed
a	2. Eligibility Criteria: (As per NIT) Valid Pakistan Engineering Council (PEC) registration in Category "C4" and above in discipline CE-10 & EE05	C-2 Expired (Renewal Letter Attached)	C-4 Expired (Renewal Letter Attached) (not fulfilling the Specializing Codes)	C-4/E
b	Valid NTN certificate from Income Tax Authorities	Provided	Provided (Online Verification Page)	Provided
c	Should be in Construction Business for the last 5 years or more	Provided	Provided	Provided
d	Affidavit that the firm is not Blacklisted or engaged in any Litigation on any Project.	Provided	Provided	Not Provided
e	Should have completed 2 contracts of similar nature and value of Pak Rs 50.00 million in the last 5 years.	Provided (but below 50 m Projects)	Provided (but below 50 m Projects)	Provided
f	Average Annual Construction Turn Over for the last three years of Pak Rs 50 million	Provided	Provided	Not Provided
	3. Substantial Responsiveness	No	No	No
	4. Accepted for Detailed Examination	No	No	No

Farhan
DR. FARHAN FAROOQ
Project Director (KSEZ)

Yusuf
MR. YUSUF SHIEKH
Assistant Commissioner,
Commissioner Office,
New SUKKUR

Sana
Ms. SANA URBAN ALI
Assistant Manager
CONTRACTS (NIP)

S.NO:	DESCRIPTION	Engineer's Estimate	Blue Stone Associates.	M/s Kashif Constructors	M/s Mehran Associate
		AMOUNT	AMOUNT	AMOUNT	AMOUNT
A	SUBMITTED AMOUNT	-	68,966,920	66,122,300	76,582,640
B	AFTER ARITHMETIC CHECK				
1	CIVIL WORKS	1,478,656	1,979,770	1,198,300	2,238,290
2	ELECTRICAL WORKS	76,308,650	66,987,150	64,924,000	78,257,000
	Less Rebat on Electrical Works if any.		0%	0%	5% (3,912,850)
	GRAND TOTAL AMOUNT. (B)	77,787,306	68,966,920	66,122,300	76,582,440.00
	Difference (B - A)		-	-	(200)
	% below/above Engineer's Estimate ----->		-11.34%	-15.00%	-1.55%
	% above Lowest Bidder ----->		4.12%	-	15.82%

Farooq
DR. FAKHAR FAROOQ
P.O KSEZ

Yousuf
MR. YOUSUF SHADEKH
Asst. Comm

Sana
Ms. SANA UMAIR ALI
Asst Manager contracts
(Nip)

Construction of Main Substation

S.No	GOVT.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate	
					CSR SINDH SCHD. 2012 / Non Schedule RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
PART-A (SCHEDULE ITEMS)												
1	Item # 18(b)+18(i.ii)/ P-4+75/ Vol. III,Part II & III,(General & PHEW)	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation in foundation and dewatering in all kind of soil of building, bridges and other structures including daggelling dressing refilling around structure with (suitable) excavated earth watering, ramming complete and disposal of surplus excavated material to designated area i/c all load & lift. etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	100	M ³	303.92	30,392	330.00	33,000	200.00	20,000	350.00	35,000
2	Item # 22+13 (b+cii)/P-3 & 4/Vol-III,Part-II, (General)	IMPORTED EARTH FILLING FROM OUTSIDE SOURCES Supplying and filling watering and ramming earth under floor with new earth excavated from outside in 150mm layers leveling dressing and watering for compaction and to obtain 95% modified AASHTO density. Complete including all lead & lifts etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	253	M ³	167.42	42,356	550.00	139,150	150.00	37,950	700.00	177,100
3	Item # 2 / P-15 /Vol-III,Part-II, (General)	STONE SOLING Providing and laying dry rammed brick or stone ballast / soling 1-1/2" to 2" gauge from approved quarry including hand packing & filling voids with sprawls & chips, consolidating & compacting with power or hand roller,etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	97	M ³	1,175.27	114,001	1,750.00	169,750	600.00	58,200	2,800.00	271,600
4	Item # 5(i) / P-16 /Vol-III,Part-II, (General)	PCC CONCRETE (1:4:8) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing at stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.										
a)		Below foundation, plinth beam etc.	5	M ³	3,987.19	19,936	4,500.00	22,500	2,500.00	12,500	4,400.00	22,000
b)		Under floor and where required etc.		M ³	3,987.19	15,949	4,500.00	18,000	2,500.00	10,000	4,400.00	17,600

DR. FARHAN PAROOL
P.O KSEZ

MR. ABUSUF SHIEKH
Asst. Commr

MS. SARAF ULLAH
Asst Manager cont.

Construction of Main Substation

S.No	GOVT.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate	
					CSR SINDH SCHED. 2012 / Non Schedule RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
5	Item # 5(h) / P-16 /Vol-III,Part-II, (General)	PCC CONCRETE (1:3:6) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing at stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	1	M ³	4,448.55	4,449	5,000.00	5,000	3,000.00	3,000	5,500.00	5,500
6	Item # 19b(i+ii/2) / P-18 /Vol-III,Part-II, (General)	WOODEN FORMWORKS/SHUTTERING Providing, fixing, erecting and removal of partial wood centering (shuttering / formwork) of approved quality for RCC or plain cement concrete works etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.										
i		Form work for 1:4:8 concrete	12	M ²	361.31	4,336	300.00	3,600	300.00	3,600	450.00	5,400
ii		Form work for 1:3:6 concrete	6	M ²	361.31	2,168	300.00	1,800	300.00	1,800	450.00	2,700
7	Item # 6a(ii) / P-16,17 /Vol-III,Part-II, (General)	RCC CONCRETE SUB-STRUCTURE -Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately.This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.										
		RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)										
i)		Footing and Concrete Pads	6	M ³	12,326.68	73,960	12,000.00	72,000	10,000.00	60,000	12,000.00	72,000
ii)		Plinth Beams	2	M ³	12,326.68	24,653	12,000.00	24,000	10,000.00	20,000	12,000.00	24,000
iii)		Column up to Plinth level	1	M ³	12,326.68	12,327	12,000.00	12,000	10,000.00	10,000	12,000.00	12,000
iv)		Cable Trench (Wall & Slab)	8	M ³	12,326.68	98,613	12,000.00	96,000	10,000.00	80,000	12,000.00	96,000

Farhan Farooq
Dr. FARHAN FAROOQ
A D KSEZ

Yousaf Shiekh
MR YOUSAF SHIEKH
ASST. COMM

Sana Umaid Ali
MS. SANA UMAID ALI
ASST. MANGER CONT (NIP)

Construction of Main Substation.

S.No	GOVT.OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate	
					CSR SINDH SCHD. 2012 / Non Schedule RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
3	Item # 8b / P-17 /Vol-III,Part-II, (General)	STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting,bending,laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	2	Ton	100.034	200,068	110,000	220,000	90,000	180,000	150,000	300,000
9	Item # 9 / P-71 /Vol-III,Part-II, (General)	BITUMEN COATING Providing and applying industrial bitumen paint/coating to plastered or cement concrete surface etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	58	M ²	83.72	4,856	210.00	12,180	60.00	3,480	100.00	5,800
10	Item # 28b / P-19 / Vol-III,Part- II,(General)	(D.P.C) DAMP PROOF COURSE Providing and laying DPC damp proof course with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture with leveling, curing, finishing etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	4	M ²	421.02	1,684	420.00	1,680	350.00	1,400	500.00	2,000
11	Item # 92 / P-109 / Vol-III,Part- II,(General)	TERMITE TREATMENT Providing Anti-Termite treatment by spraying / sprinkling / spreading Neptactin 0.5% Emulsion as an overall pre construction treatment in slab type construction under the slab and along attached perches or entrances etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (Plinth area will be measured one time for payment whereas the number of applications will be three times on all horizontal & vertical surfaces of the excavations for termite proofing).	192	M ²	104.80	20,122	210.00	40,320	60.00	11,520	200.00	38,400

Farooq

Dr. FARHAN FAROQ
P.O (KSEZ)

Yousuf Shiekh

MR. YOUSUF SHIEKH
Asst Comm

Sana Ullah Ali

Ms. SANA ULLAH ALI
Asst Manager (NIP)

Construction of Main Substation

S.No	GOVT.OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate		
					CSR SINDH SCHD. 2012 / Non Schedule RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	
12	Item # 6a(ii) / P-16,17 /Vol-III,Part-II, (General)	RCC CONCRETE SUPER-STRUCTURE-Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid seperately.This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.											
		RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)											
		i) Column	4	M ³	12,326.68	49,307	12,000.00	48,000	10,000.00	40,000	15,000.00	60,000	
	ii) Beams, Lintels, Projections, Pads, brackets and Sills	5	M ³	12,326.68	61,633	12,000.00	60,000	10,000.00	50,000	15,000.00	75,000		
	iii) Slab i/c Projection	8	M ³	12,326.68	98,613	12,000.00	96,000	10,000.00	80,000	15,000.00	120,000		
13	Item # 8b / P-17 /Vol-III,Part-II, (General)	STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting,bending,laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	2	Ton	100.034	200,068	110,000	220,000	90,000	180,000	150,000	300,000	
		BRICK MASONRY Providing and laying pucca brick masonry work (1st class quality) in ground floor super structure up to any height and at any floor etc. laid and jointed with 1:6 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	17	M ³	4,476.55	76,102	4,900.00	81,600	4,500.00	76,500	5,500.00	93,500	
14	Item # 5(1e) / P-21 /Vol-III,Part-II, (General)												

Dr FATHAN FAROOQ
P.O. KSEZ

MR. YOUSUF SHEKH
Asst Commr

MS. SANA UMMAH AH
Asst manager contracts.

Construction of Main Substation

S.No	GOVT.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate	
					CSR SINDH SCHD. 2012 / Non Schedule RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
15	Item # 11b / P-52 / Vol. III, Part- II, (General)	PLASTER (INTERNAL WALL SURFACE) Providing and applying 15mm (1/2") thick cement plaster to internal walls, columns, beams, etc. with cement mortar 1:4 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	120	M ²	245.75	29,490	480.00	57,600	250.00	30,000	300.00	36,000
16	Item # 30a+b / P- 73 / Vol. III, Part II, (General)	PAINT (INTERNAL WALL SURFACE) Providing and applying painting on all internal wall surface with Enamel Paint of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	120	M ²	152.98	18,358	380.00	45,600	150.00	18,000	250.00	30,000
17	Item # 10b / P-52 / Vol. III, Part- II, (General)	PLASTER (INTERNAL CEILING SURFACE) Providing and applying 15mm (1/2") thick cement plaster to internal ceiling, soffits of beams and projections etc. with cement mortar 1:3 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	57	M ²	252.28	14,380	480.00	27,360	230.00	13,110	300.00	17,100

Farooq
DR. FATHAN FAROOQ
P.O (KSEZ)

Yousif Shiekh
MR YOUSIF SHIEKH
Asst. Comm

S. Sana Umaid Ali
MS. SANA UMAID ALI
Asst. manager Contract

Construction of Main Substation

S.No	GOVT.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate	
					CSR SINDH SCHD. 2012 / Non Schedule RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
18	Item # 30a+b / P-73 / Vol.III,Part II, (General)	<p>PAINT (INTERNAL CEILING SURFACE) Providing and applying painting on all ceiling surface with Enamel Paint of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>	57	M ²	152.98	8,720	320.00	18,240	140.00	7,980	300.00	17,100
19	Item # 13c / P-52 / Vol. III,Part-II,(General)	<p>PLASTER (EXTERNAL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to external walls, columns, beams, etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).</p>	147	M ²	278.74	40,974	520.00	76,440	200.00	29,400	320.00	47,040
20	Item # 38a+b+b / P-56 / Vol.III,Part II, (General)	<p>PAINT (WEATHERSHIELD ON EXTERNAL SURFACE) Providing and applying preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick /sand paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (At any height)</p>	147	M ²	276.31	40,618	310.00	45,570	200.00	29,400	350.00	51,450

Rasheed

Yusuf Shiekir

S. Sana Umais

Dr. FATHAN FAROOQ
P.O (KSEZ)

MR YUSUF SHIEKIR
Asst. comm

MS. SANA UMAIS (Asst. Manager (CIP))

Construction of Main Substation

S.No	GOVT.OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate	
					CSR SINDH SCHD. 2012 / Non Schedule RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
21	Item # 2+3 / P-91 / Vol.III,Part II, (General)	MS WORKS Providing, fabrication, erecting and fitting in position of heavy steel works with (angles,tees,flat iron, round iron and sheet iron for making trusses, girders, tanks etc.including cutting tanks etc. including cutting, drilling, riveling, handling assembling and fixing in position etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.										
i		For MS Louvered Door	29	Kg	103.99	3,016	145.00	4,205	80.00	2,320	200.00	5,800
ii		For MS Windows	63	Kg	103.99	6,551	145.00	9,135	80.00	5,040	200.00	12,600
iii		For MS Chequered Plat over cable trench	560	Kg	103.99	58,235	145.00	81,200	80.00	44,800	200.00	112,000
22	Item # 5d(T,ii)/ P-70 / Vol.III,Part II, (General)	PAINT (ON MS WORKS) Providing and applying preparing the surface and painting in all types of MS guard bars, gates of iron bars, grating, railings (including standard braces etc) and similar open work with priming coat / enamel coating of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (At any height)	52	M ²	136.74	7,111	520.00	27,040	100.00	5,200	350.00	18,200
Total Amount of Schedule Items-A						1,383,046		1,768,970		1,125,200		2,082,890

Dr. FARHAN FAROOQ
P.O (KSEZ)

MR. YOUSUF SHIEKH
Asst. Comm

MS. SANVA UMMAID ALI
Asst. Manager (NIB)

Construction of Main Substation

S.No	GOVT OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate	
					CSR SINDH SCHED. 2012 / Non Schedule RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
PART-B (NON-SCHEDULE ITEMS)												
23		<p>ROOF PROTECTION Providing & laying complete roof water treatment at any floor and any height as shown in the drawings & details consisting of following items complete in all respect as per drawing, standards, specifications and direction of the Engineer. (For payment roof screed area will be measured)</p> <p>i) Providing and laying 25mm thick average with (1:4) cement sand mortar base plaster for achieving leveled surface. ii) Providing and laying in position sticking coat of Bitumen 70-90 Grade @ 10 Lbs /10 Sqm iii) Providing and laying in position flood coat of Bitumen 10-20 Grade @ 35 Lbs /10 Sqm iv) Providing and laying 75mm thick minimum (1:2:4) with 3000 psi strength concrete screed including Fiber mesh 150 @ 0.05 Lbs/cement bag of approved equivalent in required slope curing, making ridges, valleys, chamfered edges etc</p>	50	M ²	1,350.00	67,500	2,200.00	110,000	1,000.00	50,000	2,000.00	100,000
24		<p>FLOORING Providing, and laying 50mm thick 1:2:4 granolithic floor finish including compacting, paneling, leveling, finishing and curing (over all thickness shown in drawings) etc, complete in all respect as per drawing, standard, specifications and direction of the Engineer.</p>	47	M ²	550.00	25,850	2,000.00	94,000	300.00	14,100	1,000.00	47,000
25		<p>WATER SPOUT Providing & Fixing CC precast or cast in situ water spout 450 mm x 450 mm for rain water drain (at any floor & height) as per given details shown in drawings etc, complete in all respect as per drawing, standard, specifications and direction of the Engineer.</p>	1	Each	1,000.00	1,000	5,000.00	5,000	5,000.00	5,000	2,000.00	2,000

Lashar
DR. FARHAN FAROOQ
P.O (KSEZ)

Muzammil
MR. YOUSUF SHIKH
Asst. Commr

S. Kashif
MS. SANA UMMAH Ali
Asst. manager (NIP)

Construction of Main Substation

S.No	GOVT.OF SINDH CSR 2012 item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate	
					CSR SINDH SCHD. 2012 / Non Schedule RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)	RATE (Rs.)	AMOUNT (Rs.)
26		Providing and fixing of 100 mm dia PVC pipes and fittings as per BS & ASTM standard for rain water pipes including non struct concrete around pipes, silicon mastic filling, jali, cleanout plug, clamps, hanger collars, supports, specials (bend, tees, Y-tee etc) as shown in the drawing, (at any floor & height) as per given drawing etc, complete in all respect as per drawing, standard, specifications and direction of the Engineer.	4	Rm	315.00	1,260	450.00	1,800	1,000.00	4,000	1,600.00	6,400
Total Amount of Non-Schedule Items-B						95,610		210,800		73,100		155,400
TOTAL AMOUNT CARRIED TO GRAND SUMMARY A+B						1,478,656		1,979,770		1,198,300		2,238,290

Lashan
Dr. FARHAN FAROOQ
P.O (KSEZ)

Yousuf
MR. YOUSUF SHAIKH
Asst. Comm

S. Sana Umair Ali
Ms. SANA Umair Ali
Asst Manager (NIP)

Item No.	Description	Qty.	Unit	Engineer's Estimate		Blue Stone Associates.		M/s Kashif Constructors		M/s Mehran Associate	
				Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)
Non Schematic Item:											
E-1	MV SWITCHBOARD Supply, installing, testing & commissioning of following floor standing totally enclosed, cubical type, dust protected and vermin proof, medium voltage switchgear including all component, Control wiring as per specifications and drawing. Complete in all respect.	1	Job.	15,969,600	15,969,600	12,500,000	12,500,000	12,450,000	12,450,000	2000000	2,000,000
E-2	Providing, and laying of Rubber insulation mat 1 meter wide and 6mm thick to be installed all along MV Panel in Substation, suitable to provide insulation for 15 kV working as per the requirement and specification, complete in all respect.	1	Job.	35,000	35,000	15,000	15,000	100,000	100,000	200,000	200,000
E-3	Providing and fixing of Danger Board, Shock chart, First chart having signs & designation on external doors of Sub-Station.	1	Job.	5,100	5,100	12,000	12,000	30,000	30,000	27,000	27,000
MV CABLE											
E-4	Providing, laying, termination, testing and commissioning of following 15 KV Aluminium conductor M.V cable from SEPCO to Main Substation and Main Substation to Substation No.1,2,3 & 4, directly laid in ground and partly in already laid PVC ducts, as per drawings and specification, including, cable lugs, cable glands, 300x300x50 mm concrete pile, warning tape, identification markers, etc., complete in all respect.										
i	3 core-300 Sq.mm Al. XLPE /SWA/ PVC Cable	5700	Rm	5,880	33,516,000	5,500	31,350,000	4,700	26,790,000	7,000	39,900,000
ii	3 core-240 Sq.mm Al. XLPE /SWA/ PVC Cable	4220	Rm	5,625	23,737,500	4,400	18,568,000	4,300	18,146,000	6,500	27,430,000

DR. FARHAN FAROOQ
P.O (KSEZ)

MR. YOUSUF SHIEKH
Asst comm

MS. SANA ULLAH AHMAD
Asst manager contract (NIP)

ht

No.	Description	Qty.	Unit	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)
Non-Schedule Item											
E-5	Providing, termination, testing and commissioning of following termination kits and joints of approved manufacturer, as per specification and detail shown on drawing, with all accessories, complete in all respect.										
i	MV termination Kit 300 sq.mm 3 Core (In door)	4	Nos.	38,200	152,800	4,000	16,000	25,000	100,000	30,000	120,000
ii	MV termination Kit 300 sq.mm 3 Core (Out door)	4	Nos.	44,900	179,600	5,000	20,000	25,000	100,000	30,000	120,000
iii	MV termination Kit 240 sq.mm 3 Core (In door)	16	Nos.	38,200	611,200	6,000	96,000	25,000	400,000	30,000	480,000
iv	MV Straight Joint Kit 300 sq.mm 3 Core (Outdoor)	10	Nos.	44,900	449,000	5,000	50,000	25,000	250,000	70,000	700,000
v	MV Straight Joint Kit 240 sq.mm 3 Core (Outdoor)	8	Nos.	44,900	359,200	6,000	48,000	25,000	200,000	70,000	560,000
E-6	Excavation of trench, in hard / soft soil (including excavation for cable loops) and back filling after laying of cable, cost including providing fresh sand 100 mm above and 100 mm under cable, laying protection concrete tile on sand, warning tape and backfilling, compaction etc., as per detail shown on drawing, complete in all respect.	2600	Cu.m	325	845,000	1,500	3,900,000	2,000	5,200,000	2,000	5,200,000
LOW VOLTAGE CABLES											
E-7	Providing, laying, testing, termination at both ends and commissioning of following Aluminium conductor armoured cables, directly under ground and partly already laid PVC ducts of size as may required, as per drawings and specification, including cable glands, identification markers, etc., excavation & filling of trench as per specification, complete in all respect.										
i	4c-10 Sq.mm PVC (S) / PVC (600/1000V)	170	Rm	465	79,050	450	76,500	750	127,500	2,000	340,000

Handwritten signature

Handwritten signature

DR. FARHAN FAROOQ
P.O KSEZ

MR. YOUSUF SHIEKH
Asst com

MS. SANA UMMAIR AH
Asst manager (wip)

No.	Description	Qty.	Unit	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)
Non Schedule Items											
ii	1c-6 Sq.mm Cu.PVC as ECC (450/750V)	170	Rm	130	22,100	120	20,400	100	17,000	1,000	170,000
EARTHING SYSTEM											
E-8	Providing and prepare Earth pit with 600 mm x 600 mm x 3 mm thick copper plate type electrode for earthing system, including cost of excavation up to water level, with filling mixture material as per specification to achieve earthing resistance not more than 1 ohm, connection with earth leads of 2 x 70 sq.mm Bare copper conductor up to earth testing point, Inspection pit 600 mm x 600 mm x 450 mm deep (min) with 450 mm dia heavy duty C.I cover, complete as per detail drawing & instruction of consultant, providing as built drawings, test reports documents to Employer / Consultant representative. Complete in all respect.	2	Nos.	45,000	90,000	40,000	80,000	300,000	600,000	75,000	150,000
E-9	Providing, installation, testing and commissioning of 70 sq.mm hard drawn bare Cu.Conductor as earth continuity conductor (ECC) installed on surface or in already installed raceway or in already excavated trench or in already laid pipe complete in all respect.	80	Rm	1,000	80,000	1,200	96,000	1,500	120,000	2,500	200,000
E-10	Providing, installation, testing and commissioning of Copper Earth connecting Bar 300 mm x 50 mm x 06 mm for earthing system as per drawings and instruction of consultant, including all mounting accessories etc., complete in all respect.	1	No.	10,000	10,000	15,000	15,000	10,000	10,000	100,000	100,000

Lashari

Yousuf Shiekh

S. Sana Umeed Ali

Dr. FARHAN FAROOQ
P. O. (KSEZ)

MR. YOUSUF SHIEKH
Asst Comm

MS. SANA UMEED ALI
Asst manager (N/A)

No.	Description	Qty.	Unit	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)
Non Schedule Items											
E-11	UPVC Pipe Providing and laying of following size uPVC class "D" pipe for opening sleeves of sub station to buildings. Buried in ground, under roads crossing as per drawing. Including excavation for laying of pipe, 5 mm dia nylon rope, backfilling with new and fresh sand (100 mm under and 100 mm above pipe), compaction and plugging of pipe ends etc., as shown on drawing, complete in all respect.										
i	150 mm (internal dia)	20	Rm	2,430	48,600	500	10,000	1,500	30,000	1,500	30,000
ii	100 mm (internal dia)	1	Rm	1,695	1,695	400	400	2,000	2,000	1,000	1,000
DISTRIBUTION BOARDS.											
E-12	Supply, installation, testing & commissioning of surface/recessed mounted DB-MSS as per single line diagram and specifications, with all accessories including civil works, approved by engineer, complete in all respect.	1	Job.	48,500	48,500	50,000	50,000	50,000	50,000	450,000	450,000
LIGHTING FIXTURES											
E-13	Supply, installation, testing and commissioning of following light fixtures complete with Electronic ballast (unless mention otherwise), lamps, lamps holder, all mounting accessories etc., as per drawing and specification, complete in all respects.										
i	Surface mounted Fluorescent light fixture Philips TMS or Approved Equivalent type with 2x28 W TL5 Color 84 lamp	6	Nos.	5,070	30,420	4,500	27,000	5,000	30,000	3,600	21,600
ii	Surface/Wall mounted Bulkhead Outdoor light fixture (IP-65) with 1x18W CFL lamp.	1	No.	5,270	5,270	4,000	4,000	4,000	4,000	1,800	1,800

Farhan

Yousuf Shiekh

Sana Umair Ali

Dr. FARHAN FAROOD
P.O (KSEZ)

MR. YOUSUF SHIEKH
Asst Comm

MS. SANA UMAIR ALI
ASST Manager (NIP)

No.	Description	Qty.	Unit	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)
Non-Standard Items											
E-14	FANS Supply, installation, testing and commissioning of 16" dia Exhaust Fan Metal body with Louvre, as per specification complete in all respects	2	Nos.	4,350	8,700	4,500	9,000	10,000	20,000	3,500	7,000
E-15	LIGHTING CONTROL SWITCH Supply, installation, testing and commissioning of 10 Amps, 5-gang switch, including 16 SWG sheet steel powder coated back boxes, recessed in wall with all accessories, as per specification, complete in all respects.	1	No.	1,115	1,115	750	750	10,000	10,000	1,000	1,000
E-16	SWITCH SOCKET OUTLET Supply, installation, testing and commissioning of 15 Amps, 3Pin switch socket outlet, including 16 SWG sheet steel powder coated back boxes, recessed in wall with all accessories, as per specification, complete in all respects.	2	Nos.	1,065	2,130	850	1,700	20,000	40,000	800	1,600
E-17	WIRING Supply, installation, testing & commissioning of circuit wiring from DB to switch board with 3x2.5 sq.mm single core, Cu. conductor PVC insulated wires including 25 mm dia. PVC conduit surface / recessed in wall, column, ceiling, etc., complete with all accessories, as per specification, complete in all respect.	1	No.	1,690	1,690	1,800	1,800	10,000	10,000	5,000	5,000
E-18	Supply, installation, testing & commissioning of wiring from switch board to light / fan point with 3x1.5 sq.mm, single core, Cu. conductor PVC insulated wires including 20 mm dia PVC conduit, surface / recessed with all accessories, complete in all respect.	5	Nos.	1,440	7,200	1,200	6,000	7,500	37,500	4,000	20,000

Faham Farooq

Yousuf Shiekh

Sy. Farhan Umer

Dr. FAHAM FAROOQ
P.O (KSEZ)

MR. YOUSUF SHIEKH
Asst Comm

MS. SANA UMAR ALI
Asst Manager (W/P)

87

No.	Description	Qty.	Unit	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)	Rate (Rupees)	Amount (Rupees)
Non Schedule Items											
E-19	Supply, installation, testing & commissioning of wiring between light point to light point with 3x1.5 sq.mm single core Cu. conductor PVC insulated wires including 20 mm dia PVC conduit, surface / recessed with all accessories, as per specification, complete in all respect.	4	Nos.	1,015	4,060	2,000	8,000	7,500	30,000	3,000	12,000
E-20	Supply, installation, testing & commissioning of circuit wiring for Power socket outlet with 2 x 4 sq.mm. + 1x 4 sq.mm. as ECC, single core Cu. conductor PVC installed wire including 20 mm dia. PVC conduit surface / recessed in wall, column, ceiling, etc., complete with all conduit accessories as per drawings and specification.	2	Nos.	4,060	8,120	2,800	5,600	10,000	20,000	4,500	9,000
Total					76,308,650		66,987,150		64,924,000		78,257,000

[Handwritten Signature]

[Handwritten Signature]

Dr. FARHAN FAROOQ
 P.O (KSEZ)

MR. YOUSUF SHIEKH
 Asst. comm

MS. SANA UMair Ali
 Asst manager (NIP)

SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY

CONTRACT EVALUATION FORM

TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC CONTRACTS OF WORKS, SERVICES & GOODS

- 1) NAME OF THE ORGANIZATION / DEPTT. KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)
- 2) PROVINCIAL / LOCAL GOVT./ OTHER PROVINCIAL
- 3) TITLE OF CONTRACT Construction of Effluent Pipe line From STP out falling Rohri Canal
- 4) TENDER NUMBER 1360/2017
- 5) BRIEF DESCRIPTION OF CONTRACT Treated Effluent Pipe line outfalling to Rohri Canal.
- 6) FORUM THAT APPROVED THE SCHEME Procuring Agency
- 7) TENDER ESTIMATED VALUE Rs- 30,671,372 =
- 8) ENGINEER'S ESTIMATE (For civil works only) Rs- 34,439,055 =
- 9) ESTIMATED COMPLETION PERIOD (AS PER CONTRACT) 180 Days
- 10) TENDER OPENED ON (DATE & TIME) March 15, 2017
- 11) NUMBER OF TENDER DOCUMENTS SOLD (Attach list of buyers) 04 (Four)
- 12) NUMBER OF BIDS RECEIVED 02 (Two)
- 13) NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BIDS 02.
- 14) BID EVALUATION REPORT (Enclose a copy) Attached
- 15) NAME AND ADDRESS OF THE SUCCESSFUL BIDDER M/S Blue Stone Associates
A-603 West Point Tower
PHASE-II, DHA, KARACHI
- 16) CONTRACT AWARD PRICE Rs- 30,671,372 =
- 17) RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT (i.e. 1st, 2nd, 3rd EVALUATION BID). 1st Evaluation Bid
- 18) METHOD OF PROCUREMENT USED : - (Tick one)
- a) SINGLE STAGE - ONE ENVELOPE PROCEDURE Domestic/ Local
- b) SINGLE STAGE - TWO ENVELOPE PROCEDURE
- c) TWO STAGE BIDDING PROCEDURE
- d) TWO STAGE - TWO ENVELOPE BIDDING PROCEDURE

PLEASE SPECIFY IF ANY OTHER METHOD OF PROCUREMENT WAS ADOPTED i.e. EMERGENCY, DIRECT CONTRACTING ETC. WITH BRIEF REASONS

19) APPROVING AUTHORITY FOR AWARD OF CONTRACT Procuring Agency KSEZ

20) WHETHER THE PROCUREMENT WAS INCLUDED IN ANNUAL PROCUREMENT PLAN?

Yes	<input type="checkbox"/>	No	<input type="checkbox"/>
-----	--------------------------	----	--------------------------

21) ADVERTISEMENT :

i) SPPRA Website
(If yes, give date and SPPRA Identification No.)

<input checked="" type="checkbox"/> Yes	S.No. 10935 dated 19 MAY, 2017
<input type="checkbox"/> No	

ii) News Papers
(If yes, give names of newspapers and dates)

<input checked="" type="checkbox"/> Yes	The News, Jang, K-wich dated 17 February, 2017
<input type="checkbox"/> No	

22) NATURE OF CONTRACT

Domestic/Local	<input checked="" type="checkbox"/>	Int.	<input type="checkbox"/>
----------------	-------------------------------------	------	--------------------------

23) WHETHER QUALIFICATION CRITERIA
WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

24) WHETHER BID EVALUATION CRITERIA
WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

25) WHETHER APPROVAL OF COMPETENT AUTHORITY WAS OBTAINED FOR USING A
METHOD OTHER THAN OPEN COMPETITIVE BIDDING?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

26) WAS BID SECURITY OBTAINED FROM ALL THE BIDDERS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

27) WHETHER THE SUCCESSFUL BID WAS LOWEST EVALUATED
BID / BEST EVALUATED BID (in case of Consultancies)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

28) WHETHER THE SUCCESSFUL BIDDER WAS TECHNICALLY
COMPLIANT?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

29) WHETHER NAMES OF THE BIDDERS AND THEIR QUOTED PRICES WERE READ OUT AT
THE TIME OF OPENING OF BIDS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

30) WHETHER EVALUATION REPORT GIVEN TO BIDDERS BEFORE THE AWARD OF
CONTRACT?

(Attach copy of the bid evaluation report)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

31) ANY COMPLAINTS RECEIVED
(If yes, result thereof)

Yes	
No	✓

32) ANY DEVIATION FROM SPECIFICATIONS GIVEN IN THE TENDER NOTICE / DOCUMENTS
(If yes, give details)

Yes	
No	✓

33) WAS THE EXTENSION MADE IN RESPONSE TIME?
(If yes, give reasons)

✓ Yes	Procurement Committee is unanimous in its view that wider competition can be ensured to extend the response time.
No	

34) DEVIATION FROM QUALIFICATION CRITERIA
(If yes, give detailed reasons.)

Yes	
No	✓

35) WAS IT ASSURED BY THE PROCURING AGENCY THAT THE SELECTED FIRM IS NOT BLACK LISTED?

Yes	✓	No	
-----	---	----	--

36) WAS A VISIT MADE BY ANY OFFICER/OFFICIAL OF THE PROCURING AGENCY TO THE SUPPLIER'S PREMISES IN CONNECTION WITH THE PROCUREMENT? IF SO, DETAILS TO BE ASCERTAINED REGARDING FINANCING OF VISIT, IF ABROAD:
(If yes, enclose a copy)

Yes		No	✓
-----	--	----	---

37) WERE PROPER SAFEGUARDS PROVIDED ON MOBILIZATION ADVANCE PAYMENT IN THE CONTRACT (BANK GUARANTEE ETC.)?

Yes	✓	No	
-----	---	----	--

38) SPECIAL CONDITIONS, IF ANY
(If yes, give Brief Description)

Yes	
No	

Signature & Official Stamp of
Authorized Officer _____

FOR OFFICE USE ONLY

PROJECT OFFICE
KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)
DISTRICT KHAIRPUR

KHAIRPUR
SPECIAL ECONOMIC ZONE

No. DPD/KSEZ/KHP-2017/ 1687

Dated: 29/05/2017

M/S Blue Stone Associates
A-603 West Point Tower
Phase-II, DHA, KARACHI.
MOB: 0300-2338188

**CONSTRUCTION OF TREATED EFFULENT PIPE LINE FROM STP OUT FALLING TO
ROHRI CANAL RD: 85+263**

- Letter of Award /Acceptance

Dear Sir,

Reference is made to your Bid submitted for the above-mentioned Works dated March 7th 2017.

We are pleased to inform you that the Employer, "Project Office- Khairpur Special Economic Zone (KSEZ)" has accepted your bid based on the final offer amounting to Rs. 30,671,372/- (Pak Rupees: Thirty Million, six Hundred Seventy One Thousand, Three Hundred seventy two Only) for the execution of the subject Works; subject to the following Conditions:

- a. The Works shall be executed strictly in accordance with the conditions set out in the Bidding and Contract Document.
- b. Time is of essence, you will be required to complete the Work within 180 days.
- c. You will be liable to pay liquidated damages to the Employer as stated in the Contract Document in case of any delay in the completion of the Project beyond the stipulated period.
- d. The B.O.Q unit rates included in the Contract are firm & fixed and will not be subject to change for any reason whatsoever, and will be considered the Bid rates for all contractual purposes. No price escalation is admissible under this Contract.
- e. All conditions/stipulations/requests, if any, attached with your Bid whether made a part of your Bid or otherwise are to be treated as null and void. The Contract conditions contained in the Bidding Document shall be applicable and considered as part of the Contract Agreement.

You are required to immediately contact "National Industrial Parks Development & Management Company (NIP)" and proceed with the formalities required under the Bidding Document for expeditious execution of the Contract Agreement and commencement of Work at the Site at the earliest possible date. You are requested to take the following actions within 07 days from the receipt of this letter.-

**PROJECT OFFICE
KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)
DISTRICT KHAIRPUR**

No. DPD/KSEZ/KHP/-26

Dated: / /20

1. You are required to furnish Guarantees and Insurance Policies as per the Contract.
2. You are required to depute your authorized representative(s) with proper Power of Attorney for the purpose of accepting and executing the Contract Agreement with the Employer, Project Office- Khairpur Special Economic Zone on form set out in the Bidding Document on non-judicial stamp paper of appropriate value.
3. You will positively start the work within 14 days from the date of signing of the Contract Agreement.
4. M/s EA Consulting Pvt. Ltd. appointed for the purpose shall act as "Engineer" under the Agreement.
5. Till such time a formal Agreement is executed, this Letter of Acceptance along with your offer as detailed above shall constitute a binding Agreement between us.
6. Please sign, date, affix your Company's seal and return one copy of the Letter of Award/Acceptance in token of your acceptance of this Letter.

Thanking you,

For & on behalf of
Project Office - Khairpur Special Economic Zone


DR FARHAN FAROOQ (PAS)

Project Director

KHAIRPUR SPECIAL ECONOMIC ZONE

Blue Stone Associates

ACCEPTED

Proprietor


(Name, Designation & Signature of Authorized Representatives with Seal of M/S Blue Stone Associates)

Date: _____

C.C

1. Sr. Manager Technical, NIP
2. M/s EA Consulting Pvt. Ltd. (The Engineer)

100
Rupees



D. SIALI STAMP VENDOR

Phone No. 118 P.O. No. 8-977

8554

30 MAY 2017

Muhammad Waris Khan Ajmeri
Advocate
Lodger No. 18117



FORM OF CONTRACT AGREEMENT

THIS CONTRACT AGREEMENT (hereinafter called the "Agreement") made on the 01 day of June 2017 between **Project Office Khairpur Special Economic Zone (KSEZ)** (hereinafter called the "Procuring Agency") of the one part and **Blue Stone Associates** (hereinafter called the "Contractor") of the other part.

WHEREAS the Procuring Agency is desirous that certain Works, viz Construction of treated Effluent Pipe Line From STP out falling to Rohri Canal RD: 85+263 should be executed by the Contractor and has accepted a Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein.

NOW this Agreement witnessed as follows:

1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to



Page No.

The following documents after incorporating addenda, if any except those parts relating to Instructions to Bidders, shall be deemed to form and be read and construed as part of this Agreement, viz:

- (a) The Letter of Acceptance;
- (b) The completed Form of Bid along with Schedules to Bid;
- (c) Conditions of Contract & Contract Data;
- (d) The priced Schedule of Prices/Bill of quantities (BoQ);
- (e) The Specifications; and
- (f) The Drawings



In consideration of the payments to be made by the Procuring Agency to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Procuring Agency to execute and complete the Works and remedy defects therein in conformity and in all respects within the provisions of the Contract.

The Procuring Agency hereby covenants to pay the Contractor, in consideration of the execution and completion of the Works as per provisions of the Contract, the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

IN WITNESS WHEREOF the parties hereto have caused this Contract Agreement to be executed on the day, month and year first before written in accordance with their respective laws

Signature of the Contractor

Blue Stone Associates

(Seal)

Proprietor

Signed, Sealed and Delivered in the presence of:

Witness:

(Name, Title and Address)

Signature of the Procuring Agency


(Seal)

Witness:

(Name, Title and Address)

WESTER
 WAVEED JAHAN & CO.
 PUBLIC ACCOUNTANTS
 KARACHI-CENTRAL
 Notary Public
 KARACHI (Pakistan)

2022



Amount in words: Rs. Thirty Million, Seven Lacs and Fifty Two Rupees
~~Rs. Thirty Million, Seven Lacs and Fifty Two Rupees~~

TOTAL COST OF THE PROJECT

30,671,314

3,824,974
26,227,400
619,000

AMOUNT (Rs.)

DESCRIPTION

PERMANENT WORKS

Civil Works
Construction of Pump Room & Underground Tank
Electrical Works (Pump House)
Other Works

GRAND SUMMARY
BILL OF QUANTITIES

STATE ELECTRICAL ZONE (SEZ)

Location of Pump Room & U.G Tank

CODE OF SIIIDH CSR 2012	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SIIIDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
Item #/Page#/ Vol. schd ref.						
Item # 1(1)-18(iii)/ P-204751/Vol. II,Part-III, PHEW1	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation in foundation and dewatering in all kind of soil of building, bridges and other structures including dogbelling dressing refilling around structure with (suitable) excavated earth watering, ramming complete and disposal of surplus excavated material to designated area i/c all lead & lift etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	326	M ³	380	303.92	
Chapter-4 Item # 5(i) / P- 13 /Vol-III,Part-II, (General)	PCC CONCRETE (1:4:8) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing of stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	6	M ³	4700	3,997.19	
Chapter-4 Item # 19(i)(ii)/2) / P- 18 /Vol-III,Part-II, (General)	WOODEN FORMWORKS/SHUTTERING Providing, fixing erecting and removal of partial wood centering (shuttering / formwork) of approved quality for RCC or plain cement concrete works etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	325	M ²	290	361.31	
Chapter-4 Item # 6a(ii) / P- 16 /Vol- III,Part-II, (General)	Form work for 1:4:8 concrete RCC CONCRETE (Sub-Structure) Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	90	M ³	14700	12,326.62	
	RCC Concrete Cylindrical strength 21 Mpa (3000 Psi) U.G Tank (Top & Bottom Slab + Wall)					

Handwritten signatures and stamps at the bottom of the page.

BILL OF QUANTITIES

CODE OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
Chapter-4 Item # 3b / P-17 Vol-III, Part-II, (General)	<p>STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>	14.7	Ton	119,000	100,034	16,11,000
Chapter-11 Item # 27 P-71 Vol-III, Part-II, (General)	<p>BITUMEN COATING Providing and applying industrial bitumen paint/coating to plastered or cement concrete surface etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>	168	M ²	3-00	83.72	3,30,000
Chapter-4 Item # 3a [1] / P-16, 17 / Vol-III, Part-II, (General)	<p>RCC CONCRETE SUPER-STRUCTURE-Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>					
	RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)					
	Pump Room (Slab & Beam)	9	M ³	12300	12,326.68	1,10,000
	Column	2	M ³	12300	12,326.68	2,46,000
	For Ramp	0.2	M ³	12300	12,326.68	2,46,000
Chapter-4 Item # 3b / P-17 Vol-III, Part-II, (General)	<p>STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>	1.9	Ton	119,000	100,034	2,10,000

19,17,000



500 P-10

BILL OF QUANTITIES

Sl. No. GOVT. OF SINDH CSR 2012 Item #/Page#/Vol.sched ref.	DESCRIPTION	QTY	UNIT	RATE (To be fill by bidder) (Rs.)	CSR SINDH SCHED 2012 RATE (Rs.)	AMOUNT (Rs.)
Chapter-4 Item # 23 / P-19 Vol-III,Part-II, (General)	<p>BLOCK MASOIRY (For Walls & Steps) Providing and laying Block masonry work in ground floor super structure up to any height and of any floor etc. laid and jointed with 1:3 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>	40	M ³	5350	5,164.20	23100
Chapter-8 Item # 16c+75 / P-42,50 / Vol. III,Part-II, (General)	<p>ROOF TREATMENT Provide and lay roof treatment over roof & skirting as per specifications, as shown in drawings & details, consisting of following items. Provide and laying 2" (50 mm) thick topping cement concrete 1:2:4 screed floor including surface finishing, leveling curing and dividing into panels with P/fixing glass strip 4mm for flooring up to 1" depth of specified pattern & design etc.</p>	34	M ²	580	472.53	10170
Chapter-7 Item # 13 / P-35 / Vol. III,Part-II, (General)	Provide and apply 2 coats of bitumen laid hot using @ 34 lbs for % sft over roof screed and blinded with sand of one Cft.Per % sft	34	M ²	200	203.08	6900
Chapter-8 Item # 16c+75 / P-42,50 / Vol. III,Part-II, (General)	<p>FLOORINGS Providing and laying 2" (50 mm) thick topping cement concrete 1:2:4 floor including surface finishing, leveling curing and dividing into panels with P/fixing glass strip 4mm for flooring up to 1" depth of specified pattern & design with steel trowel finished maintaining proper level etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>	21	M ²	580	472.53	11550
Chapter-9 Item # 13c / P-52 / Vol. III,Part-II, (General)	<p>PLASTER (INTERNAL WALL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to internal walls, columns, beams, etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).</p>	79	M ²	130	278.74	33100

BILL OF QUANTITIES

GOVT OF SIKH CSR 2012	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SIKH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
Item #/Page#/ Vol.sched.ref						
Chapter-10 Item # 384#b / P-27 / Vol.III,Part II (General)	<p>PAINT (INTERNAL WALL SURFACE) Providing and applying painting on all internal wall surface with Enamel Paint of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>	79	M ²	310	152.98	24470
Chapter-9 Item # 13b / P- 51 / Vol.III,Part II (General)	<p>PLASTER (INTERNAL CEILING SURFACE) Providing and applying 12mm (1/2") thick cement plaster to internal ceiling, soffits of beams and projections etc. with cement mortar 1:6 i/c all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).</p>	21	M ²	380	237.43	7920
Chapter-9 Item # 23124a-b/c / P- 51 / Vol.III,Part II (General)	<p>PAINT (INTERNAL CEILING SURFACE) Providing and applying painting on all internal ceiling surface with Berger Robbialac or equivalent Oil Bound Distemper of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the</p>	21	M ²	290	340.94	6040
Item # 13b / P- 52 / Vol.III,Part II (General)	<p>PLASTER (EXTERNAL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to external walls, columns, beams, etc. with cement mortar 1:6 i/c all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).</p>	108	M ²	480	278.74	57440
Item # 38a#b / P-56 / Vol.III,Part II (General)	<p>PAINT (WEATHERSHIELD ON EXTERNAL SURFACE) Providing and applying preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick /sand paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (At any height)</p>	115	M ²	290	276.31	31775


 BIDDING

Sl. No.	SCOPE OF WORK CSR 2012 Item #/Page #/ Vol. Sched. ref.	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SCHEDULE SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
MS WORKS							
15	Chapter - 17 Item # 2+2 / P- 10 Vol III, Part II, (General)	Providing, fabrication, erecting and fitting in position of heavy steel works with (angles, tees, flat iron, round iron, and sheet iron for making trusses, girders, tanks etc. including cutting tanks etc. including cutting, drilling, riveting, handling assembling and fixing in position etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.					
16		For MS Louvered Door	150	Kg	140	103.99	15598.50
17		For MS Windows	325	Kg	140	103.99	45596.75
18		For MS Girder (Size W 12 x 30)	200	Kg	140	103.99	28798.00
PAINT (ON MS WORKS)							
19	Item # Sd (i, ii) P-20, Vol III, Part II (General)	Providing and applying preparing the surface and painting in all types of MS guard bars, gates of iron bars, grating, railings (including standard braces etc) and similar open work with priming coat / enamel coating of approved make (1st coat, 2nd & subsequent coat) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (At any height)	18	M ²	460	136.74	2461.32
Total Amount of Schedule Items							57794.57
Total Amount of Schedule Items-A							57794.57
NON-SCHEDULE ITEMS							
20		Providing and applying 20mm (3/4") thick cement plaster to walls of U.G Tank with cement mortar 1:4 mixed with Pudo. ic all corners, recesses, jambs, taking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	150	M ²	450		67500.00
21		Providing and laying 2" (50 mm) thick cement concrete 1:2:4 floor including surface finishing, leveling curing finish with steel trowel maintaining proper level etc. complete in all respects as per standard specification, drawing and entire	50	M ²	520		26000.00
22		Providing and fixing 20 mm M.S Steel Rung Epoxy coated embedded in wall complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	38	Mos	700		26600.00
Total Amount of Non-Schedule Items							120100.00
Grand Total Amount of Schedule & Non-Schedule Items (A + B)							177894.57

Collection of Treated Effluent Pipe Line

Sl. No.	Item #/ Page #/ Attached ref.	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SCHED. 2012 RATE (Rs.)	REMARKS (Rs.)
(1) EXCAVATIONS, BACKFILLING AND DEWATERING							
1	Item # 4(11+150-07) / 2, 2012-15-104, (P) (S) (R) (S) (W)	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation for pipe line in trenches, and test pits (upto 1.5m depth) in all kind of soft soils i/c trimming and dressing sides to true alignment, and shape, leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth with in a one chain as directed by the Engineer, providing 1000mm guard light flags and temporary crossing for non vehicular traffic where ever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5 m) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.					
of		Trench Depth (0.0-1.5) m	7,119	MP	390	31035	220000
of	Item # 4(12+150-09-157) / 2, 2012-15-104	Trench Depth (1.5-2.5) m	4,214	MP	330	33827	142000
(2) SAND BEDDING							
1	Chapter 1 Item # 29 / 2012-15-104, Part-B (General)	SAND BEDDING Supplying and filling sand under floor in trench around pipe and plugging in walls etc. complete in all respect as per drawings and specification, and as directed by the Engineer incharge.	716	MP	390	40302	288000
(3) PCC CONCRETE (1:2:4) FOR THRUST BLOCK (PROVISIONAL)							
1	Item # 5(1) / 4-16 / 2012-15-104, Part-B (General)	Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening, shuttering and washing of stone aggregate without shuttering etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.					
of		Below NGI	2	M ³	4200	4,448.55	8800
(4) PIPES (HDPE)							
1	Chapter 2 Item # 5(1) / P-2012-15-104, Part-B (General)	Providing, laying, fixing in trench i/c filling, jointing & testing etc. complete in all respect the high density polyethylene (P.E) Pipe (HDPE - 100) for W/S conforming ISO 4427/DIN8074/8075 BS 3505 S. PSI 3051.					
of		250mm (OD) and 226mm (ID)	5,885	R.M	3150	3,422.08	202000
Total Amount of Schedule Items							
Total Amount of Schedule Items-A							



CODE OF BIDDING 2012 Item #/Page#/ Vol sched ref.	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
(This section is intentionally left blank)						
	FITTINGS (HDPE) Supplying, installing, jointing and fixing all fittings (tees, bends etc.) conforming to ISO - 4427, ISO - 1167 DIN 8074/75 & PS 3580: 1994 & DWS 2207 -1, of approved manufacturer's specification and standard etc. complete in all respect as per drawings and specification and as directed by the Engineer Incharge.					
	BENDS (Provisional) 11.25degree/250mm dia 45degree/250mm dia 90degree/250mm dia	9 7 5	Nos Nos Nos	17,000 16,000 17,000		153,000 112,000 85,000
	TEE (UNEQUAL) 250mm X 250mm X 75mm	10	Nos	25,000		250,000
	GATE VALVES Providing, fixing, jointing and testing of Cast Iron flanged Gate valve with extra flanges of approved quality, including all accessories such as nut, bolts gasket and washers etc. complete in all respect as per drawings and specification and as directed by the Engineer in charge.					
	250mm dia(PH-10)	2	Nos	90,000		180,000
	AIR RELIEF VALVES Providing, fixing, testing and commissioning and installing imported double acting flanged Air Relief Valve with extra flanges required from approved manufacturers including 50mm dia Isolating flanged gate valve, CI Adaptor, Nut, bolt, gasket, pipe piece with flanges etc. complete in all respect as per drawings and specification and as directed by the Engineer in charge.					
	75mm dia	10	Nos	10,000		1,00,000
	WASH OUT VALVES Providing and installing washout arrangement with extra flanges required for draining out the lines including pipe, fittings etc. complete in all respect as per drawings and specification and as directed by the Engineer In charge.					
	250mm dia	4	Nos	20,000		80,000



SCOPE OF SMDH CSR 2012 Item B/Page# referred ref.	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SMDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
	<p>NON RETURN VALVE Providing, fixing, testing and commissioning of flanged non return valve with extra flanges, required from approved manufacturers including all accessories such as nuts, bolt, washer and rubber gaskets etc. complete in all respect as per drawings and specification and as directed by the Engineer incharge.</p>	1	Nos	20,000		20,000
	<p>250mm dia VALVE CHAMBERS Providing, making and constructing of R.C.C Chamber for Gate Valve, Washout Valve, Air relief valve and Non Return Valve work comprising of (Lean concrete 1:4:8, Rcc concrete 1:2:4 Base and top slab, formwork, steel reinforcement, 1:2:4 solid concrete block work wall, internal plaster, 1:3:6 benching/support concrete, MS iron steps, wrap of HDPE pipe and bitumen coating if required as per drawing and specification and as per instructions of Engineer complete in all respect.</p>	17	Nos	45,000		765,000
	<p>PUMPS AND MOTORS Providing, installing, testing and commissioning of MWP single stage, non clogging horizontal centrifugal pump including cost of motor of approved quality and required H.P. having rpm not exceeding 1450, i/c the cost of all fillings and accessories & also i/c the cost of electrical panels with all electrical fillings and fixture etc complete in all respect as per drawings and specification and as directed by the Engineer incharge.</p>	2	Nos	450,000		900,000
	<p>Pumps (660 Gpm) and head of 40.0 m (1) ROAD CUTTING AND REINSTATEMENT (Provisional) Dismantling of road hard crust in full thickness including bitumen carpet, road metalling, sealing etc from existing road surface i/c its removal & disposal of dismantled materials and reinstatement as per original condition complete in all respects as directed by the Engineer.</p>	31	M ²	4500		139,500

18,24,500



BILL OF QUANTITIES

PIPE WORKS

ITEM NO. & DESCRIPTION	DESCRIPTION	QTY	UNIT	RATE (To be fill by bidder) (Rs.)	CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
1	OUTFALL CONNECTION WITH EXISTING CANAL Providing, making & constructing of stone pitching wall & R.C.C Structure i/c Excavation, Backfilling, Reinforced Cement Concrete with shuttering steel reinforcement & flap valve as shown in drawing or specified location of approved design all works etc. complete in all respect, as per specifications & relevant drawings and all works to the entire satisfaction of the Engineer.	1	Job	400,000		400,000
Total Amount of Non-Schedule Items						400,000
Grand Total amount of Schedule & Non-Schedule Items (A + B)						400,000





Item	Description	Unit	Quantity	Rate (Rs.)	Amount (Rs.)
1	Electrical Works for Pump Room as per drawing and specification, complete in all respect.	Job.	1	GR/004	GR/004

TOTAL AMOUNT (RS.)

GR/004

BILL OF QUANTITIES

SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY

CONTRACT EVALUATION FORM

TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC CONTRACTS OF WORKS, SERVICES & GOODS

- 1) NAME OF THE ORGANIZATION / DEPTT. KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)
- 2) PROVINCIAL / LOCAL GOVT. / OTHER PROVINCIAL
- 3) TITLE OF CONTRACT Construction of Brick masonry Retaining wall & Exit Gate along with Gated office
- 4) TENDER NUMBER 1360/2017
- 5) BRIEF DESCRIPTION OF CONTRACT Brick masonry wall on Periphery along with Exit Gate.
- 6) FORUM THAT APPROVED THE SCHEME Procuring Agency
- 7) TENDER ESTIMATED VALUE Rs. 20,052,984 =
- 8) ENGINEER'S ESTIMATE (For civil works only) Rs. 24,240,393 =
- 9) ESTIMATED COMPLETION PERIOD (AS PER CONTRACT) 180 Days
- 10) TENDER OPENED ON (DATE & TIME) March 15, 2017
- 11) NUMBER OF TENDER DOCUMENTS SOLD (Attach list of buyers) 09 (Nine)
- 12) NUMBER OF BIDS RECEIVED 03 (Three)
- 13) NUMBER OF BIDDERS PRESENT AT THE TIME OF OPENING OF BIDS 03
- 14) BID EVALUATION REPORT (Enclose a copy) Attached
- 15) NAME AND ADDRESS OF THE SUCCESSFUL BIDDER Mrs Sikandar Ali Khokhar
Plot No:-A-41 Sachal Sarmest Township
Near SZABIST LARKANA
- 16) CONTRACT AWARD PRICE Rs- 20,052,984 =
- 17) RANKING OF SUCCESSFUL BIDDER IN EVALUATION REPORT (i.e. 1st, 2nd, 3rd EVALUATION BID). 1st Evaluation Bid.

18) METHOD OF PROCUREMENT USED : - (Tick one)

- a) SINGLE STAGE - ONE ENVELOPE PROCEDURE Domestic/ Local
- b) SINGLE STAGE - TWO ENVELOPE PROCEDURE
- c) TWO STAGE BIDDING PROCEDURE
- d) TWO STAGE - TWO ENVELOPE BIDDING PROCEDURE

PLEASE SPECIFY IF ANY OTHER METHOD OF PROCUREMENT WAS ADOPTED i.e. EMERGENCY, DIRECT CONTRACTING ETC. WITH BRIEF REASONS:

19) APPROVING AUTHORITY FOR AWARD OF CONTRACT Procuring Agency KSEZ

20) WHETHER THE PROCUREMENT WAS INCLUDED IN ANNUAL PROCUREMENT PLAN?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

21) ADVERTISEMENT :

i) SPPRA Website
(If yes, give date and SPPRA Identification No.)

Yes	S.No:- 10935 dated:- 19 MAY, 2017
No	

ii) News Papers
(If yes, give names of newspapers and dates)

Yes	The News, Jang, Kawish dated: 17 February 2017
No	

22) NATURE OF CONTRACT

Domestic/Local	<input checked="" type="checkbox"/>	Int.	<input type="checkbox"/>
----------------	-------------------------------------	------	--------------------------

23) WHETHER QUALIFICATION CRITERIA WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

24) WHETHER BID EVALUATION CRITERIA WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?
(If yes, enclose a copy)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

25) WHETHER APPROVAL OF COMPETENT AUTHORITY WAS OBTAINED FOR USING A METHOD OTHER THAN OPEN COMPETITIVE BIDDING?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

26) WAS BID SECURITY OBTAINED FROM ALL THE BIDDERS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

27) WHETHER THE SUCCESSFUL BID WAS LOWEST EVALUATED BID / BEST EVALUATED BID (in case of Consultancies)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

28) WHETHER THE SUCCESSFUL BIDDER WAS TECHNICALLY COMPLIANT?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

29) WHETHER NAMES OF THE BIDDERS AND THEIR QUOTED PRICES WERE READ OUT AT THE TIME OF OPENING OF BIDS?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

30) WHETHER EVALUATION REPORT GIVEN TO BIDDERS BEFORE THE AWARD OF CONTRACT?

(Attach copy of the bid evaluation report)

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

31) ANY COMPLAINTS RECEIVED
(If yes, result thereof)

Yes	
No	<input checked="" type="checkbox"/>

32) ANY DEVIATION FROM SPECIFICATIONS GIVEN IN THE TENDER NOTICE / DOCUMENTS
(If yes, give details)

Yes	
No	<input checked="" type="checkbox"/>

33) WAS THE EXTENSION MADE IN RESPONSE TIME?
(If yes, give reasons)

<input checked="" type="checkbox"/> Yes	Procurement Committee is unanimous in its view that wider competition can be ensured to extend the response time.
No	

34) DEVIATION FROM QUALIFICATION CRITERIA
(If yes, give detailed reasons.)

Yes	
No	<input checked="" type="checkbox"/>

35) WAS IT ASSURED BY THE PROCURING AGENCY THAT THE SELECTED FIRM IS NOT BLACK LISTED?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

36) WAS A VISIT MADE BY ANY OFFICER/OFFICIAL OF THE PROCURING AGENCY TO THE SUPPLIER'S PREMISES IN CONNECTION WITH THE PROCUREMENT? IF SO, DETAILS TO BE ASCERTAINED REGARDING FINANCING OF VISIT, IF ABROAD:
(If yes, enclose a copy)

Yes	<input type="checkbox"/>	No	<input checked="" type="checkbox"/>
-----	--------------------------	----	-------------------------------------

37) WERE PROPER SAFEGUARDS PROVIDED ON MOBILIZATION ADVANCE PAYMENT IN THE CONTRACT (BANK GUARANTEE ETC.)?

Yes	<input checked="" type="checkbox"/>	No	<input type="checkbox"/>
-----	-------------------------------------	----	--------------------------

38) SPECIAL CONDITIONS, IF ANY
(If yes, give Brief Description)

Yes	
No	<input checked="" type="checkbox"/>

Signature & Official Stamp of
Authorized Officer

Farhan Farooq
Project Director
Khairpur Special Economic Zone

FOR OFFICE USE ONLY



**PROJECT OFFICE
KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)
DISTRICT KHAIRPUR**

No. DPD/KSEZ/KHP/-2017/1686

Dated: 29/05/2017

M/s Sikandar ALI KHOKHAR,
Plot No:A-41 Sachal Sarmast Township
Near SZABIST LARKANA.
Mobile:0300-2904937
0333-7548170

**CONSTRUCTION OF BRICK MASONRY RETAINING WALL ALONG MC-02, MC-03 PERIPHERY
AND EXIT GATE ALONG WITH GATE OFFICE**

- Letter of Award/ Acceptance

Dear Sir,

Reference is made to your Bid submitted for the above-mentioned Works dated March 7th 2017.

We are pleased to inform you that the Employer, "Project Office- Khairpur Special Economic Zone (KSEZ)" has accepted your bid based on the final offer amounting to Rs. 20,052,984/- (Pak Rupees: Twenty Million, fifty two Thousand, Nine Hundred eighty-four Only) for the execution of the subject Works; subject to the following Conditions:

- a. The Works shall be executed strictly in accordance with the conditions set out in the Bidding and Contract Document.
- b. Time is of essence, you will be required to complete the Work within 180 days.
- c. You will be liable to pay liquidated damages to the Employer as stated in the Contract Document in case of any delay in the completion of the Project beyond the stipulated period.
- d. The B.O.Q unit rates included in the Contract are firm & fixed and will not be subject to change for any reason whatsoever, and will be considered the Bid rates for all contractual purposes. No price escalation is admissible under this Contract.
- e. All conditions/stipulations/requests, if any, attached with your Bid whether made a part of your Bid or otherwise are to be treated as null and void. The Contract conditions contained in the Bidding Document shall be applicable and considered as part of the Contract Agreement.

You are required to immediately contact "National Industrial Parks Development & Management Company (NIP)" and proceed with the formalities required under the Bidding Document for expeditious execution of the Contract Agreement and commencement of Work at the Site at the earliest possible date. You are requested to take the following actions within 07 days from the receipt of this letter:-



**PROJECT OFFICE
KHAIRPUR SPECIAL ECONOMIC ZONE (KSEZ)
DISTRICT KHAIRPUR**

No. DPD/KSEZ/KHP/2017/1686

Dated: 29/05/2017

1. You are required to furnish Guarantees and Insurance Policies as per the Contract.
2. You are required to depute your authorized representative(s) with proper Power of Attorney for the purpose of accepting and executing the Contract Agreement with the Employer, Project Office- Khairpur Special Economic Zone on form set out in the Bidding Document on non-judicial stamp paper of appropriate value.
3. You will positively start the work within 14 days from the date of signing of the Contract Agreement.
4. M/s EA Consulting Pvt. Ltd. appointed for the purpose shall act as "Engineer" under the Agreement.
5. Till such time a formal Agreement is executed, this Letter of Acceptance along with your offer as detailed above shall constitute a binding Agreement between us.
6. Please sign, date, affix your Company's seal and return one copy of the Letter of Award /Acceptance in token of your acceptance of this Letter

Thanking you,

For & on behalf of
Project Office - Khairpur Special Economic Zone


Project Director


ACCEPTED

(Name, Designation & Signature of Authorized Representatives with Seal of M/S Engineering Links International


Date: M/s Sikander Ali Khokhar 29/05/17
Govt: Contractor
LARKANA

C.C

- ✓1. Sr. Manager Technical, NIP
2. M/s EA Consulting Pvt. Ltd. (The Engineer)



1065 Issued by: M/s Sikander Ali Khokhar Govt. Contractor Larkana.

20 May 2017


FORM OF CONTRACT AGREEMENT

THIS CONTRACT AGREEMENT (hereinafter called the "Agreement") made on the 20th day of (month) May 2017 between Project Office Khairpur Special Economic Zone (KSEZ) District Khairpur Mirs, (hereinafter called the "Procuring agency") of the one part and M/s Sikander Ali Khokhar, Larkana. (Hereinafter called the "Contractor") of the other part.

WHEREAS the procuring agency is desirous that certain Works, viz Construction of Brick Masonry Retaining Wall Along MC-01, MC-03, Periphery and Exit Gate Along With Gate Office Khairpur Mirs, an amounting of Rs.20,052,984/- should be executed by the Contractor and has accepted a Bid by the Contractor for the execution and completion of such Works and the remedying of any defects therein.


NOW this Agreement witnessed as follows:

1. In this Agreement words and expressions shall have the same meaning as are respectively assigned to them in the Conditions of Contract hereinafter referred to.
2. The following documents after incorporating addenda, if any, except those parts relating to instruction to Bidders shall be deemed to form and be read and construed as part of this Agreement viz:
 - a) The Contract Agreement;
 - b) The Letter of Acceptance;
 - c) The completed Form of Bid;
 - d) Special Stipulations (Appendix-A to Bid);
 - e) The special Conditions of Contract – Part II;
 - f) The General Conditions – Part I;
 - g) The priced Bill of Quantities (Appendix-D to Bid);
 - h) The completed Appendices to Bid (B, C, E to L);
 - i) The Drawings;
 - j) The Specifications;
 - k) _____ (Any other).



M/s Sikander Ali Khokhar
Govt. Contractor
LARKANA

In consideration of the payments to be made by the procuring agency to the Contractor hereinafter mentioned, the Contractor hereby covenants with the procuring agency to complete the Works and remedy defects therein in conformity and in all respect with the provisions



106 Issued by: M/s Sikander Ali Khokhar Govt. Contractor Larkana.

[Handwritten signature]

26 MAY 2017
CA-2

4. Procuring agency hereby covenants to pay the Contractor, in consideration of the execution and completion of the Works as per provisions of the Contract Price or such other sum as may become payable under the provisions of the Contract at the times and in the manner prescribed by the Contract.

IN WITNESS WHEREOF the parties hereto have caused this Agreement to be executed on the 26th day, month May and year 2017 first before written in accordance with the their respective laws.

Signature of the Contractor

[Signature]
M/s Sikander Ali Khokhar
Govt. Contractor
LARKANA
(Seal)

Signature of Procuring Agency

[Signature]
DR. FARHAN FAROOQ
Project Director
Chairman, Special Economic Zone
(Seal)

Signed, Sealed and Delivered in the presence of:

Witness:

[Signature]
Ishtiaque Ahmed Kakepoto
House No. 43-A Ali Akbar Jalbani Road,
Sachal Colony Larkana.

Witness:

[Signature]
Ghulam Rasool Khokhar
House No. 41-A Ali Akbar Jalbani Road,
Sachal Colony Larkana.


ATTESTED

[Signature]
ADVOCATE B.A, LL.B
NOTARY PUBLIC
DISTRICT KHARPUJA



Amman
02/05/17

For 36/05/2017
Project - Design for Khayma Special Economic Zone -
Kingdom of Saudi Arabia
Mr. David



GRAND SUMMARY


W/s Sikander Ali Khokhar
Govt: Contractor
LARKANA.

BILL OF QUANTITIES
GRAND SUMMARY

Sl. No.	DESCRIPTION	AMOUNT (Rs.)
A	PERMANENT WORKS	
B	Civil Works Brick Masonry Retaining Wall Along the Road MC-02, MC-03 Periphery	16277162
i	Gate Office	3482972
C	Electrical Works (Gate Office)	346850
TOTAL COST OF THE PROJECT		= 20106984/-


M/s Sikaider Ali Khokhar
Govt. Contractor
LARIKANA

Rs. Twenty Million One. Hundred Six Thousand Nine
Hundred Eighty Four Only. 20.05.2011

M/s Sikander Ali Khodhar
Govt: Contractor
LARKANA

CIVIL WORKS

BRICK MASONRY RETAINING
WALL ALONG THE ROAD MC-02,
MC-03 Periphery


M/s Siltander Ali Khokhar
Govt: Contractor
LARKANA

Brick Masonry Retaining Wall Along The Road MC-02 & MC-03

S.No	GOVT OF SINDH CSR 2012 Item #/Page #/ Vol. Sched ref.	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
MAJOR ITEMS							
1	Item # 18(b)+18(ii) / P-4+75 / Vol. III, Part II & III, (General & PHEW)	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation in foundation and dewatering in all kind of soil of building, bridges and other structures including dogbelling dressing refilling around structure with (suitable) excavated earth watering, ramming complete and disposal of surplus excavated material to designated area i/c all lead & lift, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	3432	M ³	339	303.92	1163448
2	Item # 22+13 (b+cii) / P-3 & 4 / Vol-III, Part-II, (General)	IMPORTED EARTH FILLING FROM OUTSIDE SOURCES Supplying and filling watering and ramming earth under floor with new earth excavated from outside in 150mm layers leveling dressing and watering for compaction and to obtain 95% modified AASHTO density. Complete including all lead & lifts etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	3413	M ³	187	167.42	638231
3	Item # 20 / P-10 / Vol-III, Part-II, (General)	DSMANTLING OF EXISTING COLUMN Dismantling cement concrete reinforced sepraling reinfor cement from concrete cleaning and straightening the same etc complete in all respect as per standard specification, drawing and entire satisfaction of the Engineer.	54	M ³	2153	1,923.17	116262
4	Item # 5(b) / P-16 / Vol-III, Part-II, (General)	PCC CONCRETE (1:3:6) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing of stone aggregate without shuttering etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	154	M ³	4981	4,448.55	767074
5	Item # 19b(i+ii) / P-18 / Vol-III, Part-II, (General)	WOODEN FORMWORKS/SHUTTERING Providing, fixing, erecting and removal of partal wood centering (shuttering / formwork) of approved quality for RCC or plain cement concrete works etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	342	M ²	404	361.31	138168
6	Item # 6a(ii) / P-16, 17 / Vol-III, Part II, (General)	RCC CONCRETE Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid seperately. This rate also includes all kinds of forms moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc, complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	171	M ³	13805	12,326.68	2360645

W/s Sikkander Ali Kholdhar
 Govt. Contractor
 LARIKANA

Bid: Masonry Retaining Wall Along The Road MC-02 & MC-03

S.No.	GOVT.OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
	Item #/Page#/Vol.sched ref.						
7	Item # B1 / P-17 / Vol.III,Part-II, (General)	<p>STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of Tor / deformed steel reinforcement for cement concrete including cutting,bending,laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>	14	Ton	120000	100.034	1680000
8	Item # 5(11) / P-21 / Vol.III,Part-II, (General)	<p>BRICK MASONRY Providing and laying pucca brick masonry work (1st class quality) in ground floor super structure up to any height and at any floor etc. laid and jointed with 1:3 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.</p>	1234	M ³	5425	4844.28	6694150
9	Item # 11C / P-52 / Vol. III,Part-II,(General)	<p>PLASTER (EXTERNAL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to external walls, columns, beams, etc. with cement mortar 1:4 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height). (S.R cement to be used)</p>	2077	M ²	362	324.50	751874
Total Amount of Schedule Items-A							14310160

Sikander Ali Khokhar
M/s Sikander Ali Khokhar
Govt: Contractor
LARKANA

Brick Masonry Retaining Wall Along The Road MC-02 & MC-03

Sl. No.	GOVT OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
UNRECORDED ITEM							
1		REMOVING & RE-FIXING OF FENCE removing of existing fence including Chiseling, cutting of existing column consisting of [G.I wire net, G.I pipe 10swg, nuts & bolt, flat, hold last] etc, and where required as shown in the drawings cutting of fence with gas cutter including cleaning, debris stacking at appropriate place and dispose off at locations which approved by the the Engineer with all leads and fill etc. complete as per drawing and specifications and approval of the Engineer.	1821	M ²	500		910500
2		REMOVING & RE-FIXING OF FOOTPATH Removing of existing foot path paver and slaking at site as per instruction of the engineer including re fixing of these after completion masonry work, refilling and compaction work complete as per (Case-1) drawing and specifications and approval of the Engineer.	504	M ²	500		252000
3		75mm Thick C.C Coping Providing and laying (1:3) plain cement sand mortar coping concrete over brick masonry or where required including all formwork, rodding, leveling, compacting curing and finishing etc. complete as per drawing and specifications and approval of the Engineer.	29	M ³	500		14500
4		BRICK MASONRY WORK (Bricks Supplied by the Client) Providing and laying pucca brick masonry work in ground floor super structure up to any height and at any floor etc, laid and jointed with 1:3 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. <i>NOTE: Bricks are provided by the client at site, only laying rate is required with CS mortar</i>	900	M ³	600		540000
5		Providing and fixing new periphery fence made from 50x4mm wire net fixed to 50mm dia x 10 swg G.I pipe frame panels of 2400 x 1700 mm size fixed with each other with 50mm x 5mm holdlasts vertically at three points. The G.I pipe supports to be embedded into RCC 1:2:4 pedestals of size 600 x 250 x to required height over RCC 1:2:4 footings of size 1000 x 500 x 300 mm high. Top of pedestal to matched as per existing, including excavation, lean concrete, etc. Complete in all respect as per drawings, specifications and direction of the Engineer.	125	Rm	2000		250000

Signature
M/s Sileander Ali Khokhar
Govt. Contractor
LARKANA

Block Masonry Retaining Wall Along The Road MC-02 & MC-03

Sl. No	GOVT. OF SINDH CSR 2012	DESCRIPTION	QTY	UNIT	RATE (To be fill by bidder) (Rs.)	CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
	Item #/Page#/ Vol. sched ref.						
6		SWEET EARTH Supplying and spreading of earth loam to loamy sand free from salinity & pebbles etc, from approved source i/c leveling, dressing, breaking clods, & compaction etc, complete as per direction of the Engineer. (Loose thickness)	440	M ³			
7		MANURE/COW DUNG Supplying stacking and spreading cow dung manure / slaughter house manure and mixing the same up to depth in the already laid sweet earth including breaking clods, dressing line for trees or grass and sprinkling water, raking and rolling complete in all respect as per direction of the Engineer.	203	M ³			
8		GRASS Providing and planting of grass of specific manner including watering till grass get green & grow up well and maintaining of same till completion of contract etc, complete in all respect as per direction of the Engineer.	1365	M ²			
APPLICABLE							
Total Amount of Non-Schedule Items-B							1767000
TOTAL CARRIED TO GRAND SUMMARY (A + B)							6277100

M/s Sikander Ali Kholthar
Govt. Contractor
LARIKANA

GATE OFFICE

M/s Sikander Ali Kholhar
Govt: Contractor
LARIKANA

Construction of Gate Office

S.No	GOV.OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	RATE (to be Fill by bidder) (Rs.)	CSR SINDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
PART A (SCHEDULE ITEM)							
1	Item # 18(b)+18(iii)/ P-4/75/ Vol. III, Part II & III, [General & PHEW]	EXCAVATIONS, BACKFILLING AND DEWATERING Excavation in foundation and dewatering in all kind of soil of building, bridges and other structures including daggelling dressing refilling around structure with (suitable) excavated earth watering, ramming complete and disposal of surplus excavated material to designated area i/c all lead & lift, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	155	M ³	339	303.92	52545
2	Item # 22+13 (b+ci)/P-3 & 4/Vol-III, Part-II, [General]	IMPORTED EARTHFILLING FROM OUTSIDE SOURCES. Supplying and filling watering and ramming earth under floor with new earth excavated from outside in 150mm layers leveling dressing and watering for compaction and to obtain 95% modified AASHTO density. Complete including all lead & lifts etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	27	M ³	187	167.42	5119
3	Item # 2 / P-15 /Vol-III, Part-II, [General]	STONE SOLING Providing and laying dry rammed brick or stone ballast / soling 1 1/2" to 2" gauge from approved quarry including hand packing & filling voids with spraws & chips, consolidating & compacting with power or hand roller, etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	30	M ³	1316	1,175.27	39480
4	Item # 5(i) / P-16 /Vol-III, Part-II, [General]	PCC CONCRETE (1:4:8) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing of stone aggregate without shuffling etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	12	M ³	4465	3,987.19	53580
5	Item # 5(h) / P-15 /Vol-III, Part-II, [General]	PCC CONCRETE (1:3:6) Providing and laying cement concrete plain including placing compacting, finishing, leveling and curing (including screening and washing of stone aggregate without shuffling etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	3	M ³	4981	4,448.55	14943
6	Item # 19b(i+ii)/2 / P-18 /Vol-III, Part-II, [General]	WOODEN FORMWORKS/SHUTTERING Providing, fixing, erecting and removal of partial wood centering (shuttering / formwork) of approved quality for RCC or plain cement concrete works etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	22	M ²	404	361.31	8888
7		Form work for 1:3:6 concrete	5	M ²	404	361.31	2020

W/s Sileander Ali Khokhar
Govt. Contractor

LARKANA

Construction of Gate Office

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol./sched ref.	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
7	Item # 6a(ii) / P-16,17 / Vol-III, Part II, (General)	RCC CONCRETE SUB-STRUCTURE-Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. This rate also includes all kinds of forms, moulds lifting fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.					
		RCC Concrete Cylindrical strength 21 Mpa (3000 Psi)					
i)		Footing and Concrete Pads	25	M ³	13805	12,326.68	345125
ii)		Plinth Beams	7	M ³	13805	12,326.68	96685
iii)		Column up to Plinth level	3	M ³	13805	12,326.68	41415
8	Item # 8b / P-17 / Vol-III, Part II, (General)	STEEL REINFORCEMENT Providing, supplying, cutting, fabrication of tor / deformed steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	4	Ton	120000	100.034	480000
9	Item # 9 / P-71 / Vol-III, Part II, (General)	BITUMEN COATING Providing and applying industrial bitumen paint/coating to plastered or cement concrete surface etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	270	M ²	92	83.72	24810
10	Item # 2B) / P-19 / Vol-III, Part II, (General)	(D.P.C) DAMP PROOF COURSE Providing and laying DPC damp proof course with (cement sand and shingle concrete 1:2:4) including 2 coats of asphaltic mixture with leveling, curing, finishing etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	5	M ²	474	421.02	2355
11	Item # 92 / P-109 / Vol-III, Part II, (General)	TERMITE TREATMENT Providing Anti-termite treatment by spraying / sprinkling / spreading Neptochlor 0.5% Emulsion as an overall pre-construction treatment in slab type construction under the slab and along attached perches or entrances etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. <i>(Plinth area will be measured one time for payment whereas the number of applications will be three times on all horizontal & vertical surfaces of the excavations for termite proofing).</i>	20	M ²	116	104.80	2321

M/s Sikanter Ali Khattak
Govt. Contractor
LARIKANA

Construction of Gate Office

No.	GOVT. OF SINDH CSR 2012 Item #/Page#/Vol. Sched. ref.	DESCRIPTION	QTY	UNIT	RATE (To be fill by bidder) (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
RCC CONCRETE							
12	Item # 6a(ii) / P-16,17 / Vol-III, Part-II, (General)	SUPER-STRUCTURE-Providing and laying Reinforced cement concrete work including all labor and material except the cost of steel reinforcement and its labor for bending and binding which will be paid separately. This rate also includes all kinds of forms moulds filling fixing of shuttering and its removal and vibrating, curing, rendering and finishing the exposed surface (including screening and washing of shingle) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.					
i)		RCC Concrete Cylindrical strength 21 Mpa (3000 Psi) Column	9	M ³	13805	12,326.68	12424
ii)		Beams, lintels, Projections, Pads, brackets and Sills	4	M ³	13805	12,326.68	55220
iii)		Slab i/c Projection	4	M ³	13805	12,326.68	55220
STEEL REINFORCEMENT							
13	Item # 8b / P-17 / Vol-III, Part-II, (General)	Providing, supplying, cutting, fabrication of tor / delomed steel reinforcement for cement concrete including cutting, bending, laying in position making joints and fastening including cost of binding wire (also includes removal of) etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	2	Ton	120000	100,034	240000
BRICK MASONRY							
14	Item # 5(1e) / P-21 / Vol-III, Part-II, (General)	Providing and laying pucca brick masonry work (1st class quality) in ground floor super structure up to any height and at any floor etc. laid and jointed with 1:4 cement sand mortar using approved quality screened sand including racking out and cleaning of joints and pointing, masonry to be laid in course, true to line, level and plumb, properly cured, etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	14	M ³	5013	4,476.58	70180
BRICK MASONRY STEPS							
15	Item # 4(1c) / P-21 / Vol-III, Part-II, (General)	Providing and laying pucca brick work (1st class quality) in foundation and plinth for entrance steps laid and jointed with 1:4 cement sand mortar using approved quality screened sand masonry to be laid in course, true to line, level and plumb, properly cured, etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. For Steps and where required	1	M ³	4944	4,415.50	4944

Sikander Ali
M/s Sikander Ali Kholdan
Govt. Contractor
LARKANA

Construction of Gale Office

S.No	GOVI.OF SHHDH CSR 2012 Item #/Page#/ Vol.sched.ref.	DESCRIPTION	QTY	UNIT	RATE (To be fill by bidder) (Rs.)	CSR SHHDH SCHED. 2012 RATE (Rs.)	AMOUNT (Rs.)
16	Item # 84(a) / P-108 / Vol.III,Part-II, (General)	ALUMINIUM WINDOWS / VENTILATORS Supplying & fixing in position Aluminium channels framing for sliding windows & ventilators of Alcop made with 5mm thick tinted glass glazing (Belgium) & Aluminium fly screen l/c handles stoppers & locking arrangement etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	5	M ²	19193	17,137	95965
17	Item # 13c / P-52 / Vol. III,Part-II,(General)	PLASTER (INTERNAL WALL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to internal walls, columns, beams, etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height). PAINT (INTERNAL WALL SURFACE) Providing and applying painting on all internal wall surface with Enamel Paint of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	42	M ²	311	278.74	13062
18	Item # 30a+b / P-73 / Vol.III,Part II, (General)	PLASTER (INTERNAL CEILING SURFACE) Providing and applying 12mm (1/2") thick cement plaster to internal ceiling, soffits of beams and projections etc. with cement mortar 1:4 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height). PAINT (INTERNAL CEILING SURFACE) Providing and applying painting on all internal ceiling surface with Berger Robbialac or equivalent Oil Bound Distemper of approved shade three coats over and including a coat of primer over plastered surface at any height in any floor including preparation of surface, filling depression with putty, rubbing, sand papering and cleaning etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer.	42	M ²	170	152.98	7140
19	Item # 11b / P-52 / Vol. III,Part-II,(General)	PLASTER (EXTERNAL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to external walls, columns, beams, etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	25	M ²	274	245.75	6850
20	Item # 23+24a+b+c / P-54 / Vol.III,Part II, (General)	PLASTER (EXTERNAL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to external walls, columns, beams, etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	25	M ²	380	340.94	9500
21	Item # 13c / P-52 / Vol. III,Part-II,(General)	PLASTER (EXTERNAL SURFACE) Providing and applying 20mm (3/4") thick cement plaster to external walls, columns, beams, etc. with cement mortar 1:6 in all corners, recesses, jambs, raking out joints of masonry, scaffolding etc. complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (up to any height).	155	M ²	311	278.74	48505

Sikander Ali Khokhar
#/s Sikander Ali Khokhar
Govt. Contractor
LAKHANA

Construction of Gate Office

S.No	GOVT.OF SINDH CSR 2012 Item #/Page#/Vol.sched ref.	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
22	Item # 38a+b+b / P-56 / Vol.III,Part II, (General)	PAINT (WEATHERSHIELD ON EXTERNAL SURFACE) Providing and applying preparing the surface and painting with weather coat i/c rubbing the surface with rubbing brick /sand paper, filling the voids with chalk/ plaster of Paris and then painting with weather coat of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (At any height)	155	M ²	309	276.31	47895
23	Item # 2+3 / P-21 / Vol.III,Part II, (General)	MS WORKS Providing, fabrication, erecting and fitting in position of heavy steel works with (angles,tees,flat iron, round iron and sheet iron for making trusses, girders, tanks etc.including cutting tanks etc. including cutting, drilling, riveting, handling assembling and fixing in position etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. For Pre-engineered Steel Structure For MS Grill / Gate Gate	8605 3750	Kg Kg	115 115	103.99 103.99	989548 431250
24	Item # 5d(i,ii) / P-70 / Vol.III,Part II, (General)	PAINT (ON MS WORKS) Providing and applying preparing the surface and painting in all types of MS guard bars, gates of iron bars, grating, railings (including standard braces etc) and similar open work with priming coat / enamel coating of approved make (1st coat, 2nd & subsequent coat) etc complete in all respects as per standard specification, drawing and entire satisfaction of the Engineer. (At any height)	262	M ²	150	136.74	39824
Total Amount of Schedule Items-A					M/s Sikkander Ali Khokhar Govt. Contractor LARKANA		340824

Construction of Gate Office

S.No	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol.sched ref.	DESCRIPTION	QTY	UNIT	RATE (To be Fill by bidder) (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
25		<p>ROOF PROTECTION Provide and lay roof treatment as per specifications, and shown in drawings and details shown consisting of following items (For payment only Tile area will be measured) etc. complete in all respects and as directed by the Engineer.</p> <p>i) 1-1/2" thick tiles grouted with cement sand Mortar including making slope, curing, hacking and chipping of existing surface for bonding where necessary, etc. complete</p> <p>ii) 2 layers of water proofing 3" mud filling / plaster with husk with curing etc.</p> <p>iii) 2 layers of polythene sheets 004"-005" thick</p> <p>iv) Bitumen flood coat 10/20 grade 35 lbs / 100 sq ft</p> <p>v) Bitumen flood coat 70/90 grade 5 lbs / 100 sq ft</p>	26	M ²	600		15600
26		<p>DOOR SHUTTER Providing and fixing 38mm thick solid core soft wood filling flush door shutters with 1/8" thick commercial ply on either sides complete cross band of standard specification with 5/8" thick edge solid Red maranti wood lipping all around, as produced by standard manufacturers under power driven hydraulic press as approved by the Engineer-in charge including 1 1/2" x 1/2" Red maranti wood beading / Architraves, approved Local Lock, 9" lower bolt, Door Stopper etc., painting 3 coats with approved enamel paint over a coat of primer (of any floor & height) as per drawing and specifications and to the entire satisfaction of the Engineer.</p>	3	M ²	800		2400
27		<p>FLOORING Providing and laying 9 mm thick floor of Porcelain tiles Matt size 300 x 300 in grey cement, bedding material with cement sand mortar (1:6) including setting the tiles with cement slurry over mortar, jointing and washing the tiles with cement slurry of matching color, grinding, rubbing, polishing and curing etc. complete as per drawings, specifications and approval of the Engineer.</p>	16	M ²	1800		28800
28		<p>SKIRTING Providing and fixing Porcelain tiles Matt 12" x 12" x 1/4" (or equivalent in mm) on skirting in grey cement, with cement sand mortar base (1:6) including setting the tiles with cement slurry over mortar, jointing and matching color, and curing etc. complete as per drawings, specifications and approval of the Engineer.</p>	16	RM	1400		22400


M/s Siltander Ali Khokhar
Govt. Contractor
LARKANA

Construction of Gate Office

Sl. No.	GOVT. OF SINDH CSR 2012 Item #/Page#/ Vol. sched ref.	DESCRIPTION	QTY	UNIT	RATE (To be fill by bidder) (Rs.)	CSR SINDH SCHD. 2012 RATE (Rs.)	AMOUNT (Rs.)
1	2	3	4	5	6	7	8 (A+B)
29		<p>RAIN WATER DRAIN Providing and fixing 75 mm dia UPVC pipe for rain water drain of approved class and make complete with SS jali and all required necessary clamps, fittings, jointing material and mastic filling silicon etc. complete in all respects as per drawing, specifications and as directed by the Engineer. (up to any height).</p>	5	RM	500		2500
30		<p>G.I DOOR FRAME Providing, making and fixing G.I molded sheet 16 Swg door frame size 2"x5" including steel hinges 3 Nos. fixing with cements sand mortar (1:6) painting 3 coats with approved enamel paint over a coat of primer (at any floor & height) as per drawing and specifications and to the entire satisfaction of the Engineer. (Door frame)</p>	6	RM	500		3000
Total Amount of Non-Schedule Items-B							14700
TOTAL CARRIED TO GRAND SUMMARY (A + B)							34829.72

Sikander Ali Kholhar
 M/s Sikander Ali Kholhar
 Govt. Contractor
 LARIKANA

ELECTRICAL WORKS



W/s Siltander Ali Khokhar
Govt: Contractor
LARKANA

Item Nos.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
1	LIGHTING FIXTURES Supply, installation, testing and commissioning of following light fixtures complete with Electronic ballast (unless mention otherwise): lamps, lamps holder, mounting accessories etc. or as per specification, complete in all respects. Lighting fixtures Sample must be submitted to consultant for approval.				
	a) Wall mounted Fluorescent Light Fixture Philips TMS Type with 1 x 36W TLD. Color 84	Nos.	2	1500	3000
	b) Wall mounted Flood Light Fixture Philips CON TEMPO RVP-250 Type weatherproof (IP 65) with 1 x 150W SON-T Lamp.	Nos.	4	1500	6000
	c) Wall mounted Light Fixture Philips type weatherproof with 18W CFL Lamp (IP-54)	Nos.	3	1200	3600
2	L.V DISTRIBUTION BOARDS Supply, installation, testing & commissioning of wall mounted LV Distribution Boards (DB's) as per single line diagram, dust protected, vermin proof housing coated with approved color including all mounting accessories as per specification & drawing complete in all respect.				
	i Distribution Board (DB-GR)	Job	1	100000	100000
3	LOW VOLTAGE CABLES Supply, installation, testing and commissioning of following size of multi core PVC insulated, PVC sheathed unarmoured copper conductor 0.6 kV/1 kV voltage grade cable in already laid raceways or in trench including all accessories lugs, cable gland etc. as per drawings and specification.				
	i 1 x 4 Core - 16 Sq.mm PVC/PVC + 1 x 1-core 16 Sq.mm PVC as ECC	Rm	10	1200	12000
4	WIRINGS				
a	Supply, installation, testing & commissioning of Circuit wiring from DB to switch board with 3x2.5 sq.mm single core, Cu. conductor PVC insulated wires including 20 mm dia. PVC conduit surface / recessed in wall, column, ceiling, etc., complete with all accessories as per specification, complete in all respect.	No.	1	800	800
b	Supply, installation, testing & commissioning of Point wiring from switch board to light point with 3x1.5 sq.mm. wires in 20 mm dia PVC conduit, surface / recessed with all accessories, or as per specification, complete in all respect.	Nos.	5	600	3000
				SUB TOTAL	128400/-

Sikander Ali Khokhar
Sikander Ali Khokhar
Govt. Contractor,
LARKANA

Item Nos.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
Non-eligible item					
c	Supply, installation, testing & commissioning of Circuit wiring from DB to Flood Light point with 3x2.5 sq.mm single core, Cu. conductor PVC insulated wires including 20 mm dia. PVC conduit surface / recessed in wall, column, ceiling, etc., complete with all accessories as per specification and drawing, complete in all respect.	No.	1	800	800 ✓
d	Supply, installation, testing & commissioning of Point wiring for flood light point to flood light point with 3x2.5 sq.mm. wires in 20 mm dia PVC conduit, surface / recessed with all accessories, or as per specification, complete in all respect.	Nos.	3	3000	9000 ✓
5	LIGHTING CONTROL SWITCH Supply, installation, testing and commissioning of following 10 Amps switches, including 16 SWG sheet steel powder coated back boxes, recessed on wall with all accessories, as per drawing and specification, complete in all respects.				
	i Five gang switch	No.	1	500	500 ✓
	ii One gang dimmer with switch 10A	No.	1	250	250 ✓
6	SWITCH SOCKET OUTLET Supply, installation, testing and commissioning of following 3 pin, 5 Amps. switch socket outlets including 16 SWG sheet steel powder coated back boxes, recessed on wall with all accessories, complete in all respects.				
	i 5A, 3 Pin Universal switched socket outlet	No.	1	700	700 ✓
7	CONDUIT Supply & installation of following size (inner dia) PVC conduit as race ways with all accessories recessed/ surface on wall / column / under floor for Power. As per relevant specification, complete in all respect.				
	i 20 mm dia	Rm	10	500	5000 ✓
8	FAN				
a	Supply, installation, testing and commissioning of 56" Sweep ceiling fan with hook including all connecting accessories as per drawings, specifications, complete in all respects.	No	1	4200	4200
				SUB TOTAL	20450/-

(Signature)
 Mr. Sikander Ali Khan
 Govt. Contractor
 LARIKANA

Item Nos.	Description	Unit	Qty.	Rate (Rs.)	Amount (Rs.)
9	EARTHING Supply, installation, testing and commissioning of following items for complete earthing system including all connecting accessories as per drawings & specifications complete in all respects.				
	i. Earth pit with Rod type earth electrode, 20mm dia 3 meter long copper rod, including earthing lead 2x70sq.mm Bare copper conductor.	Job	1	9000	9000
	ii. 1 x 1:Core - 16 Sq.mm as ECC	Rm	15	2200	33000
10	uPVC Pipe Providing and laying of size of 50 mm internal dia uPVC class "D" pipe. Buried in ground as per drawing. Including excavation for laying of pipe and backfilling with clean sand (under and above pipe), compaction nylon rope 5mm and plugging of conduits ends etc. as shown on drawing complete in all respect.	Rm	20	300	6000
11	TELECOMMUNICATION SYSTEM				
a	Providing, fixing, testing & commissioning of RJ-11 telephone outlet (simplex) Weatherpool type with 16 SWG back box, complete in all respect.	No	1	8000	8000
b	Providing, fixing, testing & commissioning of wiring 2 pair CAT-5 cable in 25mm dia PVC Conduit from TJB to telephone outlet as per drawing or as per specification, complete in all respect.	Rm	20	350	7000
				SUB TOTAL	498000/-
				GRAND TOTAL FOR ONE UNIT	346850/-

Govt. Contractor
 LARKANA
 29/11/2019