



KARACHI WATER AND SEWERAGE BOARD
OFFICE OF THE EXECUTIVE ENGINEER, (WATER-I)
GULSHAN-E-IQBAL TOWN

ST-2, BLOCK-14, SCHEME-24, MAIN UNIVERSITY ROAD NEAR CIVIC CENTRE

NO.EE/GIT/W-I/KW&SB/AC/ESTT:/2018-1955

DATED:- 9/11/2018

To,
The Director Capacity Building,
Sindh Public Procurement Regulatory Authority(SPPRA),
Government of Sindh,
Block-8, Sindh Secretariate #4-A,
Karachi

SUBJECT:- **SUBMISSION OF BID EVALUATION REPORT FOR THE WORK OF "RE-LOCATION OF OLD & CONTAMINATED 6"DIA A/C WATER PIPE LINE BY 200MMDIA 'P.E' PIPE FROM HASSAN SUQAE TO ESSA NAGRI AT SIR SHAH SULEMAN ROAD, GULSHAN-E-IQBAL TOWN".**

Reference: **Serial No. 34943 I.D. No. 2017.**

Enclosed please find herewith, the bid evaluation report, for the above referred subject work is being submitted for early hosting of authority's website of SPPRA.

Attendance of the contractor.

EXECUTIVE ENGINEER (WATER-I)
GULSHAN-E-IQBAL TOWN KW&BS

Copy for information to:-

1. The Superintending Engineer, (East),KW&SB.
2. Office Copy.

SPPRA INWARD DIARY

NO : 4445

DATED : 10-01-18

NIT No. SPPRA Serial No.34943

Method of Procurement: Single Stage Single Envelope.

Name of Work: RE-LOCATION OF OLD & CONTAMINATED 6" DIA A/C WATER PIPE LINE BY 200MM DIA 'P.E' PIPE FROM HASSAN SQUARE TO ESSA NAGRI AT SIR SHAH SULEMAN ROAD, GULSHAN-E-IQBAL TOWN

MINUTES OF BID OPENING MEETING.


A meeting of the procurement committee of this department was held on 14-11-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).


2. Three bidders submitted their bids till the deadline of submission.
 - xiii. M/s.King Asif Rehman & Brothers ✓
 - xiv. M/s. Shah Faisal & Brothers ✓
 - xv. M/s.Gul Sawab & Co. ✓
3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.King Asif Rehman & Bros.	Rs.12,58,544/-	Rs.500/-	P.O # 13892582 dt:02-11-2017 from UBL Chandni Chowk Branch Karachi
02	M/s.Shah Faisal & Brothers	Rs.18,22,947/-	Rs.38,000/-	P.O # AAA 14058797 dt:14-11-2017 Rs.18,000/- & P.O # AAA 14058768 Rs.20,000/- dt:08-11-2017 from ABL Paria Street Branch Karachi ✓
03	M/s.Gul Sawab & Company	Rs.18,51,890/-	Rs.40,000/-	P.O # AAA 14058770 Rs.20,000/- & P.O # AAA 14058769 Rs.20,000/- dt:08-11-2017 from ABL Paria Street Branch Karachi ✓


4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the vote of thanks to and from the chair.


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Imdad Hussain Magsi)
S.E (District East-B)
Member


(Saifuddin)
Director (Design & Estimate)
Convener



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	KW&SB/DPR/127/17 published in daily "National Courier", "Dunya" & daily "Pak" "Jasarat" "Pakistan Observer" dt: 24-10-2017. SPPRA Serial No.34943 I.D No.
3	Tender Description/Name of Work/Item:	RE-LOCATION OF OLD & CONTAMINATED 6" DIA A/C WATER PIPE LINE BY 200MM DIA 'P.E' PIPE FROM HASSAN SUQAE TO ESSA NAGRI AT SIR SHAH SULEMAN ROAD, GULSHAN-E-IQBAL TOWN
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through Press & SPPRA Web Site
6	Total Bid Documents Sold:	3 Nos
7	Total Bid Received:	3 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	01 No
11	Financial Bid Opening Date:	14-11-2017

12 BID EVALUATION REPORT

S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.King Asif Rehman & Bros.	Rs.12,22,544/-	-	@34.066% Below	Less amounts Pay Order attached, required documents are available. P.O # 13892582 dt:02-11-2017 Rs.500/-from UBL Chandni Chowk Branch Karachi	Un Responsive
2	M/s.Shah Faisal & Brothers	Rs.18,22,947/-	1 st Lowest	@1.686% Below	Pay Order and required documents are available. P.O # AAA 14058797 dt:14-11-2017 Rs.18,000/- & P.O # AAA 14058768 Rs.20,000/- total Rs.38,000/- dt:08-11-2017 from ABL Paria Street Branch Karachi	Substantially Responsive
3	M/s.Gui Sawab & Company	Rs.18,51,890/-	2 nd Lowest	@0.125% Below	Pay Order and required documents are available. P.O # AAA 14058770 Rs.20,000/- & P.O # AAA 14058769 Rs.20,000/- Total Rs.40,000/-dt:08-11-2017 from ABL Paria Street Branch Karachi	Substantially Responsive

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 M/s.Shah Faisal & Brothers declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary

(Imdad Hussain Magsi)
S.E (District East-B)

(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Saifuddin)
Director (Design & Estimate)

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)


Description of work: RE-LOCATION OF OLD & CONTAMINATED 6" DIA A/C WATER PIPE LINE BY 200MM DIA 'P.E' PIPE FROM HASSAN SQUARE TO ESSA NAGRI AT SIR SHAH SULEMAN ROAD, GULSHAN-E-IQBAL TOWN

Date of Opening: 14-11-2017 ✓


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name		
		M/s.King Asif Rehman & Bros.	M/s.Shah Faisal & Brothers	M/s.Gul Sawab & Co.
1.	Registration with PEC (if applicable)	N/A	N/A	N/A
2.	NTN	No	Yes ✓	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	No	Yes ✓	Yes
	Qualification Criteria:			
5.	Minimum three years' experience of relevant field.	No	Yes ✓	Yes
6.	Turnover of at least last three years	No	Yes ✓	Yes
7.	Required Bid Security is attached.	No	Yes ✓	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	No	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A	N/A
10.	Qualified/ disqualified	Disqualified	Qualified	Qualified


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Imdad Hussain Magsi)
S.E (District East-B)
Member


(Saifuddin)
Director (Design & Estimate)
Convener

COMPARATIVE STATEMENT

Name of Work: RE-LOCATION OF OLD & CONTAMINATED 6" DIA A/C WATER PIPE LINE BY 200MM DIA 'P.E' PIPE
FROM HASSAN SQUARE TO ESSA NAGRI AT SIR SHAH SULEMAN ROAD, GULSHAN-E-IQBAL TOWN


Item No	Description of Work	Estimated Cost				M/s.King Asif Rehman & Brothers		M/s.Shah Faisal & Brothers		M/s.Gul Sawab & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removal road metalling	2270.00	Cft	605.00	%Cft	13,733.50	500	11,350.00	600	13,620.00	600	13,620.00
2	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m).	8000.00	Cft	4650.00	%0Cft	37,200.00	500	4,000.00	4,500	36,000.00	4,650	37,200.00
3	Excavation for pipe line in trenches and pits in Har Rock by hammering and chilseling i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m).	14700.00	Cft	24150.00	%0Cft	355,005.00	4,000	58,800.00	23,150	340,305.00	24,000	352,800.00
4	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	18.00	Days	1500.00	P/Day	27,000.00	50	900.00	1,800	32,400.00	1,800	32,400.00

**Name of Work: RE-LOCATION OF OLD & CONTAMINATED 6" DIA A/C WATER PIPE LINE BY 200MM DIA 'P.E' PIPE
FROM HASSAN SQUARE TO ESSA NAGRI AT SIR SHAH SULEMAN ROAD, GULSHAN-E-IQBAL TOWN**


Item No	Description of Work	Estimated Cost				M/s.King Asif Rehman & Brothers		M/s.Shah Faisal & Brothers		M/s.Gul Sawab & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	Rate	Amount	
5	P/F M.S split collar tee for PRCC pipe of different dia sizes having with as mentioned against each item to suit. The size of connection fabricated with 3/8" thick M.S plate excluding the cost of neck, it includes the cost of 3/4" M.S square bard on both ends, 4 Nos 3/4" thick M.S fnages with a total weight as mentioned against each item it includes the cost of nuts & bolt, rubber packing, labour and sealing materials and all the tools and plants. (2'-6" wide) Weight = 128.170 kg (12"x12")	1.00	No	22622.00	Each	22,622.00	5,000	5,000.00	22,500	22,500.00	22,500	22,500.00
6	P/F 0-9" long 3/8" thick M.S "Neck" to existing M.S pipe or to a split collar tee. It included the cost of fabrication and welding to the split collar tee. Weight = 15.75Kg 8" Dia	1.00	No	2804.00	Each	2,804.00	10,000	10,000.00	2,800	2,800.00	2,800	2,800.00
7	P/F "M.S" Flange made of M.S Plate having a thickness and total weight as mentioned against each item i/c the cost of making holes, facing, welding, nut bolts, rubber packing with lead fitter, cartage etc complete Weight = 4.044 Kg 8" Dia 1/2" Dia thickness plate	1.00	No	1973.00	Each	1,973.00	20,000	20,000.00	1,950	1,950.00	1,950	1,950.00
	Providing Laying & Fixing in trenches i/c fitting jointing and testing etc. complete in all respect the high density Polyethylene P.E pipes (HDPE-100) for W/S conforming ISO 4427 DIN-8074-8075 B.S 3580 & PSI 3051. 200 mm (PN-10)	1500.00	Rft	833.00	P/Rft	1,249,500	580	870,000.00	825	1,237,500	830	1,245,000
	110 mm (PN-10)	20.00	Rft	268.00	P/Rft	5,360.00	580	11,600.00	265	5,300.00	265	5,300.00
	High Density Polyethylene fitting (PE-100) (per each). Equivalent (PN-10) Elbow 45° 200 mm dia	2.00	Nos	5431.00	Each	10,862.00	5,000	10,000.00	5,400	10,800.00	6,000	12,000.00
	Stab End Piece 200 mm dia	1.00	No	6601.00	Each	6,601.00	5,000	5,000.00	6,000	6,000.00	6,000	6,000.00
	Stab End Piece 110 mm dia	1.00	No	2020.00	Each	2,020.00	5,000	5,000.00	2,000	2,000.00	2,000	2,000.00


**Name of Work: RE-LOCATION OF OLD & CONTAMINATED 6" DIA A/C WATER PIPE LINE BY 200MM DIA 'P.E' PIPE
FROM HASSAN SQUARE TO ESSA NAGRI AT SIR SHAH SULEMAN ROAD, GULSHAN-E-IQBAL TOWN**

Item No	Description of Work	Estimated Cost				M/s.King Asif Rehman & Brothers		M/s.Shah Faisal & Brothers		M/s.Gul Sawab & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	Rate	Amount	
8	C.I Sluice Valve heavy pattern (Test Pressure 21.0 Kg/sq.com or 300 lb/sq.inch) (Imported).08" Dia	1.00	No	17,940	Each	17,940.00	30,000	30,000.00	17,500	17,500.00	17,000	17,000.00
	04" Dia	1.00	No	5,460	Each	5,460.00	30,000	30,000.00	5,400	5,400.00	5,400	5,400.00
9	Fixing of sluice valve with 2 cast iron tail pieces one end flanged & other with socket i/c the cost of nut, bolts & rubber packing, labour etc complete.08" Dia	1.00	No	2,790	Each	2,790.00	10,000	10,000.00	2,500	2,500.00	2,500	2,500.00
	04" Dia	1.00	No	1,532	Each	1,532.00	10,000	10,000.00	1,500	1,500.00	1,500	1,500.00
10	Construction of C.C. Block Masonry chamber 6'-0x6'-0x6'-0 inside with 24"x24" C.I Cover and frame weight 65 Kg fix in RCC 1:2:4 slab 6" thick with steel 1/2" dia tor main bars @6" C/C bentup 1/4" dia 8" C.C distribution bars 6" thick B/M wall set 1:6 cm 6" thick C.C 1:4:8 in foundation 2" thick CC 1:2:4 flooring 1/2" thick 1-0 to al in side wall surfaced top & bottom slab outer side wall surface 1-0 deep upto roof slab i/c M.S footrest 5/8" dia bars at every 2-0 deep i/c curing de-watering excavation refilling & disposal of surplus of earth etc complete. (4'-4"x4')	1.00	No	28357.00	Each	28,357.00	20,000	20,000.00	25,000	25,000.00	28,500	28,500.00
11	Add or Deduct for extra depth p/inch beyond 4'-0" i/c cost of footrest etc.	12.00	Inch	187.20	P/inch	2,246.40	2.00	24.00	185	2,220.00	185	2,220.00
12	Refilling the excavated stuff in trench 6" thick layer i/c watering ramming to full compaction etc.	22174.00	Cft	2760.00	%0Cft	61,200.24	5,000	110,870.00	2,600	57,652.40	2,760	61,200.24
	TOTAL QUOTED / CORRECTED COST					1,854,206		1,222,544		1,822,947		1,851,890


(Muhammad Nawaz Khan)
D.A.O (Distt. East)
Member / Secretary


(Saif-ul-Haque)
Addl. Director Internal Audit
KMC - Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member


(Imdad Hussain Magsi)
S.E (District East-B)
Member


(Saifuddin)
Director (Design & Estimate)
Convener

KARACHI WATER AND SEWERAGE BOARD

ATTENDANCE SHEET OF CONTRACTORS

NAME OF WORK: RE-LOCATION OF OLD & CONTAMINATED 6"DIA A/C WATER PIPE LINE BY 200MMDIA 'P.E' PIPE FROM HASSAN SUQAE TO ESSA NAGRI AT SIR SHAH SULEMAN ROAD, GULSHAN-E-IQBAL TOWN".

4. Date of Opening & Time: 14-11-2017 At 2.30 PM.

5. Estimated Cost. Rs. 18,54,206/=

6. Serial No. SPPRA SERIAL NO. 34943.

S.No,	NAME OF FIRM	NAME OF REPRESENTATIVES & DESIGNATION	SIGNATURE
①	شاہد احمد	شاہد احمد	شاہد احمد
②	گل خواجہ ابراہیم	گل خواجہ ابراہیم	گل خواجہ ابراہیم
③	Kang Asif Rehman		Asif
	بکری		