



**KARACHI WATER & SEWERAGE BOARD**  
**OFFICE OF THE EXECUTIVE ENGINEER (SEW)**  
**(CLIFTON, DISTRICT SOUTH)**

NO. EE/SEW/C/D.S/KW&SB/2017/40

Dated: 16-05-017

To,  
The Director Capacity Building,  
Sindh Public Procurement Regulatory(SPPRA),  
Government of Sindh  
Block-8, Sindh Secretariat # 4-A,  
Karachi.

SUBJECT:- **SUBMISSION OF DOCUMENTS FOR THE WORK OF "REPLACEMENT & PROVIDING / LAYING 12" DIA, 8" DIA RCC SEWERAGE LINES AND CONSTRUCTION OF INTEMEDIATE MANHOLE IN GHIZRI COLONY AND DIFFERENT AREAS OF CLIFTON, DISTRICT SOUTH.**

Reference:- Serial No. 32695

Enclosed please find herewith, necessary documents for compliance of Rule-45, for early hoisting on Authority Website of SPPRA and issuance I.D

Enclosed:-

1. The Bid Evaluation Report.
2. Minutes of Bid Opening Meeting.
3. Bidders Eligibility / Qualification Report.
4. Comparative Statement.
5. Attendance of the Contractors.(Original)

EXECUTIVE ENGINEER (SEW)  
CLIFTON/DISTRICT SOUTH  
(KW&SB)

Copy for information:-

- 1.Superintending Engineer (South),KW&SB.
- 2.Office Copy.

RECEIVED DIARY  
NO. 578  
DATED: 16-05-17



# KARACHI WATER & SEWERAGE BOARD

## OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

### BID EVALUATION REPORT


1	Name of Procuring Agency :	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.32695 I.D No. _____
3	Tender Description/Name of Work/Item:	<b>REPLACEMENT &amp; PROVIDING / LAYING 12" DIA, 8" DIA RCC SEWERAGE LINES AND CONSTRUCTION OF INTERMEDIATE MANHOLE IN GHIZRI COLONY AND DIFFERENT AREAS OF CLIFTON, DISTRICT SOUTH</b>
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>Through SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>3 Nos</u>
7	Total Bid Received:	<u>3 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>01 No</u>
11	Financial Bid Opening Date:	<u>04-05-2017</u>

#### 12 BID EVALUATION REPORT


S #	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARIS ON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1.	M/s.N&S Builders	Rs.9,85,996/-	1 <sup>st</sup> Lowest	@0.339% Below	Pay order and other required documents are available. P.O#AAA 13321479 dt:28-04-2017 Rs.20,000/-from ABL Paria Street Branch Karachi	Substantially Responsive
2	M/s.Siddiqui Brothers & Co.	Rs.9,95,840/-	2 <sup>nd</sup> Lowest	@0.656% Above	Pay order and other required documents are available. P.O#AAA 13321478 dt:28-04-2017 Rs.20,500/-from ABL Paria Street Branch Karachi	Substantially Responsive
3	M/s.Serena Enterprises	Not Quoted	-	-	Pay order not attached required documents are available	Un Responsive

The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.N&S Builders** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

  
(Muhammad Nawaz Khan)  
D.A.O (Dist. South)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Aftab Alam Chandio)  
S.E (District South-B)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener


## COMPARATIVE STATEMENT

**Name of Work: REPLACEMENT & PROVIDING / LAYING 12" DIA, 8" DIA RCC SEWERAGE LINES AND CONSTRUCTION OF INTERMEDIATE MANHOLE IN GHIZRI COLONY AND DIFFERENT AREAS OF CLIFTON, DISTRICT SOUTH**

Item No	Description of Work	Estimated Cost				M/s.N&S Builders		M/s.Siddiqui Brothers & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Scarifying the existing road surface	1743.00	Sft	116.16	%Sft	2,024.67	116.00	2,021.88	120.00	2,091.60
2	Dismantling and removing road metalling etc.	1743.00	Cft	605.00	%Cft	10,545.15	605.00	10,545.15	610.00	10,632.30
3	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). Lift upto 0' - 5'ft	6972.00	Cft	4650.00	%0Cft	32,419.80	4645.00	32,384.94	4670.00	32,559.24
	Lift upto 5' to 8'	1743.00	Cft	5200.00	%0Cft	9,063.60	5200.00	9,063.60	5220.00	9,098.46
4	Providing & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 12" Dia Pipe	456.00	Rft	367.00	P/Rft	167,352.00	365.00	166,440.00	375.00	171,000.00
	08" Dia Pipe	150.00	Rft	206.00	P/Rft	30,900.00	200.00	30,000.00	210.00	31,500.00
5	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. (i)Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	29.00	Days	1500.00	P/Day	43,500.00	1490.00	43,210.00	1520.00	44,080.00
6	Providing manhole 4' feet (inside) without RCC manhole cover 5 feet clear depth cast in situ with 1:2:4 CC in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of engineer incharge i/c C.I Frame (15 Kg)	30.00	Nos	14529.29	Each	435,878.70	14525.00	435,750.00	14535.00	436,050.00

**Name of Work: REPLACEMENT & PROVIDING / LAYING 12" DIA, 8" DIA RCC SEWERAGE LINES AND CONSTRUCTION OF INTERMEDIATE MANHOLE IN GHIZRI COLONY AND DIFFERENT AREAS OF CLIFTON, DISTRICT SOUTH**


Item No	Description of Work	Estimated Cost				M/s.N&S Builders		M/s.Siddiqui Brothers & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
7	Add or deduct for extra / less depth then 5ft to 4ft dia manhole i/c footrest.	42.00	(+)Ft	2538.62	P/ft	106,622.04	2530.00	106,260.00	2545.00	106,890.00
8	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	18.00	Nos	180.00	Each	3,240.00	170.00	3,060.00	190.00	3,420.00
9	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	5459.68	Cft	2760.00	%Cft	15,068.72	2750.00	15,014.12	2770.00	15,123.31
10	Sand Haro or any other source sand of same modules of the fineness (Hill Sand)	2614.50	Cft	2425.00	%Cft	63,401.63	2420.00	63,270.90	2430.00	63,532.35
11	Carriage of 100 Cft / 5 Tons of all matrials like stonne aggregate, spawl, coal, lime, surkhi etc B.G Rail fastening points and crossing bridges, Girders, pipes sheet Rail, M.S Bars etc. or 1000 Nos bricks, 10"x 5"x3" or 1000 Nos: tiles, 12" x6"x2" or 150 Cft of timber or 100 Maunds of fuel wood by trucks or any other means owned by the Contractors. <u>Carriage for 05 Miles</u>	5869.82	Cft	714.29	%Cft	41,927.54	710.00	41,675.72	720.00	42,262.70
12	Manufacturing and supplying of 21" dia RCC Manhole covers cast in situ 1:2:4 concrete ratio 3" deep at centre, reinforced with 1/2" dia tor steel bars at 4" C/C welded to a 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting i/c cutting and transportation with in 10 miles. 21" dia cover.	30.00	Nos	913.63	Each	27,408.90	910.00	27,300.00	920.00	27,600.00
TOTAL QUOTED / CORRECTED COST						989,352		985,996		995,840

  
(Muhammad Nawaz Khan)  
D.A.O (Distt. South)  
Member / Secretary

  
(Saif-ul-Haque)  
Addl. Director Internal Audit  
KMC - Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (K.M.C)  
Member

  
(Aftab Alam Chandio)  
S.E (District South-B)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

• NIT Sr. No. SPPRA Serial No.32695

• Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT & PROVIDING / LAYING 12" DIA, 8" DIA RCC SEWERAGE LINES AND CONSTRUCTION OF INTERMEDIATE MANHOLE IN GHIZRI COLONY AND DIFFERENT AREAS OF CLIFTON, DISTRICT SOUTH

**MINUTES OF BID OPENING MEETING.**

A meeting of the procurement committee of this department was held on 04-05-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders.

**(Attendance sheet is enclosed).**

2. Three bidders submitted their bids till the deadline of submission.

- i. M/s.N&S Builders
- ii. M/s.Siddiqui Brothers & Co.
- iii. M/s.Serena Enterprises


3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
1.	M/s.N&S Builders	Rs.9,85,996/-	Rs.20,000/-	P.O # AAA 13321479 dt:28-04-2017 from ABL Paria Street Branch Karachi
2.	M/s.Siddiqui Brothers & Co.	Rs.9,95,840/-	Rs.20,500/-	P.O # AAA 13321478 dt:28-04-2017 from ABL Paria Street Branch Karachi
3.	M/s.Serena Enterprises	Not Quoted	-	Pay order not attached


4. The bids do not contain any cutting and over-writing.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the vote of thanks to and from the chair.

  
(Muhammad Nawaz Khan)  
D.A.O (Dist. South)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit - KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Aftab Alam Chandio)  
S.E (District South-B)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage–One Envelope)


Description of work: REPLACEMENT & PROVIDING / LAYING 12" DIA, 8" DIA RCC SEWERAGE LINES AND CONSTRUCTION OF INTERMEDIATE MANHOLE IN GHIZRI COLONY AND DIFFERENT AREAS OF CLIFTON, DISTRICT SOUTH

Date of Opening: 04-05-2017


**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name		
		M/s.N&S Builders	M/s.Siddiqui Brothers & Co.	M/s.Serena Enterprises
1.	Registration with PEC (if applicable)	N/A	N/A	N/A
2.	NTN	Yes	Yes	Yes
3.	Sales Tax Registration	N/A	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes	Yes
	<b>Qualification Criteria:</b>			
5.	Minimum three years' experience of relevant field.	Yes	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes	No
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified	Disqualified

  
(Muhammad Nawaz Khan)  
D.A.O (Dist. South)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Aftab Alam Chandio)  
S.E (District South-B)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

