



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.35064 I.D No. _____
3	Tender Description/Name of Work/Item:	REPLACEMENT / PROVIDING & LAYING 110 MM & 160 MM WATER SUPPLY LINE AT STREET NO.21, 20 SECTOR NO.J-1, JUNEJO TOWN, MANZOOR COLONY, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	3 Nos
7	Total Bid Received:	3 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	01 No
11	Financial Bid Opening Date:	21-11-2017

12 BID EVALUATION REPORT

S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Ali Mohammad & Sons	Rs.9,88,295/-	1 st Lowest	@0.024% Below	Pay Order and required documents are available. P.O # 17319540 revalidate on 17-11-2017 Rs.20,000/- from HBL Paposh Nagar Branch Karachi	Substantially Responsive
2	M/s.A. Dawood Shah & Co.	Rs.9,90,021/-	2 nd Lowest	@0.150% Above	Pay Order and required documents are available. P.O # 17177650 Revalidate on 30-10-2017 Rs.18,200/- from HBL P.E.C.H.S Co. Branch Karachi & P.O # 17908595 dt:01-11-2017 Rs.2,000/- from HBL Taimuria Market Branch Karachi Total Rs.20,200/-	Substantially Responsive
3	M/s.Nawab & Co.	Rs.9,92,311/-	-	@0.382% Above	Pay Order not attached. required documents are available.	Un Responsive

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 M/s.Ali Mohammad & Sons declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary

(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Roshin Din Memon)
S.E (District East-A)

(Saifuddin)
Director (Design & Estimate)

COMPARATIVE STATEMENT

Name of Work: REPLACEMENT / PROVIDING & LAYING 110 MM & 160 MM WATER SUPPLY LINE AT STREET NO.21, 20 SECTOR NO.-J, JUNEJO TOWN, MANZOOR COLONY, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN

Item No	Description of Work	Estimated Cost				M/s. Ali Mohammad & Son		M/s. A. Dawood Shah & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Scarifying the Existing road Surface.	3400.00 ^o	Sft	116.16	%Sft	3,949.44	150.00	5,100.00	150.00	5,100.00
2	Dismantling and removal road metalling	5100.00 ^o	Cft	605.00	%Cft	30,855.00	600.00	30,600.00	600.00	30,600.00
3	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge. Providing fence, lights, flags and temporary crossing for non-vehicular traffic wherever required lift upto 5" ft (1.52m) and lead upto one chain (30.5m). 0' to 5'	10200.00	Cft	4650.00	%Cft	47,430.00	4700.00	47,940.00	4800.00	48,000.00
4	Excavation for pipe line in trenches and pits in Wet Soils clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge. Providing fence, lights, flags and temporary crossing for non-vehicular traffic wherever required lift upto 5'-0" ft (1.52m) and lead upto one chain (30.5m).	6800.00	Cft	5400.00	%Cft	36,720.00	5400.00	36,720.00	5000.00	34,000.00
5	Add: for additional lift 5' to 8'	7800.00	Cft	5950.00	%Cft	46,410.00	6000.00	46,800.00	6000.00	46,800.00
6	Providing Laying & Fixing of Polyethylene pipe in trench i/c fitting jointing and testing etc. complete in all respect the high density Polyethylene P-E pipes (HDPE-100) for W/S conforming ISO 4427/DIN-8074/8075 B.S 3580 & PSI 3051 (PN-10). 110 MM	1200.00	Rft	268.00	P/Rft	321,600.00	270.00	324,000.00	280.00	336,000.00
	160 MM	400.00	Rft	530.00	P/Rft	212,000.00	500.00	200,000.00	400.00	160,000.00
7	Full hire charges of pumping set p/day inclusive wages of driver & assistant fuel or electric energy plate forms required for placing pumps etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches i/c cost of erection and dismantling after completion of the job. i) Hire charges of pumping set of upto 10 H.P pumping out water from 10ft deep trench).	16.00	Days	1500.00	P/Day	24,000.00	1500.00	24,000.00	1600.00	25,600.00







Name of Work: REPLACEMENT / PROVIDING & LAYING 110 MM & 160 MM WATER SUPPLY LINE AT STREET NO.21, 20 SECTOR NO.1-
JUNEJO TOWN, MANZUOR COLONY, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN

Item No	Description of Work	Estimated Cost			M/s. Ali Mohammad & Son		M/s. A. Dawood Shah & Co.			
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
8	P/F M.S split collar tee for PRC pipe of different dia sizes having with as mentioned against each item to suit. The size of connection fabricated with 3/8" thick M.S plate excluding the cost of neck, it includes the cost of 3/4" M.S square hard on both ends, 4 Nos 3/4" thick M.S flanges with a total weight as mentioned against each item it includes the cost of nuts & bolt, rubber packing, labour and scaling materials and all the tools and plants. Net Weight 128.17 Kgs (Width 2-6")	4.00	Nos	22622.00	Each	90,488.00	23000.00	92,000.00	22000.00	88,000.00
9	Providing / Fixing 0-9" long 3/8" thick M.S "Neck" to existing M.S pipe or to a split collar tee. It included the cost of fabrication and welding to the split collar tee Net Wt. 6.666 Kg 4" Dia Net Wt. 10.909 Kg 6" Dia	3.00	Nos	1229.00	Each	3,687.00	1500.00	4,500.00	1000.00	3,000.00
		1.00	No	1984.00	Each	1,984.00	2000.00	2,000.00	2000.00	2,000.00
10	Providing High Density polyethylene fittings (PE-100) DIN-10 including transportation charges, external dia Elbow 90° PN-10 110 MM Elbow 90° PN-10 160 MM	4.00	Nos	2069.00	Each	8,276.00	3000.00	12,000.00	3000.00	12,000.00
		1.00	No	4349.00	Each	4,349.00	4000.00	4,000.00	4000.00	4,000.00
11	Providing C.I Sluice Valve heavy pattern (Test Pressure 21.0 Kgs/sq.com or 300 lb/sq.inch) (Imported), 4" Dia 6" Dia	3.00	Nos	5460.00	Each	16,380.00	6000.00	18,000.00	8000.00	24,000.00
		1.00	No	9360.00	Each	9,360.00	9000.00	9,000.00	10000.00	10,000.00
12	Fixing of sluice valve with 2 cast iron tail pieces one end flanged & other with socket i/c the cost of nut, bolts & rubber packing, labour etc complete. 4" Dia 6" Dia	3.00	Nos	1532.00	Each	4,596.00	1600.00	4,800.00	2000.00	6,000.00
		1.00	No	1886.00	Each	1,886.00	2000.00	2,000.00	3000.00	3,000.00
13	Construction of Block Masonry chamber with 24"x24" C.I Cover and frame weight 65 Kg fix in RCC 1:2:4 slab 6" thick with steel 1/2" dia tor main bars @6" C/C bentup 1/4" dia 8" C.C distribution bars B/M wall set 1:6 cm 6" thick C.C 1:4:8 in foundation 2" thick CC 1:2:4 flooring 1/2" thick 1-0 to al in side wall surfaced top & bottom slab outer side wall surface 1-0 deep upto roof slab i/c M.S footrest 5/8" dia bars at every 2-0 deep i/c curing de-watering excavation refilling & disposal of surplus of earth etc complete. Chamber size 4'x4'x4'	2.00	Nos	28357.00	Each	56,714.00	28000.00	56,000.00	30000.00	60,000.00

Handwritten signature/initials

Handwritten signature/initials

Name of Work: REPLACEMENT / PROVIDING & LAYING 110 MM & 160 MM WATER SUPPLY LINE AT STREET NO.21, 20 SECTOR NO.J-11
 JUNEJO TOWN, MANZOOR COLONY, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN

Item No	Description of Work	Estimated Cost				M/s. Ali Mohammad & Son		M/s. A. Dawood Shah & Co.		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
14	Refilling the excavated stuff in trench 6" thick layer i/c watering ramming to full compaction etc.	24584.05	Cft	2760.00	%0Cft	67,851.98	2800.00	68,835.34	3700.00	90.9
TOTAL QUOTED / CORRECTED COST						988,536		988,295		99

(Muhammad Nawaz Khan)
 D.A.O (Distt. East)
 Member / Secretary

(Saif-ur-Raquee)
 Addl. Director Internal
 Audit KMC - Member

(Magsobd Ahmed Shaikh)
 Superintending Engineer (K.M.C)
 Member

(Roshin Din Memon)
 S.E (Distt. East-A)
 Member

(Saifuddin)
 Director (Design & Estin)
 Convener

NIT No. SPPRA Serial No.35064

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)


Description of work: REPLACEMENT / PROVIDING & LAYING 110 MM & 160 MM WATER SUPPLY LINE AT STREET NO.21, 20 SECTOR NO.J-1, JUNEJO TOWN, MANZOOR COLONY, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN


Date of Opening: 21-11-2017


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:

S. No.	Eligibility / Qualification Criteria	Bidders' Name		
		M/s.Ali Mohammad & Sons	M/s.A.Dawood Shah & Co	M/s.Nawab & Co.
1.	Registration with PEC (if applicable)	N/A	N/A	N/A
2.	NTN	Yes	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes	Yes
	Qualification Criteria:			
5.	Minimum three years' experience of relevant field.	Yes	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified	Disqualified


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Saifuddin)
Director (Design & Estimate)
Convener

NIT No. SPPRA Serial No.35064

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT / PROVIDING & LAYING 110 MM & 160 MM WATER SUPPLY LINE AT STREET NO.21, 20 SECTOR NO.J-1, JUNEJO TOWN, MANZOOR COLONY, FOR IMPROVEMENT OF WATER SUPPLY IN JAMSHED TOWN

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 21-11-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. **(Attendance sheet is enclosed).**

2. Three bidders submitted their bids till the deadline of submission.

- i. M/s. Ali Mohammad & Sons
- ii. M/s. A.Dawood Shah & Co.
- iii. M/s.Nawab & Co.


3. The bids were opened at 2:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.

S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Ali Mohammad & Sons	Rs.9,88,295/-	Rs.20,000/-	P.O # 17319540 revalidate on 17-11-2017 from HBL Paposh Nagar Branch Karachi
02	M/s.A. Dawood Shah & Co.	Rs.9,90,021/-	Rs.20,200/-	P.O # 17177650 Revalidate on 30-10-2017 Rs.18,200/- from HBL P.E.C.H.S Co. Branch Karachi & P.O # 17908595 dt:01-11-2017 Rs.2,000/- from HBL Taimuria Market Branch Karachi
03	M/s.Nawab & Co.	Rs.9,92,311/-	-	Pay Order not attached


4. The bids do not contain any cutting or over-writing.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.


(Muhammad Nawaz Khan)
D.A.O (District East)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Roshin Din Memon)
S.E (District East-A)
Member


(Saifuddin)
Director (Design & Estimate)
Convener

