



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE CHIEF ENGINEER (IP&D)

BID EVALUATION REPORT


1	Name of Procuring Agency	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No	Serial No.21602 I.D No. /2014
3	Tender Description/Name of Work/Item	REHABILITATION OF DEFECTIVE / OUTLET 12" DIA & 8" DIA RCC RUBBER RING SEWER AT N.NO.G-23 TO G-33 SECTOR-03 OF UC NO.04 & P/M SUPPLYING & FIXING OF 21" DIA RCC COVER AND RING SLAB FOR SITE TOWN (SEWERAGE)
4	Method of Procurement	Single Stage (One Envelop)
5	Tender Published	Through Website
6	Total Bid Documents Sold	02 Nos
7	Total Bid Received	02 Nos
8	Technical Bid Opening Date (if applicable)	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) rejected	Nil
11	Financial Bid Opening Date	5/11/2014

12 Bid Evaluation Report


S #	NAME OF FIRM OR BIDDER	COST OFFERED BY THE BIDDERS	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE/ REJECTION	REMARKS
1	M/s. S.O.H Const Co	Rs. 982,263/-	1st Lowest	@ 0.0099% Below	Substantially Responsive	P.O # 50607820 Dt:05-11-2014 Rs. 20,000/- Summit Bank Gulshan-e-Iqbal Br.
2	M/s. Safeer Enterprises	Rs. 982,797/-	2nd Lowest	@ 0.0445% Above	Substantially Responsive	P.O # 11537046 Dt:10-10-2014 Rs. 20,000/- HBL Rizvia Society Nazimabad Br.


The all concerned bidder are being informed accordingly.


The E.E Concerned for compliance of rule 45 of SPPRA 2010 M/s. S.O.H Const Co. declared as the lowest responsive bidder by the Committee and recommended for Sanction from Competent Authority.


(Muhammad Khalid Khan)
Accounts Officer (West)
Member/Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit - KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Owais Malik)
Chief Engineer (West)
Member


(Abdul Rahim Khattai)
Chief Engineer (IPD),
(Convener)

Method of Procurement: Single Stage Single Envelope.

Name of Work: REHABILITATION OF DEFECTIVE / OUTLET 12" DIA & 8" DIA RCC RUBBER RING SEWER AT N.NO.G-23 TO G-33 SECTOR-03 OF UC NO.04 & P/M SUPPLYING & FIXING OF 21" DIA RCC COVER AND RING SLAB FOR SITE TOWN (SEWERAGE).

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 05-11-2014 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.

- i. M/s. S.O.H Const Co
- ii. M/s. Safer Enterprises


3. The bids were opened at 02:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s. S.O.H Const Co	Rs. 982,263/-	Rs.20,000/-	P.O # 50607820 Dt:05-11-2014 Summit Bank Gulshan-e-Iqbal Br.
02	M/s. Safer Enterprises	Rs. 982,797/-	Rs.20,000/-	P.O # 11537046 Dt:10-10-2014 HBL Rizvia Society Nazimabad Br.

4. The bids do not contain any over-writing or cutting.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the vote of thanks to and from the chair.


(Muhammad Khalid Khan)
Accounts Officer (West)
Member / Secretary


(Owais Malik)
Chief Engineer (West)
Member


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Abdul Raheem Khattai)
Chief Engineer (IPD)
Convener

NIT NO. 21602

Method and procedure of procurement: Open Competitive Bidding(National/ International Competitive Bidding) (Single Stage – One Envelope)

Description of work: REHABILITATION OF DEFECTIVE / OUTLET 12" DIA & 8" DIA RCC RUBBER RING SEWER AT N.NO.G-23 TO G-33 SECTOR-03 OF UC NO.04 & P/M SUPPLYING & FIXING OF 21" DIA RCC COVER AND RING SLAB FOR SITE TOWN (SEWERAGE)


Name of Bidder: M/s. S.O.H Const Co.

BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:

S. No.	Eligibility / Qualification Criteria	Bidders' name M/s. S.O.H Const Co.
1.	Registration with PEC (if applicable)	N/A
2.	NTN	Yes
3.	Sales Tax Registration	N/A
4.	Professional Tax	Yes
5.	Registration with Sindh Revenue Board (SRB)	N/A
	Qualification Criteria:	
6.	Minimum three years' experience of relevant field.	Yes
7.	Turnover of at least last three years.	Yes
8.	Required Bid Security is attached.	Yes
9.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes
10.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A
11.	Qualified/ disqualified	Qualified

Note: The procuring agency may modify the criteria as per their requirements.


(Muhammad Khalid Khan)
Accounts Officer (West)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Ovais Malik)
Chief Engineer (West)
Member


(Abdul Raheem Khatti)
Chief Engineer (IPD)
Convener

COMPARATIVE STATEMENT

NAME OF WORK: REHABILITATION OF DEFECTIVE / OUTLET 12" DIA & 8" DIA RCC RUBBER RING SEWER AT N.NO.G-23 TO G-33
SECTOR-03 OF UC NO.04 & P/M SUPPLYING & FIXING OF 21" DIA RCC COVER AND RING SLAB FOR SITE TOWN (SEWERAGE)

S.No	Description of Work	Engineer's Estimate			M/s. S.O.H Const Co		M/s. Safer Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
1	Dismantling and removing road matting. Execution for pipe line in trenches and pits in all kinds of soils of murum i/c trimming and dressing sides to true alignment and shapes leveling of bed of trenches to correct level and grade cutting joint holes and disposal of surplus earth with in a one chain as directed by engineering Incharge providing fence guard. lights flags and temporary crossing for non vehicular traffic where ever required lift up to 5' (1.52m) and lead up to one chain (30.5m)	2530 Cft	605.00	% Cft	15,306.50	605.00	15,306.50	605.00	15,306.50
2	Providing Laying RCC Pipe with (Rubber Ring Joint & Fitting) in trench i/c cutting fitting and jointing with rubber ring i/c testing with water to specific pressure.	11860 Cft	4,650.00	% 0 Cft	55,149.00	4,650.00	55,149.00	4,650.00	55,149.00
3	Providing Manhole 4ft inside with C.I frame (15Kg) & 5ft clear depth 1:2:4 cost in situ in 9" thick wall 1:4:8 C.C in 6 ft dia & 6" inch thick in foundation 1:2:4 C.C in benching 1/2" thick C.P 1:3 motor or inside wall & surface of channel and benching making required nos of main and branches channels 3/4" dia bars M.S foot at 12" dia C/C i/c cost of excavation in all kind of soil back filling and disposal of excavated stuff etc. complete as per design & instruction of the Engineer Incharge.	580 Rft 316 Rft	367.00 206.00	P/Rft P/Rft	212,860.00 65,096.00	367.00 206.00	212,860.00 65,096.00	367.00 206.00	212,860.00 65,096.00
4		26 Nos	14,529.29	Each	377,761.54	14,529.00	377,754.00	14,530.00	377,780.00

[Signature]

[Signature]

[Signature]

[Signature]

NAME OF WORK: REHABILITATION OF DEFECTIVE / OUTLET 12" DIA & 8" DIA RCC RUBBER RING SEWER AT N.NO.G-23 TO G-33
 SECTOR-03 OF UC NO.04 & P/M SUPPLYING & FIXING OF 21" DIA RCC COVER AND RING SLAB FOR SITE TOWN (SEWERAGE)

S.No	Description of Work	Engineer's Estimate				M/s. S.O.H Const Co		M/s. Safear Enterprises	
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
5	Add/deduct per ft depth. Making Connection with the existing Manholes i/c the cost of cutting holes in wall making them good in cement concrete 1:2:4 and making the required channel etc complete.	4 Rft	2,538.62	P/Rft	10,154.48	2,538.00	10,152.00	2,540.00	10,160.00
6	Refilling the excavated stuff in trenches 6" thick layer i/c watering removing to full compaction etc.	20 Nos	180.00	Each	3,600.00	180.00	3,600.00	180.00	3,600.00
7	Manufacturing and supplying of 21" dia RCC manhole cover cost in 1:2:4 concrete ratio 3 inch deep at centre rain forced with 1/2" dia for steel bars at 4" C/C welded to 3/10" thick 2" wide MS plate two hook of 3/8" dia tor bar including compacting i/c during and transportation within 10 miles.	10977 Cft	2,760.00	% 0 Cft	30,296.52	2,760.00	30,296.52	2,760.00	30,296.52
8	Manufacturing and supplying of RCC Ring Slab of 21" dia inside 36" dia outside 7.5 width and 6" thick i/c 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks coasted in 1:1 1/2":3 concrete with embedded 15 Kg C.I frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to Town Office (A minimum of 25 slabs per trip will be transported).	70 Nos	913.63	Each	63,954.10	913.00	63,910.00	915.00	64,050.00
9		60 Nos	1,906.60	Each	114,396.00	1,906.00	114,360.00	1,910.00	114,600.00

[Handwritten signature]

[Handwritten signature]


[Handwritten signature]

[Handwritten signature]


[Handwritten signature]


NAME OF WORK: REHABILITATION OF DEFECTIVE / OUTLET 12" DIA & 8" DIA RCC RUBBER RING SEWER AT N.NO.G-23 TO G-33
 SECTOR-03 OF UC NO.04 & P/M SUPPLYING & FIXING OF 21" DIA RCC COVER AND RING SLAB FOR SITE TOWN (SEWERAGE)

S.No	Description of Work	Engineer's Estimate			M/s. S.O.H Const Co		M/s. Safer Enterprises		
		Quantity	Rate	Unit	Amount	Rate	Amount	Rate	Amount
10	Shifting to the site & fixing of 36" dia Ring Slab in perfect position on damaged manhole i/c cutting of manhole in damaged portion in proper shape and laying of cement mortar of 2" thickness & disposal of debris.	60 Nos	563.09	Each	33,785.40	563.00	33,780.00	565.00	33,900.00
	Total Quoted / Corrected Cost				982,359.54		982,263.02		982,797.02
	Say				982,360		982,263		982,797


 (Muhammad Khalid Khan)
 Accounts Officer (West)
 Member/Secretary


 (Owais Malki)
 Chief Engineer (West)
 Member


 (Saif-ul-Haque)
 Additional Director Internal
 Audit - KMC Member


 (Abdul Rahim Khatt)
 Chief Engineer (IPD), (Convener)


 (Magsood Ahmed Shaikh)
 Superintending Engineer (KMC)
 Member



Name of Work :

REHABILITAION OF DEFECTIVE / OUTLET 12" DIA & 8" DIA RCC
RUBBER RING SEWER AT N.NO.G-23 TO G-33 SECTOR-03 OF UC
NO. 04 & P/M SUPPLYING & FIXING OF 21" DIA RCC COVER AND
RING SLAB FOR SITE TOWN (SEWERAGE)

Date of Opening & Time : 05-11-2014

2:30 PM

Estimated Cost : 9,82,360/-

S.NO	NAME OF FIRM	NAME OF PERSON & DESIGNATION	SIGNATURE
1	M/s. S.O.M Const Co	M. Nadeem Uddin	
2	M/s. Sajwal Ent	S. Sajwal Ali	
3	M/s.		
4			
5			
6			
7			
8			
9			
10			