

NIT No. SPPRA Serial No.33262

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)

Description of work: REPLACEMENT OF CHOKED ERODED SUNK DOWN PORTION OF 12" DIA & 15" DIA RCC SEWERAGE LINE AT HAMZA CHOWK BABAR MASJID SHIREEN JINNAH COLONY KEAMARI TOWN

Date of Opening: 30-05-2017

BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT

Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.Hassam & Brothers	M/s.Riaz & Co
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	Qualification Criteria:		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	No
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Disqualified



(Muhammad Khalid Khan)
Accounts Officer (Dist. West)
Member / Secretary




(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member



(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member



(Owais Malik)
S.E (District West-A)
Member



(Saleem Ahmed)
30/05/17
Director (Design & Estimate)
Convener

● NIT' Sr. No. SPPRA Serial No.33262

Method of Procurement: Single Stage Single Envelope.

Name of Work: **REPLACEMENT OF CHOKED ERODED SUNK DOWN PORTION OF 12" DIA & 15" DIA RCC SEWERAGE LINE AT HAMZA CHOWK BABAR MASJID SHIREEN JINNAH COLONY KEAMARI TOWN**

MINUTES OF BID OPENING MEETING.

A meeting of the procurement committee of this department was held on 30-05-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders.

(Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
 - i. M/s. Hassam & Brothers
 - ii. M/s. Riaz & Co.
3. The bids were opened at 11:30 A.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.

S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Hassam & Brothers	Rs.9,94,724/-	Rs.20,000/-	P.O # 18031049 dt:11-04-2017 from HBL Sindh Secretariat Branch Karachi
02	M/s.Riaz & Co.	Rs.9,99,026/-	-	Pay Order not attached

4. The one bid contain over-writting.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).

The meeting ended with the vote of thanks to and from the chair.



(Muhammad Khalid Khan)
Accounts Officer (Dist. West)
Member / Secretary




(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member



(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member



(Owais Malik)
S.E (District West-A)
Member



30/05/17

(Saleem Ahmed)
Director (Design & Estimate)
Convener



KARACHI WATER & SEWERAGE BOARD

OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.33262 I.D No. _____
3	Tender Description/Name of Work/Item:	REPLACEMENT OF CHOKED ERODED SUNK DOWN PORTION OF 12" DIA & 15" DIA RCC SEWERAGE LINE AT HAMZA CHOWK BABAR MASJID SHIREEN JINNAH COLONY KEAMARI TOWN
4	Method of Procurement:	Single Stage (One Envelop)
5	Tender Published:	Through SPPRA Web Site
6	Total Bid Documents Sold:	2 Nos
7	Total Bid Received:	2 Nos
8	Technical Bid Opening Date (if applicable):	N/A
9	No. of Bid Technically Qualified (if applicable)	N/A
10	Bid (s) Rejected:	01 No
11	Financial Bid Opening Date:	30-05-2017

12. BID EVALUATION REPORT

S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Hassam & Brothers	Rs.9,94,726/-	1 st Lowest	@0.008% Below	Pay Order and required documents are available. P.O # 18031049 dt:11-04-2017 Rs.20,000/-from HBL Sindh Secretariat Branch Karachi	Substantially Responsive
2	M/s.Riaz & Co.	Rs.9,99,026/-	-	@0.424% Above	Pay Order not attached, required documents are available.	Un Responsive

The all concerned bidders are being informed accordingly.

The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Hassam & Brothers** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

(Muhammad Khalid Khan)
Accounts Officer (Dist. West)
Member / Secretary

(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member

(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member

(Owais Malik)
S.E (District West-A)
Member

(Saleem Ahmed)
21/05/17
Director (Design & Estimate)
Convener

COMPARATIVE STATEMENT


Name of Work: REPLACEMENT OF CHOKED ERODED SUNK DOWN PORTION OF 12" DIA & 15" DIA RCC SEWERAGE LINE AT HAMZA CHOWK BABAR MASJID SHIREEN JINNAH COLONY KEAMARI TOWN

Item No	Description of Work	Estimated Cost				M/s.Hassam & Brothers		
		Quantity	Rate	Per	Amount	Rate	Amount	
1	Dismantling and removing road metalling	3225.00	Cft	605.00	%Cft	19,511.25	605.00	19,511.25
2	Excavation for pipe line in trenches and pits in Wet Silt clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). Lift 0' - 5'ft	16125.00	Cft	5400.00	%0Cft	87,075.00	5400.00	87,075.00
3	Add for additional lift every 3' (5' - 8')	7875.00	Cft	5950.00	%0Cft	46,856.25	5950.00	46,856.25
4	Add for additional lift every 3' (8' - 11')	6075.00	Cft	6500.00	%0Cft	39,487.50	6500.00	39,487.50
5	Add for additional lift every 3' (11' - 14')	4275.00	Cft	7050.00	%0Cft	30,138.75	7050.00	30,138.75
6	Providing, & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 12" Dia	450.00	Rft	367.00	P/Rft	165,150.00	367.00	165,150.00
	15" Dia	150.00	Rft	436.00	P/Rft	65,400.00	436.00	65,400.00
7	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 15 ft deep trench	12.00	Days	1500.00	P/Day	18,000.00	1500.00	18,000.00
8	Providing manhole 4' feet inside with C.I Frame 15 Kg and 5 feet clear depth cast in situ with 1:2:4 CC in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of Engineer Incharge.	11.00	Nos	13479.29	Each	148,272.19	13479.00	148,269.00
9	Extra depth beyond 5 ft for depth lesser than 5 ft deducted at same rate i/c C.I footrest of depth.	96.00	(+)Ft	2538.62	P/ft	243,707.52	2538.00	243,648.00




Name of Work: REPLACEMENT OF CHOKED ERODED SUNK DOWN PORTION OF 12" DIA & 15" DIA RCC SEWERAGE LINE AT HAMZA CHOWK BABAR MASJID SHIREEN JINNAH COLONY KEAMARI TOWN

Item No	Description of Work	Estimated Cost				M/s.Hassam & Brothers	
		Quantity	Rate	Per	Amount	Rate	Amount
10	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	8.00	Nos	180.00	Each	1,440.00	180.00 1,440.00
11	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	33532.00	Cft	2760.00	%0Cft	92,548.32	2760.00 92,548.32
12	Manufacturing and supplying of 21" dia RCC Manhole covers cast in situ 1:2:4 concrete ratio 3" deep at centre, reinforced with 1/2" dia tor steel bars at 4" C/C welded to a 3/16" thick 2" wide M.S plate two hook of 3/8" dia tor bar including compacting i/c cutting and transportation with in 10 miles. 21" dia cover.	11.00	Nos	913.63	Each	10,049.93	913.00 10,043.00
13	Manufacturing and supplying of RCC Ring Slab of 21" dia (inside) and 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted in 1:1 ^{1/2} :3 concrete with embedded 15 Kg C.I Frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office. (A minimum of 25 slabs per trip will be transported.	11.00	Nos	1906.60	Each	20,972.60	1906.00 20,966.00
14	Shifting to the site and Fixing of 36" dia Ring Slab in perfect position on damaged manholes i/c cutting of the position of damaged manhole in layer of C.M in 2" thickness and disposal of debris.	11.00	Nos	563.09	Each	6,193.99	563.00 6,193.00
TOTAL QUOTED / CORRECTED COST						994,803	994,726


(Muhammad Khalid Khan)
Accounts Officer (Dist. West)
Member / Secretary


(Saif-ul-Haque)
Addl. Director Internal Audit
KMC - Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (K.M.C)
Member


(Owaid Malik)
S.E (District West)
Member




(Saleem Ahmed)
31/05/17
Director (Design & Estimate)
Convener

ATTENDANCE OF PARTICIPATE CONTRACTOR

Name of Work: - REPLACEMENT OF CHOCKED ERODED SUNK DOWN PORTION OF 12" DIA & 15" DIA RCC SEWERAGE LINE AT HAMZA CHOWK BABAR MASJID SHIREEN JINNAH COLONY KEAMARI TOWN

Date of Opening & Time :

Estimated Cost :

S.NO	NAME OF FIRM	NAME OF PERSON & DESIGNATION	SIGNATURE
1	M/s. Hassam and Brothers	M. Arnik	
2	M/s. Riaz 4 C.	Riaz Ahmed.	
3	M/s.		
4			
5			
6			
7			
8			
9			
10			

29
15
/

ut