

## FIRMS / CONTRACTORS

NAME OF WORK: REMOVAL OF CONTAMINATION THROUGH RODDING / CLEANING REPLACEMENT OF DAMAGED / CHOKED PORTION A.C / C.I WATER LINE FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AT UC-37, 38 IN LIAQUATABAD ZONE (SEW).

Date of Opening: 06-06-2017

Time of Receiving: 11:00 AM

Time of Opening: 11:30 AM

Serial No. 33408

S.NO	NAME OF CONTRACTOR	NAME OF FIRMS	SIGNATURE
01	Jasir & Co	M/S Shah Faizal & Bros	Jasir & Co
02	Rajp	M/S L. S. ENT P	Rajp



**KARACHI WATER & SEWERAGE BOARD**  
**OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)**

**BID EVALUATION REPORT**


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.33408 I.D No. _____
3	Tender Description/Name of Work/Item:	<b>REMOVAL OF CONTAMINATION THROUGH RODDING / CLEANING REPLACEMENT OF DAMAGE / CHOKED PORTION A.C / C.I WATER LINE FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AT UC-37, 38 IN LIAQUATABAD ZONE</b>
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>Through SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>2 Nos</u>
7	Total Bid Received:	<u>2 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>Nil</u>
11	Financial Bid Opening Date:	06-06-2017

**12 BID EVALUATION REPORT**

S #	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.L.S Enterprises	Rs.9,93,454/-	1 <sup>st</sup> Lowest	@0.091% Below	Pay Order and required documents are available. P.O # 13382618 dt:06-06-2017 Rs.20,000/-from UBL Clifton Branch Karachi	Substantially Responsive
2	M/s.Shah Faisal & Bros	Rs.9,95,366/-	2 <sup>nd</sup> Lowest	@0.102% Above	Pay Order and required documents are available. P.O # 03774848 dt:03-06-2017 Rs.20,000/-from Bank Al Habib Ltd Clifton Branch Karachi	Substantially Responsive


The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.L.S Enterprises** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

  
(Arshad Ali)  
D.A.O (District Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Tauqeer Ahmed Khan)  
S.E (District Central-B)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

Method of Procurement: Single Stage Single Envelope.

Name of Work: REMOVAL OF CONTAMINATION THROUGH RODDING / CLEANING REPLACEMENT OF DAMAGE / CHOKED PORTION A.C / C.I WATER LINE FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AT UC-37, 38 IN LIAQUATABAD ZONE

MINUTES OF BID OPENING MEETING.


A meeting of the procurement committee of this department was held on 06-06-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
  - i. M/s. L.S Enterprises
  - ii. M/s. Shah Faisal & Brothers
3. The bids were opened at 12:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.L.S Enterprises	Rs.9,93,453/-	Rs.20,000/-	P.O # 13382618 dt:06-06-2017 from UBL Clifton Branch Karachi
02	M/s.Shah Faisal & Brothers	Rs.9,95,365/-	Rs.20,000/-	P.O # 03774848 dt:03-06-2017 from Bank Al Habib Ltd Clifton Branch Karachi


4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.

  
(Arshad Ali)  
D.A.O (District Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Tauqeer Ahmed Khan)  
S.E (District Central-B)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

**Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)**

Description of work: REMOVAL OF CONTAMINATION THROUGH RODDING / CLEANING REPLACEMENT OF DAMAGE / CHOKED PORTION A.C / C.I WATER LINE FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AT UC-37, 38 IN LIAQUATABAD ZONE

Date of Opening: 06-06-2017


**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.L.S Enterprises	M/s.Shah Faisal & Brothers
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
<b>Qualification Criteria:</b>			
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified

  
(Arshad Ali) 06/06/17  
D.A.O (District Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Tauqeer Ahmed Khan)  
S.E (District Central-B)  
Member

  
(Saleem Ahmed) 06/06/17  
Director (Design & Estimate)  
Convener

## COMPARATIVE STATEMENT

**Name of Work: REMOVAL OF CONTAMINATION THROUGH RODDING / CLEANING REPLACEMENT OF DAMAGE / CHOKED PORTION A.C / C.I WATER LINE FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AT UC-37, 38 IN LIAQUATABAD ZONE**

Item No	Description of Work	Estimated Cost				M/s.L.S Enterprises		M/s.Shah Faisal & Brothers		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removing road metalling	10000.00	Cft	605.00	%Cft	60,500.00	605.00	60,500.00	605.00	60,500.00
2	Excavation for pipe line in trenches and pits in all kind of soils of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m).	44738.17	Cft	4650.00	%0Cft	208,032.49	4650.00	208,032.49	4650.00	208,032.49
3	Labour taken for taking out existing pipe from trenches than cleaning of pies and re-laying of pipes after cleaning.									
	(i) Labour for taking out	30.00	Nos	250.00	Each	7,500.00	250.00	7,500.00	250.00	7,500.00
	(ii) Labour for cleaning	30.00	Nos	250.00	Each	7,500.00	250.00	7,500.00	250.00	7,500.00
	(iii) Labour for re-laying	30.00	Nos	250.00	Each	7,500.00	250.00	7,500.00	250.00	7,500.00
	(iv) Fitter	15.00	Nos	400.00	Each	6,000.00	400.00	6,000.00	400.00	6,000.00
4	Providing Laying & Fixing in trenches i/c fitting jointing and testing etc. complete in all respect the high density Polyethylene P.E pipes (HDPE-100) for W/S conforming ISO 4427 DIN-8074-8075 B.S 3580 & PSI 3051. 90 mm Dia	700.00	Rft	178.00	P/Rft	124,600.00	178.00	124,600.00	178.00	124,600.00
	160 mm Dia	300.00	Rft	530.00	P/Rft	159,000.00	530.00	159,000.00	530.00	159,000.00
5	C.I Sluice Valve heavy pattern (Test Pressure 21.0 Kg/sq.com or 300 lb/sq.inch) (Imported) 3" Dia	2.00	Nos	4290.00	Each	8,580.00	4200.00	8,400.00	4400.00	8,800.00
	6" Dia	2.00	Nos	9360.00	Each	18,720.00	9000.00	18,000.00	9500.00	19,000.00
6	Fixing of sluice valve with 2 cast iron tail pieces one end flanged & other with socket i/c the cost of nut, bolts & rubber packing, labour etc complete 3" dia	2.00	Nos	1254.00	Each	2,508.00	1254.00	2,508.00	1260.00	2,520.00
	6" Dia	2.00	Nos	1886.00	Each	3,772.00	1886.00	3,772.00	1886.00	3,772.00

*Qasim*  
07/6

*Singh* *W* *Ch* *W*

**Name of Work: REMOVAL OF CONTAMINATION THROUGH RODDING / CLEANING REPLACEMENT OF DAMAGE / CHOKED PORTION A.C / C.I WATER LINE FOR IMPROVEMENT OF WATER SUPPLY SYSTEM AT UC-37, 38 IN LIAQUATABAD ZONE**

Item No	Description of Work	Estimated Cost				M/s.L.S Enterprises		M/s.Shah Faisal & Brothers		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
7	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	10.00	Days	1500.00	P/Day	15,000.00	1500.00	15,000.00	1550.00	15,500.00
8	Repair of leakages of joints (External Vatta) on PRCC Pipe line. It includes the cost of excavation, labour, sealing material, gunny bags, de-watering and refilling of the excavation stuff etc. complete. 12" Dia	5.00	Nos	9716.00	Each	48,580.00	9716.00	48,580.00	9716.00	48,580.00
	15" Dia	5.00	Nos	10729.00	Each	53,645.00	10729.00	53,645.00	10729.00	53,645.00
	18" Dia	6.00	Nos	13841.00	Each	83,046.00	13841.00	83,046.00	13841.00	83,046.00
9	Construction of C.C. block masonry chamber of size 4'x4'x4' inside with 24" x 24" C.I cover & frame Weight 65 kg fixed in RCC Slab 1:2:4: 6" thick with steel 1/2" dia bars 6" C/C bend up both way, 12" inch thick C:C: 1:3:6 block masonry 6" inch C.C 1:4:8 in foundation, 2" thick C.C 1:2:4 flooring, 1/2" thick cement plaster i/c P/F M.S footrest 5/8" bars at every 2'.0" feet deep i/c curing watering excavation refilling and disposal of surplus earth complete. 4'x4'x4'	2.00	Nos	28357.00	Each	56,714.00	28357.00	56,714.00	28357.00	56,714.00
10	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	44621.75	Cft	2760.00	%0Cft	123,156.03	2760.00	123,156.03	2760.00	123,156.03
TOTAL QUOTED / CORRECTED COST						994,354		993,454		995,366

*(Arshad AH)*  
D.A.O (Dist. Central)  
Member / Secretary

*(Saif-ul-Haque)*  
Addl. Director Internal Audit  
KMC - Member

*(Maqsood Ahmed Shaikh)*  
Superintending Engineer (K.M.C)  
Member

*(Tauqeer Ahmed Khan)*  
S.E (District Central-B)  
Member

*(Saleem Ahmed)*  
Director (Design & Estimate)  
Convener