



KARACHI WATER & SEWERAGE BOARD
OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

BID EVALUATION REPORT

1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.33358 I.D No. _____
3	Tender Description/Name of Work/Item:	REPLACEMENT OF 8", 12" DIA SUN DOWN SEWER AT BLOCK-3C NAZIMABAD NEAR DOLLY PARK OF LIAQUATABAD ZONE (SEW)
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>Through SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>2 Nos</u>
7	Total Bid Received:	<u>2 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>NIL</u>
11	Financial Bid Opening Date:	05-06-2017


12 **BID EVALUATION REPORT**

S #	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Yar Jan & Brothers	Rs.8,88,058/-	1 st Lowest	@0.095% Below	Pay Order and required documents are available. P.O # 17909412 dated: 05-06-2017 Rs.20,000/-from HBL Taimuria Market Branch Karachi	Substantially Responsive
2	M/s.Yousuf Khan & Bros	Rs.8,97,708/-	2 nd Lowest	@0.990% Above	Pay Order and required documents are available. P.O # 17909413 dated: 05-06-2017 Rs.20,000/-from HBL Taimuria Market Branch Karachi	Substantially Responsive


The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Yar Jan & Brothers** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.


(Arshad Ali)
D.A.O (District Central)
Member Secretary


(Tauqeer Ahmed Khan)
S.E (District Central-B)
Member


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Saleem Ahmed)
Director (Design & Estimate)
Convener

FIRMS / CONTRACTORS

NAME OF WORK: REPLACEMENT OF 8", 12" DIA SUNK DOWN SEWER AT BLOCK-3C NAZIMABAD NEAR DOLLY PARK OF LIAQUATABAD ZONE (SEW).

Date of Opening: 05-06-2017

Time of Receiving: 11:00 AM

Time of Opening: 11:30 AM

Serial No. 33358

S.NO	NAME OF CONTRACTOR	NAME OF FIRMS	SIGNATURE
①	YAR SAN BROTHER		يار سان
②	YOUSUF KHAN BROTHER		يوسف خان

NIT No. SPPRA Serial No.33358

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT OF 8", 12" DIA SUN DOWN SEWER AT BLOCK-3C NAZIMABAD NEAR DOLLY PARK OF LIAQUATABAD ZONE (SEW)

MINUTES OF BID OPENING MEETING.


A meeting of the procurement committee of this department was held on 05-06-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
 - i. M/s. Yar Jan & Brothers
 - ii. M/s. Yousuf Khan & Brothers
3. The bids were opened at 11:30 A.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s. Yar Jan & Brothers	Rs.8,88,057.84	Rs.20,000/-	P.O # 17909412 dated:05-06-2017 from HBL Taimuria Market Branch Karachi
02	M/s. Yousuf Khan & Brothers	Rs.8,97,707.84	Rs.20,000/-	P.O # 17909413 dated:05-06-2017 from HBL Taimuria Market Branch Karachi


4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


,The meeting ended with the vote of thanks to and from the chair.


(Arshad Ali)
D.A.O (District Central)
Member / Secretary


(Saif-ul-Haque)
Additional Director Internal
Audit – KMC Member


(Maqsood Ahmed Shaikh)
Superintending Engineer (KMC)
Member


(Tauqeer Ahmed Khan)
S.E (District Central-B)
Member


(Saleem Ahmed)
Director (Design & Estimate)
Convener

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)


Description of work: REPLACEMENT OF 8", 12" DIA SUN DOWN SEWER AT BLOCK-3C NAZIMABAD NEAR DOLLY PARK OF LIAQUATABAD ZONE (SEW)

Date of Opening: 05-06-2017


BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s. Yar Jan & Brothers	M/s. Yousuf Khan & Brothers
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	Qualification Criteria:		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified


 (Arshad Ali)
 D.A.O (District Central)
 Member Secretary


 (Saif-ul-Haque)
 Additional Director Internal
 Audit - KMC Member


 (Maqsood Ahmed Shaikh)
 Superintending Engineer (KMC)
 Member


 (Tauqeer Ahmed Khan)
 S.E (District Central-B)
 Member


 (Saleem Ahmed)
 Director (Design & Estimate)
 Convener

COMPARATIVE STATEMENT

Name of Work: REPLACEMENT OF 8", 12" DIA SUN DOWN SEWER AT BLOCK-3C NAZIMABAD NEAR DOLY PARK OF
LIAQUATABAD ZONE (SEW)

Item No	Description of Work	Estimated Cost				M/s.Yar Jan & Brothers		M/s.Yousuf Khan & Brothers		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removing road metalling	3050.00	Cft	605.00	%Cft	18,452.50	600.00	18,300.00	600.00	18,300.00
2	Excavation for pipe line in trenches and pits in all kind of soil of murum i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). Lift 0' - 5'ft	15250.00	Cft	4650.00	%0Cft	70,912.50	4650.00	70,912.50	4650.00	70,912.50
	Add for additional lift of every three ft or part there of in item No.1 to 15 (A&B) excavations for pipe lines and storage tanks trenches and pits. 05' to 08' ft	5400.00	Cft	5200.00	%0Cft	28,080.00	5200.00	28,080.00	5200.00	28,080.00
3	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	17.00	Days	1500.00	P/Day	25,500.00	1500.00	25,500.00	1500.00	25,500.00
4	Providing, & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 08" Dia	500.00	Rft	206.00	P/Rft	103,000.00	205.00	102,500.00	205.00	102,500.00
	12" Dia	600.00	Rft	367.00	P/Rft	220,200.00	367.00	220,200.00	367.00	220,200.00

Qumbar
06/6

T

W

Sand


Jan


Name of Work: REPLACEMENT OF 8", 12" DIA SUN DOWN SEWER AT BLOCK-3C NAZIMABAD NEAR DOLY PARK OF LIAQUATABAD ZONE (SEW)

Item No	Description of Work	Estimated Cost				M/s.Yar Jan & Brothers		M/s.Yousuf Khan & Brothers		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
5	Providing manhole 4' feet internal diameter without RCC manhole cover with C.I. Frame (15 KG) and 5 feet clear depth cast in situ with 1:2:4 CC in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of engineer incharge.	20.00	Nos	14529.29	Each	290,585.80	14525.00	290,500.00	15000.00	300,000.00
6	Extra for depth beyond 5' depth, if less than 5' deduction will be made at the same rate.	30.00	(+)Rft	2538.62	P/Rft	76,158.60	2535.00	76,050.00	2540.00	76,200.00
7	Making connection with the existing manhole including the cost of cutting hole in wall, making them good in C.C 1:2:4 and making the required channel etc. complete	10.00	Nos	180.00	Each	1,800.00	180.00	1,800.00	180.00	1,800.00
8	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	19643.24	Cft	2760.00	%0Cft	54,215.34	2760.00	54,215.34	2760.00	54,215.34
TOTAL QUOTED / CORRECTED COST						888,905		888,058		897,708


 (Arshad Ali)
 D.A.O. (Distt Central)
 Member / Secretary


 (Saif-ul-Haque)
 Addl. Director Internal
 Audit KMC - Member


 (Maqsood Ahmed Shaikh)
 Superintending Engineer (K.M.C)
 Member


 (Tauqeer Ahmed Khan)
 S.E (District Central-B)
 Member


 (Saleem Ahmed)
 Director (Design & Estimate)
 Convener