

NAME OF WORK:- CONSTRUCTING OF ROAD BRIDGE ALONG SEHRA BRANCH @ RD-30+00

**SCHEDULE "A TO BID"**

| QUANTITY        |    | ITEM OF WORK   | RATE     | UNIT   | AMOUNT |
|-----------------|----|--|----------|--------|--------|
| 7040<br>Cft.    | 01 | Excavation in foundation of building, bridges and other structures including dagbelling, dressing refilling around structure with excavated earth watering and ramming lead up to 5 ft.<br>(b) In ordinary soil<br>(P-4 / I-18(b))   | 3176/25  | %Cft.  | 22361  |
| 1408<br>Sft.    | 02 | Preparing, watering and ramming surface for laying concrete (for head works only).<br>Horizontal floor<br>(P-18/I-18(a))   | 228/09   | %Sft.  | 3212   |
| 668<br>Sft.     | 03 | Erection and removal of centering for R.C.C or plain cement concert work (b)<br>Portal wood (Horizontal)<br>(P-18 / I-19(b))   | 3588/48  | %Sft.  | 23971  |
| 1408<br>Cft.    | 04 | Cement concrete bricks or stone ballast 1 1/2" to 2" gauge. Ratio 1:4:8<br>(P-15/I-4(b))   | 9416/28  | %Cft.  | 132581 |
| 1376<br>cft     | 05 | Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering).<br>(h) Ration 1:3:6<br>(P-16/I-5(h))   | 12595/00 | %Cft.  | 173307 |
| 1344<br>Cft     | 06 | Pacca brick work in foundation and plinth in cement sand mortar 1:4<br>(P-20/I-4(c))   | 12501/41 | % Cft  | 168019 |
| 1698<br>Cft     | 07 | Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for its bending & which will be paid separately, this rate also i/c all kinds of form moulds lifting shuttering curing rendering and finishing the exposed surface and washing of shingle) Ratio 1:2:4<br>a) RCC work in roof, slab, beams, column rafts, lintels and other structural members. laid in situ or pre-cast laid in position completed in all respects Ratio 1:2:4 90 LBS cement 2cft sand 4cft shingle 1/8" to 1/4" gauge<br>(P-16 / I-6(a)) | 337/00   | P/Cft. | 572226 |
| 106.125<br>Cwt. | 08 | Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, laying in position making joints and fastenings i/c cost of binding wire (also includes removal of (b) using tar bars<br>(P-17 / I-8(b))  | 5001/70  | P/Cwt. | 530805 |

(21)

G.H.B Construction  
Company

|                     |    |   |          |        |        |
|---------------------|----|---|----------|--------|--------|
| 2303<br>Cft         | 09 | Pacca brick work other then building including striking of joints up to 20 ft height in (c) Cement sand mortar Ratio 1:4 (P-22, I-7(c))   | 12899/70 | % Cft  | 297080 |
| 1204<br>Sft         | 10 | Cement Plaster 1:2 upto 12' ht: (c) 3/4" thick (P-52 / I-9(c))  | 3056/62  | % Sft  | 36802  |
| 422<br>Cft          | 11 | Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing at stone aggregate without shuttering ) (f) Ration 1:2:4 (P-16, I-5(f))   | 14429/25 | % Cft  | 60891  |
| 32800<br>Cft        | 12 | Barrow pit excavation undressed lead upto 100' Ft. (a) Ordinary Soil.(P-1 / I-3(a))   | 2117/50  | % Cft. | 69454  |
| 32800<br>Cft.       | 13 | Carriage of 100 Cft./5 tons of all material like tone aggregate spwall coal line Surkhi etc. BG Rails fastening points and crossing Bridges and Girders pipes sheets, rails M.S Bar etc are 1000 Nos. bricks 10"x5"x3" are 1000 Nos. Tiles 12"x6"x2" are 150 Cft. of timber of 1000 mounds of fuel wood by Trucks or any other means owned by Contractor 2 miles. (P-1 / I-1)   | 502/52   | % Cft. | 164826 |
| 51<br>HOURS<br>Days | 14 | Full hire charge of the pumping set per day inclusive of wage of driver and Assistant fuel or electric energy plate forms required for placing pumps etc at lower depths with suction and delivery pipes for pumping out water found at various depths from trenches including the cost of erection and dismantling after the completion of the (ii) higher charges of pumping set of upto 10 HP out water from 20' depth job.(P-76 / I-23) PHED Schedule | 2500/00  | P/Day  | 127500 |
| 408<br>Hrs.         | 15 | Note:<br>For working the beyond at hours the following payment shall be made. The higher of the pumping set it self being for 24 hours (1) for a pumping set of upto 10 HP trench.(P-77 / I-23) PHED Schedule   | 250/00   | P/Hour | 102000 |

TOTAL: 2485035

Note: No Premium will be on item No. 13

Add: 55.56 % above / Below

Total= 3774143/2

164826  
2320209  
1289108  
1648261

Checked by  
Divisional Head Draftsman  
Rohri Division Kandiaro

CHECKED.

CIRCLE HEAD DRAFTSMAN  
ROHRI CANAL CIRCLE  
HYDERABAD

G.H.B Construction  
Company

EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO

Circle Head Draftsman  
Sukkur Barrage Left Bank Region  
Sukkur

92

NAME OF WORK:- CONSTRUCTING RETAINING WALL ALONG SEHRA BRANCH FROM RD-4+00 TO 7+00 B/S.

SCHEDULE "A TO BID"

| QTY:          |    | ITEM OF WORK  | RATE     | UNIT   | AMOUNT   |
|---------------|----|---|----------|--------|----------|
| 240000 Cft    | 1  | Excavation in foundation of building bridges and other structures including dag-belling dressing rifling around structure with excavated earth watering and ramming lead up to 5 ft. (b) in ordinary soil (P-4/I-18b)   | 3176/25  | % Cft  | 762300   |
| 48000 Sft     | 2  | Preparing and watering and ramming surface for laying concrete (for head works only). (a) Horizontal floor (P-18/I-18a)   | 228/09   | % Sft  | 109483   |
| 60000 Sft     | 3  | Erection and removal of centering for RCC or plain cement concrete works of Deodar wood (2 <sup>nd</sup> class).(ii)vertical (P-18/I-19aii)   | 7000/-   | % Sft  | 4200000  |
| 48000 Sft     | 4  | Cement Concrete brick or Stone ballast 1 1/2" to 2" gauge ratio 1:4: 8 (P-15/I-4(b))  | 9416/28  | % Cft  | 4519814  |
| 42000 Cft     | 5  | Cement concrete plain including placing compacting , finishing and curing , complete (including screening and washing of stone aggregate without shuttering )(h)Ration 1:3:6 (P-16/I-5h)  | 12595/-  | % Cft  | 5289900  |
| 57490 Cft     | 6  | Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for its bending & which will be paid separately, this rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c Screening and washing of shingle)<br>a) RCC work in roof, slab, beams, column rafts, lintels and other structural members laid in situ or pre-cast laid in position completed in all respects (i) Ratio 1:2:4 90 Lbs cement 2 cft Sand 4 cft Shingle 1/8" to 1/4" gauge (P-16 & 17 / I-6(6i)) | 309/78   | P/Cft. | 17809252 |
| 2566.518 Cwt. | 7  | Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, laying in position making joints and fastenings i/c cost of binding wire (also includes removal of (b)using tar bars (P-17 / I-8(b))   | 5001/70  | P/Cwt. | 12836953 |
| 31680 Cft     | 8  | Pacca brick work in foundation and plinth in cement sand mortar 1:4 (P-20/I-4(c))   | 12501/41 | % Cft  | 3960447  |
| 153216 Cft    | 9  | Pacca brick work other then building including striking of joints up to 20 ft height in (c) Cement sand mortar Ratio 1:4 (P-22 , I-7(c))  | 12899/70 | % Cft  | 19764404 |
| 45600 Sft     | 10 | Cement Pointing struck joints on Walls (a) ratio 1:2 (P-53/I-19 (a))  | 1287/44  | % Sft  | 587073   |

93



**G.H.B Construction  
Company**

|             |     |  |          |        |         |
|-------------|-----|--|----------|--------|---------|
| 13500 Cft.  | 11  | Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering).<br>(f) Ration 1:2:4 (P-16/I-5f)  | 14429/25 | %Cft.  | 1947949 |
| 288000 Cft  | 12  | Barrow pit excavation undressed lead upto 100' Ft.<br>(a) Ordinary Soil.(P-1 / I-3(a))   | 2117/50  | %0Cft. | 609840  |
| 288000 Cft. | 13  | Carriage of 100 Cft. / 5 tons of all material like tone aggregate spwall coal line Surkhi etc. BG Rails fastening points and crossing Bridges and Girders pipes sheets, rails M.S Bar etc are 1000 Nos. bricks 9"x4 1/2"x3" are 1000 Nos. Tiles 12"x6"x2" are 150 Cft. of timber of 1000 mounds of fuel wood by Trucks or any other means owned by Contractor 1- mile.<br>(P-1 / I-1/ schedule of Carriage)  | 407/00   | %Cft.  | 1172160 |
| 288000 Cft. | 14  | Earthwork compaction soft ordinary or hard soil<br>(b) laying earth in 6" layers leveling, dressing, watering for compaction etc. complete.<br>P-3 / I-13(b)   | 354/00   | %0Cft. | 101952  |
| 112 Day     | 15  | (Full hire charge of the pumping set per day inclusive of wage of driver and Assistant fuel or electric energy plate forms required for placing pumps etc at lower depths with suction and delivery pipes for pumping out water found at various depths from trenches including the cost of erection and dismantling after the completion of the<br>(ii) higher charges of pumping set of upto 10 HP out water from 20' depth<br>Job.(P-76 / I-23) PHED Schedule | 1500/00  | P/Day  | 168000  |
| 896 Hrs.    | (b) | Note:<br>For working the beyond at hours the following payment shall be made. The higher of the pumping set it self being for 24 hours (1) for a pumping set of upto 10 HP trench.(P-77 / I-23) PHED Schedule  | 250/00   | P/Hour | 224000  |

Total Rs. 740635271-

Note: No Premium will be allowed on item No. 13

Add: 55.56 % above / Below

1172160  
 72891367 =  
 408984431  
 1172160  
 Total = 1145819701

checked by  
 Divisional Head Draftsman  
 Rohri Division Kandiaro

CHECKED.  
 Circle Head Draftsman  
 ROHRI CANAL CIRCLE  
 HYDERABAD

G.H.B Construction  
 Company

EXECUTIVE ENGINEER,  
 ROHRI DIVISION KANDIARO

Circle Head Draftsman  
 Sukkur Barrage Left Bank Region  
 Sukkur

94

|             |     |  |          |        |         |
|-------------|-----|--|----------|--------|---------|
| 13500 Cft.  | 11  | Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering).<br>(f) Ration 1:2:4 (P-16/I-5f)  | 14429/25 | %Cft.  | 1947949 |
| 288000 Cft  | 12  | Barrow pit excavation undressed lead upto 100' Ft.<br>(a) Ordinary Soil.(P-1 / I-3(a))   | 2117/50  | %0Cft. | 609840  |
| 288000 Cft. | 13  | Carriage of 100 Cft. / 5 tons of all material like tone aggregate spwall coal line Surkhi etc. BG Rails fastening points and crossing Bridges and Girders pipes sheets, rails M.S Bar etc are 1000 Nos. bricks 9"x4 1/2"x3" are 1000 Nos. Tiles 12"x6"x2" are 150 Cft. of timber of 1000 mounds of fuel wood by Trucks or any other means owned by Contractor 1- mile.<br>(P-1 / I-1/ schedule of Carriage)  | 407/00   | %Cft.  | 1172160 |
| 288000 Cft. | 14  | Earthwork compaction soft ordinary or hard soil<br>(b) laying earth in 6" layers leveling, dressing, watering for compaction etc. complete.<br>P-3 / I-13(b)   | 354/00   | %0Cft. | 101952  |
| 112 Day     | 15  | (Full hire charge of the pumping set per day inclusive of wage of driver and Assistant fuel or electric energy plate forms required for placing pumps etc at lower depths with suction and delivery pipes for pumping out water found at various depths from trenches including the cost of erection and dismantling after the completion of the<br>(ii) higher charges of pumping set of upto 10 HP out water from 20' depth<br>Job.(P-76 / I-23) PHED Schedule | 1500/00  | P/Day  | 168000  |
| 896 Hrs.    | (b) | Note:<br>For working the beyond at hours the following payment shall be made. The higher of the pumping set it self being for 24 hours (1) for a pumping set of upto 10 HP trench.(P-77 / I-23) PHED Schedule  | 250/00   | P/Hour | 224000  |

Total Rs. 740635271-

Note: No Premium will be allowed on item No. 13

Add: 55.56 % above / Below

1172160  
 72891367/=  
 408984431  
 11721605  
 1145819701

Total =

checked by  
 Divisional Head Draftsman  
 Rohri Division Kandiaro

CHECKED.  
 CIRCLE HEAD DRAFTSMAN  
 ROHRI CANAL CIRCLE  
 HYDERABAD

G.H.B Construction  
 Company

EXECUTIVE ENGINEER,  
 ROHRI DIVISION KANDIARO

Circle Head Draftsman  
 Sukkur Barrage Left Bank Region  
 Sukkur

94

IN WITNESS WHEREOF the parties hereto have caused this Agreement to be executed on the day, month and year first before written in accordance with their respective laws.

Signature of the Contactor

G.H.B Construction  
(Seal)  
Company

Signature of Procuring Agency

(Seal)

Signature of Procuring Agency  
Rohri Division Kandiaro

Signed, Sealed and Delivered in the presence of:

Witness:

Witness Signature

AL HUMAN & AL Haseeb

(Name, Title and Address)

Govt Contractor

Witness:

Muhammad Sami Samio  
Divisional Accounts Officer  
Rohri Division Kandiaro

(Name, Title and Address)

House No C 218  
Gulshan Sojad  
Qasim Ebad Hyderabad

**SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY**  
**CONTRACT EVALUATION FORM**  
**TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC WORKS,**  
**SERVICES & GOODS**

|   |  |   |
|---|--|---|
| 1) NAME OF THE ORGANIZATION / DEPTT.  | <b>IRRIGATION DEPARTMENT</b>   |   |
| 2) PROVINCIAL / LOCAL GOVT./ OTHER  | <b>PROVINCIAL</b>  |   |
| 3) TITLE OF CONTRACT  | <b>ADP SCHEME # 1175<br/>FOR YEAR 2014-15</b>                                    |   |
| 4) TENDER NUMBER  | No. TC/G-55/KRO/901, DATE: 06.07.2015 &<br>Corrigendum No. 1078 dated 18.08.2015 |   |
| 5) BRIEF DESCRIPTION OF CONTRACT  | <b>Package # 01</b>  | CONSTRUCTING STONE PITCHING ALONG<br>SEHRA BRANCH FROM RD 21 TO 23 BOTH<br>SIDE 27 TO 29 NIP AND 36+500 TO 40 NIP<br>SIDE, CONSTRUCTING VILLAGE ROAD BRIDGE<br>ALONG SEHRA BRANCH AT RD 30,<br>CONSTRUCTING RETAINING WALL ALONG<br>SEHRA BRANCH RD 4 TO 7 B/S. |
| 6) FORUM THAT APPROVED THE SCHEME   | <b>CHIEF ENGINEER SUKKUR BARRAGE LEFT<br/>BANK REGION SUKKUR</b>                 |   |
| 7) TENDER ESTIMATED VALUE   | <b>147902144</b>   |   |
| 8) ENGINEER'S ESTIMATE<br>(For civil works only)  | <b>129855402</b>   |   |
| 9) ESTIMATED COMPLETION PERIOD (AS PER<br>CONTRACT)   | <b>24 Months</b>   |   |
| 10) TENDER OPENED ON (DATE & TIME)  | <b>18-09-2015</b>  |   |
| 11) NUMBER OF TENDER DOCUMENTS SOLD   | <b>03</b>  |   |
| 12) NUMBER OF BIDS RECEIVED   | <b>03</b>  |   |
| 13) NUMBER OF BIDDERS PRESENT AT THE TIME OF<br>OPENING OF BIDS   | <b>03</b>  |   |
| 14) BID EVALUATION REPORT<br>(Enclose a copy)   | <b>(Copy attached)</b>   |   |
| 15) NAME AND ADDRESS OF THE SUCCESSFUL<br>BIDDER  | <b>GHB CONSTRUCTION COMPANY</b>  |   |
| 16) CONTRACT AWARD PRICE  |  |   |
| 17) RANKING OF SUCCESSFUL BIDDER IN<br>EVALUATION REPORT<br>(i.e. 1st, 2nd, 3rd EVALUATION BID).  | GHB Construction Company<br>M/S Mir Muhammad Saryo & Co<br>M/S Jamali & Brothers |   |
| 18) METHOD OF PROCUREMENT USED : - (Tick one)   |  |   |
| a) SINGLE STAGE -- ONE ENVELOPE PROCEDURE   | <b>Domestic</b>  | <b>Local</b>  |
| b) SINGLE STAGE - TWO ENVELOPE PROCEDURE  |  | <b>X</b>  |
| c) TWO STAGE BIDDING PROCEDURE  |  | <b>X</b>  |
| d) TWO STAGE -- TWO ENVELOPE BIDDING<br>PROCEDURE   |  | <b>X</b>  |
| PLEASE SPECIFY IF ANY OTHER METHOD OF PROCUREMENT WAS ADOPTED i.e.<br>EMERGENCY, DIRECT CONTRACTING /ETC. WITH BRIEF REASONS: BRIEF REASONS |  |   |

19) APPROVING AUTHORITY FOR AWARD OF CONTRACT \_ Chief Engineer Sukkur Barrage left Bank Region Sukkur

20) WHETHER THE PROCUREMENT WAS INCLUDED IN ANNUAL PROCUREMENT PLAN?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

21) ADVERTISEMENT :

i) SPPRA Website  
(If yes, give date and SPPRA Identification No.)

|     |             |
|-----|-------------|
| Yes | S. No 24735 |
| No  |             |

ii) News Papers  
(If yes, give names of newspapers and dates)

|     |  |
|-----|--|
| Yes | Daily Jung, Daily Kawish,<br>Daily Dawn dated 09.07.2015 |
| No  |  |

22) NATURE OF CONTRACT

|                    |                                     |      |                          |
|--------------------|-------------------------------------|------|--------------------------|
| Domestic/<br>Local | <input checked="" type="checkbox"/> | Int. | <input type="checkbox"/> |
|--------------------|-------------------------------------|------|--------------------------|

23) WHETHER QUALIFICATION CRITERIA  
WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?  
(If yes, enclose a copy)

|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

24) WHETHER BID EVALUATION CRITERIA  
WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?  
(If yes, enclose a copy)

|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

25) WHETHER APPROVAL OF COMPETENT AUTHORITY WAS OBTAINED FOR USING A  
METHOD OTHER THAN OPEN COMPETITIVE BIDDING?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

26) WAS BID SECURITY OBTAINED FROM ALL THE BIDDERS?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

27) WHETHER THE SUCCESSFUL BID WAS LOWEST EVALUATED  
BID / BEST EVALUATED BID (in case of Consultancies)

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

28) WHETHER THE SUCCESSFUL BIDDER WAS TECHNICALLY  
COMPLIANT?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

29) WHETHER NAMES OF THE BIDDERS AND THEIR QUOTED PRICES WERE READ OUT AT  
THE TIME OF OPENING OF BIDS?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

30) WHETHER EVALUATION REPORT GIVEN TO BIDDERS BEFORE THE AWARD OF  
CONTRACT?  
(Attach copy of the bid evaluation report)

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|



31) ANY COMPLAINTS RECEIVED  
(If yes, result thereof)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

32) ANY DEVIATION FROM SPECIFICATIONS GIVEN IN THE TENDER NOTICE / DOCUMENTS  
(If yes, give details)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

33) WAS THE EXTENSION MADE IN RESPONSE TIME?  
(If yes, give reasons)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

34) DEVIATION FROM QUALIFICATION CRITERIA  
(If yes, give detailed reasons.)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

35) WAS IT ASSURED BY THE PROCURING AGENCY THAT THE SELECTED FIRM IS NOT  
BLACK LISTED?

|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

36) WAS A VISIT MADE BY ANY OFFICER/OFFICIAL OF THE PROCURING AGENCY TO THE  
SUPPLIER'S PREMISES IN CONNECTION WITH THE PROCUREMENT? IF SO, DETAILS TO  
BE ASCERTAINED REGARDING FINANCING OF VISIT, IF ABROAD:  
(If yes, enclose a copy)

|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

37) WERE PROPER SAFEGUARDS PROVIDED ON MOBILIZATION ADVANCE PAYMENT IN  
THE CONTRACT (BANK GUARANTEE ETC.)?

|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

38) SPECIAL CONDITIONS, IF ANY  
(If yes, give Brief Description)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

Signature & Official Stamp of **Executive Engineer Rohri Division Kandiaro**  
Authorized Officer **Executive Engineer Rohri Division Kandiaro**

*NA*

*Muhammad Ismail Samio*  
**Divisional Accounts Officer  
Rohri Division Kandiaro**

**FOR OFFICE USE ONLY**

**SPPRA, Block. No.8, Sindh Secretariat No.4-A, Court Road, Karachi**

Tele: 021-9205356; 021-9205369 & Fax: 021-9206291

FORM OF CONTRACT AGREEMENT

THIS CONTRACT AGREEMENT (hereinafter called the "Agreement") made on the 2nd day of October (month) 2016 between Executive Engineer and G.H.B Construction Company (hereafter called the "Procuring Agency") of the one part and G.H.B Construction Company (hereafter called the "Contractor") of the other part.

WHEREAS the Procuring Agency is desirous that certain works, viz. from RD 21 to 29 along S. H. Rd 27 to 29, 36 to 500 to 40 N 2P Const. Road Bridge along S. H. Rd 30 Const. Retaining wall S. H. Rd 4 to 7 should be executed by the Contractor and has accepted a bid by the Contractor for the execution and completion of such works and the remedying of any defects therein.

NOW this Agreement witnesseth-- as follows:

1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to.
2. The following documents after incorporating addenda, if any, except those parts relating to Instructions to bidders shall be deemed to form and be read and construed as part of this Agreement, viz:
  - (a) The Contract Agreement;
  - (b) The Letter of Acceptance;
  - (c) The completed Form of Bid;
  - (d) Special Stipulations (Appendix-A to Bid);
  - (e) The Special Conditions of Contract – Part II;
  - (f) The General Conditions – Part I;
  - (g) The priced Bill of Quantities (Appendix-D to Bid);
  - (h) The completed Appendices to Bid (B, C, E to I);
  - (i) The Drawings;
  - (j) The Specifications.
  - (k) \_\_\_\_\_ (any other)
3. In consideration of the payments to be made by the procuring agency to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the procuring agency to execute and complete the works and remedy defects therein in conformity and in all respects with the provisions of the contract.
4. Procuring agency hereby covenants to pay the contractor, in consideration of the execution and completion of the works as per provisions of the contract, the contract Price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.

Constructing stone pitching along S. H. Rd 27 to 29, 36 to 500 to 40 N 2P Const. Road Bridge along S. H. Rd 30 Const. Retaining wall S. H. Rd 4 to 7

(INTEGRITY PACT)

DECLARATION OF FEES, COMMISSION AND BROKERAGE ETC; PAYABLE BY CONTRACTORS.  
(FOR CONTRACTS WORTH RS. 10.00 MILLION OR MORE)

Contract No. 901 Dated 6.7.2015

Contract Value: 147902144

Contract Title: Constructing stone pitching along Schra branch from RD 21 to 23  
halk.s.d.s 27 k-28 NEP 236+500 to 40/over P.S. ke Const# VRB along Schra branch

..... [name of Contractor] hereby declares that it has not obtained or induced the procurement of any contract, right, interest, privilege or other obligation or benefit from Government of Sindh (GoS) or any administrative subdivision or agency thereof or any other entity owned or controlled by it (GoS) through any corrupt business practice.

*RD 30 Constt  
Retaining walls  
along Schra sm  
RD 4 to 7 B/S*

Without limiting the generality of the foregoing, [name of Contractor] represents and warrants that it has fully declared the brokerage, commission, fees etc. paid or payable to anyone and not given or agreed to give and shall not give or agree to give to anyone within or outside Pakistan either directly or indirectly through any natural or juridical person, including its affiliate, agent, associate, broker, consultant, director, promoter, shareholder, sponsor or subsidiary, any commission, gratification, bribe, finder's fee or kickback, whether described as consultation fee or otherwise, with the object of obtaining or inducing the procurement of a contract, right, interest, privilege or other obligation or benefit in whatsoever form from, from Procuring Agency (PA) except that which has been expressly declared pursuant hereto.

[name of Contractor] accepts full responsibility and strict liability that it has made and will make full disclosure of all agreements and arrangements with all persons in respect of or related to the transaction with PA and has not taken any action or will not take any action to circumvent the above declaration, representation or warranty.

[name of Contractor] accepts full responsibility and strict liability for making any false declaration, not making full disclosure, misrepresenting facts or taking any action likely to defeat the purpose of this declaration, representation and warranty. It agrees that any contract, right, interest, privilege or other obligation or benefit obtained or procured as aforesaid shall, without prejudice to any other rights and remedies available to PA under any law, contract or other instrument, be voidable at the option of PA.

Notwithstanding any rights and remedies exercised by PA in this regard, [name of Supplier/Contractor/Consultant] agrees to indemnify PA for any loss or damage incurred by it on account of its corrupt business practices and further pay compensation to PA in an amount equivalent to ten times the sum of any commission, gratification, bribe, finder's fee or kickback given by [name of Contractor] as aforesaid for the purpose of obtaining or inducing the procurement of any contract, right, interest, privilege or other obligation or benefit in whatsoever form from PA.

*[Signature]*  
[Procuring Agency]  
Executive Engineer  
Rohri Division Kandiaro

[Contractor]  
G.H.B Construction  
Company

**OFFICE OF THE EXECUTIVE ENGINEER ROHRI DIVISION KANDIARO.**

No. TC/ G-55 / 1263 of 2015

Kandiara, dated 02 / 10 / 2015.

To,

M/S G H B CONSTRUCTION  
COMPANY  
E-17/17, AHMED ARCADE, KHAYABN-E-JAMI  
GIZRI ROAD CLIFTON KARACHI.

**LETTER OF COMMENCEMENT /WORK ORDER**

**SUBJECT: CONSTRUCTING STONE PITCHING ALONG SEHRA BRANCH RD 21 TO 23 BOTH SIDES 27 TO 29 NIP AND 36+500 TO 40 NIP SIDE CONSTRUCTING VILLAGE ROAD BRIDGE ALONG SEHRA BRACH AT RD 30, CONSTRUCTING RETAINING WALL ALONG SEHRA BRANCH RD 4 TO 7 BOTH SIDES.**

**Reference: Your tender dated 16.09.2015**

The rate of Rs. 55.56% above (Rupees Fifty Five Point Fifty Six percent above) on the schedule of price which works out 13.90% above (Rupees Thirteen point ninety percent above) estimate quoted by you through tender has been sanctioned by the Chief Engineer Sukkur Barrage Left Bank Region Sukkur letter No. WB-II/RDK/2015/4-W/5412, dated 30.09.2015 for Rs. 147902144/-

You are direct to please start the work within three days (under the supervision of Assistant Executive Engineer Tharushah Irrigation Sub Division-I.

Please start: the work should be carried out strictly according PWD specification and should be completed in stipulated period.

The time for completion of work is (24 Months).

  
EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO

Copy with schedule price forwarded to Assistant Executive Engineer Tharuhsah Irrigation Sub Division-I for information and necessary action. He is directed to report the actual date of start as well as the progress of work and see that the work should be completed within stipulated period.

  
EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO

**NAME OF WORK:- CONSTRUCTING STONE PITCHING ALONG SEHRA BRANCH FROM RD-21 TO 23 BOTH SIDES, 27 TO 29 & 36+500 TO 40 NIP.**

**SCHEDULE "A TO BID"**

| QUANTITY   | ITEM OF WORK  | RATE     | UNIT   | AMOUNT  |
|------------|---|----------|--------|---------|
| 561801 Cft | Excavation in foundation, of building bridges and other structures including dagbelling, dressing, refilling around structure with excavated earth watering and ramming lead up to 5 ft. (b) In ordinary soil (P-4 / I-18b) | 3176/25  | %0Cft  | 1784420 |
| 280900 Cft | Re-handling of earth work<br>(a) lead up to a shingle throw of kassi, Phawrsh or a =shovel (b) Up to a lead of 50 ft (P-2/I-9b)   | 1058/75  | %0 Cft | 297403  |
| 85500 Cft  | Stone filling dry hand packed as filling behind retaining walls or in pitching and apron (P-31/I-16)  | 2684/00  | %Cft   | 2294820 |
| 10412 Cft  | Coursed rubble masonry hammer dressed. (d) In cement sand mortar, Ratio 1:6 (P-28/I-4diii)  | 26288/46 | %Cft   | 2737154 |
| 124844 Sft | Formation, dressing and preparing Sub-Grading (b) on slopes. (P-74 / I-1(b))  | 453/75   | %Sft   | 566933  |
| 79588 Cft  | Stone pitching i/c Sub-Base with hammer dressed stone on surface laid in courses i/c carriage of material (P-32 / I-23)   | 5377/63  | %Cft   | 9657578 |
| 9500 Sft   | Erection and removal of centering for RCC or plain cement concrete works of Deodar wood (2nd class )<br>(b) For Portal wood (ii) vertical (P-18/I-19b ii)   | 3127/41  | %Sft   | 297104  |
| 9500 Cft   | Cement concrete plain including placing compacting finishing and curing complete (including screening and washing at stone aggregate without shuttering (f) Ratio 1:2:4). (P-16/I-5)  | 14429/25 | % Cft  | 1370779 |

Total Rs. 19006191

Add: 55.56 % above / Below 10559840

Total= 29566031/-

Checked by  
Divisional Head Draftsman  
Rohri Division Kandiaro

CHECKED

CIRCLE HEAD DRAFTSMAN  
ROHRI CANAL CIRCLE  
HYDERABAD

G.H.B Construction  
Company

EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO

Circle Head Draftsman  
Sukkur Barrage Left Bank Region  
Sukkur

90

**NAME OF WORK:- RE-SECTIONING & EARTHWORK ALONG KANDIARO ESCAPE # 1**

**SCHEDULE "A TO BID "**

| QUANTITY         | ITEM OF Work  | RATE    | UNIT    | AMOUNT   |
|------------------|---|---------|---------|----------|
| 9072600<br>Cft.  | 01 Earthwork excavation in irrigation channels drains etc. dressed to designed section, grades and profiles excavated material disposed off and dressed within 50' Ft. lead (a) ordinary soil. P-1, I-5(a)  | 2420/00 | %0 Cft. | 21955692 |
| 27214800<br>Cft. | 02 Re-handling of earthwork. (b) upto a lead of 50' ft. P-2, I-9(b)   | 1058/75 | %0 Cft. | 28813670 |
| 1703725<br>Cft.  | 03 Barrow pits excavation undressed lead upto 100' Ft. (a) Ordinary soil. P-1, I-3(a)   | 2117/50 | %0 Cft. | 3607638  |
| 1703725<br>Cft.  | 04 Carriage of 100 Cft. 5 tons of all material like tonic aggregate sp wall coal line Surkhi etc. BG Rails fastening points and crossing Bridges and Girders pipes sheets, rails M.S Bar etc are 1000 Nos. bricks 10"x5"x3" are 1000 Nos. Tiles 12"x6"x2" are 150 Cft. of timber of 1000 mounds of fuel wood by Trucks or any other means owned by Contractor 2 miles. P-1, I-1(a) Schedule of carriage | 502/52  | % Cft.  | 8561559  |
| 1703725<br>Cft.  | 05 Earthwork compaction soft ordinary or hard soil (b) laying earth in 6" layers levelling, dressing, watering for compaction etc. complete. P-3, I-13(a)   | 263/00  | %0 Cft. | 448080   |

TOTAL RS.

63386639/-

Note: No Premium will be on item No. 4

Add 4% above / below

Total =

8561559/-  
54825080/-  
22478282/-  
8561559/-  
85864921/-

Head Draftsman  
Division Kandiaro

CHECKED  
HEAD DRAFTSMAN  
CANAL CIRCLE  
DERABAD

G.H.B Construction  
Company

EXECUTIVE ENGINEER  
Rohri Division Kandiaro

Qty and Amount  
of item No. 2 is  
within the provision  
of sanctioned estimate

Circle Head Draftsman  
Sukkur Barrage L. Region

NAME OF WORK:- REPAIR / RE-CONSTRUCTION OF COMPOUND WALL @ KANDIARO  
IRRIGATION SUB DIVISION-I & II.

SCHEDULE "A TO BID"

| QUANTITY       | ITEM OF WORK   | RATE     | UNIT   | AMOUNT |
|----------------|--|----------|--------|--------|
| 5950<br>Cft.   | Excavation in foundation of building bridges and other structure i/c deg bellying dressing refilling around structure with excavated earth, watering and ramming lead up to 5' ft. in ordinary soil.<br>Page # 5, I # 18(b)            | 3176/25  | %0Cft. | 18899  |
| 1360<br>Sft.   | 2<br>Erection and removal of centering for RCC or plain cement concrete works (2nd class). For Portal wood (ii) vertical (P-18/I-19aii)  | 3127/41  | %Sft.  | 42533  |
| 1360<br>Cft.   | 3<br>Cement concrete plain including placing compacting finishing and curing complete including screening and washing at stone aggregate without shuttering ration (1:3:6)<br>Page # 16, I # 05(h)                                     | 12595/00 | % Cft. | 171292 |
| 2210<br>Cft.   | 4<br>Pacca brick work in foundation and plinth in cement, sand, mortar ratio (1:4)<br>Page # 20, I # 4(i)  | 12501/41 | % Cft. | 276281 |
| 4080<br>Cft.   | 5<br>Pacca Brick work in ground floor in Cement, Sand mortar Ratio (1:4)<br>Page # 21, I # 5i(c)   | 13227/41 | % Cft. | 539678 |
| 936.4<br>Cft.  | 6<br>R.C.C Work in Roof Slab Beams Columns Rafts Lintel and other structure members laid in situ or pre-cast laying in position complete in all respects.<br>Page # 19, I # 06 a(i)  | 337/00   | P/Cft. | 315567 |
| 41.803<br>Cwt. | 7<br>Fabrication of mild steel reinforcement for cement concrete i/c cutting bending laying in position making the joints and fastenings i/c cost of binding wire (and also includes removal of using tor bars.<br>Page # 17, I # 8(b) | 5001/70  | P/Cwt. | 209086 |
| 15300<br>Sft.  | 8<br>Cement Plaster 1:3 upto 3/4" thick upto 12' height<br>Page # 52, I # 10-(c)   | 2795/30  | %Sft.  | 427681 |
| 15300<br>Sft.  | 9<br>Cement Plaster 1:3 upto 1/2" thick upto 12' height.<br>Page # 53, I # 10 (b)  | 2344/59  | %Sft.  | 358722 |

|               |    |   |         |        |        |
|---------------|----|---|---------|--------|--------|
| 95200<br>Cft. | 10 | Barrow pit excavation undressed lead upto 100' Ft. (a) Ordinary Soil.<br>(P-1/1-3(a))<br>Page # 1, I # 3-(a)  | 2117/50 | %0Cft. | 201586 |
| 95200<br>Cft. | 11 | Carriage of 100 Cft./5 tons of all material like tone aggregate spwall coal line Surkhi etc. BG Rails fastening points and crossing Bridges and Girders pipes sheets, rails M.S Bar etc are 1000 Nos. bricks 10"x5"x3" are 1000 Nos. Tiles 12"x6"x2" are 150 Cft. of timber of 1000 mounds of fuel wood by Trucks or any other means owned by Contractor 2 miles.<br>Page # 1, I # 1(schedule of carriage)  | 502/52  | %Cft.  | 478399 |
| 80.0<br>Sft.  | 12 | Supplying and fixing special heavy type steel doors for look - ups within angle iron frame of 2-1/2 to 2-1/2 into 3/8 size and shutter of 2" x 2" x 3/8" with 1" dia meter M.S Bars placed at 4" center to center with a separate locking box having size of 12" x 12" of M.Steel sheet embedded in masonry with proper locking arrangement as per approved design including cost of erection of steel gate and fixing masonry wall in cement concert 1:2:4 etc. complete as per instruction of Engineer incharge.<br>Page # 93, I # 27 | 930/76  | P/Sft. | 74460  |
| 15300<br>Sft. | 13 | White washing (b) 2 Coats<br>Page # 54, I # 26-(b)  | 425/84  | %Sft.  | 65154  |

TOTAL RS. 3179338

Note: No Premium will be on item No. 11

Add 41.0 % above / below

478399/-  
2700939/-  
1107385/-  
478399/-  
Total = 4286723/-

Checked by  
28/11/20  
Regional Head Draftsman  
Rohri Division Kandiaro

CHECKED.

Regional Head Draftsman  
Rohri Division Kandiaro  
HYDERABAD

Regional Head Draftsman  
Rohri Division Kandiaro  
Sukkur

G.H.B Construction  
Company

EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO



**NAME OF WORK:- CONSTRUCTING RETAINING WALL ALONG KANDIARO ESCAP-1  
FROM RD-4+00 TO 7+00 L/S.**

**SCHEDULE "A TO BID"**

| QTY:          | ITEM OF WORK   | RATE     | UNIT   | AMOUNT   |
|---------------|--|----------|--------|----------|
| 180000 Cft    | 1 Excavation in foundation of building bridges and other structures including dag-belling dressing rifling around structure with excavated earth watering and ramming lead up to 5 ft. (b) in ordinary soil (P-4/I-18b)  | 3176/25  | % Cft  | 571725   |
| 27000 Sft     | 2 Preparing and watering and ramming surface for laying concrete (for head works only). (a) Horizontal floor (P-18/I-18a)  | 228/09   | % Sft  | 61584    |
| 30000 Sft     | 3 Erection and removal of centering for RCC or plain cement concrete works of Deodar wood (2 <sup>nd</sup> class). (ii) vertical (P-18/I-19aii)  | 7000/-   | % Sft  | 2100000  |
| 27000 Sft     | 4 Cement Concrete brick or Stone ballast 1 1/2" to 2" gauge ratio 1:4: 8 (P-15/I-4(b))   | 9416/28  | % Cft  | 2542396  |
| 24000 Cft     | 5 Cement concrete plain including placing compacting, finishing and curing, complete (including screening and washing of stone aggregate without shuttering )(h)Ration 1:3:6 (P-16/I-5n)   | 12595/-  | % Cft  | 3022800  |
| 25880 Cft     | 06 Reinforced cement concrete work i/c all labour and material except the cost of steel reinforcement and its labour for its bending & which will be paid separately, this rate also i/c all kinds of forms moulds lifting shuttering curing rendering and finishing the exposed surface i/c Screening and washing of shingle)<br>a) RCC work in roof, slab, beams, column rafts, lintels and other structural members laid in situ or pre-cast laid in position completed in all respects (i) Ratio 1:2:4 90 Lbs cement 2 cft Sand 4 cft Shingle 1/8" to 1/4" gauge (P-16 & 17 / I-6(6i)) | 309/78   | P/Cft. | 8017106  |
| 1155.357 Cwt. | 07 Fabrication of mild steel reinforcement for cement concrete i/c cutting bending, laying in position making joints and fastenings i/c cost of binding wire (also includes removal of (b)using tar bars (P-17 / I-8(b))   | 5001/70  | P/Cwt. | 5778749  |
| 18720 Cft     | 8 Pacca brick work in foundation and plinth in cement sand mortar 1:4 (P-20/I-4(c))  | 12501/41 | % Cft  | 2340264  |
| 115200 Cft    | 9 Pacca brick work other then building including sticking of joints up to 20 ft height in (c) Cement sand mortar Ratio 1:4 (P-22, I-7(c))  | 12899/70 | % Cft  | 14860454 |

|             |       |   |          |        |        |
|-------------|-------|---|----------|--------|--------|
| 36000 Sft   | 10    | Cement Pointing struck joints on Walls<br>(a) ratio 1:2 (P-53/I-19 (a))   | 1287/44  | % Sft  | 463478 |
| 6750 Cft.   | 11    | Cement concrete plain including placing<br>compacting, finishing and curing, complete<br>(including screening and washing at stone<br>aggregate without shuttering).<br>(f)Ration 1:2:4 (P-16/I-5f)   | 14429/25 | %Cft.  | 973974 |
| 225000 Cft. | 12    | Barrow pit excavation undressed lead upto 100' Ft.<br>(a) Ordinary Soil.(P-1 / I-3(a))  | 2117/50  | %0Cft. | 476438 |
| 225000 Cft. | 13    | Carriage of 100 Cft. / 5 tons of all material like tone<br>aggregate spwall coal line Surkhi etc. BG Rails<br>fastening points and crossing Bridges and Girders<br>pipes sheets, rails M.S Bar etc are 1000 Nos. bricks<br>9"x41/2"x3" are 1000 Nos. Tiles 12"x6"x2" are 150<br>Cft. of timber of 1000 mounds of fuel wood by Trucks<br>or any other means owned by Contractor 1- miles.<br>(P-1 / I-1/ schedule of Carriage)   | 407/00   | %Cft.  | 915750 |
| 225000 Cft. | 14    | Earthwork compaction soft ordinary or hard soil<br>(b) laying earth in 6" layers leveling, dressing,<br>watering for compaction etc. complete- 3 / I-<br>13(b)  | 354/00   | %0Cft. | 79650  |
| 128 Day     | 15    | Full hire charge of the pumping set per day<br>inclusive of wage of driver and Assistant fuel or<br>electric energy plate forms required for placing<br>pumps etc at lower depths with suction and<br>delivery pipes for pumping out water found at<br>various depths from trenches including the cost of<br>erection and dismantling after the completion of<br>the<br>(ii) higher charges of pumping set of upto 10 HP<br>out water from 20' depth<br>job.(P-76 / I-23) PHED Schedule | 1500/00  | P/Day  | 192000 |
| 1024 Hrs.   | (iii) | Note:<br>For working the beyond at hours the following<br>payment shall be made. The higher of the<br>pumping set it self being for 24 hours (1) for a<br>pumping set of upto 10 HP<br>trench.(P-77 / I-23) PHED Schedule   | 250/00   | P/Hour | 256000 |

Total Rs. 42652368/-

Note: No Premium will be allowed on item No.13 & 16

915750  
41736618/-  
171120141/-  
Total = 915750/-

Add 4% % above / below

59764382/-

CHECKED.

Divisional Head Draftsman  
Rohri Canal Circle  
Hyderabad

Divisional Head Draftsman  
Rohri Canal Circle  
Hyderabad

G.H.B Construction  
Company

EXECUTIVE ENGINEER,  
ROHRI DIVISION KANDIARO

25

|             |       |   |          |        |        |
|-------------|-------|---|----------|--------|--------|
| 36000 Sft   | 10    | Cement Pointing struck joints on Walls<br>(a) ratio 1:2 (P-53/I-19 (a))   | 1287/44  | % Sft  | 463478 |
| 6750 Cft.   | 11    | Cement concrete plain including placing<br>compacting, finishing and curing, complete<br>(including screening and washing at stone<br>aggregate without shuttering).<br>(f)Ration 1:2:4 (P-16/I-5f)   | 14429/25 | %Cft.  | 973974 |
| 225000 Cft. | 12    | Barrow pit excavation undressed lead upto 100' Ft.<br>(a) Ordinary Soil.(P-1 / I-3(a))  | 2117/50  | %0Cft. | 476438 |
| 225000 Cft. | 13    | Carriage of 100 Cft. / 5 tons of all material like tone<br>aggregate spwall coal line Surkhi etc. BG Rails<br>fastening points and crossing Bridges and Girders<br>pipes sheets, rails M.S Bar etc are 1000 Nos. bricks<br>9"x41/2"x3" are 1000 Nos. Tiles 12"x6"x2" are 150<br>Cft. of timber of 1000 mounds of fuel wood by Trucks<br>or any other means owned by Contractor 1- miles.<br>(P-1 / I-1/ schedule of Carriage)   | 407/00   | %Cft.  | 915750 |
| 225000 Cft. | 14    | Earthwork compaction soft ordinary or hard soil<br>(b) laying earth in 6" layers leveling, dressing,<br>watering for compaction etc. complete- 3 / I-<br>13(b)  | 354/00   | %0Cft. | 79650  |
| 128 Day     | 15    | Full hire charge of the pumping set per day<br>inclusive of wage of driver and Assistant fuel or<br>electric energy plate forms required for placing<br>pumps etc at lower depths with suction and<br>delivery pipes for pumping out water found at<br>various depths from trenches including the cost of<br>erection and dismantling after the completion of<br>the<br>(ii) higher charges of pumping set of upto 10 HP<br>out water from 20' depth<br>job.(P-76 / I-23) PHED Schedule | 1500/00  | P/Day  | 192000 |
| 1024 Hrs.   | (iii) | Note:<br>For working the beyond at hours the following<br>payment shall be made. The higher of the<br>pumping set it self being for 24 hours (1) for a<br>pumping set of upto 10 HP<br>trench.(P-77 / I-23) PHED Schedule   | 250/00   | P/Hour | 256000 |

Total Rs. 42652368/-

Note: No Premium will be allowed on item No.13 & 16

915750  
41736618/-  
171120141/-  
Total = 915750/-

Add 4% % above / below

59764382/-

CHECKED.

Divisional Head Draftsman  
Rohri Canal Circle  
Hyderabad

Divisional Head Draftsman  
Rohri Canal Circle  
Hyderabad

G.H.B Construction  
Company

EXECUTIVE ENGINEER,  
ROHRI DIVISION KANDIARO


25

IN WITNESS WHEREOF the parties hereto have caused this Agreement to be executed on the day, month and year first before written in accordance with their respective laws.

Signature of the Contactor

(Seal) 

Signature of Procuring Agency

(Seal)   
Executive Engineer  
Rohri Division Kandiaro

Signed, Sealed and Delivered in the presence of:

Witness:



AL Hussain & Al Haseeb int'l pr. 33  
(Name, Title and Address)

Witness:

  
Muhammad Jamil Samio  
Divisional Accounts Officer  
Rohri Division Kandiaro

(Name, Title and Address)

House No 218 C  
Gulshan-e-Sijad  
Dist: in Cba Hydwar Cba

**SINDH PUBLIC PROCUREMENT REGULATORY AUTHORITY**  
**CONTRACT EVALUATION FORM**  
**TO BE FILLED IN BY ALL PROCURING AGENCIES FOR PUBLIC WORKS,**  
**SERVICES & GOODS**

|   |  |   |
|---|--|---|
| 1) NAME OF THE ORGANIZATION / DEPTT.  | <b>IRRIGATION DEPARTMENT</b>   |   |
| 2) PROVINCIAL / LOCAL GOVT./ OTHER  | <b>PROVINCIAL</b>  |   |
| 3) TITLE OF CONTRACT  | <b>ADP SCHEME # 1175<br/>FOR YEAR 2014-15</b>                                    |   |
| 4) TENDER NUMBER  | No. TC/G-55/KRO/901, DATE: 06.07.2015 &<br>Corrigendum No. 1078 dated 18.08.2015 |   |
| 5) BRIEF DESCRIPTION OF CONTRACT  | <b>Package # 02</b>  | CONSTRUCTING STONE PITCHING ALONG<br>MEHRABPUR BRANCH FROM RD 29 TO 38<br>BOTH SIDE, RESECTIONING AND EARTH WORK<br>ALONG KANDIARO ESCAPE NO.1 FROM RD 0<br>TO 22 ,REPAIR / RECONSTRUCTION OF<br>COMPOUND WALL OF KANDIARO SUB<br>DIVISION-I & II, CONSTRUCTING RETAINING<br>WALL ALONG KANDIARO ESCAPE NO.1 FROM<br>RD 4 TO 7 L/S. |
| 6) FORUM THAT APPROVED THE SCHEME   | <b>CHIEF ENGINEER SUKKUR BARRAGE LEFT<br/>BANK REGION SUKKUR</b>                 |   |
| 7) TENDER ESTIMATED VALUE   | <b>198421969</b>   |   |
| 8) ENGINEER'S ESTIMATE<br>(For civil works only)  | <b>173628469</b>   |   |
| 9) ESTIMATED COMPLETION PERIOD (AS PER<br>CONTRACT)   | <b>24 Months</b>   |   |
| 10) TENDER OPENED ON (DATE & TIME)  | <b>18-09-2015</b>  |   |
| 11) NUMBER OF TENDER DOCUMENTS SOLD   | <b>03</b>  |   |
| 12) NUMBER OF BIDS RECEIVED   | <b>03</b>  |   |
| 13) NUMBER OF BIDDERS PRESENT AT THE TIME OF<br>OPENING OF BIDS   | <b>03</b>  |   |
| 14) BID EVALUATION REPORT<br>(Enclose a copy)   | <b>(Copy attached)</b>   |   |
| 15) NAME AND ADDRESS OF THE SUCCESSFUL<br>BIDDER  | <b>GHB CONSTRUCTION COMPANY</b>  |   |
| 16) CONTRACT AWARD PRICE  |  |   |
| 17) RANKING OF SUCCESSFUL BIDDER IN<br>EVALUATION REPORT<br>(i.e. 1st, 2nd, 3rd EVALUATION BID).  | GHB Construction Company<br>M/S Mir Muhammad Saryo & Co<br>M/S Jamali & Brothers |   |
| 18) METHOD OF PROCUREMENT USED :- (Tick one)  |  |   |
| a) SINGLE STAGE – ONE ENVELOPE PROCEDURE  | <b>Domestic</b>  | <b>Local</b> <input checked="" type="checkbox"/>  |
| b) SINGLE STAGE – TWO ENVELOPE PROCEDURE  |  | <b>X</b>  |
| c) TWO STAGE BIDDING PROCEDURE  |  | <b>X</b>  |
| d) TWO STAGE – TWO ENVELOPE BIDDING<br>PROCEDURE  |  | <b>X</b>  |
| PLEASE SPECIFY IF ANY OTHER METHOD OF PROCUREMENT WAS ADOPTED i.e.<br>EMERGENCY, DIRECT CONTRACTING /ETC. WITH BRIEF REASONS: BRIEF REASONS |  |   |

19) APPROVING AUTHORITY FOR AWARD OF CONTRACT \_ Chief Engineer Sukkur Barrage left Bank Region Sukkur

20) WHETHER THE PROCUREMENT WAS INCLUDED IN ANNUAL PROCUREMENT PLAN?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

21) ADVERTISEMENT :

i) SPPRA Website  
(If yes, give date and SPPRA Identification No.)

|     |             |
|-----|-------------|
| Yes | S. No 24735 |
| No  |             |

ii) News Papers  
(If yes, give names of newspapers and dates)

|     |  |
|-----|--|
| Yes | Daily Jung, Daily Kawish,<br>Daily Dawn dated 09.07.2015 |
| No  |  |

22) NATURE OF CONTRACT

|                |                                     |      |                          |
|----------------|-------------------------------------|------|--------------------------|
| Domestic/Local | <input checked="" type="checkbox"/> | Int. | <input type="checkbox"/> |
|----------------|-------------------------------------|------|--------------------------|

23) WHETHER QUALIFICATION CRITERIA WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?  
(If yes, enclose a copy)

|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

24) WHETHER BID EVALUATION CRITERIA WAS INCLUDED IN BIDDING / TENDER DOCUMENTS?  
(If yes, enclose a copy)

|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

25) WHETHER APPROVAL OF COMPETENT AUTHORITY WAS OBTAINED FOR USING A METHOD OTHER THAN OPEN COMPETITIVE BIDDING?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

26) WAS BID SECURITY OBTAINED FROM ALL THE BIDDERS?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

27) WHETHER THE SUCCESSFUL BID WAS LOWEST EVALUATED BID / BEST EVALUATED BID (in case of Consultancies)

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

28) WHETHER THE SUCCESSFUL BIDDER WAS TECHNICALLY COMPLIANT?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

29) WHETHER NAMES OF THE BIDDERS AND THEIR QUOTED PRICES WERE READ OUT AT THE TIME OF OPENING OF BIDS?

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

30) WHETHER EVALUATION REPORT GIVEN TO BIDDERS BEFORE THE AWARD OF CONTRACT?  
(Attach copy of the bid evaluation report)

|     |                                     |    |                          |
|-----|-------------------------------------|----|--------------------------|
| Yes | <input checked="" type="checkbox"/> | No | <input type="checkbox"/> |
|-----|-------------------------------------|----|--------------------------|

31) ANY COMPLAINTS RECEIVED  
(If yes, result thereof)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

32) ANY DEVIATION FROM SPECIFICATIONS GIVEN IN THE TENDER NOTICE / DOCUMENTS  
(If yes, give details)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

33) WAS THE EXTENSION MADE IN RESPONSE TIME?  
(If yes, give reasons)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

34) DEVIATION FROM QUALIFICATION CRITERIA  
(If yes, give detailed reasons.)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

35) WAS IT ASSURED BY THE PROCURING AGENCY THAT THE SELECTED FIRM IS NOT  
BLACK LISTED?

|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

36) WAS A VISIT MADE BY ANY OFFICER/OFFICIAL OF THE PROCURING AGENCY TO THE  
SUPPLIER'S PREMISES IN CONNECTION WITH THE PROCUREMENT? IF SO, DETAILS TO  
BE ASCERTAINED REGARDING FINANCING OF VISIT, IF ABROAD:  
(If yes, enclose a copy)

|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

37) WERE PROPER SAFEGUARDS PROVIDED ON MOBILIZATION ADVANCE PAYMENT IN  
THE CONTRACT (BANK GUARANTEE ETC.)?


|     |                          |    |                                     |
|-----|--------------------------|----|-------------------------------------|
| Yes | <input type="checkbox"/> | No | <input checked="" type="checkbox"/> |
|-----|--------------------------|----|-------------------------------------|

38) SPECIAL CONDITIONS, IF ANY  
(If yes, give Brief Description)

|     |   |
|-----|---|
| Yes |   |
| No  | / |

  
Executive Engineer  
Rohri Division Kandiaro  
Signature & Official Stamp of

Authorized Officer, Executive Engineer Rohri Division Kandiaro

  
Muhammad Sami Samio  
Divisional Accounts Officer  
Rohri Division Kandiaro

**FOR OFFICE USE ONLY**

SPPRA, Block No.8, Sindh Secretariat No.4-A, Court Road, Karachi

Tele: 021-9205356; 021-9205369 & Fax: 021-9206291

FORM OF CONTRACT AGREEMENT

THIS CONTRACT AGREEMENT (hereinafter called the "Agreement") made on the 2nd day of October (month) 2015 between Executive Engineer, Robert D. V. O'Brien, Kaua'i (hereafter called the "Procuring Agency") of the one part and G.H.B. Const. Company (hereafter called the "Contractor") of the other part.

WHEREAS the Procuring Agency is desirous that certain works, viz. *Constructing stone P. tch. along Highway 100 from RD 295 to the side of the road*, should be executed by the Contractor and has accepted a bid by the Contractor for the execution and completion of such works and the remedying of any defects therein.

NOW this Agreement witnesseth-- as follows:

1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract hereinafter referred to.
2. The following documents after incorporating addenda, if any, except those parts relating to Instructions to bidders shall be deemed to form and be read and construed as part of this Agreement, viz:
  - (a) The Contract Agreement;
  - (b) The Letter of Acceptance;
  - (c) The completed Form of Bid;
  - (d) Special Stipulations (Appendix-A to Bid);
  - (e) The Special Conditions of Contract – Part II;
  - (f) The General Conditions – Part I;
  - (g) The priced Bill of Quantities (Appendix-D to Bid);
  - (h) The completed Appendices to Bid (B, C, E to L);
  - (i) The Drawings;
  - (j) The Specifications.
  - (k) \_\_\_\_\_ (any other)
3. In consideration of the payments to be made by the procuring agency to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the procuring agency to execute and complete the works and remedy defects therein in conformity and in all respects with the provisions of the contract.
4. Procuring agency hereby covenants to pay the contractor, in consideration of the execution and completion of the works as per provisions of the contract, the contract Price or such other sum as may become payable under the provisions of the contract at the times and in the manner prescribed by the contract.

*Report / Reconst. Kaua'i Irt 2005 IRT Constructing Retention wall along KRO Exp No 2 RD 467*



(INTEGRITY PACT)

DECLARATION OF FEES, COMMISSION AND BROKERAGE ETC; PAYABLE BY CONTRACTORS.

(FOR CONTRACTS WORTH RS. 10.00 MILLION OR MORE)

Contract No. 901 Dated 06-7-2015

Contract Value: 198421969/-

Contract Title: Construction of stone P. fch. ms along Mehrab Div Am RD 29 to 38 10/5  
Resection work along KRO Esplanade from RD 0 to 22 Reps/Account of

G.H.B. Construction Company [name of Contractor] hereby declares that it has not obtained or induced the procurement of any contract, right, interest, privilege or other obligation or benefit from Government of Sindh (GoS) or any administrative subdivision or agency thereof or any other entity owned or controlled by it (GoS) through any corrupt business practice.

*Handwritten notes:*  
Compensation  
KRO Esplanade  
Div. 6.0 RD 1 to 4  
Const Retaining  
Wall along KRO  
Esplanade  
RD 4 to 7

Without limiting the generality of the foregoing, [name of Contractor] represents and warrants that it has fully declared the brokerage, commission, fees etc. paid or payable to anyone and not given or agreed to give and shall not give or agree to give to anyone within or outside Pakistan either directly or indirectly through any natural or juridical person, including its affiliate, agent, associate, broker, consultant, director, promoter, shareholder, sponsor or subsidiary, any commission, gratification, bribe, finder's fee or kickback, whether described as consultation fee or otherwise, with the object of obtaining or inducing the procurement of a contract, right, interest, privilege or other obligation or benefit in whatsoever form from, from Procuring Agency (PA) except that which has been expressly declared pursuant hereto.

[name of Contractor] accepts full responsibility and strict liability that it has made and will make full disclosure of all agreements and arrangements with all persons in respect of or related to the transaction with PA and has not taken any action or will not take any action to circumvent the above declaration, representation or warranty.

[name of Contractor] accepts full responsibility and strict liability for making any false declaration, not making full disclosure, misrepresenting facts or taking any action likely to defeat the purpose of this declaration, representation and warranty. It agrees that any contract, right, interest, privilege or other obligation or benefit obtained or procured as aforesaid shall, without prejudice to any other rights and remedies available to PA under any law, contract or other instrument, be voidable at the option of PA.

Notwithstanding any rights and remedies exercised by PA in this regard, [name of Supplier/Contractor/Consultant] agrees to indemnify PA for any loss or damage incurred by it on account of its corrupt business practices and further pay compensation to PA in an amount equivalent to ten times the sum of any commission, gratification, bribe, finder's fee or kickback given by [name of Contractor] as aforesaid for the purpose of obtaining or inducing the procurement of any contract, right, interest, privilege or other obligation or benefit in whatsoever form from PA.

*Signature*  
[Procuring Agency]  
Rohri Division Kandiaro

[Contractor]  
G.H.B. Construction Company

**OFFICE OF THE EXECUTIVE ENGINEER ROHRI DIVISION KANDIARO.**

No. TC/ G-55 / **1265** of 2015

KandiARO, dated **02 / 10 / 2015.**

To,

M/S G H B CONSTRUCTION  
COMPANY  
E-17/17, AHMED ARCADE, KHAYABN-E-JAMI  
GIZRI ROAD CLIFTON KARACHI.

**LETTER OF COMMENCEMENT /WORK ORDER**

**SUBJECT: CONSTRUCTING STONE PITCHING ALONG MEHRAB PUR BRANCH FROM RD 29 TO 38 BOTH SIDES, RESECTIONING AND EARTH WORK ALONG KANDIARO ESCAPE NO. 1 FROM RD 0 TO 22, REPAIR/RECONSTRUCTION OF COMPOUND WALL KANDIARO IRRIGATION SUB DIVISION-I & II CONSTRUCTING RETAINING WALL ALONG KANDIARO ESCAPE NO 1 FROM RD 4 TO 7 LEFT SIDE.**


**Reference: Your tender dated 16.09.2015**

The rate of Rs. 41.0% above (Rupees Forty One Point zero percent above) on the schedule of price which works out 14.28% above (Rupees Thirteen point ninety percent above) estimate quoted by you through tender has been sanctioned by the Chief Engineer Sukkur Barrage Left Bank Region Sukkur letter No. WB-II/RDK/2015/4-W/5413, dated 30.09.2015 for Rs. **198421969/-**


You are direct to please start the work within three days (under the supervision of Assistant Executive Engineer KandiARO Irrigation Sub Division-I.

Please start: the work should be carried out strictly according PWD specification and should be completed in stipulated period.

The time for completion of work is (24 Months).

  
EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO

Copy with schedule price forwarded to Assistant Executive Engineer KandiARO Irrigation Sub Division-I for information and necessary action. He is directed to report the actual date of start as well as the progress of work and see that the work should be completed within stipulated period.

  
EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO

ADP # 1175  
Part (A)

**Name of Work:- CONSTRUCTING STONE PITCHING ALONG MEHRABPUR BRANCH  
FROM RD 29+0 TO 38+0 BOTH SIDES.**

**SCHEDULE "A TO BID"**

| Quantity  | Item of work  | Rate     | Unit  | Amount     |
|-----------|---|----------|-------|------------|
| 7860 Cft  | 1 Excavation in foundation of building bridges and other structures including dagbelling dressing rifling around structure with excavated earth watering and ramming lead up to 5 ft. (b) in ordinary soil (P-4/I-18-b) | 3176/25  | % Cft | 1740140    |
| 7860 cft  | 2 Rehandling of earth work<br>(a) lead up to a shingle throw of kassi, Phawrsh or a Shovel<br>(b) Up to a lead of 50 ft (P-2/I-9-b)   | 1058/75  | % Cft | 580047/-   |
| 62000 Cft | 3 Stone filling dry hand packed as filling behind retaining walls or in pitching and apron. (P-31/I-16)   | 2684/-   | % Cft | 4348080/-  |
| 7200 cft  | 4 Coursed rubble masonry hammer dressed. (d) In cement sand mortar, Ratio 1:6 (P-28/I-4diii)  | 26288/46 | % Cft | 4921200/-  |
| 6640 Sft  | 5 Formation dressing and preparing sub grade on slopes (b) on slopes (P-74/I-1 b)   | 453/75   | % Sft | 1182654/-  |
| 480 Cft   | 6 Stone pitching including sub base with hammer dressed stone on surface laid in courses including carriage of material. (P-32/I-23)  | 5377/63  | % Cft | 17771992/- |
| 6000 Sft  | 7 Erection and removal of centering for RCC or plain cement concrete works of Deodar wood (2 <sup>nd</sup> class) (b) (ii) vertical (P-18/I-19b ii)   | 7000/-   | % Sft | 1260000/-  |
| 6000 Cft  | 8 Cement concrete plain including placing compacting finishing and curing complete (including screening and washing of stone aggregate without shuttering (f) Ratio 1:2:4) (P-16/I-5)                                   | 14429/25 | % Cft | 2597265/-  |

Total Rs. 34401378/-

Add: 41.0% above/below

14104565/-

Total = 48505943/-

Divisional Head Draftsman  
Rohri Division Kandiaro

CHECKED

HEAD DRAFTSMAN  
CIRCULAR  
HYDERABAD

Circle Head Draftsman  
Sukkur Barrage Left Bank Region  
Sukkur

G.H.B Construction  
Company

EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO

**OFFICE OF THE EXECUTIVE ENGINEER ROHRI DIVISION KANDIARO**

No. TC/G-55/ 438 of 2016

Kandiaro, dated 27/04 /2016.

To,

*The Managing Director  
Sindh Public Procurement Regulatory Authority  
Karachi.*

**SUBJECT: SUBMISSION OF WORK AWARD AND CONTRACT EVOLUTION FORM.**

It is submitted that after completion of all codel formalities the related documents such as the contract evolution form including work award, BOQ agreement as per rule-50 of SPPRA 2010 (amended 2013) and integrity pact are submitted here with for favour of further hoisting on web site, SPPRA Sr. No. 24735.

This is for favour of kind information.

D.A/as above

  
EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO

Copy forwarded for information to:-

- 1- The Chief Engineer Sukkur Barrage Left Bank Region Sukkur for favour of kind information.
- 2- The Superintending Engineer Rohri Canal Circle Hyderabad for favour of kind information.

  
EXECUTIVE ENGINEER  
ROHRI DIVISION KANDIARO

# **BID EVALUATION REPORT**

**EXECUTIVE ENGINEER ROHRI DIVISION KANDIARO**

1. Name of Procuring Agency:

2. Tender Reference No:

No. TC/G-55/KRO/901, DATE: 06.07.2015 & Corrigendum  
No. 1078 dated 18.08.2015

3. Tender Description/Name of work/item:

CONSTRUCTING STONE PITCHING ALONG MEHRABPUR  
BRANCH FROM RD 29 TO 38 BOTH SIDE, RESECTIONING AND  
EARTH WORK ALONG KANDIARO ESCAPE NO.1 FROM RD 0  
TO 22 ,REPAIR / RECONSTRUCTION OF COMPOUND WALL OF  
KANDIARO SUB DIVISION-I & II, CONSTRUCTING RETAINING  
WALL ALONG KANDIARO ESCAPE NO.1 FROM RD 4 TO 7 L/S.  
(ADP # 1175).

4. Method of Procurement:

**National Competitive Bidding**

(Single stage one Envelope procedure)

5. Tender Published:

The NIT was published in the following SPPRA web  
site & newspapers.  
SPPRA Sr. No. 24735, Daily Jung Karachi, Daily Kawish  
Hyderabad, Daily Dawn, dated 09.07.2015 & Corrigendum  
published in Daily Dawn & Daily Jung dated 24.08.2015

6. Total Bid documents Sold;

**03 Nos**

7. Total Bids Received:

**03 Nos**

8. Technical Bid Opening date: (if applicable) \_\_\_\_\_ **N/A** \_\_\_\_\_

(Provide details in separate form)

9. No. of Bid technically qualified (if applicable): \_\_\_\_\_ **N/A** \_\_\_\_\_


10. Bid(s) Rejected: \_\_\_\_\_ **NIL** \_\_\_\_\_


11. Financial Bid Opening date: \_\_\_\_\_ **18/09/2015** \_\_\_\_\_

## **12. Bid Evaluation Report:**


| S No | Name of Firm or Bidder      | Cost offered by the Bidder | Ranking in terms of cost | Comparison with Estimated cost | Reasons for acceptance/rejection    | Remarks   |
|------|-----------------------------|----------------------------|--------------------------|--------------------------------|-------------------------------------|---|
| 1    | GHB Construction Company    | 198421969                  | 1 <sup>st</sup> Lowest   | 14.28%                         | 1 <sup>st</sup> Lowest (Responsive) | Accepted being 1 <sup>st</sup> Lowest and recommended for award of work |
| 2    | M/S Mir Muhammad Saryo & Co | 203634866                  | 2 <sup>nd</sup> Lowest   | 17.28%                         | Highest (Responsive)                | Highest   |
| 3    | M/S Jamali & Brothers       | 204436850                  | 3 <sup>rd</sup> Lowest   | 17.74%                         | Highest                             | Highest   |


*Signature of members of committee.*

  
**(Niaz Ahmed Memon)**  
Executive Engineer,  
Rohri Division Kandiaro  
(Member)

  
**Imtiaz Ahmed Memon**  
Executive Engineer,  
Rohri Division Moro  
(Member)

  
**Ahmed Ali Jatoi**  
Executive Engineer,  
High Division N-Feroze  
(Member)

  
**(Muhammad Ismail Samtio)**  
Divisional Account Officer  
Rohri Division Kandiaro  
(Member)

  
**(Syed Sardar Ali Shah)**  
Superintending Engineer  
Rohri Canal Circle Hyderabad  
(Chairman)

# **BID EVALUATION REPORT**

1. Name of Procuring Agency:

**EXECUTIVE ENGINEER ROHRI DIVISION KANDIARO**

2. Tender Reference No:

No. TC/G-55/KRO/901, DATE: 06.07.2015 & Corrigendum 1078 dated 18.08.2015

3. Tender Description/Name of work/item:

**CONSTRUCTING STONE PITCHING ALONG SEHRA BRANCH FROM RD 21 TO 23 BOTH SIDE 27 TO 29 NIP AND 36+500 TO 40 NIP SIDE, CONSTRUCTING VILLAGE ROAD BRIDGE ALONG SEHRA BRANCH AT RD 30, CONSTRUCTING RETAINING WALL ALONG SEHRA BRANCH RD 4 TO 7 B/S. (ADP # 1175).**

4. Method of Procurement:

**National Competitive Bidding**  
**(Single stage one Envelope procedure)**

5. Tender Published:

The NIT was published in the following SPPRA web site & newspapers.  
SPPRA Sr. No. 24735, Daily Jung Karachi, Daily Kawish Hyderabad, Daily Dawn, dated 09.07.2015 & Corrigendum published in Daily Dawn & Daily Jung dated 24.08.2015

6. Total Bid documents Sold:

**03 Nos**

7. Total Bids Received:

**03 Nos**

8. Technical Bid Opening date: (if applicable)

**N/A**

(Provide details in separate form)

9. No. of Bid technically qualified (if applicable):

**N/A**

10. Bid(s) Rejected:

**NIL**


11. Financial Bid Opening date:


**18/09/2015**


## **12. Bid Evaluation Report:**


| S No | Name of Firm or Bidder      | Cost offered by the Bidder | Ranking in terms of cost | Comparison with Estimated cost | Reasons for acceptance/rejection    | Remarks   |
|------|-----------------------------|----------------------------|--------------------------|--------------------------------|-------------------------------------|---|
| 1    | GHB Construction Company    | 147902144                  | 1 <sup>st</sup> Lowest   | 13.90%                         | 1 <sup>st</sup> Lowest (Responsive) | Accepted being 1 <sup>st</sup> Lowest and recommended for award of work |
| 2    | M/S Mir Muhammad Saryo & Co | 148222485                  | 2 <sup>nd</sup> Lowest   | 14.14%                         | Highest (Responsive)                | Highest   |
| 3    | M/S Jamali & Brothers       | 148740682                  | 3 <sup>rd</sup> Lowest   | 14.54%                         | Highest (Responsive)                | Highest   |


*Signature of members of committee.*

  
**(Niaz Ahmed Memon)**  
Executive Engineer,  
Rohri Division Kandiaro  
**(Member)**

  
**Imtiaz Ahmed Memon**  
Executive Engineer,  
Rohri Division Moro  
**(Member)**

  
**(Umed Ali Jatoi)**  
Executive Engineer,  
High Division N-Feroze  
**(Member)**

  
**(Muhammad Ismail Samtio)**  
Divisional Account Officer  
Rohri Division Kandiaro  
**(Member)**

  
**(Syed Sardar Ali Shah)**  
Superintending Engineer  
Rohri Canal Circle Hyderabad  
**(Chairman)**



**OFFICE OF THE EXECUTIVE ENGINEER ROHRI DIVISION KANDIARO.**

No. TC/G-55/KRO/ 901, of 2015 Kandiaro Dated 06.07.2015 & Corrigendum No. TC/G-55/1078 Dated 18.08.2015.

**MINUTES OF BID OPENING MEETING.**

A meeting of the procurement committee of this department has held on 18.09.2015 for opening the bids in respect of subjected NIT but (Chairman of Procurement Committee is out of head quarter on 17.09.2015 hence opened next working day 18.09.2015 as per SPPRA rules) Bids received back till the deadlines of submission i.e. 14:00 hours and opened at 15:00 hours on 18.09.2015. The meeting was attended by all/ following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

1. Superintending Engineer  
Rohri Canal Circle Hyderabad (Chairman)
2. Executive Engineer,  
Rohri Division,  
Kandiaro (Member).
3. Executive Engineer,  
Rohri Division,  
Moro. (Member)
4. Executive Engineer  
Highway Division  
Naushahro Feroze. (Member)
5. Divisional Accounts Officer  
Rohri Division kandiaro. (Member)

The following bidders purchased & submitted their bids till the deadline of submission:

- 1) GHB Construction Company
- 2) M/S Mir Muhammad Saryo & Co
- 3) M/S Jamali & Brothers

The bids were opened at 15:00 hours in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of Procurement Committee. All the members of the procurement committee signed each and every page of financial proposal/ bids. The bids do not contain any over-writing or cutting. (Also mention cuttings or over writing if any). Following is the details of bids announced:

1. **NAME OF WORK:** CONSTRUCTING STONE PITCHING ALONG SEHRA BRANCH FROM RD 21 TO 23 BOTH SIDE 27 TO 29 NIP AND 36+500 TO 40 NIP SIDE, CONSTRUCTING VILLAGE ROAD BRIDGE ALONG SEHRA BRANCH AT RD 30, CONSTRUCTING RETAINING WALL ALONG SEHRA BRANCH RD 4 TO 7 B/S.

| S.No | Name of Bidder                  | Offered Price | Amount of Bid Security | Call Deposit No./ Date                       |
|------|---------------------------------|---------------|------------------------|--|
| 01.  | i. GHB Construction Company     | 147902144     | 2600000/-              | CD No. 5266678, dated 16.09.2015 UBL Halani  |
| 02.  | ii. M/S Mir Muhammad Saryo & Co | 148222485     | 2608000/-              | CD No. 5266674, dated 16.09.2015 UBL Halani. |
| 03.  | iii. M/S Jamali & Brothers      | 148740682     | 2604000/-              | CD No. 5266676, dated 16.09.2015 UBL Halani  |


2. **NAME OF WORK:** CONSTRUCTING STONE PITCHING ALONG MEHRABPUR BRANCH FROM RD 29 TO 38 BOTH SIDE, RESECTIONING AND EARTH WORK ALONG KANDIARO ESCAPE NO.1 FROM RD 0 TO 22 ,REPAIR / RECONSTRUCTION OF COMPOUND WALL OF KANDIARO SUB DIVISION-I & II, CONSTRUCTING RETAINING WALL ALONG KANDIARO ESCAPE NO.1 FROM RD 4 TO 7 L/S.


| S.No | Name of Bidder                  | Offered Price | Amount of Bid Security | Pay Order No./ Date                         |
|------|---------------------------------|---------------|------------------------|---|
| 01   | i. GHB Construction Company     | 198421969     | 3600000/-              | CD No. 5266677, dated 16.09.2015 UBL Halani |
| 02   | ii. M/S Mir Muhammad Saryo & Co | 203634866     | 3610000/-              | CD No. 5266673, dated 16.09.2015 UBL Halani |
| 03   | iii. M/S Jamali & Brothers      | 204436850     | 3605000/-              | CD No. 5266675, dated 16.09.2015 UBL Halani |


The committee shall examine all the bids as per the Qualification/ eligibility criteria provided in the bidding documents, arithmetical checks and verify the documents and bid security submitted by the bidders.


The meeting ended with the note of thanks to and from the chair.

  
(NIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION KANDIARO  
(MEMBER)

  
(NIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION MORO  
(MEMBER)

  
(AHMED ALI JATOI)  
EXECUTIVE ENGINEER,  
PROVINCIAL HIGHWAY DIVISION  
NAUSHAHRO FEROZE.  
(MEMBER)

  
(MUHAMMAD ISMAIL SAMTJO)  
DIVISIONAL ACCOUNTS OFFICER,  
ROHRI DIVISION KANDIARO.  
(MEMBER)

  
(SYED SARDAR ALI SHAH)  
SUPERINTENDING ENGINEER,  
ROHRI CANAL CIRCLE, HYDERABAD  
(CHAIRMAN)





**COMPARATIVE STATEMENT**  
**GOVERNMENT OF SINDH**


**IRRIGATION DEPARTMENT**


TENDER INVITED PRE-QUALIFICATION CONTRACTORS VIDE EXECUTIVE ENGINEER ROHRI DIVISION KANDIARO OFFICE, NO: No. TC/G-55/KRO/ 901, OF 2015 KANDIARO DATED 06.07.2015 & CORRIGENDUM NO. TC/G-55/1078 DATED 18.08.2015.


**NAME OF WORK: CONSTRUCTING STONE PITCHING ALONG SEHRA BRANCH FROM RD 21 TO 23 BOTH SIDE 27 TO 29 NIP AND 36+500 TO 40 NIP SIDE, CONSTRUCTING VILLAGE ROAD BRIDGE ALONG SEHRA BRANCH AT RD 30, CONSTRUCTING RETAINING WALL ALONG SEHRA BRANCH RD 4 TO 7 B/S. (Scheme # 1175)**


| S.No | Name of Contractor          | Date of Receipt of Sealed Bid/Tender | Percentage rate entered in contract documents | Remarks                                     |
|------|-----------------------------|--------------------------------------|---|---|
| 1.   | GHB Construction Company    | 18.09.2015                           | 55.56%  | CD No. 5266678, dated 16.09.2015 UBL Halani |
| 2.   | M/S Mir Muhammad Saryo & Co | 18.09.2015                           | 55.90%  | CD No. 5266674, dated 16.09.2015 UBL Halani |
| 3.   | M/S Jamali & Brothers       | 18.09.2015                           | 56.45%  | CD No. 5266676, dated 16.09.2015 UBL Halani |


The tenders were open by the tendering committee comprised of the officers as below.

  
(NIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION KANDIARO  
(MEMBER)

  
(IMTIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION MORO  
(MEMBER)

  
(AHMED ALI JATOI)  
EXECUTIVE ENGINEER,  
HIGHWAY DIVISION  
NAUSHAHRO FEROZE.  
(MEMBER)

  
(MUHAMMAD ISMAIL SAMTIO)  
DIVISIONAL ACCOUNTS OFFICER,  
ROHRI DIVISION KANDIARO.  
(MEMBER)

  
(SYED SARDAR ALI SHAH)  
SUPERINTENDING ENGINEER,  
ROHRI CANAL CIRCLE, HYDERABAD  
(CHAIRMAN)



**COMPARATIVE STATEMENT**  
**GOVERNMENT OF SINDH**


**IRRIGATION DEPARTMENT**


TENDER INVITED PRE-QUALIFICATION CONTRACTORS VIDE EXECUTIVE ENGINEER ROHRI DIVISION KANDIARO OFFICE, NO. TC/G-55/KRO/ 901, OF 2015 KANDIARO DATED 06.07.2015 & CORRIGENDUM NO. TC/G-55/1078 DATED 18.08.2015.


**NAME OF WORK:** CONSTRUCTING STONE PITCHING ALONG MEHRABPUR BRANCH FROM RD 29 TO 38 BOTH SIDE, RESECTIONING AND EARTH WORK ALONG KANDIARO ESCAPE NO.1 FROM RD 0 TO 22 ,REPAIR / RECONSTRUCTION OF COMPOUND WALL OF KANDIARO SUB DIVISION-I & II, CONSTRUCTING RETAINING WALL ALONG KANDIARO ESCAPE NO.1 FROM RD 4 TO 7 L/S. (Scheme # 1175)


| S.No | Name of Contractor          | Date of Receipt of Sealed Bid/Tender | Percentage rate entered in contract documents | Remarks                                     |
|------|-----------------------------|--------------------------------------|---|---|
| 1.   | GHB Construction Company    | 18.09.2015                           | 41%   | CD No. 5266677, dated 16.09.2015 UBL Halani |
| 2.   | M/S Mir Muhammad Saryo & Co | 18.09.2015                           | 44.90%  | CD No. 5266673, dated 16.09.2015 UBL Halani |
| 3.   | M/S Jamali & Brothers       | 18.09.2015                           | 45.50%  | CD No. 5266675, dated 16.09.2015 UBL Halani |


The tenders were open by the tendering committee comprised of the officers as below.

  
(NIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION KANDIARO  
(MEMBER)

  
(IMTIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION MORO  
(MEMBER)

  
(UMMED ALI JATOI)  
EXECUTIVE ENGINEER,  
HIGHWAY DIVISION  
NAUSHAHRO FEROZE.  
(MEMBER)

  
(MUHAMMAD ISMAIL SAMTLO)  
DIVISIONAL ACCOUNTS OFFICER,  
ROHRI DIVISION KANDIARO.  
(MEMBER)

  
(SYED SARDAR ALI SHAH)  
SUPERINTENDING ENGINEER,  
ROHRI CANAL CIRCLE, HYDERABAD  
(CHAIRMAN)

Method and procedure of procurement Open Competitive Bidding (National Competitive Bidding) (Single stage one Envelope)


**Description of work:** CONSTRUCTING STONE PITCHING ALONG MEHRABPUR BRANCH FROM RD 29 TO 38 BOTH SIDE, RESECTIONING AND EARTH WORK ALONG KANDIARO ESCAPE NO.1 FROM RD 0 TO 22 ,REPAIR / RECONSTRUCTION OF COMPOUND WALL OF KANDIARO SUB DIVISION-I & II, CONSTRUCTING RETAINING WALL ALONG KANDIARO ESCAPE NO.1 FROM RD 4 TO 7 L/S. (ADP # 1175)


**BIDDER ELIGIBILITY / QUALIFICATION REPORT**


**Eligibility Qualification Criteria**


| S.No | Eligibility Qualification Criteria                                    | GHB Construction Company | M/S Mir Muhammad Saryo & Co | M/S Jamali & Brothers |
|------|---|--------------------------|-----------------------------|-----------------------|
| 01   | Registration with PEC   | Yes                      | Yes                         | Yes ( below limit)    |
| 02   | NTN   | Yes                      | Yes                         | Yes                   |
| 03   | Sale Tax Registration   | Yes                      | Yes                         | Yes                   |
| 04   | Professional Tax  | Yes                      | Yes                         | Yes                   |
| 05   | Minimum three years experience of relevant field                      | Yes                      | Yes                         | Yes                   |
| 06   | Turnover of at least last three years                                 | Yes                      | Yes                         | Yes                   |
| 07   | Required Bid security is attached                                     | Yes                      | Yes                         | Yes                   |
| 08   | Bid is signed named and stamped by the authorized person of the firm. | Yes                      | Yes                         | Yes                   |
| 09   | Qualified/disqualified  | Qualified                | Qualified                   | Disqualified          |

  
**(NIAZ AHMED MEMON)**  
 EXECUTIVE ENGINEER,  
 ROHRI DIVISION KANDIARO  
**(MEMBER)**

  
**(IMTIAZ AHMED MEMON)**  
 EXECUTIVE ENGINEER,  
 ROHRI DIVISION MORO  
**(MEMBER)**

  
**(UMMED ALI JATOI)**  
 EXECUTIVE ENGINEER,  
 HIGHWAY DIVISION  
 NAUSHAHRO FEROZE.  
**(MEMBER)**

  
**(MUHAMMAD ISMAIL SAMTIO)**  
 DIVISIONAL ACCOUNTS OFFICER,  
 ROHRI DIVISION KANDIARO.  
**(MEMBER)**

  
**(SYED SARDAR ALI SHAH)**  
 SUPERINTENDING ENGINEER,  
 ROHRI CANAL CIRCLE, HYDERABAD  
**(CHAIRMAN)**


Method and procedure of procurement Open Competitive Bidding (National Competitive Bidding) (Single stage one Envelope)


**Description of work: CONSTRUCTING STONE PITCHING ALONG SEHRA BRANCH FROM RD 21 TO 23 BOTH SIDE 27 TO 29 NIP AND 36+500 TO 40 NIP SIDE, CONSTRUCTING VILLAGE ROAD BRIDGE ALONG SEHRA BRANCH AT RD 30, CONSTRUCTING RETAINING WALL ALONG SEHRA BRANCH RD 4 TO 7 B/S, (ADP # 1175)**


**BIDDER ELIGIBILITY / QUALIFICATION REPORT**


**Eligibility Qualification Criteria**


| S.No | Eligibility Qualification Criteria                                    | GHB Construction Company | M/S Mir Muhammad Saryo & Co | M/S Jamali & Brothers |
|------|---|--------------------------|-----------------------------|-----------------------|
| 01   | Registration with PEC   | Yes                      | Yes                         | Yes                   |
| 02   | NTN   | Yes                      | Yes                         | Yes                   |
| 03   | Sale Tax Registration   | Yes                      | Yes                         | Yes                   |
| 04   | Professional Tax  | Yes                      | Yes                         | Yes                   |
| 05   | Minimum three years experience of relevant field                      | Yes                      | Yes                         | Yes                   |
| 06   | Turnover of at least last three years                                 | Yes                      | Yes                         | Yes                   |
| 07   | Required Bid security is attached                                     | Yes                      | Yes                         | Yes                   |
| 08   | Bid is signed named and stamped by the authorized person of the firm. | Yes                      | Yes                         | Yes                   |
| 09   | Qualified/disqualified  | Qualified                | Qualified                   | Qualified             |

  
(NIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION KANDIARO  
(MEMBER)

  
(IMTIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION MORO  
(MEMBER)

  
(UMMED ALI JATOI)  
EXECUTIVE ENGINEER,  
HIGHWAY DIVISION  
NAUSHAHRO FEROZE.  
(MEMBER)




  
(MUHAMMAD ISMAIL SAMTIO)  
DIVISIONAL ACCOUNTS OFFICER,  
ROHRI DIVISION KANDIARO.  
(MEMBER)


  
(SYED SARDAR ALI SHAH)  
SUPERINTENDING ENGINEER,  
ROHRI CANAL CIRCLE, HYDERABAD  
(CHAIRMAN)


## ATTENDANCE SHEET


We the undersigned Contractors/Firms do here by state that the Standard Bidding Documents complete in all respects forms for the below mentioned work have been issue to us Executive Engineer Rohri Division Kandiaro on dated 16.09.2015 with instruction to drop before tendering committee after filling rates for opening in the office Executive Engineer Rohri Division Kandiaro on 17.09.2015, as the Chairman of committee is on leave hence opened on next day 18.09.2015.


**NAME OF WORK:** - CONSTRUCTING STONE PITCHING ALONG SEHRA BRANCH FROM RD 21 TO 23 BOTH SIDE 27 TO 29 NIP AND 36+500 TO 40 NIP SIDE, CONSTRUCTING VILLAGE ROAD BRIDGE ALONG SEHRA BRANCH AT RD 30, CONSTRUCTING RETAINING WALL ALONG SEHRA BRANCH RD 4 TO 7 B/S.


| S# | Name of Contractor/Firm     | Signature of contractor/Firm  |
|----|-----------------------------|---|
| 1  | GHB Construction Company    |   |
| 2  | M/S Mir Muhammad Saryo & Co |  |
| 3  | M/S Jamali & Brothers       |  |

  
(NIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION KANDIARO  
(MEMBER)

  
(IMTIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION MORO  
(MEMBER)

  
(USAID ALI JATOI)  
EXECUTIVE ENGINEER,  
PROVINCIAL HIGHWAY DIVISION  
NAUSHAHRO FEROZE.  
(MEMBER)

  
(MUHAMMAD ISMAIL SAMIO)  
DIVISIONAL ACCOUNTS OFFICER,  
ROHRI DIVISION KANDIARO.  
(MEMBER)

  
(SYED SARDAR ALI SHAH)  
SUPERINTENDING ENGINEER,  
ROHRI CANAL CIRCLE, HYDERABAD  
(CHAIRMAN)




# ATTENDANCE SHEET

Scheme # 1175


Package # 02


We the undersigned Contractors/Firms do here by state that the Standard Bidding Documents complete in all respects forms for the below mentioned work have been issue to us Executive Engineer Rohri Division Kandiaro on dated 16.09.2015 with instruction to drop before tendering committee after filling rates for opening in the office Executive Engineer Rohri Division Kandiaro on 17.09.2015, as the Chairman of committee is on leave hence opened on next day 18.09.2015.


**NAME OF WORK:** - CONSTRUCTING STONE PITCHING ALONG MEHRABPUR BRANCH FROM RD 29 TO 38 BOTH SIDE, RESECTIONING AND EARTH WORK ALONG KANDIARO ESCAPE NO.1 FROM RD 0 TO 22 ,REPAIR / RECONSTRUCTION OF COMPOUND WALL OF KANDIARO SUB DIVISION-I & II, CONSTRUCTING RETAINING WALL ALONG KANDIARO ESCAPE NO.1 FROM RD 4 TO 7 L/S.


| S# | Name of Contractor/Firm     | Signature of contractor/Firm  |
|----|-----------------------------|---|
| 1  | GHB Construction Company    |   |
| 2  | M/S Mir Muhammad Saryo & Co |  |
| 3  | M/S Jamali & Brothers       |  |

  
(NIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION KANDIARO  
(MEMBER)

  
(IMTIAZ AHMED MEMON)  
EXECUTIVE ENGINEER,  
ROHRI DIVISION MORO  
(MEMBER)


  
(USaid ALI JATOL)  
EXECUTIVE ENGINEER,  
PROVINCIAL HIGHWAY DIVISION  
NAUSHAHRO FEROZE.  
(MEMBER)

  
(MUHAMMAD ISMAIL SAMTIO)  
DIVISIONAL ACCOUNTS OFFICER,  
ROHRI DIVISION KANDIARO.  
(MEMBER)

  
(SYED SARDAR ALI SHAH)  
SUPERINTENDING ENGINEER,  
ROHRI CANAL CIRCLE, HYDERABAD  
(CHAIRMAN)

**PROCUREMENT PLAN (Development/Capital)  
OFFICE OF THE EXECUTIVE ENGINEER ROHRI DIVISION KANDIARO  
FOR THE YEAR OF 2015 -16**

| P. No/<br>ADP No. | Name of Scheme & Estimated Cost  | Allocated<br>Funds | Cost of ongoing<br>works<br>(Expenditure<br>already<br>incurred) | Funds<br>earmarked<br>for ongoing<br>works | Cost of New<br>Works | Funds for New<br>Works (c-e) | Nature of<br>Procurement | Method of<br>Procurement         | Anticipated/<br>Actual Date of<br>Advertisement | Anticipated/<br>Actual Date of<br>Start | Anticipated/<br>Actual Date of<br>Completion |
|-------------------|--|--------------------|--|--|----------------------|------------------------------|--------------------------|----------------------------------|---|---|--|
| a                 | b  | c                  | d  | e  | f                    | g                            | h                        | i                                | j   | k                                       | l  |
| ADP #<br>1175     | CONSTRUCTING STONE PITCHING ALONG SEHRA BRANCH FROM RD 21 TO 23 BOTH SIDE 27 TO 29 NIP AND 36+500 TO 40 NIP SIDE,  |                    |  |  |                      |                              |                          |                                  |   |   |  |
| ADP #<br>755      | CONSTRUCTING VILLAGE ROAD BRIDGE ALONG SEHRA BRANCH AT RD 30, CONSTRUCTING RETAINING WALL ALONG SEHRA BRANCH RD 4 TO 7 B/S, CONSTRUCTING STONE PITCHING ALONG MEHRABPUR BRANCH FROM RD 29 TO 38 BOTH SIDE, RESECTIONING AND EARTH WORK ALONG KANDIARO ESCAPE NO.1 FROM RD 0 TO 22 ,REPAIR / RECONSTRUCTION OF COMPOUND WALL OF KANDIARO SUB DIVISION-I & II, CONSTRUCTING RETAINING WALL ALONG KANDIARO ESCAPE NO.1 FROM RD 4 TO 7 L/S |                    |  |  |                      |                              |                          |                                  |   |   |  |
| P# (i)            | CONSTRUCTING STONE PITCHING ALONG SEHRA BRANCH FROM RD 21 TO 23 BOTH SIDE 27 TO 29 NIP AND 36+500 TO 40 NIP SIDE, CONSTRUCTING VILLAGE ROAD BRIDGE ALONG SEHRA BRANCH AT RD 30, CONSTRUCTING RETAINING WALL ALONG SEHRA BRANCH RD 4 TO 7 B/S.  | 50.00              |  |  |                      |                              | NCB                      | Single Stage one envelope method | 18.08.2015                                      | 26.09.2015                              | 25.09.2017<br>(24 Months)                    |
| P# (ii)           | CONSTRUCTING STONE PITCHING ALONG MEHRABPUR BRANCH FROM RD 29 TO 38 BOTH SIDE, RESECTIONING AND EARTH WORK ALONG KANDIARO ESCAPE NO.1 FROM RD 0 TO 22 ,REPAIR / RECONSTRUCTION OF COMPOUND WALL OF KANDIARO SUB DIVISION-I & II, CONSTRUCTING RETAINING WALL ALONG KANDIARO ESCAPE NO.1 FROM RD 4 TO 7 L/S.  |                    |  |  |                      |                              |                          |                                  |   |   |  |

  
 EXECUTIVE ENGINEER  
 ROHRI DIVISION KANDIARO