





# KARACHI WATER & SEWERAGE BOARD

## OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

### BID EVALUATION REPORT


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.33397 I.D No. _____
3	Tender Description/Name of Work/Item:	<b>CLEANING OF 33" DIA MAIN SEWERAGE LINE THROUGH WINCHING MACHINE FROM GUJJAR NALLAH TOWARDS TOWN PLAZA SECTOR 11-E FOR IMPROVEMENT OF SEWERAGE SYSTEM OF NORTH KARACHI</b>
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>Through SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>2 Nos</u>
7	Total Bid Received:	<u>2 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>NIL</u>
11	Financial Bid Opening Date:	05-06-2017

### 12 BID EVALUATION REPORT


S #	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Samu Associates	Rs.9,95,383/-	1 <sup>st</sup> Lowest	@0.087% Below	Pay Order and required documents are available. P.O # 18031667 dt:05-06-2017 Rs.20,000/-from HBL Sindh Secretariat Branch Karachi	Substantially Responsive
2	M/s.Mehboob Enterprises	Rs.9,98,082/-	2 <sup>nd</sup> Lowest	@0.184% Above	Pay Order and required documents are available. P.O # 17909258 dt:25-05-2017 Rs.20,000/-from HBL Taimuria Market Branch Karachi	Substantially Responsive


The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Samu Associates** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

  
(Arshad Ali)  
D.A.O (District Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

NIT No. SPPRA Serial No.33397

Method of Procurement: Single Stage Single Envelope.

Name of Work: CLEANING OF 33" DIA MAIN SEWERAGE LINE THROUGH WINCHING MACHINE FROM GUJJAR NALLAH TOWARDS TOWN PLAZA SECTOR 11-E FOR IMPROVEMENT OF SEWERAGE SYSTEM OF NORTH KARACHI

MINUTES OF BID OPENING MEETING.


A meeting of the procurement committee of this department was held on 05-06-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. (Attendance sheet is enclosed).

2. Two bidders submitted their bids till the deadline of submission.
  - i. M/s. Samu Associates
  - ii. M/s. Mehboob Enterprises
3. The bids were opened at 12:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.


S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Samu Associates	Rs.9,95,381/-	Rs.20,000/-	P.O # 18031667 dt:05-06-2017 from HBL Sindh Secretariat Branch Karachi
02	M/s.Mehboob Enterprises	Rs.9,98,079/-	Rs.20,000/-	P.O # 17909258 dt:25-05-2017 from HBL Taimuria Market Branch Karachi


4. The bids do not contain any cutting or over-writing.
5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.

  
(Arshad Ali)  
D.A.O (District Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)

Description of work: CLEANING OF 33" DIA MAIN SEWERAGE LINE THROUGH WINCHING MACHINE FROM GUJJAR NALLAH TOWARDS TOWN PLAZA SECTOR 11-E FOR IMPROVEMENT OF SEWERAGE SYSTEM OF NORTH KARACHI

Date of Opening: 05-06-2017


**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**


Eligibility/ Qualification Criteria:


S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.Samu Associates	M/s.Mehboob Enterprises
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	<b>Qualification Criteria:</b>		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified

  
 (Arshad Ali)  
 D.A.O (District Central)  
 Member / Secretary

  
 (Saif-ul-Haque)  
 Additional Director Internal  
 Audit – KMC Member

  
 (Maqsood Ahmed Shaikh)  
 Superintending Engineer (KMC)  
 Member

  
 (Ghulam Muhammad Hub)  
 S.E (District Central-A)  
 Member

  
 (Saleem Ahmed)  
 Director (Design & Estimate)  
 Convener

## COMPARATIVE STATEMENT

**Name of Work: CLEANING OF 33" DIA MAIN SEWERAGE LINE THROUGH WINCHING MACHINE FROM GUJJAR NALLAH TOWARDS TOWN PLAZA SECTOR 11-E FOR IMPROVEMENT OF SEWERAGE SYSTEM OF NORTH KARACHI**

Item No	Description of Work	Estimated Cost				M/s.Samu Associates		M/s.Mehboob Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Dismantling and removing road matling	1314.06	Cft	605.00	%Cft	7,950.06	612.00	8,042.05	585.00	7,687.25
2	Excavation for pipe line in trenches and pits in Wet Soil clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m). i) Lift 0' - 5'ft	5256.25	Cft	5400.00	%0Cft	28,383.75	5408.00	28,425.80	5388.00	28,320.68
	ii) Lift upto 05' - 08'	2718.75	Cft	5950.00	%0Cft	16,176.56	5820.00	15,823.13	5910.00	16,067.81
	iii) Lift upto 08' - 11'	1903.12	Cft	6500.00	%0Cft	12,370.28	6436.00	12,248.48	6520.00	12,408.34
3	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	15.00	Days	1500.00	P/Day	22,500.00	1436.00	21,540.00	1315.00	19,725.00
4	Providing & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 33" Dia	145.00	Rft	1273.00	P/Rft	184,585.00	1294.00	187,630.00	1288.00	186,760.00
5	Providing Manhole 5ft dia inside, 14ft depth (for vehicular traffic) as per drawing design & specification upto 15 ft dpeth with 1:2:4 24" dia RCC manhole cover and 1 Cwt C.I fram 3/8" dia M.S bar (0.25 Cwt) 12" thick 1:2:4 C.C. wall on on 8ft dia & 6" thick 1:4:8 C.C. bed in foundation 1/2" thick 1:3 cement plaster on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, i/c the cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete .	1.00	Nos	63129.00	Each	63,129.00	60450.00	60,450.00	62745.00	62,745.00
6	Add or deduct per ft depth.	-4.50	(-)Ft	4180.04	P/ft	(18,810.18)	4456.00	(20,052.00)	4270.00	(19,215.00)

*Amir*  
06/6

*[Signature]*

*bb*

*[Signature]*

*[Signature]*

**Name of Work: CLEANING OF 33" DIA MAIN SEWERAGE LINE THROUGH WINCHING MACHINE FROM GUJJAR NALLAH TOWARDS TOWN PLAZA SECTOR 11-E FOR IMPROVEMENT OF SEWERAGE SYSTEM OF NORTH KARACHI**

Item No	Description of Work	Estimated Cost				M/s.Samu Associates		M/s.Mehboob Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
7	Preparing Sub-base by supplying and spreading well graded pit or bed run gravel having a liquid limit not greater than 25 and plasticity index not greater than 6 in proper camber and grade i/c watering, rolling and compacting in layers not exceeding 6" compacted upto 98-100% density as per modified AASHO density (Rates i/c all cost of materials T&P and carriage upto 3 chains).	3153.75	Cft	3341.71	%Cft	105,389.18	3069.00	96,788.59	3332.00	105,082.95
8	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	5521.33	Cft	2760.00	%Cft	15,238.87	2776.00	15,327.21	2782.00	15,360.34
9	Cleaning inside Sewerage line completely restoring original silt free space / diameter of pipe lines by labour and equipment (Mechanically / Electrically driven). Including accessories like pulley's steel rope, buckets and draggers sizing from 6" to 18" dia their "to and fro" pulling action (No of passes shall be as many as required) would be undertaken in two phases (First phase entire length from down stream to up stream) bringing down peak hours sewage to flow inside pipe line (as free flow) and in 2nd phase from up stream to down stream of entire length using no silt to observed in bucket (6" dia to 18" dia) except only sewage water finally passing a ball of 12" lesser than the diameter of pipe but not exceeding 48" dia ball even for larger dia pipe to ensure perfect cleaning. The job including all the hire / cost of equipment and accessories of above winching machine / devises alongwith / Engine with winching drum set having, steel rope pulley mounted over it, steel bucket 6" to 18" dia hocks and other protection like safety barriers, traffic signs, traffic cones ensuring no damages to pipe line alongwith ensuring safety to labour and other public property / lives and removal of silts / solid during desilting and clearance of site etc complete as per full satisfaction of site Engineer. 33" dia	1920.00	Rft	273.70	P/Rft	525,504.00	282.00	541,440.00	277.00	531,840.00

*Amir*  
06/6

*T*


*g*

*ll*


*S*


**Name of Work: CLEANING OF 33" DIA MAIN SEWERAGE LINE THROUGH WINCHING MACHINE FROM GUJJAR NALLAH TOWARDS TOWN PLAZA SECTOR 11-E FOR IMPROVEMENT OF SEWERAGE SYSTEM OF NORTH KARACHI**


Item No	Description of Work	Estimated Cost				M/s.Samu Associates		M/s.Mehboob Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
10	Manufacturing and supplying of RCC Ring Slab of 21" dia (inside) and 36" dia outside 7.5" width and 6" thick i/c 3/8" dia tor steel bars two concentric rings with 3/8" dia 8 Nos cross linked bars welded and two sunk type hooks, casted in 1:1 1/2" 3 concrete with embedded 15 Kg C.I Frame in perfect position i/c transportation charges for an average lead of 20 Km per trip from casting yard to town office. (A minimum of 25 slabs per trip will be transported.	10.00	Nos	1906.60	Each	19,066.00	1530.00	15,300.00	1745.00	17,450.00
11	Shifting to the site and fixing 36" dia ring slab in perfect position on damaged manhole i/c cutting of the position of damaged manhole in proper shape laying in layer of C.M in 2" thickness and disposal of the debris.	10.00	Nos	563.09	Each	5,630.90	480.00	4,800.00	530.00	5,300.00
12	Manufacturing and supplying of 21" inch dia RCC Manhole Covers cast in 1:2:4 cement concrete ratio 3" inch deep at centre rein-forced with 1/2" dia M.S tor bars with 4" c/c welded to a 3/16" thick 2" wide M.S Plate and two hook of 3/8" dia tor bars including compacting, curing and transportation within 10 miles etc. 21" Dia	10.00	Nos	913.63	Each	9,136.30	762.00	7,620.00	855.00	8,550.00
TOTAL QUOTED / CORRECTED COST						<b>996,250</b>		<b>995,383</b>		<b>998,082</b>

  
(Ashraf Ali)  
D.A.O. (Dist. Central)  
Member / Secretary  
06/06/17

  
(Saif-ul-Plaque)  
Addl. Director Internal Audit  
KMC - Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (K.M.C)  
Member

  
(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener  
06/06/17

# ATTENDANCE SHEET



## FIRMS / CONTRACTORS

NAME OF WORK: REPLACEMENT / LAYING OF 12" DIA DAMAGED MAIN SEWERAGE LINE AT VARIOUS PLACES IN SECTOR 5-C, 5-D, 5-E, 11-A, 11-C & 11-G OF NORTH KARACHI.

Date of Opening: 05-06-2017

Time of Opening: 12:30 PM

Serial No.: 33397

S. NO.	NAME OF CONTRACTOR	NAME OF FIRMS	SIGNATURE
1	Muhamma Arpha	M/S. Samy Associates	
2	Salem	M/S. Mehboob Bmt	





# KARACHI WATER & SEWERAGE BOARD

## OFFICE OF THE DIRECTOR (DESIGN & ESTIMATE)

### BID EVALUATION REPORT


1	Name of Procuring Agency:	KARACHI WATER & SEWERAGE BOARD
2	Tender Reference No:	SPPRA Serial No.33397 I.D No. _____
3	Tender Description/Name of Work/Item:	<b>REPLACEMENT / LAYING OF 12" DIA DAMAGED MAIN SEWERAGE LINE AT VARIOUS PLACES IN SECTOR 5-C, 5-D, 5-E, 11-A, 11-C &amp; 11-G OF NORTH KARACHI</b>
4	Method of Procurement:	<u>Single Stage (One Envelop)</u>
5	Tender Published:	<u>Through SPPRA Web Site</u>
6	Total Bid Documents Sold:	<u>2 Nos</u>
7	Total Bid Received:	<u>2 Nos</u>
8	Technical Bid Opening Date (if applicable):	<u>N/A</u>
9	No. of Bid Technically Qualified (if applicable)	<u>N/A</u>
10	Bid (s) Rejected:	<u>NIL</u>
11	Financial Bid Opening Date:	05-06-2017

### 12 BID EVALUATION REPORT


S#	Name of Firm / Bidder	COST OFFERED BY THE BIDDER	RANKING IN TERMS OF COST	COMPARISON WITH ESTIMATED COST	REASON FOR ACCEPTANCE / REJECTION	REMARKS
1	M/s.Samu Associates	Rs.9,92,132/-	1 <sup>st</sup> Lowest	@0.121% Below	Pay Order and required documents are available. P.O # 03774516 dt:20-05-2017 Rs.20,000/-from Bank Al Habib Ltd. Clifton Branch Karachi	Substantially Responsive
2	M/s.Mehboob Enterprises	Rs.9,96,454/-	2 <sup>nd</sup> Lowest	@0.314% Above	Pay Order and required documents are available. P.O # 03448238 dt:24-03-2017 Rs.20,000/- from Bank Al Habib Ltd. U.P More Branch Karachi	Substantially Responsive


The all concerned bidders are being informed accordingly.


The E.E Concerned for compliance of Rule-45 of SPPRA 2010 **M/s.Samu Associates** declared as the lowest responsive bidder by the Committee and recommended for sanction from Competent Authority.

  
(Arshad Ali)  
D.A.O (District Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

NIT No. SPPRA Serial No.33397

Method of Procurement: Single Stage Single Envelope.

Name of Work: REPLACEMENT / LAYING OF 12" DIA DAMAGED MAIN SEWERAGE LINE AT VARIOUS PLACES IN SECTOR 5-C, 5-D, 5-E, 11-A, 11-C & 11-G OF NORTH KARACHI

**MINUTES OF BID OPENING MEETING.**

A meeting of the procurement committee of this department was held on 05-06-2017 for opening the bids received in respect of subject NIT till deadlines of submission. The meeting was attended by all / following members of the procurement committee and the representative of bidders. **(Attendance sheet is enclosed).**

2. Two bidders submitted their bids till the deadline of submission.

- i. M/s. Samu Associates
- ii. M/s. Mehboob Enterprises


3. The bids were opened at 12:30 P.M in the presence of the above mentioned participants and the rates quoted by bidders were read aloud and encircled by Chairman of the Procurement Committee.

S. No	Name of Firm	Quoted Price	Amount of Bid Security	Pay Order No. / Date
01	M/s.Samu Associates	Rs.9,92,131/-	Rs.20,000/-	P.O # 03774516 dt:20-05-2017 from Bank Al Habib Ltd. Clifton Branch Karachi
02	M/s.Mehboob Enterprises	Rs.9,96,453/-	Rs.20,000/-	P.O # 03448238 dt:24-03-2017 from Bank Al Habib Ltd. U.P More Branch Karachi


4. The bids do not contain any cutting or over-writing.


5. The committee shall examine all the bids as per the qualification / eligibility criteria provided in the bidding document and verify the documents and bid security submitted by the bidders (if required).


The meeting ended with the vote of thanks to and from the chair.

  
(Arshad Ali)  
D.A.O (District Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

Method and procedure of procurement: Open Competitive Bidding (National/ International Competitive Bidding) (Single Stage-One Envelope)


Description of work: REPLACEMENT / LAYING OF 12" DIA DAMAGED MAIN SEWERAGE LINE AT VARIOUS PLACES IN SECTOR 5-C, 5-D, 5-E, 11-A, 11-C & 11-G OF NORTH KARACHI

Date of Opening: 05-06-2017


**BIDDERS' ELIGIBILITY/ QUALIFICATION REPORT**


Eligibility/ Qualification Criteria:

S. No.	Eligibility / Qualification Criteria	Bidders' Name	
		M/s.Samu Associates	M/s.Mehboob Enterprises
1.	Registration with PEC (if applicable)	N/A	N/A
2.	NTN	Yes	Yes
3.	Sales Tax Registration (FBR)	N/A	N/A
4.	Registration with Sindh Revenue Board (SRB)	Yes	Yes
	<b>Qualification Criteria:</b>		
5.	Minimum three years' experience of relevant field.	Yes	Yes
6.	Turnover of at least last three years	Yes	Yes
7.	Required Bid Security is attached.	Yes	Yes
8.	Bid is signed, named and stamped by the authorized person of the firm along with Authorization letter.	Yes	Yes
9.	Any other factor deemed to be relevant by the procuring agency subject to provision of Rule-44	N/A	N/A
10.	Qualified/ disqualified	Qualified	Qualified

  
(Akshad Ali)  
D.A.O (District Central)  
Member / Secretary

  
(Saif-ul-Haque)  
Additional Director Internal  
Audit – KMC Member

  
(Maqsood Ahmed Shaikh)  
Superintending Engineer (KMC)  
Member

  
(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

  
(Saleem Ahmed)  
Director (Design & Estimate)  
Convener

## COMPARATIVE STATEMENT

Name of Work: REPLACEMENT / LAYING OF 12" DIA DAMAGED MAIN SEWERAGE LINE  
AT VARIOUS PLACES IN SECTOR 5-C, 5-D, 5-E, 11-A, 11-C & 11-G OF NORTH KARACHI

Item No	Description of Work	Estimated Cost				M/s.Samu Associates		M/s.Mehboob Enterprises		
		Quantity	Rate	Per	Amount	Rate	Amount	Rate	Amount	
1	Excavation for pipe line in trenches and pits in Wet Soil clay or mud i/c trimming and dressing sides to true alignment and shape leveling of beds of trenches to correct level and grade cutting joints holes and disposal of surplus earth within one chain as directed by Engineer Incharge providing fence guards, lights, flags sand temporary crossing for non-vehicular traffic wherever required lift upto 5 ft (1.52 m) and lead upto one chain (30.5m).	21360.00	Cft	5400.00	%0Cft	115,344.00	5410.00	115,557.60	5436.00	116,112.96
	05' - 08' ft	7485.00	Cft	5950.00	%0Cft	44,535.75	5865.00	43,899.53	5974.00	44,715.39
2	Full hire charges of pumping set per day i/c of wages of driver and assistant fuel or electric energy platform for placing the pump etc at lower depth with suction and delivery pipes for pumping out water found at various depth from trenches including the cost of erection and dismantling after completion of the job. Hire charges of pumping set upto 10 HP pumping out water from 10 ft deep trench	13.00	Days	1500.00	P/Day	19,500.00	1375.00	17,875.00	1130.00	14,690.00
3	Providing & Laying of RCC Pipes with Rubber Ring Joint and fitting in trench including cutting, fitting, jointing with rubber ring i/c testing with water to specified pressure. 12" Dia	1068.00	Rft	367.00	P/Rft	391,956.00	386.00	412,248.00	372.00	397,296.00
4	Providing manhole 4' feet internal diameter without RCC manhole cover with C.I. Frame (15 KG) and 5 feet clear depth cast in situ with 1:2:4 CC in 9" thick wall, 1:4:8: C.C in 6ft dia and 6" inch thick in foundation 1:2:4 C.C in benching 12" thick cement plastering with 1:3 C.M on all inside wall surfaces, channel and benching i/c making required nos of main and branch channels, 3/4" dia m.s foot rest @12" c/c i/c cost of excavation in all kinds of soil, backfilling and disposal of excavated stuff etc complete as per design and instruction of engineer incharge.	17.00	Nos	14529.29	Each	246,997.93	13620.00	231,540.00	14500.00	246,500.00
5	Add / deduct per ft depth	39.00	(+)Rft	2538.62	P/Rft	99,006.18	2418.00	94,302.00	2585.00	100,815.00
6	Refilling the excavated stuff in trenches 6" thick layer i/c watering ramming to full compaction etc complete.	27534.20	Cft	2760.00	%0Cft	75,994.39	2786.00	76,710.28	2772.00	76,324.80
<b>TOTAL QUOTED / CORRECTED COST</b>						<b>993,334</b>		<b>992,132</b>		<b>996,454</b>

(Asif Ali)  
D.A.O (Distt. Central)  
Member / Secretary

(Saif-ul-Haque)  
Addl. Director Internal Audit  
KMC - Member

(Maqsood Ahmed Shaikh)  
Superintending Engineer (K.M.C)  
Member

(Ghulam Muhammad Hub)  
S.E (District Central-A)  
Member

(Saleem Ahmed)  
Director (Design & Estimate)  
Convener